

(पंजीकृत डाक)

भा.वि.प्रा./आरपीआर/व.प्र.(अभि-सि)/विशेष सिविल मरम्मत कार्य/2024/ 1835-46

दिनांक: 29.10.2024

सेवा में,
मेसर्स एस. के. कंस्ट्रक्शन
विलेज - बरेमा, पोस्ट - रामेश्वर,
वाराणसी (उ.प्र.) - 221405

To,
M/s S.K. Construction,
Village - Barema, Post - Rameshwar
Varansi (U.P.) - 221405

विषय:- स्वामी विवेकानन्द हवाई अड्डा, रायपुर में प्रचालन क्षेत्र में विविध सिविल मरम्मत और रख-रखाव का कार्य (2024-25)

Sub:- Miscellaneous Special Civil Repair and Maintenance works in Operational area at S.V. Airport, Raipur.(2024-25)

Tender ID:- 2024_AAI_208633_1

संदर्भ :- आपकी ई-निविदा जो दिनांक 21.10.2024 को खोली गयी |

Ref:- Your E-tender opened on 21.10.2024

महोदय/Sir,


1. अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से उपरोक्त कार्य के लिए आपकी निविदा स्वीकार की जाती है आपके द्वारा उद्धृत राशि रु 42,35,760.00 (रुपये बयालीस लाख पैतीस हजार सात सौ साठ मात्र) (जी.एस.टी. छोड़कर) जो कि अनुमानित लागत रु. 54,27,000.00 (रुपये चौवन लाख सत्ताईस हजार मात्र) (जी.एस.टी. छोड़कर) से 21.95% कम है |

Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to Rs 42,35,760.00 (Rupees Forty-Two Lakhs Thirty-Five Thousand Seven Hundred Sixty Only) (Excluding GST) which is 21.95% below the estimated cost put to tender of Rs. 54,27,000.00 (Rupees Fifty-Four Lakhs Twenty-Seven Thousand Only) (Excluding GST).

2. वरिष्ठ प्रबंधक (अभि-सि), भा.वि.प्रा., स्वामी विवेकानन्द हवाई अड्डा, रायपुर इस कार्य के प्रभारी अभियंता होंगे | आपसे अनुरोध है कि कृपया दिनांक 23.11.2024 तक स्वामी विवेकानंद हवाई अड्डा, रायपुर पर अधोहस्ताक्षरकर्ता के कार्यालय में उपस्थित रहकर संविदा करार पर हस्ताक्षर करने तथा करार की कार्यवाही पूर्ण करने का कष्ट करें | यह संविदा करार 100/- रुपये (सौ रुपये मात्र) के गैर-न्यायिक स्टैम्प पेपर पर निष्पादित किया जायेगा, जिसका खर्च आपके द्वारा वहन किया जायेगा |

Senior Manager (Engg-Civil), AAI, Swami Vivekananda Airport, Raipur shall be the Engineer-In-charge of the work. You are requested to attend the office of the undersigned at Swami Vivekananda Airport, Raipur by 23.11.2024 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

3. संविदा करार के पेज नंबर 16 पर धारा नं. 1A के अनुसार आपके निविदा के साथ प्राप्त धरोहर राशि रुपये 1,08,540.00 (रुपये एक लाख आठ हजार पाँच सौ चालीस मात्र) को जमानत जमा के एक हिस्से के रूप में जमा माना जायेगा | कृपया इस कार्यदेश के जारी होने के तिथि से 10 दिनों के भीतर जमानत जमा के शेष रुपये 3,15,036.00 (रुपये तीन लाख पंद्रह हजार छतीस मात्र) इस कार्यालय में जमा कराये अन्यथा यह कांट्रैक्ट डॉक्यूमेंट के पेज नंबर 16 पर धारा नं 1A के अनुसार काटा जायेगा |



The Earnest Money amount of Rs. 1,08,540.00 (Rupees One Lakhs Eight Thousand Five Hundred Forty Only) received along with your tender will be treated and converted as part of security deposit as per Clause no. 1A on Page 16 of contract document. Please deposit Rs. 3,15,036.00 (Rupees Three Lakhs Fifteen Thousand Thirty-Six Only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause no. 1A at Page 16 of contract document.

4. आपसे अनुरोध है कि संविदा करार के पेज नंबर 52 पर धारा नं. 19 के अनुसार आप ठेका श्रमिक (विनियमन एवं उन्मूलन) अधिनियम 1970 के उपबंधों का अनुपालन करें, साथ ही ठेका श्रमिक (विनियमन एवं उन्मूलन) केन्द्रीय नियमावली 1971, बाल श्रम (निषेध एवं विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार और सेवा की हालत का विनियमन) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 तथा केंद्र और राज्य सरकारों के अधिनियमों के प्रावधानों का पूर्णतः अनुपालन करेंगे।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause no. 19 on Page no. 52 of GCC of tender and rules of Central and State Governments.

5. आपसे यह भी अनुरोध है कि आप कर्मचारी भविष्य निधि और विविध प्रावधान अधिनियम, 1952 और ईएसआई अधिनियम, 1948 (सभी संशोधनों सहित) एवं उस के अंतर्गत बनाये गये सभी नियमों एवं प्रावधानों का पूर्णतः अनुपालन करेंगे तथा क्षेत्रीय पीएफ आयुक्त द्वारा आबंटित पीएफ खाता कोड संख्या एवं ई.एस.आई. कॉर्पोरेशन द्वारा आबंटित ई.एस.आई. रजिस्ट्रेशन नंबर भी इस कार्यालय में जमा करायेंगे तथा पीएफ खाता कोड और ईएसआई पंजीकरण काम के वास्तविक समापन तक वैध रहे।

You are also requested to comply with all the provision of the employees Provident Fund & Misc. Provision Act, 1952 and ESI-Act, 1948 amended from time to time and rules framed there under and furnish the PF account code number allotted by Regional PF Commissioner and ESI Registration number allotted by ESI Corporation and continue to have valid PF account code and ESI registration number till actual completion of the work.

6. आपसे यह भी अनुरोध है कि आप वरिष्ठ प्रबंधक (अभि-सि.), स्वामी विवेकानंद हवाई अड्डा, रायपुर से अविलम्ब संपर्क करें जो कि आपको साइट हस्तांतरित करने की व्यवस्था करेंगे।

You are also directed to contact Sr. Manager (Engg.-Civil) immediately who will arrange to hand over the site to you.

7. कृपया ध्यान दें कि कार्य पूरा करने के लिए आपको 06 (छः) महीने का समय प्रदान किया जाता है और जो इस पत्र के जारी होने के बाद दसवें दिन से माना जायेगा।

Please note that the time allowed for carrying out the work shall be 06 (Six) months and same shall be reckoned from the 10th day after issue of this letter.

8. आगे से इस अनुबंध के संबंध में किसी भी प्रकार के पत्राचार को अधोहस्ताक्षरकर्ता को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.

9. कृपया इस पत्र की प्राप्ति-सूचना और स्वीकृति के प्रतीक रूप में इस पत्र की दूसरी प्रति हस्ताक्षर करने के बाद अधोहस्ताक्षरकर्ता को वापस भेज दें।



Please acknowledge the receipt and return the duplicate copy of this letter after signing it to the undersigned as a token of acceptance.

Note: किसी भी विसंगति की स्थिति में अंग्रेजी संस्करण/पाठ मान्य होगा।

In case any discrepancy the English version/ text shall prevail.

सधन्यवाद !

संलग्न :- 1) अनुसूची – अ
2) फॉर्म- III

भवदीय,

B. Mehta
29.10.24
(भावेश पी मेहता)

वरिष्ठ प्रबंधक (अभि.-सि.)

भा.वि.प्रा., एस.व्ही. हवाई अड्डा, रायपुर

मूलप्रति में नहीं
प्रतिलिपि:

1. क्षेत्रीय कार्यपालक निदेशक, पू.क्षे., भा.वि.प्रा. ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता -52।
2. महाप्रबंधक (इंजी), पू.क्षे., भा.वि.प्रा. ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता -52।
3. महाप्रबंधक (वित्त), पू.क्षे., भा.वि.प्रा. ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता -52।
4. उपमहाप्रबंधक (सतकर्ता), पू.क्षे., भा.वि.प्रा. ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता -52।
5. सहायक श्रम आयुक्त (सी), डी -6, आदर्श सोसाइटी, सेक्टर – 1, अवंती विहार, रायपुर।
6. क्षेत्रीय भविष्य निधि आयुक्त, भविष्य निधि कार्यालय, ब्लॉक – डी, स्कीम नं – 32, इंदिरा गांधी व्यावसायिक परिषद, पंडरी, रायपुर (छ.ग.) – 492004।

प्रतिलिपि:

1. विमानपत्तन निदेशक, भा.वि.प्रा., स्वामी विवेकानन्द हवाई अड्डा, रायपुर।
2. उपमहाप्रबंधक (अभि-सि), भा.वि.प्रा., स्वामी विवेकानन्द हवाई अड्डा, रायपुर।
3. उपमहाप्रबंधक (वित्त), भा.वि.प्रा., स्वामी विवेकानन्द हवाई अड्डा, रायपुर।
4. उपमहाप्रबंधक (अभि-विद्युत), भा.वि.प्रा., स्वामी विवेकानन्द हवाई अड्डा, रायपुर।
5. मुख्य सुरक्षा अधिकारी, भा.वि.प्रा., स्वामी विवेकानन्द हवाई अड्डा, रायपुर।

Raman Sec. Singh

B. Mehta
29.10.24
(भावेश पी मेहता)

वरिष्ठ प्रबंधक (अभि.-सि.)

Schedule of Quantity

Name of Work :- Miscellaneous spacial civil repair and maintenance works in operational area at S.V. Airport, Raipur. (2024-25)

			Annexure-A			
SI No.	Item No.	Description	Unit	Qty.	Rate	Amount
1	1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. a) All kinds of soil.	Cum	250.00	115.00	28750.00
2	2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a) 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	60.00	5860.00	351600.00
3	3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a) 1:4:8 (1 cement : 4 coarse sand (zone-iii) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	Cum	147.00	4680.00	687960.00
4	4	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns etc. for mass concrete	Sqm	540.00	180.00	97200.00
5	5	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	10.00	105.00	1050.00
6	6	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. a) Hot finished welded type tubes	Kg	1000.00	105.00	105000.00
7	7	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. a) Size of Tile 600 x 600 mm	Sqm	60.00	1080.00	64800.00
8	8	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. a) Size of Tile 600 x 600 mm	Sqm	20.00	1100.00	22000.00
9	9	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50mm (base metal of minimum 0.45mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	Sqm	40.00	490.00	19600.00
10	10	12 mm cement plaster finished with a floating coat of neat cement of mix : a) 1:4 (1 cement: 4 fine sand)	Sqm	160.00	215.00	34400.00
11	11	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : a) Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	Sqm	30.00	90.00	2700.00
12	12	Dismantling of flexible pavement (bituminous courses) by mechanical means and disposal of dismantled material up to a lead of 1 kilometre, as per direction of Engineer-in-charge.	Cum	50.00	650.00	32500.00
13	13	Dry stone pitching 22.5 cm thick including supply of stones and preparing surface complete.	Sqm	450.00	440.00	198000.00
14	14	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	Sqm	1160.00	690.00	800400.00
15	15	Providing and applying tack coat using bitumen emulsion (Rapid Setting) complying with IS:8887 spraying the bitumen with mechanically operated spray unit at the rate specified below, cleaning and preparing the existing pavement surface as per specifications complete in all respects as per direction of Engineer-In-charge. If the actual quantity of bitumen varies from the quantity specified, necessary cist adjustment for deviation in the quantity of bitumen shall be done as per rate in actual supply voucher from nearest refinery at the time of execution. The rate of bitumen excluding of GST shall only be considered for payment. a) 0.20 Kg/sqm on existing bitumenous surface.	Sqm	2800.00	30.00	84000.00
16	16	Providing and laying of Hot Mix Dense Bituminous Macadam (DBM) using crushed stone aggregate of quality, size and grading as specified and cement filler of quality as specified and Viscosity Grade Bitumen (supplied in bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-in-Charge including compacting with 8-10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [VG bitumen of grade (VG-30) shall be taken as 110 kg/m3 of mix supplied in bulk produced by Govt. Refineries and 2% cement by weight of aggregates as filler material].	Cum	30.00	7460.00	223800.00
17	17	Providing and laying of Hot Mix Semi Dense Asphaltic Concrete (SDAC) using crushed stone aggregate of quality, size and grading as specified and cement as filler of quality as specified and Viscosity Grade Bitumen (supplied in bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-in-Charge including compacting with 8-10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [VG bitumen of grade (VG-30) content shall be taken as 120 kg/m3 of mix supplied in bulk produced by Govt. Refineries and 2% cement by weight of aggregates as filler material].	Cum	50.00	8960.00	448000.00
18	18	Providing and laying of Hot Mix Dense Asphaltic Concrete (DAC) using crushed stone aggregate of quality, size and grading as specified and cement as filler of quality as specified and Viscosity Grade Bitumen (supplied in bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-in-Charge including compacting with 8 to 10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [VG bitumen of grade (VG-30) content shall be taken as 135 kg/m3 of mix supplied in bulk produced by Govt. Refineries and 2% cement by weight of aggregates as filler material].	Cum	110.00	9250.00	1017500.00
19	19	Cutting the existing bituminous pavement of runway / taxiways upto required depth by milling machine and loading in tippers with conveyor belt attachment including disposal of materials (mechanically) upto a lead of 6 (Six) km including cleaning and dressing of surface etc as directed by the engineer-in-charge. (Excluding cost of general cleaning which is taken in tack coat item)	Sqm	110.00	150.00	16500.00
			TOTAL (Rs.) 4,235,760.00			

(Rupees - Forty-Two Lakhs Thirty-Five Thousand Seven Hundred Sixty Only Excl. @18% GST)

Signature Not Verified

Digitally signed by VINAY KUMAR TAMRAKAR

Date: 2025.05.31 12:23:38 IST

Location: eProcurement System for Central PSUs