

संदर्भ : भाविप्रा/गोंदिया/अभि-सि/2025/परिधि सडक/का.आ./ 854-69
Ref.: AAI/GONDIA/ENGG-C/2025/Perimeter Road/WO/

दिनांक : 14/01/2025
Date : 14/01/2025

रजिस्टर्ड डाक/स्पीड पोस्ट/ई-मेल

सेवा में,
मेसर्स. सरफराज अमीन गोडिल,
सेल्स टैक्स कॉलोनी, फुलचुर पेट,
गोंदिया (महाराष्ट्र) - 441601
ई-मेल - ms.safeinvestment@rediffmail.com

To,
M/s. Sarfaraz Amin Godil,
Sales Tax Colony, Fulchur Peth,
Gondia (Maharashtra) - 441601
E-mail ID - ms.safeinvestment@rediffmail.com

कार्य का नाम : बिरसी विमानतल, गोंदिया में रनवे 22 के अंत की ओर नवनिर्मित/विस्तारित रनवे के साथ परिधि सडक का निर्माण।

Name of work : Construction of Perimeter Road along the newly constructed/extended Runway towards RWY 22 end at Birsi Airport, Gondia.

संदर्भ : आपकी ई-निविदा दिनांक 06.12.2024 बिड नं. 760373, (निविदा नंबर : 2024_AAI_208732_1)।

Ref. : Your e-tender opened on 06.12.2024 Bid No. 760373, (Tender Id: 2024_AAI_208732_1).

महोदय,

- ऊपर उल्लेखित कार्य हेतु आपकी निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है, आपके द्वारा बताए गये मद मूल्यों पर आपकी टेन्डर राशि कुल रु. 2,49,47,100/- (रुपये दो करोड़ उन्तालीस लाख सैंतालीस हजार एक सौ, मात्र) जिएसटी को छोड़कर है, जो कि टेन्डर की अनुमानित लागत राशि रुपये 337.13 लाख से 26.00 % नीचे है।

Your tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs. 2,49,47,100/- (Rupees Two Crores Forty Nine Lakhs Forty Seven Thousand One Hundred, Only) excluding GST**, which is **26.00 %** below the estimated cost put to tender of **Rs. 337.13 Lakhs** only.

- सहायक महाप्रबंधक (अभि-सिविल), भाविप्रा, बिरसी विमानतल, गोंदिया, कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप काम शुरू होने की निर्धारित तारीख से 15 दिनों के भीतर करारनामे को पूरा करने एवं हस्ताक्षर करने के लिए सहायक महाप्रबंधक (अभि-सि), भाविप्रा, बिरसी विमानतल, गोंदिया के कार्यालय उपस्थित हों या फिर आपकी ओर से एक पावर ऑफ अटॉर्नी रखने वाले अपने प्रतिनिधि जो की करारनामे में दस्तखत करने का अधिकार रखता हो को प्रतिनियुक्त करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो। अनुबंध का करारनामा रु. 100.00 (रु. एक सौ मात्र) के नॉन-ज्युडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा पेपर का खर्च आपके द्वारा उठाया जाएगा।

Asstt. General Manager (Engg-Civil), Airports Authority of India, Birsi Airport, Gondia shall be the Engineer-In-Charge of the work. You are requested to attend OR depute your accredited representative holding Power of Attorney who should be empowered to sign agreement on your behalf, to the O/o **Asstt. General Manager (Engg-Civil)**, AAI, Birsi Airport, Gondia within 15 days from the stipulated date of start of the work to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100.00 (Rs. One Hundred only) and the cost of the stamp paper shall be borne by you.

- रु. 6,74,260/- (रु. छह लाख चौहत्तर हजार दो सौ और साठ, मात्र) ऑनलाईन मोड के माध्यम से प्राप्त हुई धरोहर राशि सुरक्षा जमा के रूप में धरोहर राशि के बराबर यानी रु. 6,74,260/- जमा करने के बाद वापस कर दी जायेगी (डिमांड ड्राफ्ट/गॉरंटी बॉड के रूप में किसी भी शेड्युल बैंक का परंतु सहकारी या ग्रामीण बैंक का नहीं)।

अनवरत शीट / Continuation sheet - 2-

कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर सुरक्षा जमा राशि की बकाया रु. 18,20,450/- (रु. अठारह लाख बीस हजार चार सौ और पचास, मात्र) (गॉरंटी बॉड के रुप में किसी भी शेड्युल बैंक का परंतु सहकारी या ग्रामीण बैंक का नहीं) जमा करवायें, अन्यथा अनुबंध के दस्तावेज जी.सी. सी. के पृष्ठ 16 पर दी गई परिच्छेद 1ए के अनुसार इसे आपके रनिंग बिलों में से वसूल किया जायेगा।

The earnest money amount of Rs. 6,74,260/- (Rupees Six Lakhs Seventy Four Thousand Two Hundred and Sixty, Only) received through online mode shall be refunded after submission of EMD equivalent amount as Security deposit i.e. Rs. 6,74,260/- (in the form of DD/Bank Guarantee of any Schedules bank but not Co-operative or Gramin bank).

Please deposit balance Rs. 18,20,450/- (Rupees Eighteen Lakhs Twenty Thousand Four Hundred and Fifty, Only), (in the form of Bank Guarantee of any Schedules bank but not Co-operative or Gramin bank) towards security deposit within 10 days from the date of issue of this letter failing which the same will be deducted from your running bills as per Clause 1 (A) of GCC Page No. 16 of the tender document.

4. आपसे निवेदन है कि आप सभी श्रम कानूनों के तहत प्रावधानों जैसे कर्मचारी भविष्य निधि व विविध प्रावधान अधिनियम 1952, कर्मचारी राज्य बीमा (ईएसआई) अधिनियम, 1948, ठेका श्रमिक (रोजगार व सेवा की शर्त) अधिनियम, 1979 न्यूनतम मजदूरी अधिनियम, 1948, मजदूरी भूगतान अधिनियम, 1936, श्रमिक प्रतिपूर्ति अधिनियम, 1923 एवं अन्य संगत नियम व अधिनियम, अनुदेश इत्यादि जो समय समय पर जारी/प्रवर्तित किया जाते हैं का पालन करें।

You are requested to comply with provisions of all labour laws including the Employees Provident Fund & Miscellaneous Provisions Act, 1952, the Employees State Insurance (ESI) Act, 1948, the Contract Labour (Regulation & Abolition) Act, 1970, the Inter-State Migrant workmen (Regulation of employment & conditions of Service) Act, 1979, the Minimum Wages Act, 1948, the Payment of Wages Act, 1936, the Workmen's Compensation Act, 1923 and other relevant Act, Rules and Regulations, orders etc. issued from time to time.

5. आपसे यह भी अनुरोध है कि कार्य शुरू करने से पहले अनुबंध श्रम (आर एंड ए) अधिनियम, 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियम, 1971 के तहत श्रम लाइसेंस प्राप्त करें और कार्य पूरा होने तक लाइसेंस की वैधता बनाएं रखें। आवश्यक कार्यवाई के लिए फॉर्म-III (प्रमुख नियोक्ता द्वारा प्रमाण पत्र का फॉर्म) संलग्न है।

You are also requested to obtain Labour License before start of work under the Contract Labour (R&A) Act, 1970 and the Contract Labour (Regulation and Abolition) Central Rules, 1971 and retain the validity of license till completion of work. Form-III (Form of Certificate by Principal Employer) is enclosed for necessary action.

6. आपको निर्देश दिया जाता है कि आप तुरंत सहायक प्रबंधक (अभि-सिविल), भाविप्रा, बिरसी विमानतल, गोंदिया से मिलें वह आपको साइट सौंपने की व्यवस्था करेंगे। कृपया नोट कर लें कि काम करने का अनुमत समय 03 (तीन) महीने हैं जो कि इस पत्र के जारी करने के दसवे दिन से अथवा जिस दिन साइट हेण्ड ओवर की जाती है उनमें से जो भी पहले होगा उस दिन से कार्य के प्रारंभ की तिथि गिनी जाएगी।

You are also directed to contact Assistant Manager (Engg-Civil), AAI, Birsi Airport, Gondia who will arrange to handover the site to you. Please note that the time allowed for carrying out the work as entered in the tender is 03 (Three) Months and same shall be reckoned from the tenth day after issue of this letter or handing over of site whichever is earlier.

अनवरत शीट / Continuation sheet - 3-

7. इस अनुबंध के संबंध में आगे कोई भी पत्राचार सहायक महाप्रबंधक (अभि-सिविल), भाविप्रा, बिरसी हवाईअड्डा, गोंदिया के पते पर किया जाएगा ।

Any further correspondence in connection with the contract should normally be addressed to the **Asstt. General Manager (Engg-Civil)**, AAI, Birsi Airport, Gondia.

8. अनुबंध दस्तावेज जी.सी.सी. के पृष्ठ 47 में परिच्छेद – क्रम सं. 17 में उल्लिखित त्रुटि दायित्व अवधि 12 (बारह) महीने होगी ।

The defects liability period shall be 12 (Twelve) Months as mentioned in clause No. 17 of GCC, page 47 of the contract document.

9. कृपया पावती भेजे तथा इस की प्रतिलिपि हस्ताक्षर कर के अधोहस्ताक्षरी को वापस भेजे ।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

10. हिन्दी और अंग्रेजी संस्करण के बिच विसंगती की स्थिती में अंग्रेजी संस्करण मान्य होगा ।

In case of discrepancy between Hindi & English version English version will prevail.


14/01/2025

(पंकज कांबले)

सहायक महाप्रबंधक (अभि-सिविल),

भाविप्रा, बिरसी विमानतल, गोंदिया

Enclosed : 04 (Four) Page.

सलग्नक : 04 (चार) पृष्ठ ।

प्रतिलिपि / Copy to :-
आंतरिक वितरण :-

1. महाप्रबंधक (इंजी), भाविप्रा, पश्चिमी क्षेत्र, क्षेत्रिय मुख्यालय, पारसीवाडा, सहार रोड, विले पार्ले (पुर्व), मुंबई - 400099.
General Manager (Engg), AAI, Regional Head Quarter, Western Region, Parsiwada, Sahar Road, Vile Parle (E), Mumbai - 400099.
2. संयुक्त महाप्रबंधक (सतर्कता), भाविप्रा, भाविप्रा, पश्चिम क्षेत्र, क्षेत्रिय मुख्यालय, पारसीवाडा, सहार रोड, विले पार्ले (पुर्व), मुंबई - 400099.
Jt. General Manager (Vigilance), AAI, Western Region, Regional Head Quarter, Parsiwada, Sahar Road, Vile Parle (E), Mumbai - 400099.
3. विमानपत्तन निदेशक, भा.वि.प्रा, बिरसी विमानतल, गोंदिया -441601.
Airport Director, AAI, Birsi Airport, Gondia - 441601.
4. उप. महाप्रबंधक (अभि-सि), भा.वि.प्रा, डॉ. बाबासाहेब अम्बेडकर अंतरराष्ट्रीय विमानतल, नागपुर-440005.
Deputy General Manager (Engg-Civil), AAI, DBAI Airport, Nagpur-440005.
5. सहा. महाप्रबंधक (वित्त), भा.वि.प्रा, डॉ. बाबासाहेब अम्बेडकर अंतरराष्ट्रीय विमानतल, नागपुर-440005.
Asstt. General Manager (Fin), AAI, DBAI Airport, Nagpur-440005.
6. सहायक प्रबंधक (अभि-सि), भा.वि.प्रा, बिरसी विमानतल, गोंदिया -441601.
Assistant Manager (Engg-Civil), AAI, Birsi Airport, Gondia - 441601.
7. करारनामा कॉपी.
Agreement Copy.
8. सम्बंधित फाईल.
Concerned File.

बाह्य वितरण :-

1. लेबर कमिश्नर ऑफीस, 1st फ्लोवर, ब्लॉक-सी, सी.जी.ओ. कॉम्प्लेक्स, सेमिनरी हिल्स, नागपुर-440006.
Labour Commissioner Office, 1st Floor, Block-C, C.G.O Complex, Seminary Hills, Nagpur - 440006.
2. सहायक भविष्यनिधी कमिश्नर, भांडे प्लॉट, उमरेड रोड, रघुजी नगर, नागपुर - 440009.
Assistant Provident Fund Commissioner, Bhande Plot, Umred Road, Raghuji Nagar, Nagpur - 440009.
3. डी. सी. एस. टी., जी. एस. टी. भवन, सिव्हील लाईन, गोंदिया -441601.
DCST, GST Bhawan, Civil Line, Gondia -441601.
4. इनकम टॅक्स ऑफीसर, फुलचूर रोड, गोंदिया -441601.
Income Tax Officer, Fulchur Road, Gondia - 441601.


14/01/2024

सहायक महाप्रबंधक (अभि-सिविल),
भाविप्रा, बिरसी विमानतल, गोंदिया

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: AGM (E-C), AAI, Birsī Airport, Gondia.

Name of Work: Construction of Perimeter Road along the newly constructed/ extended Runway towards RWY 22 end at Birsī Airport, Gondia.

Contract No:

Name of the Bidder/ Bidding Firm / Company :	SARFARAZ AMIN GODIL
--	---------------------

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excl. GST) Rs. P	TOTAL AMOUNT (Excl. GST) in Rs. P	TOTAL AMOUNT (Excl. GST) In Words	TEXT #
1	2	4	5	13	53	55	
1	Earthwork in excavation in all kinds of soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections and transporting to embankment location with all lifts and leads upto 2.0 km within airport premises as per satisfaction and direction of Engineer-In-Charge.	6500.00	cum	90.00	585000.00	INR Five Lakh Eighty Five Thousand Only	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (Zone-III) : 4 graded stone aggregate 20 mm nominal size)	71.00	cum	4400.00	312400.00	INR Three Lakh Twelve Thousand Four Hundred Only	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 cement : 4 coarse sand (Zone-III) : 8 graded stone aggregate 40 mm nominal size)	25.00	cum	4750.00	118750.00	INR One Lakh Eighteen Thousand Seven Hundred & Fifty Only	
4	Consolidation of subgrade with power road roller 8 to 10 tonne capacity including making good the undulations etc. with earth or quarry spoils etc. and re-rolling the subgrade.	13500.00	sqm	35.00	472500.00	INR Four Lakh Seventy Two Thousand Five Hundred Only	

Signature
14/10/2024

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excl. GST) Rs. P	TOTAL AMOUNT (Excl. GST) in Rs. P	TOTAL AMOUNT (Excl. GST) In Words	TEXT #		
1	2	4	5	13	53	55			
5	Supplying and filling moorum or suitable earth obtained from approved quarry in embankment or depressions in layers not exceeding 20cm in depth (or any thickness as approved by the Engineer-in-Charge in case vibratory roller / soil compactor is used) including breaking clods, watering, consolidating each layer with power road roller 8-10 tonnes weight or vibratory roller / soil compactor of adequate capacity under optimum moisture content condition to give at least 97% of the maximum laboratory dry density (modified proctor density) as per IS code 2720 (part VIII) complete including leveling fine dressing to the required grade, camber and slope complete as per MORTH specifications and as directed by the Engineer-in-Charge with all leads and lifts (The item includes cost of work, payment of necessary royalty, carriage of moorum / suitable earth upto work site for all leads and lifts involved from all sources acquired or arranged by the Contractor. Payment to be made for compacted quantity only).	1200.00	cum	550.00	660000.00	INR Six Lakh Sixty Thousand Only			
6	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-III (size range 26.5 mm to 0.075 mm) having CBR Value-20	3000.00	cum	1900.00	5700000.00	INR Fifty Seven Lakh Only			
7	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	3000.00	cum	2000.00	6000000.00	INR Sixty Lakh Only			
8	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	6500.00	cum	100.00	650000.00	INR Six Lakh Fifty Thousand Only			
9	Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. With rapid setting bitumen emulsion. On W.B.M / W.M.M. @ 0.4kg/sqm	11000.00	sqm	10.00	110000.00	INR One Lakh Ten Thousand Only			
10	Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. With rapid setting bitumen emulsion. On bituminous surface @ 0.25kg/sqm	11000.00	sqm	8.00	88000.00	INR Eighty Eight Thousand Only			

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excl. GST) Rs. P	TOTAL AMOUNT (Excl. GST) in Rs. P	TOTAL AMOUNT (Excl. GST) In Words	TEXT #		
1	2	4	5	13	53	55			
11	Providing and laying bituminous macadam using crushed stone aggregates of specified grading premixed with bituminous binder, transported to site by tippers, laid over a previously prepared surface with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per specifications and directions of Engineer-in-Charge. 50 to 100 mm average compacted thickness with bitumen of grade VG-30 @ 3.50% (percentage by weight of total mix) prepared in Drum Type Hot Mix Plant of 60-90 TPH capacity.	820.00	cum	6750.00	5535000.00	INR Fifty Five Lakh Thirty Five Thousand Only			
12	Providing and laying Bituminous concrete using crushed stone aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site by tippers, laying with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction and density as per specification, complete and as per directions of Engineer-in-Charge. 40/50 mm compacted thickness with bitumen of grade VG-30 @ 5.5% (percentage by weight of total mix) and lime filler @ 3% (percentage by weight of Aggregate) prepared in drum Type Hot Mix Plant of 60-90 TPH capacity.	545.00	cum	7265.00	3959425.00	INR Thirty Nine Lakh Fifty Nine Thousand Four Hundred & Twenty Five Only			
13	Providing and laying non-pressure NP4 class (Heavy duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : 600 mm dia. R.C.C. pipe	130.00	Metre	1500.00	195000.00	INR One Lakh Ninety Five Thousand Only			
14	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	1825.00	Kg.	85.00	155125.00	INR One Lakh Fifty Five Thousand One Hundred & Twenty Five Only			
15	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto and above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	800.00	Kg.	85.00	68000.00	INR Sixty Eight Thousand Only			
16	Centering and shuttering including strutting, propping etc. and removal of form for all heights: Foundations, footings, bases of columns, etc. for mass concrete	166.00	sqm	200.00	33200.00	INR Thirty Three Thousand Two Hundred Only			
17	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Walls (any thickness) including attached pilasters. Butteresses, plinth & string courses etc.	50.00	sqm	350.00	17500.00	INR Seventeen Thousand Five Hundred Only			
18	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Suspended floors, roofs, landings, balconies and access platform	20.00	sqm	355.00	7100.00	INR Seven Thousand One Hundred Only			
19	Centering and shuttering including strutting, propping etc. and removal of form work for : Columns, piers, abutments, pillars, posts and struts	20.00	sqm	360.00	7200.00	INR Seven Thousand Two Hundred Only			

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excl. GST) Rs. P	TOTAL AMOUNT (Excl. GST) in Rs. P	TOTAL AMOUNT (Excl. GST) In Words	TEXT #		
1	2	4	5	13	53	55			
20	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	5.00	cum	6300.00	31500.00	INR Thirty One Thousand Five Hundred Only			
21	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	13.00	cum	4700.00	61100.00	INR Sixty One Thousand One Hundred Only			
22	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	1000.00	Kg.	109.00	109000.00	INR One Lakh Nine Thousand Only			
23	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. Hot finished welded type tubes	400.00	Kg.	105.00	42000.00	INR Forty Two Thousand Only			
24	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	2.00	cum	6900.00	13800.00	INR Thirteen Thousand Eight Hundred Only			
	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture.	100.00	sqm	155.00	15500.00	INR Fifteen Thousand Five Hundred Only			
					24947100.00	INR Two Crore Forty Nine Lakh Forty Seven Thousand One Hundred Only			

Signature Not Verified

Digitally Signed by PANKAJ GOVARDHAN
KAMBLI
Date: 20/06/2020 12:45:55 IST
Location: eProcurement System for Central PSUs

14/10/2019