



भाविप्रा/औबाद/अभि.-वि/कैप/24-25/डब्लू -07/ 583
AAI/AU/Engg-E/CAP/24-25/W-07/

दिनांक: 11.12.2024

Date: 11.12.2024

सेवा में,
मेसर्स ओके एजेंसीज,
101, निमेश इन्डस्ट्रीयल प्रिमायसेस,
विद्यालय मार्ग, भोइर नगर,
गावंपाडा, मुलुंड इस्ट,
मुंबई - 400081.

To,
M/s OK Agencies,
101, Nimesh Industrial Premises,
Vidyalaya Marg, Bhoir Nagar,
Gavanpada, Mulund East,
Mumbai - 400081

(PAN No. ABDPJ0462B)
GST No. 27ABDPJ0462B129

कार्य का नाम : 33 के. वी. एच. टी पावर केबल का स्ट्रेन्थनिंग। उपशीर्ष : औरंगाबाद हवाईअड्डे पर दो अलग फीडर्स के लिए 33 के. वी. एच. टी अंडर ग्राउंड केबल आपूर्ति एवं बिछाने का कार्य।
Strengthening of 33KV HT power cable. SH: Supply and laying of 33KV grade HT cable (UG) for two different feeders at Aurangabad Airport.

संदर्भ : 1) निविदा आई. डी संख्या : 2024_AAI_211493_1
2) आपकी ई - निविदा जो दिनांक 26.11.2024 को खोली.

महोदय, / Dear Sir (S),

1. उल्लिखित कार्य हेतु आपकी ई - निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आपके द्वारा बताए गये मद मूल्यों पर रु. 66,05,000.00 (रु. छहसठ लाख पाच हजार मात्र) (जी एस टी अतिरिक्त) के लिये स्वीकृत की जाती है जो कि अनुमानित लागत राशि रु. 81,36,889.00 से 18.83 % कम है।

Your e-tender for the work mentioned above is hereby accepted on behalf of the chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs. 66,05,000.00** (Rupees Sixty Six Lakh Five Thousand Only) (Excluding GST) which is 18.83% below the justification cost put to tender of **Rs. 81,36,889.00**.

2. वरि. प्रबंधक (अभियांत्रिकी- विद्युत), भाविप्रा, औरंगाबाद हवाईअड्डा, महाराष्ट्र कार्य के प्रभारी अभियंता होंगे, आपसे निवेदन है कि, आप दिनांक 24.12.2024 तक वरि. प्रबंधक (अभियांत्रिकी- विद्युत), भाविप्रा, औरंगाबाद हवाईअड्डा, औरंगाबाद, के कार्यालय में उपस्थित हों तथा करारनामे को पुरा करें. ठेके के करार नामा रुपये 100/- के नोनजुडिशियल स्टैम्प पर निष्पादित किया जायेगा तथा पेपर का खर्चा आपके द्वारा उठाया जायेगा।

Senior Manager (E-E), AAI, Aurangabad Airport, Maharashtra, shall be the Engineer -In -Charge of the work. You are requested to attend the office of Senior Manager (E-E), AAI, Aurangabad Airport by 24.12.2024 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees one Hundred Only) and the cost of the stamp paper shall be borne by you.

विमानक्षेत्र नियंत्रक का कार्यालय, भा.वि.प्रा., औरंगाबाद, दूरभाष : (0240) 2477802,
O/O The Airport Director, AAI, Aurangabad. Phone No: (0240)2477802,

11.12.24
व.प्रबं. अभि. (वि.)
वरि.प्रबंधक (अभि-विद्युत)
भाविप्रा औरंगाबाद हवाईअड्डा

3. आपके निविदा के साथ प्राप्त बयाना राशि **1,62,738.00** रुपए को प्रतिभूति जमा के हिस्से के रूप में परिवर्तित किया जाएगा। कृपया इस पत्र के जारी होने की तिथि से 15 दिनों के भीतर प्रतिभूति जमा राशि **4,97,762.00** रुपये ठेके के दस्तावेज के अनुसार जमा कर दें, अन्यथा निविदा में पृष्ठ जी सी सी 16 पर दी गई धारा 1(A) के अनुसार कटौती की जाएगी।

The earnest money amount of **Rs.1,62,738.00** received along with your tender will be treated and converted as part of Security Deposit. Please deposit **Rs. 4,97,762.00** towards security deposit within 15 days from the date of issue of this letter, failing which the same will be deducted as per condition of clause 1(A) at GCC Page 16 of the Contract Document.

4. आपसे निवेदन है कि आप केन्द्रीय और राज्य सरकारों के 1970 अधिनियम अनुबन्ध श्रम नियम तथा 1971 के केन्द्रीय नियम (नियमन तथा उन्मूलन) एवं केन्द्र तथा राज्य सरकारों के न्यूनतम वेतन अधिनियमों और नियमों के प्रवधानों के अनुपालन करें।

You are requested to comply with the provisions of contract labour (Regulation and abolition) Act of 1970 and contract labour (Regulation and abolition) Central rules 1971 and minimum wages Act & rules thereof Central and State Governments.

5. आपको निर्देश दिया जाता है कि आप तुरंत सहा. प्रबंधक (अभियांत्रिकी - विद्युत), से मिलें वह आपको साईट सौंपने कि व्यवस्था करेंगे।

You are also directed to contact **Asstt. Manager (Engg-Elect.)**, AAI, Aurangabad Airport immediately who will arrange to hand over the site to you.

6. कृपया नोट करें कि कार्य करने का समय **06 (छह) माह** रहेगा, जोकी कार्य आदेश जारी होने के दसवें दिन से माना जायेगा।

Please note that the time allowed for carrying out the work shall be **06 (Six) Months** and same shall be reckoned from the 10th day of the date of placing of work order.

7. यदि अंग्रेजी और हिंदी पाठ में कोई अंतर पाया जाता है तो अंग्रेजी विवरण सही माना जाएगा।
If there is any discrepancy between English and Hindi then meaning derived in English will be given precedence.

8. ई निविदा प्रक्रिया के दौरान उठाए गए सभी शुद्धी पत्र, प्रश्न, स्पष्टीकरण इत्यादि और उपर उल्लिखित पत्रों सहित उत्तरों के जवाब भी करारनामे के हिस्से होंगे।

All corrigendum, queries, clarifications etc., raised during e-tendering process and replies there of including the letters referred above shall also form part of the agreement.

9. इस ठेके के संबंध में आगे को कोई भी पत्राचार वरि. प्रबंधक (अभि.- विद्युत), भाविप्रा. औरंगाबाद हवाईअड्डा, औरंगाबाद - 431007 के पते पर किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Sr. Manager (Engg-Elect), AAI, Aurangabad Airport, Aurangabad - 431007.


10. कृपया इस पत्र को स्वीकार करें और हस्ताक्षर करने के बाद इसके साथ संलग्न पत्र की डुप्लिकेट प्रति स्वीकृति के प्रतीक के रूप में अधोहस्ताक्षरी को वापिस करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

संलग्न : मात्रा की अनुसूची

Encl : Schedule of Quantity (SOQ)

भवदीय/ Yours faithfully,


11.12.24

वरि. प्रबंधक [अभि - विद्युत]

Sr. Manager (E-E)

भाविप्रा, औरंगाबाद हवाईअड्डा, औरंगाबाद
AAI, Aurangabad Airport, Aurangabad

वरि. प्रबंधक (अभि-विद्युत)

भाविप्रा औरंगाबाद हवाईअड्डा

Validate

Print

Help


Item Rate BoQ

Tender Inviting Authority: Senior Manager (Engg.-Electrical), Airports Authority of India, Aurangabad Airport, Aurangabad- 431007.


Name of Work: Strengthening of 33KV HT power cable. SH: Supply and laying of 33 KV grade HT cable (UG) for two different feeders at Aurangabad Airport.

Contract No: 2024_AAI_211493_1


Name of the Bidder/ Bidding Firm / Company :	OK AGENCIES					
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
SI. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Without Taxes) Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Supply of 3CX 300 sq.mm size of HT XLPE insulated, stranded compact circular alumnium conductor, conductor screen with extruded semi conducting compound, Insulation screening with extruded semi conducting compound in combination with coper tape, cores laid up , inner sheath of FRLS PVC tape , galvanised flat steel strip armoured and overall FRLS PVC sheathed cable of 33 KV (UE) HT grade conforming to IS 7098/ Part - II 1985 with latest amendments.	1950	Mtr	2635.00	5138250.00	INR Fifty One Lakh Thirty Eight Thousand Two Hundred & Fifty Only
2	Supply of 200 mm dia (OD-200 mm & ID-175 mm nominal) DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete as required.	1501	Mtr	310.00	465310.00	INR Four Lakh Sixty Five Thousand Three Hundred & Ten Only


 11.12.24
 व. प्र. प्रभुकर (अभि-विद्युत)
 भा. वि. म. औरंगाबाद हवाई अड्डा

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Without Taxes) Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
3	Laying of 200 mm dia (OD-200 mm & ID-175 mm nominal) DWC HDPE pipe along with all accessories like socket, bend, couplers etc. complete with fitting and cutting, jointing etc. direct in ground (1.2 meter below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc. complete as required.	1211	Mtr	70.00	84770.00	INR Eighty Four Thousand Seven Hundred & Seventy Only
4	Laying of 200 mm dia (OD-200 mm & ID-175 mm nominal) DWC HDPE pipe along with all accessories like socket, bend, couplers etc. complete with fitting and cutting, jointing etc. direct in ground (1.2 meter below ground level) including refilling the trench but excluding excavation of trench and sand cushioning and protective covering etc., complete as required.	290	Mtr	20.00	5800.00	INR Five Thousand Eight Hundred Only
5	Excavation of the cable trenches in hard rock not exceeding 1.5 meters in width and lift up to 1.5 meters , including getting out the excavated soil and disposal of excavated soil as directed with in a lead of 50 meters (minimum depath should be 1.2 meter and width should be 0.35 meter)	122	Cum	600.00	73200.00	INR Seventy Three Thousand Two Hundred Only
6	Providing, laying and fixing of 150 mm dia G.I. pipe (C class) on surface (horizontal or vetical) complete with G.I. fittings, clamps etc as required.	56	Mtr	2000.00	112000.00	INR One Lakh Twelve Thousand Only
7	Providing and laying non pressure NP2 Class (light duty) 250 mm R.C.C Pipes with collers jointed with stiff mixture of cement mortar in proportion of 1:2 (1 Cement : 2 Sand) including cutting / breaking PCC/Bituminous area upto 400 mm deep and 400 mm width remaking the same as good as previous etc. as required.	30	Mtr	1200.00	36000.00	INR Thirty Six Thousand Only
8	Laying of one number XLPE power cable of 33 KV grade of following size in the existing RCC/ HUME/METAL/DWC HDPE pipe as required. Above 120 sq. mm and upto 400 sq. mm	1737	Mtr	20.00	34740.00	INR Thirty Four Thousand Seven Hundred & Forty Only



 11.12.24
 क. प्र. वि. वि. (अ. वि. वि. वि.)
 ११.१२.२४

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Without Taxes) Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
9	Laying of one number XLPE power cable of 33 KV grade of following size in the existing masonry open duct as required. Above 120 sq. mm and upto 400 sq. mm	102	Mtr	40.00	4080.00	INR Four Thousand & Eighty Only
10	Supplying and making indoor cable end termination with heat shrinkable jointing kit complete with all accessories including lugs suitable for 300 sq. mm x 3 core, XLPE aluminium conductor cable of 33 KV (UE) grade as required. (Required Make: Raychem or Biral - 3M only)	2	EA	15000.00	30000.00	INR Thirty Thousand Only
11	Supplying and making outdoor cable end termination with heat shrinkable jointing kit complete with all accessories including lugs suitable for 300 sq. mm x 3 core, XLPE aluminium conductor cable of 33 KV (UE) grade as required. (Required Make: Raychem or Biral - 3M only)	2	EA	16000.00	32000.00	INR Thirty Two Thousand Only
12	Supplying and making straight through cable jointing with heat shrinkable jointing kit complete with all accessories including ferrules suitable for 300 sq. mm x 3 core, XLPE aluminium conductor cable of 33 KV (UE) grade as required. (Required Make: Raychem or Birla - 3M only)	3	EA	37950.00	113850.00	INR One Lakh Thirteen Thousand Eight Hundred & Fifty Only
13	Supplying and fixing cable route marker with 10 cm X 10 cm X 5 mm thick G.I. plate with inscription there on, bolted /welded to 35 mm X 35 mm X 6 mm angle iron, 60 cm long and fixing the same in ground as required.	20	EA	500.00	10000.00	INR Ten Thousand Only


11.12.24

क. प्रबं. अफि (वि.)
वरि.प्रबंधक (अभि-विपुल)
भाविम औरंगाबाद हवाईअड्डा

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Without Taxes) Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
14	Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zoneIII) : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design : Inside size 120x90 cm and 90 cm deep including C.I. cover with frame (heavy duty) 560 mm internal diameter, total weight of cover and frame to be not less than 208 kg (weight of cover 108 kg and weight of frame 100 kg). With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	7	EA	15000.00	105000.00	INR One Lakh Five Thousand Only
15	Supply and Laying of 200 mm dia HDPE pipe with HDD trenchless method direct in ground (upto 07 meter below ground level) in all type of soil, coupling of pipe etc complete as per requirement in all aspect. (work includes obtaining NOC from railways if the HDD needs to done under the railway track).	150	Mtr	2400.00	360000.00	INR Three Lakh Sixty Thousand Only
Total in Figures					6605000.00	INR Sixty Six Lakh Five Thousand Only
Quoted Rate in Words		INR Sixty Six Lakh Five Thousand Only				



11.12.24

क. प्रबं. शक्ति (वि)
वरि.प्रबंधक (अभि-विद्युत)
भाविम औरंगाबाद हवाईअड्डा