

संदर्भ : भाविप्रा / गोंदिया / अभि-सि / 2024 / संरचनात्मक मरम्मत / का.आ. / 791-803
Ref.: AAI/GONDIA/ENGG-C/2024/Structural-Repair/WO/

दिनांक : 16/12/2024
Date : 16/12/2024

रजिस्टर्ड डाक / स्पीड पोस्ट / ई-मेल

सेवा में,
मेसर्स. बी.एन.एस. इन्फ्रास्ट्रक्चर,
प्लॉट नं. 98, ओम नगर,
वॉक्स कुलर के सामने, कोराडी रोड,
नागपुर - 440 030
ई-मेल - bnsinfrastructure@gmail.com

To,
M/s. B.N.S. Infrastructure,
Plot No. 98, Om Nagar,
Opp. Wox Coolers, Koradi Road,
Nagpur - 440 030
E-mail ID- bnsinfrastructure@gmail.com

कार्य का नाम : बिरसी विमानतल, गोंदिया में संरचनात्मक लेखा परीक्षा की सिफारिश के अनुसार टर्मिनल भवन और अन्य भवनों की मरम्मत कार्य।

Name of work : Repair works of Terminal Building & other buildings as per recommendation of structural audit at Birsi Airport, Gondia.

संदर्भ : आपकी ई-निविदा दिनांक 22.11.2024 बिड नं. 766629, (निविदा नंबर : 2024_AAI_212314_1)।

Ref : Your e-tender opened on 22.11.2024 Bid No. 766629, (Tender Id: 2024_AAI_212314_1).

महोदय,

- ऊपर उल्लेखित कार्य हेतु आपकी निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है, आपके द्वारा बताए गये मद मूल्यों पर आपकी टेन्डर राशि कुल रु. 74,91,584.01/- (रुपये चौहत्तर लाख इक्यानबे हजार पाच सौ चौरासी और पैसे एक, मात्र) जिएसटी को छोड़कर है, जो कि टेन्डर की अनुमानित लागत राशि रुपये 103.76 लाख से 27.79 % नीचे है।

Your tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs. 74,91,584.01/- (Rupees Seventy Four Lakhs Ninety One Thousand Five Hundred and Eighty Four, Only) excluding GST**, which is **27.79 %** below the estimated cost put to tender of **Rs. 103.76 Lakhs** only.

- सहा. महाप्रबंधक (अभि-सिविल), भाविप्रा, बिरसी विमानतल, गोंदिया, कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप काम शुरू होने की निर्धारित तारीख से 15 दिनों के भीतर करारनामे को पूरा करने एवं हस्ताक्षर करने के लिए महाप्रबंधक (अभि-सि), भाविप्रा, बिरसी विमानतल, गोंदिया के कार्यालय उपस्थित हों या फिर आपकी ओर से एक पावर ऑफ अटॉर्नी रखने वाले अपने प्रतिनिधि को प्रतिनियुक्त करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो। अनुबंध का करारनामा रु. 100.00 (रु. एक सौ मात्र) के नॉन-ज्युडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा पेपर का खर्च आपके द्वारा उठाया जाएगा।

Asstt. General Manager (Engg-Civil), Airports Authority of India, Birsi Airport, Gondia shall be the Engineer-In-Charge of the work. You are requested to attend OR depute your accredited representative holding Power of Attorney to sign the contract agreement on your behalf, to attend the O/o **Asstt. General Manager (Engg-Civil)**, AAI, Birsi Airport, Gondia within 15 days from the stipulated date of start of the work to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100.00 (Rs. One Hundred only) and the cost of the stamp paper shall be borne by you.

- रु. 2,07,520/- (रु. दो लाख सात हजार पाच सौ बीस, मात्र) ऑनलाईन मोड के माध्यम से प्राप्त हुई धरोहर राशि सुरक्षा जमा के रूप में धरोहर राशि के बराबर यानी रु. 2,07,520/- जमा करने के बाद वापस कर दी जायेगी (डिमांड ड्राफ्ट/गॉरंटी बॉण्ड के रूप में किसी भी शेड्युल बैंक का परंतु सहकारी या ग्रामीण बैंक का नहीं)।

अनवरत शीट / Continuation sheet - 2-

कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर सुरक्षा जमा राशि की बकाया रु. 5,41,638/- (रु. पाच लाख इकतालीस हजार छह सौ अडतीस, मात्र) (गॉरंटी बॉड के रुप में किसी भी शेड्युल बैंक का परंतु सहकारी या ग्रामीण बैंक का नहीं) जमा करवायें, अन्यथा अनुबंध के दस्तावेज जी.सी. सी. के पृष्ठ 16 पर दी गई परिच्छेद 1ए के अनुसार इसे आपके रनिंग बिलों में से वसूल किया जायेगा।

The earnest money amount of Rs. 2,07,520/- (Rupees Two Lakhs Seven Thousand Five Hundred and Twenty, Only) received through online mode shall be refunded after submission of EMD equivalent amount as Security deposit i.e. Rs. 2,07,520/- (in the form of DD/Bank Guarantee of any Schedules bank but not Co-operative or Gramin bank).

Please deposit balance Rs. 5,41,638/- (Rupees Five Lakh Forty One Thousand Six Hundred and Thirty Eight, Only), (in the form of Bank Guarantee of any Schedules bank but not Co-operative or Gramin bank) towards security deposit within 10 days from the date of issue of this letter failing which the same will be deducted from your running bills as per Clause 1 (A) of GCC Page No. 16 of the tender document.

4. आपसे निवेदन हैं कि आप सभी श्रम कानूनों के तहत प्रावधानों जैसे कर्मचारी भविष्य निधि व विविध प्रावधान अधिनियम 1952, कर्मचारी राज्य बीमा (ईएसआई) अधिनियम, 1948, ठेका श्रमिक (रोजगार व सेवा की शर्त) अधिनियम, 1979 न्यूनतम मजदूरी अधिनियम, 1948, मजदूरी भूगतान अधिनियम, 1936, श्रमिक प्रतिपूर्ति अधिनियम, 1923 एवं अन्य संगत नियम व अधिनियम, अनुदेश इत्यादि जो समय समय पर जारी/प्रवर्तित किया जाते हैं का पालन करें।

You are requested to comply with provisions of all labour laws including the Employees Provident Fund & Miscellaneous Provisions Act, 1952, the Employees State Insurance (ESI) Act, 1948, the Contract Labour (Regulation & Abolition) Act, 1970, the Inter-State Migrant workmen (Regulation of employment & conditions of Service) Act, 1979, the Minimum Wages Act, 1948, the Payment of Wages Act, 1936, the Workmen's Compensation Act, 1923 and other relevant Act, Rules and Regulations, orders etc. issued from time to time.

5. आपसे यह भी अनुरोध है कि कार्य शुरू करने से पहले अनुबंध श्रम (आर एंड ए) अधिनियम, 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियम, 1971 के तहत श्रम लाइसेंस प्राप्त करें और कार्य पूरा होने तक लाइसेंस की वैधता बनाए रखें। आवश्यक कार्यवाई के लिए फॉर्म-III (प्रमुख नियोक्ता द्वारा प्रमाण पत्र का फॉर्म) संलग्न है।

You are also requested to obtain Labour License before start of work under the Contract Labour (R&A) Act, 1970 and the Contract Labour (Regulation and Abolition) Central Rules, 1971 and retain the validity of license till completion of work. Form-III (Form of Certificate by Principal Employer) is enclosed for necessary action.

6. आपको निर्देश दिया जाता है कि आप तुरंत सहायक प्रबंधक (अभि-सिविल), भाविप्रा, बिरसी विमानतल, गोंदिया से मिलें वह आपको साइट सौंपने की व्यवस्था करेंगे। कृपया नोट कर लें कि काम करने का अनुमत समय 02 (दो) महीना है जो कि इस पत्र के जारी करने के दसवें दिन से अथवा जिस दिन साइट हैण्ड ओवर की जाती है उनमें से जो भी पहले होगा उस दिन से कार्य के प्रारंभ की तिथि गिनी जाएगी।

You are also directed to contact Assistant Manager (Engg-Civil), AAI, Birsi Airport, Gondia who will arrange to handover the site to you. Please note that the time allowed for carrying out the work as entered in the tender is 02 (Two) Months and same shall be reckoned from the tenth day after issue of this letter or handing over of site whichever is earlier.

अनवरत शीट / Continuation sheet - 3-

7. इस अनुबंध के संबंध में आगे कोई भी पत्राचार सहा. महाप्रबंधक (अभि-सिविल), भाविप्रा, बिरसी हवाईअड्डा, गोंदिया के पते पर किया जाएगा ।

Any further correspondence in connection with the contract should normally be addressed to the **Asstt. General Manager (Engg-Civil)**, AAI, Birsi Airport, Gondia.

8. अनुबंध दस्तावेज जी.सी.सी. के पृष्ठ 47 में परिच्छेद – क्रम सं. 17 में उल्लिखित त्रुटि दायित्व अवधि 12 (बारह) महीने होगी ।

The defects liability period shall be 12 (Twelve) Months as mentioned in clause No.17 of GCC, page 47 of the contract document.

9. कृपया पावती भेजे तथा इस की प्रतिलिपि हस्ताक्षर कर के अधोहस्ताक्षरी को वापस भेजे ।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

10. हिन्दी और अंग्रेजी संस्करण के बिच विसंगती की स्थिती में अंग्रेजी संस्करण मान्य होगा ।

In case of discrepancy between Hindi & English version English version will prevail.


16/12/2024

(पंकज कंबले)

सहा महाप्रबंधक (अभि-सिविल),
भाविप्रा, बिरसी विमानतल, गोंदिया

Enclosed : 04 (Four) Page.

सलंगनक : 04 (चार) पृष्ठ ।


प्रतिलिपि / Copy to :-

आंतरिक वितरण :-

1. महाप्रबंधक (इंजी), भाविप्रा, पश्चिमी क्षेत्र, क्षेत्रिय मुख्यालय, पारसीवाडा, सहार रोड, विले पार्ले (पुर्व), मुंबई - 400099.
General Manager (Engg), AAI, Reginal Head Quarter, Western Region, Parsiwada, Sahar Road, Vile Parle (E), Mumbai - 400099.
2. संयुक्त महाप्रबंधक (सतर्कता), भाविप्रा, भाविप्रा, पश्चिम क्षेत्र, क्षेत्रिय मुख्यालय, पारसीवाडा, सहार रोड, विले पार्ले (पुर्व), मुंबई - 400099.
Jt. General Manager (Vigilance), AAI, Western Region, Reginal Head Quarter, Parsiwada, Sahar Road, Vile Parle (E), Mumbai - 400099.
3. विमानपत्तन निदेशक, भा.वि.प्रा, बिरसी विमानतल, गोंदिया - 441601.
Airport Director, AAI, Birsi Airport, Gondia - 441601.
4. उप. महाप्रबंधक (अभि-सि), भा.वि.प्रा, डॉ. बाबासाहेब अम्बेडकर अंतरराष्ट्रीय विमानतल, नागपुर-440005.
Deputy General Manager (Engg-Civil), AAI, DBAI Airport, Nagpur-440005.
5. सहा. महाप्रबंधक (वित्त), भा.वि.प्रा, डॉ. बाबासाहेब अम्बेडकर अंतरराष्ट्रीय विमानतल, नागपुर-440005.
Asstt. General Manager (Fin), AAI, DBAI Airport, Nagpur-440005.
6. सहायक प्रबंधक (अभि-सि), भा.वि.प्रा, बिरसी विमानतल, गोंदिया - 441601.
Assistant Manager (Engg-Civil), AAI, Birsi Airport, Gondia - 441601.
7. करारनामा कॉपी.
Agreement Copy.
8. सम्बंधित फाईल.
Concerned File.

बाह्य वितरण :-

1. लेबर कमिश्नर ऑफिस, 1st फ्लोवर, ब्लॉक-सी, सी.जी.ओ. कॉम्प्लेक्स, सेमिनरी हिल्स, नागपुर-440006.
Labour Commissioner Office, 1st Floor, Block-C, C.G.O Complex, Seminary Hills, Nagpur - 440006.
2. सहायक भविष्यनिधी कमिश्नर, भांडे प्लॉट, उमरेड रोड, रघुजी नगर, नागपुर - 440009.
Assistant Provident Fund Commissioner, Bhande Plot, Umred Road, Raghuji Nagar, Nagpur - 440009.
3. डी. सी. एस. टी., जी. एस. टी. भवन, सिव्हील लाईन, गोंदिया - 441601.
DCST, GST Bhawan, Civil Line, Gondia - 441601.
4. इनकम टॅक्स ऑफिसर, फुलचूर रोड, गोंदिया - 441601.
Income Tax Officer, Fulchur Road, Gondia - 441601.


16/11/2024

सहा महाप्रबंधक (अभि-सिविल),
भाविप्रा, बिरसी विमानतल, गोंदिया

Item Rate BoQ

Validate Print Help

Tender Inviting Authority: AGM (E-C), AAI, Birsir Airport, Gondia.

Name of Work: Repair works of Terminal Building & other buildings as per recommendation of structural audit at Birsir Airport, Gondia.

Contract No:

BNS INFRASTRUCTURE		PRICE SCHEDULE					(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)	
Sl. No.	Item Description	NUMBER #	TEXT #	NUMBER #	BASIC RATE In Figures To be entered by the Bidder (Excl. GST) Rs. P	NUMBER #	TOTAL AMOUNT (Excl. GST) in Rs. P	TEXT #
1	2	4	5	13	53	55		
1	Providing & fixing of Aluminium gutter made out of 3mm thick AA 1100 aluminium sheet. The size of the gutter will be 1000 mm wide and 450mm/500 mm deep with 50 mm flanges including providing circular openings of dowlake pipes.	50.00	Metre	3640.00	182000.00	INR One Lakh Eighty Two Thousand Only		
2	Dismantling & refixing of old Aluminium Composite Panel 4 mm thick at required location i/c removing of silicon sealant, aluminium section, stacking of all dismantled material in proper place, refixing, sealing the joint with silicon sealant, masking tape, providing and fixing Aluminium framework, wherever required including necessary screws, at all heights of Aluminium Composite panel fixed for side cladding of Roof as directed by engineer-in-charge all complete.(Cost of silicon sealant and Aluminium sections will be paid separately) (only surface area will be measured)	328.00	sqm	1480.00	485440.00	INR Four Lakh Eighty Five Thousand Four Hundred & Forty Only		
3	Filling the gap in between joints of ACP panels by providing structural silicon sealant over backer rod of approved quality to make the joints watertight and weather proof as per and direction of Engineer-in-charge complete.Upto 20 mm depth and 20 mm width.	1910.00	Metre	184.00	351440.00	INR Three Lakh Fifty One Thousand Four Hundred & Forty Only		
4	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitted and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion: Powder coated aluminium (minimum thickness of powder coating 50 micron)	220.00	Kg.	490.00	107800.00	INR One Lakh Seven Thousand Eight Hundred Only		

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excl. GST) Rs. P	TOTAL AMOUNT (Excl. GST) in Rs. P	TOTAL AMOUNT (Excl. GST) In Words	TEXT #	
1	2	4	5	13	53	55		
5	Providing and fixing double scaffolding system (cup lock type) on the exterior side of building/structure, upto 25 metre height, above ground level, including additional rows of scaffolding in stepped manner as per requirement of site, made with 40 mm dia M.S. tube, placed 1.5 metre centre to centre, horizontal & vertical tubes joint with cup & lock system with M.S. Tubes, M.S. tube challis, M.S. clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for execution of work of cleaning and/ or pointing and/ or applying chemical and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connecting with the building etc, wherever required, if feasible, for inspection of work at required locations with essential safety features for the workmen etc., complete as per directions and approval of Engineer-in-charge. Note:- (1) The elevational area of the scaffolding shall be measured for payment purpose. (2) The payment will be made once only for execution of all items for such works.	495.00	sqm	319.00	157905.00	INR One Lakh Fifty Seven Thousand Nine Hundred & Five Only		
6	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50mm (base metal of minimum 0.45mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	100.00	sqm	670.00	67000.00	INR Sixty Seven Thousand Only		
7	Providing and fixing pre-coated galvanised steel sheet roofing accessories of total coated thickness 0.50mm (base metal of minimum 0.45mm thickness with total coating thickness of 0.05mm) with Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Flashings/ Aprons. (Upto 600 mm)	20.00	Metre	508.00	10160.00	INR Ten Thousand One Hundred & Sixty Only		
8	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. On steel work	21573.59	sqm	139.00	2998729.01	INR Twenty Nine Lakh Ninety Eight Thousand Seven Hundred & Twenty Nine and Paise One Only		
9	Grading roof for water proofing treatment with : Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	200.00	cum	6700.00	1340000.00	INR Thirteen Lakh Forty Thousand Only		

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excl. GST) Rs. P	TOTAL AMOUNT (Excl. GST) in Rs. P	TOTAL AMOUNT (Excl. GST) In Words	TEXT #		
1	2 Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer 3 mm thick water proofing membrane, black finished reinforced with non-woven polyester matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/sqm by the same membrane manufacture of density at 25°C, 0.87-0.89 kg/ litre and viscosity 70-160 cps. Over the primer coat the layer of membrane shall be laid using Butane Torch and sealing all joints etc, and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 650/ 450N/ 5cm. Tear strength in longitudinal and transverse direction as 300/250N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D - 5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane : 3 mm thick	4	5	13	53	55			
10		1630.00	sqm	706.00	1150780.00	INR Eleven Lakh Fifty Thousand Seven Hundred & Eighty Only			
11	Making khurras 45x45 cm with average minimum thickness of 5 cm cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size) over P.V.C. sheet 1 m x1 m x 400 micron, finished with 12 mm cement plaster 1:3 (1 cement : 3 coarse sand) and a coat of neat cement, rounding the edges and making and finishing the outlet complete.	34.00	each	508.00	17272.00	INR Seventeen Thousand Two Hundred & Seventy Two Only			
12	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (including equivalent design mix)	163.00	cum	670.00	109210.00	INR One Lakh Nine Thousand Two Hundred & Ten Only			
13	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, Single socketed pipes, 160 mm diameter	220.00	Metre	706.00	155320.00	INR One Lakh Fifty Five Thousand Three Hundred & Twenty Only			
14	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, Coupler 160 mm	34.00	each	274.00	9316.00	INR Nine Thousand Three Hundred & Sixteen Only			
15	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, Bend 87.5° 160 mm	68.00	each	274.00	18632.00	INR Eighteen Thousand Six Hundred & Thirty Two Only			
16	Providing and fixing unplasticised -PVC pipe clips of approved design to unplasticised - PVC rain water pipes by means of 50x50x50 mm hard wood plugs, screwed with M.S. screws of required length, including cutting brick work and fixing in cement mortar 1:4 (1 cement : 4 coarse sand) and making good the wall etc. complete. 160 mm	102.00	each	76.00	7752.00	INR Seven Thousand Seven Hundred & Fifty Two Only			
17	Providing and fixing to the inlet mouth of rain water pipe PTMT (an Engineering Thermoplastic) grating square (Slit) 150 mm square with a height of 8 mm and weighing not less than 100 gms.	34.00	each	67.00	2278.00	INR Two Thousand Two Hundred & Seventy Eight Only			
18	Supplying truck mounted boom lift on hire basis with the working height upto 24 m including the fuel and operator.	26.00	day	8500.00	221000.00	INR Two Lakh Twenty One Thousand Only			
19	Providing and fixing bolts including nuts and washers complete.	150.00	Kg.	126.00	18900.00	INR Eighteen Thousand Nine Hundred Only			

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Excl. GST) Rs. P	TOTAL AMOUNT (Excl. GST) in Rs. P	TOTAL AMOUNT (Excl. GST) In Words	TEXT #
1	2	4	5	13	53	55	
20	Repair to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer-In-Charge.	150.00	sqm	409.00	61350.00	INR Sixty One Thousand Three Hundred & Fifty Only	
21	Providing and injecting approved grout in proportion recommended by the manufacturer into cracks/honey-comb area of concrete/masonry by suitable gun/pump at required pressure including cutting of nipples after curing etc. complete as per directions of Engineer-in-Charge. (The payment shall be made on the basis of actual weight of approved grout injected.)Stirrer mixed SBR Polymer (of approved make) modified Cement slurry made with Shrinkage Compensating Cement in concrete/RCC work.	100.00	Kg.	193.00	19300.00	INR Nineteen Thousand Three Hundred Only	
Total in Figures					7491584.01	INR Seventy Four Lakh Ninety One Thousand Five Hundred & Eighty Four and Paise One Only	
Quoted Rate in Words							
INR Seventy Four Lakh Ninety One Thousand Five Hundred & Eighty Four and Paise One Only							

Signature Not Verified

Digitally signed by PANKAJ GOVARDHAN KAMBLE

Date: 2025.06.16 12:03:18 IST

Location: eProcurement System for Central PSUs