



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA



संदर्भ सं/Ref.No. AAI/RJY/ENGG (E)/BHS/2024-25/45-

दिनांक/Date: 28.03.2025

सेवा में

To,

मेसर्स फॉक्स सोल्यूशंस प्राइवेट लिमिटेड,
प्लॉट नो। एम-9, अंबाद MIDC,
नाशिक, महाराष्ट्र - 422010.
ईमेल: aai.tenders@foxindia.net
मोबाइल: 9922428242

M/s. Fox Solutions Pvt.Ltd,
Plot No.M-9, Ambad MIDC,
Nashik, Maharashtra-422010
E-mail:aai.tenders@foxindia.net
Mobile No. 9922428242

- कार्य का नाम : राजमुंदरी हवाई अड्डे पर नए घरेलू टर्मिनल भवन का निर्माण और विविध कार्य
- सुब- हेड : राजमुंदरी हवाई अड्डे पर 28 चेक-इन काउंटरों और 4 अंतहीन स्लेट प्रकार फ्लैट आगमन कैरोसेल कन्वेयर बेल्ट के लिए गैर-इनलाइन प्रस्थान बीएचएस प्रणाली का एसआईटीसी
- Name of Work : Construction of New Domestic Terminal Building and Miscellaneous Works at Rajahmundry Airport.
- Sub-Head : SITC of Non-Inline Departure BHS System for 28 Nos. Check-in Counters and 4 Nos. Endless Slat Type Flat Arrival Carousal Conveyor Belts at Rajahmundry Airport
- संदर्भ : 1. टेंडर आईडी: 2024_AAI_213046_1.
2. आपकी वित्तीय बोली (लिफाफा-II) दिनांक 20.01.2025 को खोली गई और रिवर्स नीलामी 21.01.2025 को हुई।
- Reference : 1. Tender ID: 2024_AAI_213046_1.
2. Your financial bid (Envelope-II) opened on Dt.20.01.2025 and Reverse Auction on 21.01.2025.

महोदय/Dear Sir,

1. उपर्युक्त कार्य के लिए आपकी निविदा, आपके द्वारा उद्धृत मद दरों पर, भारतीय विमानपत्तन प्राधिकरण के अध्यक्ष की ओर से स्वीकार की जाती है, जिसकी कुल कीमत ₹8,99,99,070/- (आठ करोड़ निन्यानबे लाख निन्यानबे हजार सत्तर मात्र) प्लस जीएसटी @ 18% है, जो कि उचित लागत ₹8,57,39,838/- प्लस जीएसटी @ 18% से 4.97% अधिक है।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rates quoted by you totaling to ₹8,99,99,070/- (Rupees Eight Crore Ninety Nine Lakhs Ninety Nine Thousand and Seventy Only) Plus GST @ 18% which is 4.97% above the justified cost of ₹ 8,57,39,838/- pluse GST @ 18%.

2. उप महाप्रबंधक (इंजीनियरिंग-इलेक्ट), एएआई, राजमुंदरी एयरपोर्ट, कार्य के प्रभारी इंजीनियर होंगे। आपसे अनुरोध है कि आप उप महाप्रबंधक (इंजीनियरिंग-इलेक्ट), एएआई, राजमुंदरी एयरपोर्ट के कार्यालय में 07.04.2025 तक उपस्थित होकर अनुबंध पर हस्ताक्षर करें और उसे पूरा करें। अनुबंध अनुबंध 100/- रुपये के मूल्य के गैर-न्यायिक स्टाम्प पेपर पर निष्पादित किया जाएगा और स्टाम्प पेपर की लागत आपको वहन करनी होगी।

Contd...02.

पो.डी.वाकपैजण / P.D. WAKPAIJAN
उप महाप्रबंधक (अ.वि.)
Dy. General Manager (Engg.Elect)

विमानपत्तन प्राधिकरण का कार्यालय राजमुंदरी हवाई अड्डा, मधुरपूडी (पोस्ट), राजमुंदरी - 533 102
O/o The Airport Director, Rajahmundry Airport, Madhurapudi (Post), Rajahmundry - 533102
टेली फैक्स - Tele/FAX:0883 -2487852, दूरभाष /Phone:- 0883-2020111, Engg-E: 0883-2020171



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA



:: 02 ::

Dy. General Manager (Engg-Elect), AAI, Rajahmundry Airport, shall be the Engineer-In-Charge of the work. You are requested to attend the office of the Dy. General Manager (Engg-Elect), AAI, Rajahmundry Airport by 07.04.2025 to sign and complete the agreement. The contract agreement shall be executed on a Non-Judicial stamp paper of value Rs.100/- and the cost of the stamp paper shall be borne by you.

3. कृपया इस पत्र के जारी होने की तारीख से 10 दिनों के भीतर सुरक्षा जमा के रूप में रु. 89,99,907/- (केवल उन्नासी लाख उन्नासी हजार नौ सौ सात रुपये) जमा करें, अन्यथा, अनुबंध दस्तावेज़ की शर्त के अनुसार यह राशि आपके चालू बिलों से काट ली जाएगी।

Please deposit **Rs.89,99,907/-** (Rupees Eighty Nine Lakhs Ninety Nine Thousand Nine Hundred and Seven only) towards Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted from your running bills as per condition of contract document.

4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण कार्यकर्ताओं (श्रमिकों का विनियमन और सेवा की स्थिति) अधिनियम 1996, बिल्डिंग और अन्य निर्माण श्रमिक कल्याण सेस अधिनियम 1996 जैसा कि केन्द्रीय और राज्य सरकारों के नियमों में निर्दिष्ट है।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of workers and condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in rules of Central and State Governments.

5. आपको वरिष्ठ प्रबंधक (इंजीनियरिंग-इलेक्शन), एएआई, राजमुंदरी हवाई अड्डे से तुरंत संपर्क करने का भी निर्देश दिया जाता है, जो आपको साइट सौंपने की व्यवस्था करेगा।

You are also directed to contact Sr. Manager(Engg-Elect), AAI, Rajahmundry Airport immediately who will arrange to hand over the site to you.

6. कृपया ध्यान दें कि एसआईटीसी कार्य को पूरा करने के लिए अनुमत समय 06 (छह) महीने होगा और इसकी गणना 07.04.2025 से की जाएगी और संचालन के लिए 07 (सात) वर्ष और एआईसीएमसी के लिए 02 (दो) वर्षों की दोष देयता अवधि के बाद 05 (पांच) वर्ष की अवधि होगी।

Please note that the time allowed for carrying out the SITC work shall be 06 (Six) Months and same shall be reckoned from 07.04.2025 and 07 (Seven) Years for Operation and and 05 (Five) Years for AICMC after defects lliability period of 02 (Two) Years .

पो.डी.वाकपैजण / P.D. WAKPAIJAN
उप महाप्रबंधक (अ.वि.)
उप महाप्रबंधक (Engg-Elect)

Contd...03..

विमानपत्तन निर्देशक का कार्यालय राजमुंदरी हवाई अड्डा, मधुरपूडि (पोस्ट), राजमुंदरी - 533 102

O/o The Airport Director, Rajahmundry Airport, Madhurapudi (Post), Rajahmundry - 533102

टेली फैक्स - 0883-2487852, दूरभाष / Phone:- 0883-2020111, Engg-E: 0883-2020171



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA



:: 03 ::

7. डीएसआईटीसी भाग के पूरा होने के बाद व्यापक, परिचालन और रखरखाव कार्य के लिए पूरक अनुबंध निष्पादित किया जाएगा।
Supplementary Agreement will be executed for the part of Comprehensive, Operation and Maintenance Work after completion of DSITC part.
8. अनुबंध के संबंध में कोई भी आगे का पत्राचार सामान्यतः प्रभारी अभियंता को संबोधित किया जाना चाहिए।
Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-Charge.
9. कृपया रसीद स्वीकार करें और इसके साथ संलग्न इस पत्र की डुप्लिकेट प्रति हस्ताक्षर करने के बाद स्वीकृति के प्रतीक के रूप में अधोहस्ताक्षरी को लौटा दें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

भवदीय/Yours Faithfully,

अनुलग्नक/Encl: Schedule of Quantities.



(पीवाकपैजण.डी. / P. D.Wakpaijan)
उप महाप्रबंधक (अभि-वि)/ Dy. General Manager (Engg-E)
भा वि प्रा, राजमंड्री हवाई अड्डा/AAI, Rajahmundry Airport
कृते तथा ओर से अध्यक्ष, /For & On Behalf of The Chairman
भारतीय विमानपत्तन प्राधिकरण/Airports Authority of India.

पो.डी.वाकपैजण / P.D. WAKPAIJAN
उप महाप्रबंधक (अ.वि.)
Dy. General Manager (Engg-E)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
राजमंड्री हवाई अड्डा/Rajahmundry Airport
राजमंड्री/RAJAHMUNDRI-533 102

Note: In case of discrepancy in between Hindi and English. English version shall prevail.

SCHEDULE OF QUANTITIES

Name of Work: Construction of New Domestic Terminal Building and Miscellaneous Works at Rajahmundry Airport,

Sub-Head: SITC of Non-Inline Departure BHS System for 28 Nos. Check-In Counters and 4 Nos. Endless Slat type Flat Arrival Carousal Conveyor Belts at Rajahmundry Airport

S. No.	Description of Items	Qty.	Unit	Rate (₹)	Amount(₹)
A	SH:I SITC OF PASSENGER BAGGAGE HANDLING SYSTEM				
1	SUPPLY OF DEPARTURE AND ARRIVAL CONVEYOR SYSTEM Design, Manufacturing and Supply of following equipments for Departure and Arrival conveyor system as per Technical Specifications and conveyor layout drawings, including supply of required length of power and control cables from control panel to various drive units including all item/accessories and steel structure as per site requirement complete in all respect for successful commissioning of following system :				
1.01	Check-in conveyor system in two sections comprising of Weighing & Labeling and Dispatch conveyor of minimum length 1200mm with minimum useful width of 650mm between side walls along with drive unit for each conveyor section with display range 0- 200 Kg with accuracy of + 0.05% and two displays (Each for Passenger and Airlines staff) including load sensor and toppling devices etc. One set comprises of 01 no. weighing & labeling conveyor, 01 no. dispatch conveyor and 02 nos. weighing display etc., complete as required as per technical specifications. Note - Check-in conveyors should be withdrawal type with Drum motors.	28	Set	585515.00	16394420.00
1.02	Take away/Collector conveyor with inner useful belt width of minimum 1000mm between side walls along with drive unit for collecting baggage from dispatch conveyor side walls etc., complete as required as per technical specifications.	57	Mtrs	65680.00	3743760.00
1.03	Transport Conveyor (Straight/declined/inclined/induction/T-Junction conveyor, etc.) along with drive unit for each section to match with x-ray machine level with minimum width of 1000mm between side walls etc., complete as required as per technical specifications.	124	Mtrs	55360.00	6864640.00
1.04	Queuing / Metering Conveyor with minimum 1500 mm length and minimum nominal width of 1000mm between side walls along with drive units etc., complete as required as per technical specifications.	7	Nos.	288705.00	2020935.00
1.05	Over Height Limiter made up of stainless steel with photo sensor to detect the over height of baggage including proper support arrangement and fault reset button etc., complete as required as per technical specifications.	2	Nos.	23445.00	46890.00
1.06	Draught Curtains in the openings wherever the conveyor pass through the walls, consisting of flexible overlapping slats of black belt strips as per site requirement etc., complete as required as per technical specifications.	12	Nos.	14067.00	168804.00
1.07	Motorized Security Shutter as per site requirement in the wall opening (wall between passenger and non-passenger area) including limit switches, wiring and integration with control panel etc. for arrival and departure etc., complete as required as per technical specifications.	12	Nos.	148485.00	1781820.00
1.08	Gravity Roller Table constructed from heavy duty mild steel box section formed from 50 mm diameter heavy-duty rollers at an appropriate pitch to suit the intended duty made out of utility grade stainless steel including support etc., complete as required as per technical specifications.	4	Mtrs	42201.00	168804.00



S. No.	Description of Items	Qty.	Unit	Rate (₹)	Amount(₹)
1.09	Heavy duty race track slat type flat arrival baggage re-claim carousels of 45 mtrs length with minimum useful width 1000mm between side walls, having black color slats made of antistatic, flame retardant molded rubber/PVC/ABS material of minimum 5mm thickness, slope angle as given in technical specification and drawing, speed of 24-30 meters /min etc., complete as required as per technical specifications.	4	Nos.	3282300.00	13129200.00
1.10	PLC based control panel for Departure System incorporating switch gears, protection devices, starters with all sensors and other components suitable for operation & safety of complete departure conveyor system including check-in conveyor i/c supply of all associated materials like power, control cables etc along with UPS.(Divided in minimum zones as mentioned in Technical Specifications) etc., complete as required as per technical specifications.	1	Job	2813400.00	2813400.00
1.11	PLC based control panel for Arrival System incorporating switch gears, protection devices, starters with all sensors and other components suitable for operation & safety of complete arrival conveyor system i/c supply of all associated materials like power, control cables etc along with UPS.(Divided in minimum zones as mentioned in Technical Specifications) etc., complete as required as per technical specifications.	4	Job	1250400.00	5001600.00
2	INSTALLATION, TESTING & COMMISSIONING (ITC) OF BAGGAGE CONVEYOR SYSTEM Installation, Testing and Commissioning (ITC) of following items for Departure & Arrival Conveyor System including minor civil works such as grouting of structures and making good the same including ITC of control panel along with necessary outgoing cables/wire, earthing for drive unit motor, limit switches, Emergency stop push buttons, indications, annunciation, IT network and control cables, power cabling etc. complete as required as per Technical specifications.				
2.01	Check-in conveyor system in two sections comprising of Weighing+Labeling and Dispatch conveyor	28	Set	25399.00	711172.00
2.02	Take away/collector conveyor	57	Mtr.	9769.00	556833.00
2.03	Transport Conveyor ((Straight/declined/inclined/induction/T-Junction conveyor, etc.)	124	Mtr.	7815.00	969060.00
2.04	Queuing / metering Conveyors	7	Nos.	7815.00	54705.00
2.05	Over Height limiter	2	Nos.	3126.00	6252.00
2.06	Draught curtains	12	Nos.	1719.00	20628.00
2.07	Motorized Security Shutter	12	Nos.	7815.00	93780.00
2.08	Gravity Roller Table	4	Nos.	5471.00	21884.00
2.09	Heavy duty race track slat type flat arrival baggage claim carousels of 45 mtrs length	4	Nos.	175838.00	703352.00
2.10	PLC based control panel for Departure System	1	Job	625200.00	625200.00
2.11	PLC based control panel for Arrival System	4	Jobs	468900.00	1875600.00



S. No.	Description of Items	Qty.	Unit	Rate (₹)	Amount(₹)
B	SH - II : Operation :				
3	Operation of the Departure & Arrival Baggage Handling System as provided in this scope including all electrical / mechanical, safety, control as per special conditions, technical specifications immediately after the commissioning & handing over of the system(The Minimum manpower shall be deployed is 01 No. Highly skilled & 07 Nos. Skilled person for 02 shift operation, 3 persons per shift).				
3.01	1st Year During DLP	1	Year	2527371.00	2527371.00
3.02	2nd Year During DLP	1	Year	2704287.00	2704287.00
3.03	3rd Year After DLP	1	Year	2893587.00	2893587.00
3.04	4th Year After DLP	1	Year	3096138.00	3096138.00
3.05	5th Year After DLP	1	Year	3312868.00	3312868.00
3.06	6th Year After DLP	1	Year	3544769.00	3544769.00
3.07	7th Year After DLP	1	Year	3792902.00	3792902.00
C	SH - III : AICMC :				
4	All inclusive comprehensive maintenance contract (AICMC) of Complete Baggage Handling System (1 No. of Departure conveyor system with 28 check-in counters and 4 Nos. of Flat type Slat Arrival Conveyor System) including all electrical / mechanical Equip, safety control installed under this contract as per special condition of contract and technical specification immediately after the commissioning & handing over of the system. (AICMC during DLP is covered in the SITC of conveyors installed in this scope. Bidder shall quote accordingly).				
4.01	1st Year After DLP	1	Year	1783375.00	1783375.00
4.02	2nd Year After DLP	1	Year	1916772.00	1916772.00
4.03	3rd Year After DLP	1	Year	2060146.00	2060146.00
4.04	4th Year After DLP	1	Year	2214245.00	2214245.00
4.05	5th Year After DLP	1	Year	2379871.00	2379871.00

Total Rs.: 89999070.00

GST @18%: 16199832.60

Grand Total Rs.: 106198902.60


Say Rs. 106198903.00

Rupees Ten Crore Sixty One Lakh Ninety Eight Thousand Nine Hundred and Three Only

Signature Not Verified

Digitally signed by RAVI KUMAR VANKUDOTHU
Date: 2025.04.08 15:48:11 IST
Location: eProcurement System for Central PSUs




Dy.General Manager (Engg-E)
AAI/Rajahmundry Airport

पो.डी.वाकपैजण / P.D. WAKPAIJAN
उप महाप्रबंधक (अ.वि.)
Dy. General Manager (Engg.Elect)
भारतीय विमानपत्तन प्रधिकरण
Airports Authority of India
राजमंड्री हवाई अड्डा/Rajahmundry
राजमंड्री/RAJAHMUNDRY-533