



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

मद्रुरै हवाई अड्डा, मद्रुरै - 625 022.

MADURAI AIRPORT, MADURAI - 625 022.

(ISO 9001 - 2015 & 14001 - 2015 प्रमाणित / CERTIFIED)

AAI/MDU/CIVIL/707(1)/2025/19828

Date: 08.01.2025

सेवा मे/To,

M/S.J.D. CONSTRUCTIONS,

D.No. 50-37-13, TPT Colony,

Seethammadhara,

Visakhapatnam-530013.

By Email/Speed Post

Name of work: Renovation of Toilets of NITB at Madurai Airport. SH: Civil Works.

संदर्भ Ref. : 1) Your e-tender (Cover-II Financial bid) opened on: 15.05.2024.

2) Tender ID: 2024_AAI_214259_1.

श्रीमान / Dear Sir,

1. Your e-Tender for the work mentioned above is hereby accepted on behalf of Chairman, AAI, at the item rates quoted by you totaling to **Rs.1,92,70,072.58** (Rupees One Crore Ninety Two Lakh Seventy Thousand Seventy Two and Fifty Eight Paise Only) (exclusive of GST) which is 25.29% below the estimated cost put to tender **Rs.2,57,94,758.00** (exclusive of GST).
2. Senior Manager (E-C), AAI, Madurai Airport, Madurai shall be the Engineer-in-Charge of the work. You are requested to attend the office of Senior Manager (E-C), AAI, Madurai Airport, Madurai by **23.01.2025** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper value of **Rs.100.00 (Rupees One Hundred Only)** and the cost of the stamp paper shall be borne by you.
3. As per Clause No.1A on page No: 75 of tender document, please deposit Rs.19,27,007.00 (Rupees Nineteen Lakh Twenty Seven Thousand Seven Only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted from your running bill as per GCC Clause 1A at page No: 75 of tender document.
4. You are requested to comply with the provisions of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) central rules 1971,

विमानपत्तन निदेशक का कार्यालय, मद्रुरै हवाई अड्डा, मद्रुरै - 625 022.

O/o The Airport Director, Madurai Airport, Madurai - 625 022.

दूरभाष / Tel : 0452-2690717 / फैक्स / Fax : 0452 - 2690151, 2690305 E-mail : apdmadurai@aai.aero



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

मदुरै हवाई अड्डा, मदुरै - 625 022.

MADURAI AIRPORT, MADURAI - 625 022.

(ISO 9001 - 2015 & 14001 - 2015 प्रमाणित / CERTIFIED)

Child Labour (Prohibition & Regulation) Act 1986, Construction workers (Regulation of Employment and Conditions of Service) Act 1996, Building and other Construction workers welfare cess Act 1996 as specified in clause-19 on Page no.123 of tender and rules of central and state Govt.

5. You are also requested to contact Manager (Engg-Civil), AAI, Madurai Airport, Madurai immediately who will arrange to handover the site to you.
6. Please note that time allowed for carrying out the work shall be **09 (Nine) Months** and same shall be reckoned from 10th day after issue of this letter.
7. Any future correspondence in connection with the contract should normally be addressed to the Engineer-in-Charge.
8. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Encl.: Price Schedule

Yours faithfully,

Senior Manager (Engg-Civil),
Engineer-In-Charge
AAI, Madurai Airport,

For and on behalf of the Chairman, AAI.

पि. येंडु कंडालु
वरिष्ठ प्रबंधक (ई-सी)
P. YEDU KONDALU
Sr. Manager (E-C)
AAI / Madurai Airport

Copy to:

Asst.Labour Commissioner, No:5 Lady Doak college road, Chinnachokkikulam, Madurai.

FORM-III

(Under rule 21(2) of the Contract Labour (Regulation and Abolition) Central Rules, 1971;

And


Rule 7(3) of the Inter-State Migrant Workmen (Regulation of Employment and Conditions of Service Central Rules, 1980)

Form of Certificate by Principal Employer

Certified that:

1. I have engaged the applicant **M/S.J.D. CONSTRUCTIONS**, D.No. 50-37-13, TPT Colony, Seethammadhara, Visakhapatnam-530013 as a contractor in my establishment for the work **“Renovation of Toilets of NITB at Madurai Airport. SH: Civil Works”** to be carried out from **18.01.2025 to 17.10.2025**.
2. I undertake to be bound by all the provisions of the Contract Labour (Regulation and Abolition) Act, 1970 (37 of 1970) and the Contract Labour (Regulation and Abolition) Central Rules, 1971* / the Inter-State Migrant Workmen (Regulation of Employment and Conditions of Service) Act, 1979 (30 of 1979) and the Inter-State Migrant Workmen (Regulation of Employment and Conditions of Service) Central Rules, 1980* in so far as the provisions are applicable to me in respect of the employment of contract Labour/inter-state migrant workmen* by the applicant in my establishment.
3. The engagement of contract Labour in the said work is not prohibited under sub section (1) of section 10 of the Contract Labour (Regulation and Abolition) Act, 1970 (37 of 1970) or an award or a settlement*.

Place : Madurai
Date : 08.01.2025


Signature of Principal Employer
SM(Engg-Civil),
Engineer-In-Charge
Airports Authority of India,
Madurai Airport,
Madurai - 625022.
(Reg No.CLRA/RLCMADURAI/2024/125177/R-20)

पि. येडु कोंडालु
वरिष्ठ प्रबंधक(ई-सी)
P. YEDU KONDALU
Senior (E.C)
At Madurai Airport

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Senior Manager (Engg-Civil), Airports Authority of India, Madurai Airport, Madurai – 625 022

Name of Work: Renovation of Toilets of NITB at Madurai Airport.SH: Civil Works.

Contract No: AAI/MDU/CIVIL/707(1)/2024/

Name of the
Bidder/
Bidding Firm
/ Company :

J.D.CONSTRUCTIONS

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender.
Bidders are allowed to enter the Bidder Name and Values Only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Rate (Excluding GST) Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	3	4	5	6	7
1	Dismantling of toilets Wooden/FRP/WPC doors with frame and shutter without any damage including all fittings, holdfasts etc. and stacking of serviceable materials and disposal of unserviceable material as per the direction of EIC or his representative within the airport premises. Of area 3 sq. metres and below.	88.00	each	698.16	61438.08	INR Sixty One Thousand Four Hundred & Thirty Eight and Paise Eight Only
2	Dismantling of toilet area false ceiling (Aluminium/ Gypsum/metal or any other material etc.) and doors of janitor room (Aluminium/metal/Pvc or any other material etc.) including aluminium frame for supports, fittings etc and handed over or stacking of serviceable materials as per the direction of EIC or his representative within the airport premises and disposal of unserviceable surplus material as place shown by EIC within the airport premises.	670.00	Sqm	221.08	148123.60	INR One Lakh Forty Eight Thousand One Hundred & Twenty Three and Paise Sixty Only
3	Dismantling of toilet wash basin mirrors without any damage and stacking of serviceable materials and disposal of unserviceable material as per the direction of EIC or his representative within the airport premises.	180.00	Sqm	209.45	37701.00	INR Thirty Seven Thousand Seven Hundred & One Only
4	Demolishing R.C.C. work manually/ by mechanical means and stacking of serviceable materials and disposal of unserviceable material as per the direction of EIC or his representative within the airport premises.	10.00	Cum	1745.40	17454.00	INR Seventeen Thousand Four Hundred & Fifty Four Only
5	Demolishing brick work in cement mortar manually/ by mechanical means and stacking of serviceable materials and disposal of unserviceable material as per the direction of EIC or his representative within the airport premises.	80.00	Cum	1687.22	134977.60	INR One Lakh Thirty Four Thousand Nine Hundred & Seventy Seven and Paise Sixty Only

8/1/25
P. YEDU KONDALU
Sr. Manager (E-C)
Madurai Airport

Sl. No.	Item Description	Quantity	Units	Rate (Excluding GST) Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	3	4	5	6	7
6	Demolishing cement concrete manually/ by mechanical means and stacking of serviceable materials and disposal of unserviceable material as per the direction of EIC or his representative within the airport premises.	30.00	Cum	1629.04	48871.20	INR Forty Eight Thousand Eight Hundred & Seventy One and Paise Twenty Only
7	Demolishing tile work in floors/walls with laid in cement mortar or chemical adhesive manually/ by mechanical means and stacking of serviceable materials and disposal of unserviceable material as per the direction of EIC or his representative within the airport premises. Thickness of tiles: 10 mm to 25 mm	3,830.00	Sqm	174.54	668488.20	INR Six Lakh Sixty Eight Thousand Four Hundred & Eighty Eight and Paise Twenty Only
8	Demolishing granite work in table mount wash basin with laid in cement mortar or chemical adhesive manually/ by mechanical means and stacking of serviceable materials and disposal of unserviceable material as per the direction of EIC or his representative within the airport premises. Thickness of granite: 16mm to 30mm	60.00	Sqm	314.17	18850.20	INR Eighteen Thousand Eight Hundred & Fifty and Paise Twenty Only
9	Dismantling of toilet wash basin with faucet, fittings, bottle trap and waste couplings without any damage and stacking of serviceable materials and disposal of unserviceable material as per the direction of EIC or his representative within the airport premises.	101.00	each	1163.60	117523.60	INR One Lakh Seventeen Thousand Five Hundred & Twenty Three and Paise Sixty Only
10	Dismantling of EWC with water storage tank and all associated fittings like health faucet, long body bib cock, tap, bottle trap, tissue holder, towel rod etc without any damage and stacking of serviceable materials and disposal of unserviceable material as per the direction of EIC or his representative within the airport premises.	80.00	each	1629.04	130323.20	INR One Lakh Thirty Thousand Three Hundred & Twenty Three and Paise Twenty Only
11	Dismantling of IWC with water storage tank and all associated fittings like long body bib cock, tap, bottle trap, tissue holder, towel rod etc without any damage and stacking of serviceable materials and disposal of unserviceable material as per the direction of EIC or his representative within the airport premises.	20.00	each	1396.32	27926.40	INR Twenty Seven Thousand Nine Hundred & Twenty Six and Paise Forty Only
12	Dismantling of SS dustbin, soap dispenser mounted on wall and and stacking of serviceable materials and disposal of unserviceable material as per the direction of EIC or his representative within the airport premises. Mode of measurement: Gents toilet, ladies toilet, PH toilet - 3nos)	57.00	each	581.80	33162.60	INR Thirty Three Thousand One Hundred & Sixty Two and Paise Sixty Only
13	Dismantling of urinal basin with wall mounted automatic concealed urinal sensor, urinal partition without any damage including all fittings, holdfasts etc. and stacking of serviceable materials and disposal of unserviceable material as per the direction of EIC or his representative within the airport premises.	40.00	each	1861.76	74470.40	INR Seventy Four Thousand Four Hundred & Seventy and Paise Forty Only
14	Refixing of urinal basin with wall mounted automatic concealed urinal sensor, urinal partition including all fittings, holdfasts etc. and as per the direction of EIC.	40.00	each	1861.76	74470.40	INR Seventy Four Thousand Four Hundred & Seventy and Paise Forty Only
15	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	30.00	Cum	10239.68	307190.40	INR Three Lakh Seven Thousand One Hundred & Ninety and Paise Forty Only

8/1/25 दि. येदु कोंडालु
 P. YEDU KONDALU
 प्रबन्धक (ई-सी)

Sl. No.	Item Description	Quantity	Units	Rate (Excluding GST) Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	3	4	5	6	7
16	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform	60.00	Sqm	558.53	33511.80	INR Thirty Three Thousand Five Hundred & Eleven and Paise Eighty Only
17	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering in all toilets: 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	30.00	Cum	9308.80	279264.00	INR Two Lakh Seventy Nine Thousand Two Hundred & Sixty Four Only
18	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete in all toilets. Thermo-Mechanically Treated bars of grade Fe-500D or more.	2,150.00	Kg	102.40	220160.00	INR Two Lakh Twenty Thousand One Hundred & Sixty Only
19	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within airport premises. All kind of soil	30.00	Cum	232.72	6981.60	INR Six Thousand Nine Hundred & Eighty One and Paise Sixty Only
20	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall - 25 mm nominal dia Pipes	30.00	Meter	488.71	14661.30	INR Fourteen Thousand Six Hundred & Sixty One and Paise Thirty Only
21	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall - 40 mm nominal dia Pipes	300.00	Meter	814.52	244356.00	INR Two Lakh Forty Four Thousand Three Hundred & Fifty Six Only
22	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 25 mm nominal dia Pipes	420.00	Meter	639.98	268791.60	INR Two Lakh Sixty Eight Thousand Seven Hundred & Ninety One and Paise Sixty Only
23	Providing and laying PVC in sewer line, vent pipe conforming to IS. Joining as per standards as directed by EIC with required adhesive special etc. This includes jointing of pipes & fittings with one step PVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.. 110mm dia (working pressure 10kg/sqcm)	350.00	Meter	930.88	325808.00	INR Three Lakh Twenty Five Thousand Eight Hundred & Eight Only
24	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	10.00	Cum	5352.56	53525.60	INR Fifty Three Thousand Five Hundred & Twenty Five and Paise Sixty Only

Handwritten signature and initials
 3m E-4

Sl. No.	Item Description	Quantity	Units	Rate (Excluding GST) Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	3	4	5	6	7
25	CEMENT PLASTER (IN COARSE SAND) 12 mm cement plaster of mix : 1:4 (1 cement: 4 coarse sand)	3,390.00	Sqm	186.18	631150.20	INR Six Lakh Thirty One Thousand One Hundred & Fifty and Paise Twenty Only
26	Supplying and filling in sunken portion of W.C and bath room with aerated bricks conforming to IS:2185 (Dry Density 550 Kg/cum to 650 Kg/cum) under floors including placing, dressing and filling voids with M-sand complete as per the direction of EIC.	50.00	Cum	8145.20	407260.00	INR Four Lakh Seven Thousand Two Hundred & Sixty Only
27	Providing and applying of water proofing treatment at NITB toilets as per the following specification *Surface preparation by mechanical means to remove laitance, loose particles which may hinder bond strength of the waterproofing system *All cracks shall be chased to a 6mm x 6mm groove and filled using NON SHRINKAGE GROUT *Coving at all the junctions to be done for a size of 50mm X 50mm with Cement Mortar prepared by mixing 50 kg cement + 150kg Sand + Conplast WL at 125ml + Water required for mortar consistency *Sunken slab to be primed with Nitoproof AW Primer and allowed to dry.*Sunken slab to be coated with 2coats of acrylic fibre reinforced UV stable coating Brushbond Roofguard as per manufacture specification and complete in all respect as per the direction of Engineer-in-Charge.	420.00	Sqm	1163.60	488712.00	INR Four Lakh Eighty Eight Thousand Seven Hundred & Twelve Only
28	Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily. Glazed Vitrified tiles Matt/Antiskid finish of size. Size of Tile 600 x 600 mm. Base price considered: 900/sqm. Price adjustment (plus or minus) shall be done based on tile selection by EIC with reference to base price.	520.00	Sqm	1396.32	726086.40	INR Seven Lakh Twenty Six Thousand & Eighty Six and Paise Forty Only
29	Providing and laying Vitrified tiles with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 to 10mm thickness, including grouting of joints. Size of Tile 600 x 600 mm. Base price considered: 900/sqm. Price adjustment (plus or minus) shall be done based on tile selection by EIC with reference to base price.	2,870.00	Sqm	1396.32	4007438.40	INR Forty Lakh Seven Thousand Four Hundred & Thirty Eight and Paise Forty Only
30	Providing and laying Polished Granite flooring /wall in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 to 10mm thickness, including grouting of joints.pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge.Base price considered: 1800/sqm. Price adjustment (plus or minus) shall be done based on tile selection by EIC with reference to base price.	100.00	Sqm	3025.36	302536.00	INR Three Lakh Two Thousand Five Hundred & Thirty Six Only

Handwritten signature and initials
SM(E-C)

Sl. No.	Item Description	Quantity	Units	Rate (Excluding GST) Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	3	4	5	6	7
31	Providing and fixing wall mount type water closet (European Type) of make "KOHLER" (Code K 26998IN-0) or equivalent with seat cover, suitable concealed full frame inwall tank, plastic outlet connector including all fittings nuts, bolts, frames, wall plates and gasket etc including making connection with the existing drainage system, complete in all respect as per directions of Engineer-in-Charge.. Base price considered: Rs. 20000/No. Price adjustment (plus or minus) shall be done based on fitting selection by EIC with reference to base price.	80.00	each	23853.80	1908304.00	INR Nineteen Lakh Eight Thousand Three Hundred & Four Only
32	Providing and fixing KOHLER make flush control cover (Code: K-75890IN-M-CP) or equivalent for EWC with necessary fittings complete as per the direction of EIC. Base price considered: Rs. 2200/No. Price adjustment (plus or minus) shall be done based on selection by EIC with reference to base price.	80.00	each	2676.28	214102.40	INR Two Lakh Fourteen Thousand One Hundred & Two and Paise Forty Only
33	Providing and fixing KOHLER make health faucet with side spray, metal hose in polished chrome (Code: K12927IN-CP) or equivalent complete as per the direction of EIC.. Base price considered: Rs. 3100/No. Price adjustment (plus or minus) shall be done based on selection by EIC with reference to base price.	80.00	each	3723.52	297881.60	INR Two Lakh Ninety Seven Thousand Eight Hundred & Eighty One and Paise Sixty Only
34	Providing and fixing Tissue holder in polished chrome (Code: 5632IN) or equivalent complete as per the direction of EIC. Base price considered: Rs. 1300/No. Price adjustment (plus or minus) shall be done based on selection by EIC with reference to base price.	101.00	each	1629.04	164533.04	INR One Lakh Sixty Four Thousand Five Hundred & Thirty Three and Paise Four Only
35	Providing and fixing Bottle trap of made "KOHLER" (code 7314IN-CP) or equivalent all complete as per the directions of EIC. Base price considered: 2000/No. Price adjustment (plus or minus) shall be done based on tile selection by EIC with reference to base price.	101.00	each	2443.56	246799.56	INR Two Lakh Forty Six Thousand Seven Hundred & Ninety Nine and Paise Fifty Six Only
36	Providing and fixing angle valve in polished chrome (Code: 25431IN-4-CP) or equivalent complete as per the direction of EIC.. Base price considered: Rs. 1200/No. Price adjustment (plus or minus) shall be done based on selection by EIC with reference to base price.	202.00	each	1512.68	305561.36	INR Three Lakh Five Thousand Five Hundred & Sixty One and Paise Thirty Six Only
37	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests. Base price considered: Rs. 3300/No. Price adjustment (plus or minus) shall be done based on selection by EIC with reference to base price.	20.00	each	3956.24	79124.80	INR Seventy Nine Thousand One Hundred & Twenty Four and Paise Eighty Only
38	Providing and fixing 1way bibcock in polished chrome (Code: K-16093IN-4-CP) or equivalent complete as per the direction of EIC.. Base price considered: Rs. 2800/No. Price adjustment (plus or minus) shall be done based on selection by EIC with reference to base price.	101.00	each	3374.44	340818.44	INR Three Lakh Forty Thousand Eight Hundred & Eighteen and Paise Forty Four Only
39	Providing and fixing 2way bib cock in polished chrome (Code: K-16093IN-4-CP) or equivalent complete as per the direction of EIC.. Base price considered: Rs. 2400/No. Price adjustment (plus or minus) shall be done based on selection by EIC with reference to base price.	20.00	each	2676.28	53525.60	INR Fifty Three Thousand Five Hundred & Twenty Five and Paise Sixty Only

for dilution
in (E-g)

Sl. No.	Item Description	Quantity	Units	Rate (Excluding GST) Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	3	4	5	6	7
40	Providing and fixing of soap dispenser of 300 ml capacity with suitable stand as per the direction of EIC.. Base price considered: Rs. 1200/No. Price adjustment (plus or minus) shall be done based on selection by EIC with reference to base price.	50.00	each	1454.50	72725.00	INR Seventy Two Thousand Seven Hundred & Twenty Five Only
41	Providing and fixing 6L dustpin in satinless steel (Code: K-17531T-ST) or equivalent complete as per the direction of EIC.. Base price considered: Rs. 2300/No. Price adjustment (plus or minus) shall be done based on selection by EIC with reference to base price.	101.00	each	2792.64	282056.64	INR Two Lakh Eighty Two Thousand & Fifty Six and Paise Sixty Four Only
42	Providing and fixing S.S floor gratings of size 150 mm X 150 mm with garting opening size 100 mm dia as per the directions of EIC.	252.00	each	302.54	76240.08	INR Seventy Six Thousand Two Hundred & Forty and Paise Eight Only
43	Providing and fixing 6mm thick beveled edge mirror of make SAINT GOBAIN or equivalent with 6 mm thick plywood backing fixed to walls with stainless steel studs of adequate size etc complete as approved by the EIC.	180.00	Sqm	2210.84	397951.20	INR Three Lakh Ninety Seven Thousand Nine Hundred & Fifty One and Paise Twenty Only
44	Providing of false ceiling at all heights with integral MW AL METAL PLAIN TEGULAR false ceiling tiles of Size 595mmx595mmx0.70mm ,The tile shall be electrostatically polyester powder coated using RoHS compliant powder having coating thickness ranging from 60-80 microns ,to be laid in true horizontal level suspended on inter-locking metal T-Grid of hot dipped galvanised iron section of 0.33mmthick (galvanized @ 120 grams per sqm including both sides)comprising of main-T runners of size 15x32mm of length 3600 mm,cross - T of size 15x32mm of length 1200 mm and secondaryintermediate cross-T of size 12x32mm of length 600mm to formgrid module of size 600 x 600 mm, suspended from ceiling using galvanised consisting of accessories manufactured and supplied by Knauf consisting of M6 Anchor Fasteners with hanger hole, pre-Straightened Hanger wire of dia – 2.5 mm of 1.80 m length having a tensile strength of 344-413 MPa and a minimum loading strength of 110 kgs. Additionally, adjustable hook clips made of 0.7mm thick Grade 1 C55 galvanized spring steel of dimension 100 x 20mm and 4 mm aquiline wire to be used for level adjustment during installation purpose in main runners , fixed with Glavanised iron perimeter wall angle or size 24x24x0.33 mm of length 3600 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450mm center to center and 40 mm long dry wall S.S screws. The workshall be carried out as per specifications, drawing and as per directions of the Engineer-in Charge. With MW AL METAL PLAIN MICROLOOK EDGE 600X600X0.70MM	590.00	Sqm	1396.32	823828.80	INR Eight Lakh Twenty Three Thousand Eight Hundred & Twenty Eight and Paise Eighty Only
45	Providing and fixing of restroom cubicles of 12mm thick laminated HPL boards stylam or equivalent make, door size suitable as per site condition with all accessries of SS 304 grade like gravity hinges, coat hook with door stopper, door knob, SS privacy tumb turn occupancy indicator , SS adjustable leg, SS screws, wall plugs, Noise Deafening tapes for grooves in doors & Pilasters etc., all complete as per the directions of EIC.	310.00	Sqm	5119.84	1587150.40	INR Fifteen Lakh Eighty Seven Thousand One Hundred & Fifty and Paise Forty Only

Signature
Smt (E.C)

Sl. No.	Item Description	Quantity	Units	Rate (Excluding GST) Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	3	4	5	6	7
46	Providing and fixing Fiber Glass Reinforced plastic (FRP) Door Frames of cross-section 90 mm x 45 mm having single rebate of 32 mm x 15 mm to receive shutter of 30 mm thickness. The laminate shall be moulded with fire resistant grade unsaturated polyester resin and chopped mat. Door frame laminate shall be 2mm thick and shall be filled with suitable wooden block in all the three legs. The frame shall be covered with fiber glass from all sides. M.S. stay shall be provided at the bottom to steady the frame.	70.00	Metre	570.16	39911.20	INR Thirty Nine Thousand Nine Hundred & Eleven and Paise Twenty Only
47	Providing and fixing to existing door frames.30 mm thick Fiberglass Reinforced Plastic (F.R.P.) flush door shutter in different plain and wood finish made with fire retardant grade unsaturated polyester resin, moulded to 3 mm thick FRP laminate all around, with suitable wooden blocks inside at required places for fixing of fittings and polyurethane foam (PUF)/Polystyrene foam to be used as filler material throughout the hollow panel, casted monolithically with testing parameters of F.R.P. laminate conforming to table - 3 of IS: 14856, complete as per direction of Engineer-in-charge.	30.00	Sqm	2210.84	66325.20	INR Sixty Six Thousand Three Hundred & Twenty Five and Paise Twenty Only
48	Providing and fixing of Grab Bars as per site requirement in differently abled Toilets of approved quality complete as per design approved by Engineer-in-Charge. Grab Bar 842 mm Long, Satin - 2 nos (Jaquar WAC-SAP-BR0600CS or equivalent)	10.00	Set	6981.60	69816.00	INR Sixty Nine Thousand Eight Hundred & Sixteen Only
49	Providing and fixing Dorma Make or equivalent Automatic opening door as per site requirement for differently abled toilets consist of Operator Profile, Mechanical & Electrical Components, Floor Guide, Glass clamping rail, light barrier Five Position Program Switch knob and Cable for Program Switch, Electromechanical Locking system alongwith necessary Handicap Kit-ES200 with Add on Kit complete as per the direction of EIC.	21.00	Sqm	44216.80	928552.80	INR Nine Lakh Twenty Eight Thousand Five Hundred & Fifty Two and Paise Eighty Only
50	Providing and fixing of sensor operated pillar tap in polished chrome as per approved brand and complete as per the direction of EIC.. Base price considered: Rs. 15000/No. Price adjustment (plus or minus) shall be done based on selection by EIC with reference to base price.	52.00	each	17570.36	913658.72	INR Nine Lakh Thirteen Thousand Six Hundred & Fifty Eight and Paise Seventy Two Only
51	Providing and fixing of 12 mm thick HPL urinal partition with necessary fittings of approved make as per the direction of EIC	62.00	each	2559.92	158715.04	INR One Lakh Fifty Eight Thousand Seven Hundred & Fifteen and Paise Four Only
52	Providing & fixing 12mm thick acrylic counter of approved brand fixed over 19mm thick high strength water proof plywood on MS supporting structure/concrete structure with all fittings including moulding of wash basin of size 550x430x200mm or approved size as per direction of EIC. The centre to centre spacing between two wash basin should be as per site conditionas. The price inclusive of suitable adhesive, sealent, moulding of edges, provision for fixing pipes and sanitary fittings etc and as per the direction of EIC.	50.00	Sqm	3723.52	186176.00	INR One Lakh Eighty Six Thousand One Hundred & Seventy Six Only

OK
Since

Sl. No.	Item Description	Quantity	Units	Rate (Excluding GST) Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	3	4	5	6	7
53	Providing and fixing of pillar tap in polished chrome as per approved brand and complete as per the direction of EIC.. Base price considered: Rs. 3000/No. Price adjustment (plus or minus) shall be done based on selection by EIC with reference to base price.	43.00	each	3374.44	145100.92	INR One Lakh Forty Five Thousand One Hundred and Paise Ninety Two Only
Total in Figures					19270072.58	INR One Crore Ninety Two Lakh Seventy Thousand & Seventy Two and Paise Fifty Eight Only
Quoted Rate in Words		INR One Crore Ninety Two Lakh Seventy Thousand & Seventy Two and Paise Fifty Eight Only				

(Handwritten Signature)

पि. येडु कोंडालु
वरिष्ठ प्रबंधक (ई-सी)
P. YEDU KONDALU
Sr. Manager (E-C)
AAI / Madurai Airport

Signature Not Verified

Digitally signed by Yedukondalu Polagani
Date: 2025.01.23 17:40:01 IST
Location: eProcurement System for Central PSUs

