



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

सं.:— भाविप्रा/किशनगढ़/अभि.(वि.)/अवार्ड लैटर-12/2024-25/146

दिनांक:- 05/02/2025

सेवा में,

मेसर्स मिराज एडवर्टाइजिंग वर्ल्ड

सी-44, फेज-1, मंगोल पुरी औद्योगिक क्षेत्र,

दीप हुंडई के पीछे, दिल्ली - 110083

ई-मेल- mirageadworld@gmail.com

M/s. MIRAGE ADVERTISING WORLD

C-44, Phase - 1, Mangol Puri Industrial Area,

Behind Deep Hyundai, delhi - 110083

E-mail- mirageadworld@gmail.com

विषय :- रिप्लेसमेंट ऑफ एलईडी इल्लुमिनेटेड साइन बोर्ड ऑफ टर्मिनल बिल्डिंग एंड मेन एंट्री गेट एट किशनगढ़ एयरपोर्ट, अजमेर .

Subject :- "Replacement of LED Illuminated Sign Board of Terminal Building and Main gate at Kishangarh Airport, Ajmer."

संदर्भ:- दिनांक 17/12/2024 को खोली गई आपकी बिड न.- 2024_AAI_214886_1 (वित्तिय बिड)।

Ref:- Your Bid Number-2024_AAI_214886_1 (Financial Bid) opened on dated 17/12/2024.

महोदय,

- उल्लेखित कार्य हेतु आपकी ई-निविदा आपके द्वारा उद्धृत कुल रु. **13,65,000.00** (अक्षरे तेरह लाख पैसठ हजार रुपये मात्र) (जी.एस.टी रहित) की नियत मद दर पर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से एतद् द्वारा स्वीकृत की जाती है, जो कि ई-निविदा की अनुमानित लागत रु. **27,99,551.00** (जी.एस.टी. रहित) से **51.24%** नीचे हैं।

Your E-Tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India at the item rates quoted by you totalling to **Rs. 13,65,000.00** (Rupees Thirteen Lakh Sixty Five Thousand only) **(Excluding GST)** which is **51.24%** below the estimated cost of **Rs. 27,99,551.00 (Excluding GST)**.

- सहायक महाप्रबंधक (अभियांत्रिकी-विद्युत), भा.वि.प्रा, किशनगढ़ हवाई अड्डा, अजमेर इस कार्य के इंजीनियर-इन-चार्ज होंगे। आपसे अनुरोध है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु **20/02/2025** तक सहायक महाप्रबंधक (अभियांत्रिकी-विद्युत), भा.वि.प्रा, किशनगढ़ हवाई अड्डा, अजमेर के कार्यालय में उपस्थित हो। संविदा करार रु 100/- (मात्र सौ रुपये) के न्यायिकेतर (नॉन-ज्युडिशियल) स्टांप पेपर पर बनाया जाएगा तथा स्टांप पेपर की लागत आपके द्वारा वहन की जाएगी।

Assistant General Manager (Engg-E), AAI, Kishangarh Airport, Ajmer shall be the Engineer-In-Charge of the work. You are requested to attend the office of the Assistant General Manager (Engg-E) AAI, Kishangarh Airport, Ajmer by **20/02/2025** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of **Rs. 100/-** (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

- सुरक्षा राशि रु. **1,36,500.00** (अक्षरे एक लाख छत्तीस हजार पांच सौ रुपये मात्र) को 10 दिन के भीतर जमा करें अन्यथा इस राशि की कटौति संविदा कागजात के पृष्ठ 41 पर खण्ड-1 ए के अनुसार आपके चालू बिलों से की जाएगी।

Security deposit **Rs. 1,36,500.00** (Rupees One Lakh Thirty Six Thousand Five Hundred Only) within 10 days from the date of issue of this letter, failing which, the same will be deducted as per clause no.- 1A, page no. -41 of tender/contract document.

- आप से अनुरोध है कि आप संविदा श्रम (विनियम एवं उन्मूलन) अधिनियम 1970, संविदा श्रम (विनियम एवं उन्मूलन) केन्द्रीय नियम 1971, बाल श्रम (निषेध एवं उन्मूलन) अधिनियम 1986, निमार्ण श्रमिकों (सेवा के शर्त और नियमन) अधिनियम 1986 और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 जो कि निविदा दस्तावेज के जी.सी.सी. के प्रावधानों का और केन्द्रीय व राज्य सरकारों के तदसंबंधी नियमों का अनुपालन करें।



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

You are requested to comply with the provision of Contract Labour (Regulation & Abolition) Act of 1970, Contract Labour (Regulation & Abolition) Central Rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment & Condition of Service) Act 1996, Building & Other Construction Workers Welfare Cess Act 1996 as specified in GCC of tender Document and Rules of Central and state Govt.

5. आपको प्रबन्धक (अभियांत्रिकी-विद्युत), भा.वि.प्रा., किशनगढ़ हवाई अड्डा, अजमेर से तत्काल संपर्क करने का भी निर्देश दिया जाता है। आपको कार्यस्थल (साइट) सौंपने का कार्य उनके द्वारा किया जाएगा।

You are also directed to contact Manager (Engg-E), AAI, Kishangarh Airport, Ajmer immediately who will arrange to hand over the site to you.

6. कृपया नोट करें कि कार्य पूरा करने के लिए आपको 03 माह का समय प्रदान किया जाता है जो कि इस पत्र के जारी होने की तिथि से 10 दिन बाद से प्रभावी होगी।

Please note that the time allowed for carrying out the work shall be **03 Months** & shall be reckoned from 10th day after the date of issue this letter.

7. दोष दायित्व अवधि एक (01) वर्ष होगी, जो कार्य के पुरा होने की वास्तविक दर्ज तिथि से प्रभावी होगी।

The defects liability period shall be **One (01) Year**, which will be effective from the actual recorded date of completion of the work.

8. संविदा के संबंध में भविष्य में किसी भी प्रकार का पत्र व्यवहार सामान्यतः इंजीनियर-इन-चार्ज के नाम से किया जाएगा।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-Charge.

9. कृपया पत्र की पावती भेजें।

Please acknowledge the receipt.

10. यदि कोई विसंगति पाई जाती है तो अंग्रेजी भाषा ही मान्य होगी।

In case any discrepancy is found, then English version will be taken as correct.

Enclosure :- BOQ Page-01-03

भवदीय / Yours Faithfully,

सहायक महाप्रबंधक (अभि०-वि०) / Asstt. Gen. Mgr. (Engg.-E)
कृते तथा ओर से अध्यक्ष, भा.वि.प्रा. / For and on behalf of Chairman, AAI

[Signature]
03/04/25

Tender Inviting Authority: Asstt. Gen. Manager (Engg-E), Kishangarh Airport, Ajmer-305801

Name of Work: Replacement of LED Illuminated Sign Board of Terminal Building and Main gate at Kishangarh Airport, Ajmer.

Contract No: 2024_AAL_214886_1

Name of the Bidder/ Bidding Firm / Company :		MIRAGE ADVERTISING WORLD					
PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT In Rs. P (Excluding GST)	TOTAL AMOUNT In Words	
1	2	4	5	13	53	55	
1	Arrival/Departure Zone Marker Refer design drawing 1.6a&S. 1.6a G Providing and fixing illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-In-Charge. All exterior signs should be manufactured considering harsh outdoor conditions, weatherproofing techniques and materials shall be used. Sign Face Providing and fixing entire Sign face all 4 sides, made of printed vinyl flex of high quality, with the letters/pictogram to match Pantone Black 6C and the rest of the vinyl to match Pantone Yellow C. To be mounted onto framework using appropriate clips and edge ties to be perfectly taut with no sagging. Stitching of the vinyl flex should not be visible to the customers, preferably given at the back side of the box. Suspender Providing and fixing suspension for the signs using Stainless steel Hollow section 100mm OD X 3 MM Thick (assuming typical length of 15 ft), cut, fabricated as per drawing and provided with connectors plates for mounting with holes and entire assembly finished in brush finish as approved by the Engineer -in-charge. Suspender shall be made to required lengths for each sign for its location after studying the site and ensuring a perfectly aligned and levelled sign installation. This item includes all work done on false ceiling like opening/dismantling/local cutting to pass the suspender and reinstalling/doing good/assembling the same after fixing and installation on the sign. Sign Frame Providing and fixing 25mm x 25mm x 1.3mm MS square sections hot dipped galvanized and welded together to form a framework. Frame to be directly fixed to the sign suspender. Frame to receive the sign faces. Stretching Member Providing and fixing 8mm thick acrylic strips vertically to the sign frame to help stretching the sign face. Bottom panel Bottom MS Panel powder coated in colour to match Vinyl Black of Pantone Black 6C. Lighting All internal illumination shall be using power lights from Osram or equivalent with electronic controllers, having even spread and overlaps to avoid banding and dark spots and adhering to the LUX levels mentioned in the performance specification. Cost to include all internal connections and Wiring, terminating and connecting the incoming cable laid by Airport contractor at the site. Accessories: Providing and fixing all accessories such as thimbles, end connectors, nut-inserts, screws , rivets, bolts, washers, nuts, etc. complete as per drawing. The actual structural design of the sign for its stability shall be responsibility of the contractor. Secret fixing methods should be used to fix parts together. Size - 1800 mm x 1800 mm x 1800 mm (Cube)	4	Set	75000.00	300000.00	INR Three Lakh Only	

Signature
Date

NUMBER #	TEXT #	TEXT #	TEXT #	TEXT #	TEXT #	
Sl. No.	Item Description	Quantity	Units	NUMBER #	NUMBER #	
				BASIC RATE in Figures To be entered By the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT in Rs. P (Excluding GST)	
1	2	4	5	13	53	
2	Terminal Building Announcer Refer design drawing 1.8S, 1.8G Providing and fixing illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in- Charge. All exterior signs should be manufactured considering harsh outdoor conditions, weatherproofing techniques and materials shall be used. (Considering all Alphabets for English and Hindi) Letter face: Providing and fixing White translucent 040, 5mm thick acrylic, complete face shall be covered with translucent vinyl film to match Blue Pantone 541C. Back Channel: The channel letters would be made out of 3 mm thick aluminium sheet to receive the front acrylic and house the controller and LEDs, wall 60 mm deep. All the letters would be made in profile to achieve true right angle. All mounting would be done in true plumb and using template, keeping the alignment of the letters in one level as per drawing. Lighting: All internal illumination shall be using Power LED Lights from Osram or equivalent with electronic controllers, having even spread and overlaps to avoid banding and dark spots and adhering to the LUX levels mentioned in the performance specification. Cost to include all internal connections and Wiring, terminating and connecting the incoming cable laid by Airport contractor at the site. Accessories: Providing and fixing all accessories such as thimbles, end connectors, nut-inserts, screws, rivets, bolts, washers, nuts, etc. complete as per drawing.					
2.1	किशनगर हवाई अड्डा (Hindi), (Letter body Height excluding diacritic:- 770 mm height)	2	Set	195000.00	390000.00	INR Three Lakh Ninety Thousand Only
2.2	Kishangarh Airport (English), (Letter Height :- 770 mm height)	2	Set	195000.00	390000.00	INR Three Lakh Ninety Thousand Only
2.3	AAI Logo (950 mm height)	2	Set	25000.00	50000.00	INR Fifty Thousand Only


 24/06/24
 24/06/24

NUMBER #	TEXT #	NUMBE	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT in Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
3	Periphery Airport Name Sign Refer design drawing 1.2S, 1.2G Providing and fixing illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in-Charge. All exterior signs should be manufactured considering harsh outdoor conditions, weatherproofing techniques and materials shall be used. Sign Box: The sign box shall be made in 18-gauge thick powder coated aluminium in specified blue colour RAL 5013. Router cut, grooved and folded to achieve the desired shape as per drawing fixed with the internal frame structure. Sign Face: The sign face shall be made in 18-gauge thick powder coated aluminium in specified blue colour RAL 5013, provided with backlit LED lighting and shall have laser cut profiles to receive milky white 6 mm thick acrylic sheet from back. All panels fixed using counter sunk screws. Sign Structure:- M.S. square sections 25 x 25 mm hot dipped galvanized Structure fixed to the sign box and to be fixed to the wall surface. Structure to receive the sign face. Lighting:- All internal illumination shall be using Power LED Lights from Osram or equivalent with electronic controllers, having even spread and overlaps to avoid banding and dark spots and adhering to the LUX levels mentioned in the performance specification. Cost to include all internal connections and Wiring, terminating and connecting the incoming cable laid by Airport contractor at the site. Accessories: Providing and fixing all accessories such as thimbles, end connectors, nut-inserts, screws, rivets, bolts, washers, nuts, etc. complete as per drawing.					
3.1	किशनगढ़ हवाई अड्डा (Hindi), (Letter body Height excluding diacritic:- 530 mm height)	1	Set	110000.00	110000.00	INR One Lakh Ten Thousand Only
3.2	Kishangarh Airport (English), (Letter Height :- 530 mm height)	1	Set	110000.00	110000.00	INR One Lakh Ten Thousand Only
3.3	AAI Logo (Height as per design)	1	Set	15000.00	15000.00	INR Fifteen Thousand Only
Total in Figures					1365000.00	INR Thirteen Lakh Sixty Five Thousand Only
Quoted Rate in Words					INR Thirteen Lakh Sixty Five Thousand Only	Only


25.8.2025
Page No. 51