

संदर्भ : भाविप्रा/नागपुर/इंजी -सि/2024-25/डब्ल्यू-6/ 236
Ref: AAI/NAGPUR/ENGG-C/2024-25/W-6/ 49

दिनांक : 10/01/2025
Date: 10/01/2025

रजिस्टर्ड डाक/स्पीड पोस्ट

प्रति,
मेसर्स. प्राईम कंस्ट्रक्शन,
प्लॉट नं. 145, फ्लैट नं. 401,
अमृता मंगल स्मृती अपार्टमेन्ट, पांडे ले-आऊट,
नागपुर - 440025.
ई-मेल : constructions.prime@gmail.com

To,
M/s. Prime Constructions,
Plot No. 145, Flat No. 401,
Amruta Mangal Smruti Apartment, Pandey Layout,
Nagpur - 440022.
Email : constructions.prime@gmail.com

विषय : डीबीआई हवाई अड्डे, नागपुर में इंजीनियरिंग कॉम्प्लेक्स में मानव संसाधन, वित्त और इंजीनियरिंग के कार्यालयों का नवीनीकरण और नवीकरण (सिविल और इलेक्ट्रिकल कार्य) ।

Sub : "Renovation and Refurbishment of offices of HR, Finance and Engineering in Engineering Complex at DBAI Airport, Nagpur (Civil and Electrical works)".

संदर्भ : आपकी ई-निविदा दिनांक 30.12.2024 बिड नं. 789475, (निविदा नंबर : 2024_AAI_216729_1) ।

Ref : Your e-tender opened on 30.12.2024 Bid No. 789475, (Tender Id: 2024_AAI_216729_).

महोदय,

- ऊपर उल्लेखित कार्य हेतु आपकी निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है, आपके द्वारा बताए गये मद मूल्यों पर आपकी टेन्डर राशि कुल रु. 1,57,73,778.90 /- (रुपये एक करोड़ सत्तावन लाख तिहत्तर हजार सात सौ अठहत्तर दशमलव नब्बे पैसे मात्र) जीएसटी को छोड़कर है, जो कि टेन्डर की अनुमानित लागत राशि रुपये 1,84,97,000.00 से 14.72 % नीचे है ।

Your tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs. 1,57,73,778.90 /- (Rupees One Crore Fifty Seven Lakhs Seventy Three Thousand Seven Hundred Seventy Eight Point Ninety Paise Only) excluding GST**, which is **14.72 %** below the estimated cost put to tender of **Rs. 1,84,97,000.00** only.

- वरिष्ठ प्रबंधक (अभि-सि), डॉ. बाबासाहेब अंबेडकर अंतरराष्ट्रीय विमानतल, नागपुर, कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप आपकी ओर से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वरिष्ठ प्रबंधक (अभि-सि), नागपुर विमानक्षेत्र के कार्यालय में उपस्थित हो और काम शुरू होने की निर्धारित तारीख से 15 दिनों के भीतर करारनामे को पूरा करें। अनुबंध का करारनामा रु. 100.00 (रु. एक सौ मात्र) के नॉन-ज्युडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा पेपर का खर्च आपके द्वारा उठाया जाएगा ।

Senior Manager (Engg-C), Airports Authority of India, Dr. Babasaheb Ambedkar International Airport, Nagpur shall be the Engineer-In-Charge of the work. You are requested to depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the O/o **Senior Manager (Engg-C)**, AAI Nagpur within 15 days from the stipulated date of start of the work to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100.00 (Rs. One Hundred only) and the cost of the stamp paper shall be borne by you.

अनवरत शीट / Continuation sheet - 2-

3. रु. 3,69,940.00/- (रु. तीन लाख उनसठ हजार नौ सौ चालीस मात्र) ऑनलाईन मोड के माध्यम से प्राप्त हुई धरोहर राशि सुरक्षा जमा के रुप में धरोहर राशि के बराबर यानी रु. 3,69,940.00/- जमा करने के बाद वापस कर दी जायेगी (गॉरंटी बॉड के रुप में किसी भी शेड्युल बैंक का परंतु सहकारी या ग्रामीण बैंक का नहीं)।

कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर सुरक्षा जमा राशि की बकाया रु. 12,07,438.00/- (रु. बारह लाख सात हजार चार सौ अडतीस मात्र) जमा करवायें, अन्यथा अनुबंध के दस्तावेज जी.सी.सी. के पृष्ठ 16 पर दी गई परिच्छेद 1ए के अनुसार इसे आपके रनिंग बिलों में से वसूल किया जायेगा।

The earnest money amount of Rs. 3,69,940.00/- (Rupees Three Lakhs Sixty Nine Thousand Nine Hundred Forty Only) received through online mode shall be refunded after submission of EMD equivalent amount as Security deposit i.e. Rs. 3,69,940.00/- (in the form of Guarantee Bonds of any Schedules bank but not Co-operative or Gramin bank).

Please deposit balance Rs. 12,07,438.00/- (Rupees Twelve Lakhs Seven Thousand Four Hundred and Thirty Eight only), towards security deposit within 10 days from the date of issue of this letter failing which the same will be deducted from your running bills as per Clause 1 (A) of GCC Page No. 16 of the tender document.

4. आपसे निवेदन हैं कि आप विभिन्न लागू वैधानिक अधिनियम के तहत प्रावधानों जैसे कर्मचारी भविष्य निधि व विविध प्रावधान अधिनियम 1952, कर्मचारी राज्य बीमा (ईएसआई) अधिनियम, 1948, ठेका श्रमिक (रोजगार व सेवा की शर्त) अधिनियम, 1979 न्यूनतम मजदूरी अधिनियम, 1948, मजदूरी भूगतान अधिनियम, 1936, श्रमिक प्रतिपूर्ति अधिनियम, 1923 एवं अन्य संगत नियम व अधिनियम, अनुदेश इत्यादि जो समय समय पर जारी/प्रवर्तित किया जाते हैं। उक्त वैधानिक अधिनियम व प्रावधानों का नियमित अनुपालन व इनके अंतर्गत सारी विधिक बाध्यताओं का पूर्ण प्रेक्षण आपका एकल दायित्व होगा।

You are requested to comply with the provisions under various applicable statutory enactments including the employees Provident Fund & Miscellaneous Provisions Act, 1952, the Employees State Insurance (ESI) Act, 1948, the Contract Labour (Regulation & Abolition) Act, 1970, the Inter-State Migrant workmen (Regulation of employment & conditions of Service) Act, 1979, the Minimum Wages Act, 1948, the Payment of Wages Act, 1936, the workmen's Compensation Act, 1923 and other relevant Act, Rules and Regulations, instructions etc. issued/enforced from time to time. It shall be your sole liability to abide with and fully observing the legal obligations under the aforesaid statutory acts and provisions.

5. आपसे निवेदन है कि, आप अपने आप को वस्तु एवं सेवा कर अथोरिटी के साथ रजिस्टर करा ले, यदि लागू हो तो, और इससे संबंधित प्रमाणपत्र कार्य के प्रभारी अभियंता को कार्य आदेश जारी होने के 30 दिनों में जमा कराये।

You are also requested to get yourself registered with **Goods & Services Tax** collection authorities, if applicable, and submit the documentary evidence to the Engineer- in-charge within 30 days of issue of this letter.

6. आपको निर्देश दिया जाता है कि आप तुरंत सहायक प्रबंधक (अभि-सि), डॉ. बाबासाहेब अम्बेडकर अंतरराष्ट्रीय विमानपत्तन, नागपुर से मिलें वह आपको साइट सौंपने की व्यवस्था करेंगे। कृपया नोट कर लें कि काम करने का अनुमत समय 06 (छह) महीने हैं जो कि इस पत्र के जारी करने के दसवे दिन से गिना जाएगा।

अनवरत शीट / Continuation sheet - 3-

You are also directed to contact Assistant Manager (Engg-C), AAI, Dr. Babasaheb Ambedkar International Airport, Nagpur who will arrange to handover the site to you. Please note that the time allowed for carrying out the work as entered in the tender is 06 (Six) Months and same shall be reckoned from the tenth day after issuing of this letter.

7. इस अनुबंध के संबंध में आगे कोई भी पत्राचार वरिष्ठ प्रबंधक (अभि-सि), भाविप्रा, डॉ. बाबासाहेब अम्बेडकर अंतरराष्ट्रीय हवाईअड्डा, नागपुर के पते पर किया जाएगा ।

Any further correspondence in connection with the contract should normally be addressed to the Senior Manager (Engg-C), AAI, Dr. Babasaheb Ambedkar International Airport, Nagpur.

8. अनुबंध दस्तावेज जी.सी.सी. के पृष्ठ 47 में परिच्छेद – क्रम सं. 17 में उल्लिखित त्रुटि दायित्व अवधि 12 (बारह) महीने होगी।


The defects liability period shall be 12 (Twelve) Months as mentioned in clause No.17 of GCC, page 47 of the contract document.

- 9 कृपया पावती भेजे तथा इस की प्रतिलिपि हस्ताक्षर कर के अधोहस्ताक्षरी को वापस भेजे।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Enclosed : 22 (Twenty Four) Pages.

सलग्नक : 22 (बाइस) पृष्ठ।



(कमलेश सूर्यवंशी)
वरिष्ठ प्रबंधक (इंजी-सि), नागपुर.
कमलेश सूर्यवंशी
Kamlesh Suryawanshi
वरिष्ठ प्रबंधक (अभियांत्रिकी-सिविल)
Senior Manager (Engg-Civil)
भा.वि.प्रा., डी.बी.ए.आई. विमानतल, नागपुर-05
AAI, DBAI Airport, Nagpur-05

प्रतिलिपि / Copy to :-
आंतरिक वितरण :-

1. महाप्रबंधक(एटीएम)/ समन्वय प्रभारी, भा.वि.प्रा, डॉ. बाबासाहेब अम्बेडकर अंतर्राष्ट्रीय विमानतल, नागपुर-440005.
General Manager (ATM)/ CIC, AAI, DBAI Airport, Nagpur-440005.
2. महाप्रबंधक (इंजी), भाविप्रा, पश्चिमी क्षेत्र, न्यु ऐअरपोर्ट कॉलोनी, विपरित पारसीवाडा, सहार रोड, विले पार्ले (पुर्व), मुंबई - 400099.
General Manager (Engg), AAI, Western Region, New Airport Colony, Opposite Parsiwada, Sahar Road, Vile Parle (E), Mumbai - 400099.
3. सतर्कता अधिकारी, भाविप्रा, पश्चिम क्षेत्र, भाविप्रा, न्यु ऐअरपोर्ट कॉलोनी, विपरित पारसीवाडा, सहार रोड, विले पार्ले (पुर्व), मुंबई - 400099.
The Vigilance Officer, AAI, Western Region, New Airport Colony, Opposite Parsiwada, Sahar Road, Vile Parle (E), Mumbai - 400099.
4. सयुक्त महाप्रबंधक (इंजी-सि)-III, भाविप्रा, पश्चिम क्षेत्र, भाविप्रा, न्यु ऐअरपोर्ट कॉलोनी, विपरित पारसीवाडा, सहार रोड, विले पार्ले (पुर्व), मुंबई - 400099.
Jt. General Manager (E-C)-III, AAI, Western Region, New Airport Colony, Opposite Parsiwada, Sahar Road, Vile Parle (E), Mumbai - 400099.
5. उप. महाप्रबंधक (इंजी-सि), भा.वि.प्रा, डॉ. बाबासाहेब अम्बेडकर अंतर्राष्ट्रीय विमानतल, नागपुर-440005.
Deputy General Manager (E-C), AAI, DBAI Airport, Nagpur-440005.
6. उप. महाप्रबंधक (इंजी-विद्युत), भा.वि.प्रा, डॉ. बाबासाहेब अम्बेडकर अंतर्राष्ट्रीय विमानतल, नागपुर-440005.
Deputy General Manager (E-E), AAI, DBAI Airport, Nagpur-440005.
7. सहा. महाप्रबंधक (वित्त), भा.वि.प्रा, डॉ. बाबासाहेब अम्बेडकर अंतर्राष्ट्रीय विमानतल, नागपुर-440005.
Asstt. Gen. Manager (Fin), AAI, DBAI Airport, Nagpur-440005.
8. सहायक प्रबंधक (इंजी-सि), भा.वि.प्रा, डॉ. बाबासाहेब अम्बेडकर अंतर्राष्ट्रीय विमानतल, नागपुर-440005.
Assistant Manager (E-C), AAI, DBAI Airport, Nagpur-440005.
9. करारनामा कॉपी.
Agreement Copy.
10. सम्बंधित फाईल.
Concerned File.

बाह्य वितरण :-

10. लेबर कमिशनर ऑफीस, 1st फ्लोवर, ब्लॉक-सी, सी.जी.ओ. कॉम्प्लेक्स, सेमिनरी हिल्स, नागपुर-440006.
Labour Commissioner Office, 1st Floor, Block-C, C.G.O Complex, Seminary Hills, Nagpur - 440006.
11. सहायक भविष्यनिधी कमिशनर, भांडे प्लॉट, उमरेड रोड, रघुजी नगर, नागपुर - 440009.
Assistant Provident Fund Commissioner, Bhande Plot, Umred Road, Raghuji Nagar, Nagpur - 440009.
12. कमिशनर ऑफीस, कस्टमस, सेन्ट्रल एक्साईज अँड सर्विस टॅक्स, पी. ऑ. बॉक्स नं. 81, सिव्हील लाईन्स, तेलंखेडी रोड, नागपुर - 440001.
The Commissioner Office, Customs, Central Excise and Service Tax, P. O. Box No. 81, Civil Lines, Telangkhedi Road, Nagpur - 440001.
13. निदेशक, उप क्षेत्रीय कार्यालय, कर्मचारी राज्य बीमा निगम, पंचदीप भवन, गणेशपेट, नागपुर - 440018.
The Director, Sub Regional Office, Employee's State Insurance Corporation, Panchdeep Bhavan, Ganeshpeth, Nagpur - 440018.


वरिष्ठ प्रबंधक (इंजी-सि), नागपुर
Kamlesh Surysavansi
वरिष्ठ प्रबंधक (अभियंत्रिकी-सिविल)
Senior Manager (Engg-Civil)
AAI, DBAI Airport, Nagpur-440005

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Senior Manager (E-C), AAI, DBAI Airport, Nagpur-05.

Name of Work: "Renovation and Refurbishment of offices of HR, Finance and Engineering in Engineering Complex at DBAI Airport, Nagpur (Civil and Electrical works)".

Contract No: 2024_AAI_216729_1

Name of the Bidder/ Bidding Firm / Company :	prime constructions nagpur					
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
1	SH : CIVIL WORKS					
1.01	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge. All kinds of soil	419.00	Cum	300.00	125700.00	INR One Lakh Twenty Five Thousand Seven Hundred Only
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and for all lift.	107.00	Cum	80.00	8560.00	INR Eight Thousand Five Hundred & Sixty Only
3	Extra for every additional lift of 1.5 m or part thereof in excavation banking excavated or stacked materials: All kinds of soil	11.00	Cum	20.00	220.00	INR Two Hundred & Twenty Only
4	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	30.00	Cum	2400.00	72000.00	INR Seventy Two Thousand Only
5	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	1000.00	Sqm	10.00	10000.00	INR Ten Thousand Only
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	116.47	Cum	4400.00	512468.00	INR Five Lakh Twelve Thousand Four Hundred & Sixty Eight Only
7	Providing and laying damp-proof course 40 mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 12.5 mm nominal size derived from natural sources)	13.11	Sqm	200.00	2622.00	INR Two Thousand Six Hundred & Twenty Two Only
8	Extra for providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification.	352.00	Per 50 kg cement	80.00	28160.00	INR Twenty Eight Thousand One Hundred & Sixty Only

Ramlesh
 10/01/2025
 SM(E-C)

SI. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
9	Making plinth protection 50 mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) over 75 mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth.	38.34	Sqm	400.00	15336.00	INR Fifteen Thousand Three Hundred & Thirty Six Only
10	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	45.00	Cum	6800.00	306000.00	INR Three Lakh Six Thousand Only
11	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	14.00	Cum	6800.00	95200.00	INR Ninety Five Thousand Two Hundred Only
12	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	44.00	Cum	6800.00	299200.00	INR Two Lakh Ninety Nine Thousand Two Hundred Only
13	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete	77.00	Sqm	460.00	35420.00	INR Thirty Five Thousand Four Hundred & Twenty Only
14	Centering and shuttering including strutting, propping etc. and removal of form for : Suspended floors, roofs, landings, balconies and access platform	150.00	Sqm	460.00	69000.00	INR Sixty Nine Thousand Only
15	Centering and shuttering including strutting, propping etc. and removal of form for :Lintels, beams, plinth beams, girders, bressumers and cantilevers	134.00	Sqm	460.00	61640.00	INR Sixty One Thousand Six Hundred & Forty Only
16	Centering and shuttering including strutting, propping etc. and removal of form for : Columns, Pillars, Piers, Abutments, Posts and Struts	434.00	Sqm	460.00	199640.00	INR One Lakh Ninety Nine Thousand Six Hundred & Forty Only
17	Edges of slabs and breaks in floors and walls: Under 20 cm wide	91.00	metre	100.00	9100.00	INR Nine Thousand One Hundred Only
18	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.: Thermo-Mechanically Treated bars of grade Fe-500D or more	6750.00	Kg	87.00	587250.00	INR Five Lakh Eighty Seven Thousand Two Hundred & Fifty Only
19	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.: Thermo-Mechanically Treated bars of grade Fe-500D or more	8700.00	Kg	87.00	756900.00	INR Seven Lakh Fifty Six Thousand Nine Hundred Only
20	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	151.06	Cum	6800.00	1027208.00	INR Ten Lakh Twenty Seven Thousand Two Hundred & Eight Only
21	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:4 (1 cement :4 coarse sand)	100.00	Sqm	880.00	88000.00	INR Eighty Eight Thousand Only

Sanjesh
10/01/2025
SM(E-C)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
22	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete at all levels.: Granite stone slab of colour black, Cherry/Ruby red: Area of slab upto 0.50 sqm	0.43	Sqm	4500.00	1935.00	INR One Thousand Nine Hundred & Thirty Five Only
23	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete at all levels.: Granite stone slab of colour black, Cherry/Ruby red: Area of slab over 0.50 sqm	90.59	Sqm	4500.00	407655.00	INR Four Lakh Seven Thousand Six Hundred & Fifty Five Only
24	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.: Granite Work	38.57	Metre	300.00	11571.00	INR Eleven Thousand Five Hundred & Seventy One Only
25	Extra for providing opening of required size & shape for wash basin/ kitchen sink in kitchen platform, vanity counter and similar location in marble/ Granite/stone work, including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete.	5.00	Each	500.00	2500.00	INR Two Thousand Five Hundred Only
26	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	195.89	Sqm	900.00	176301.00	INR One Lakh Seventy Six Thousand Three Hundred & One Only
27	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately): Second class teak wood	0.38	Cum	100000.00	38000.00	INR Thirty Eight Thousand Only
28	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows, fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. (Note:- Butt hinges and necessary screws shall be paid separately): Second class teak wood: 30 mm thick shutters	75.96	Sqm	3200.00	243072.00	INR Two Lakh Forty Three Thousand & Seventy Two Only
29	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick : Float glass pane: 4 mm thick glass pane (weight not less than 10kg/sqm)	75.96	Sqm	800.00	60768.00	INR Sixty Thousand Seven Hundred & Sixty Eight Only

Ramlesh
10/01/2025
SM(E-C)

SI. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
30	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	25.20	Sqm	2200.00	55440.00	INR Fifty Five Thousand Four Hundred & Forty Only
31	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete.: Fixed to openings /wooden frames with rawl plugs screws etc.	630.00	Kg	140.00	88200.00	INR Eighty Eight Thousand Two Hundred Only
32	Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm all complete.: With 2nd class teak wood beading 62X19 mm	75.96	sqm	1100.00	83556.00	INR Eighty Three Thousand Five Hundred & Fifty Six Only
33	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete.	19.00	Each	1200.00	22800.00	INR Twenty Two Thousand Eight Hundred Only
34	Providing and fixing aluminium sliding door bolts, ISI marked anodised anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : 250x16 mm	38.00	Each	350.00	13300.00	INR Thirteen Thousand Three Hundred Only
35	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :: 200x10 mm	19.00	Each	80.00	1520.00	INR One Thousand Five Hundred & Twenty Only
36	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 125 mm	38.00	Each	80.00	3040.00	INR Three Thousand & Forty Only
37	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete.: Twin rubber stopper	19.00	Each	80.00	1520.00	INR One Thousand Five Hundred & Twenty Only
38	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	303.00	Kg	120.00	36360.00	INR Thirty Six Thousand Three Hundred & Sixty Only
39	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.: Hot finished welded type tubes	4102.06	Kg	140.00	574288.40	INR Five Lakh Seventy Four Thousand Two Hundred & Eighty Eight and Paise Forty Only
40	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.: In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	150.00	Kg	120.00	18000.00	INR Eighteen Thousand Only

Handwritten:
 10/01/2025
 SM(E-G)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
41	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), including pointing the joints with white cement and matching pigments etc., complete.	44.82	Sqm	900.00	40338.00	INR Forty Thousand Three Hundred & Thirty Eight Only
42	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 600x600 mm	157.50	Sqm	1400.00	220500.00	INR Two Lakh Twenty Thousand Five Hundred Only
43	Providing & fixing on wall face unplasticised -Rigid PVC rain water pipes conforming to IS ; 13592 Type A including jointing with seal ring conforming to IS ; 5382 leaving 10 mm gap for thermal expansion.: 110 mm diameter	54.00	Metre	360.00	19440.00	INR Nineteen Thousand Four Hundred & Forty Only
44	Providing, fixing on wall face unplasticised - PVC moulded fittings /accessories for unplasticised - Rigid PVC rain water pipes conforming to IS ; 13592 Type A including jointing with seal ring conforming to IS ; 5382 leaving 10 mm gap for thermal expansion.: Coupler-110mm diameter	20.00	Each	100.00	2000.00	INR Two Thousand Only
45	Providing, fixing on wall face unplasticised - PVC moulded fittings /accessories for unplasticised - Rigid PVC rain water pipes conforming to IS ; 13592 Type A including jointing with seal ring conforming to IS ; 5382 leaving 10 mm gap for thermal expansion.: 110 mm bend	15.00	Each	100.00	1500.00	INR One Thousand Five Hundred Only
46	Providing, fixing on wall face unplasticised - PVC moulded fittings /accessories for unplasticised - Rigid PVC rain water pipes conforming to IS ; 13592 Type A including jointing with seal ring conforming to IS ; 5382 leaving 10 mm gap for thermal expansion.: 110 mm Shoe	12.00	Each	100.00	1200.00	INR One Thousand Two Hundred Only
47	Providing & fixing unplasticised - PVC pipe clips of approved design to unplasticised - PVC rain water pipes by means of 50x50x50mm hard wood plugs, screwed with .M.S. screws of required length including cutting brick work and fixing in cement mortar 1:4(1cement : 4 coarse sand) and making good the wall etc. complete.: 110mm dia	30.00	Each	50.00	1500.00	INR One Thousand Five Hundred Only
48	Providing and fixing to the inlet mouth of rain water pipe cast iron grating 15cm diameter and weighting not less than 440 grams.	8.00	Each	50.00	400.00	INR Four Hundred Only
49	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	428.00	Sqm	350.00	149800.00	INR One Lakh Forty Nine Thousand Eight Hundred Only
50	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement: 4 fine sand)	766.00	Sqm	350.00	268100.00	INR Two Lakh Sixty Eight Thousand One Hundred Only
51	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	1263.00	Sqm	90.00	113670.00	INR One Lakh Thirteen Thousand Six Hundred & Seventy Only

Signature
10/01/2025
SM(E-C)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
52	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	450.00	Sqm	100.00	45000.00	INR Forty Five Thousand Only
53	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.: Two coats	932.00	Sqm	100.00	93200.00	INR Ninety Three Thousand Two Hundred Only
54	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour Two coats	926.00	Sqm	100.00	92600.00	INR Ninety Two Thousand Six Hundred Only
55	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	858.00	Sqm	3.00	2574.00	INR Two Thousand Five Hundred & Seventy Four Only
56	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	1130.00	Sqm	100.00	113000.00	INR One Lakh Thirteen Thousand Only
57	Dismantling W.C. Pan of all sizes including disposal of dismantled materials i/c malba all complete as per directions of Engineer-in- Charge.	3.00	Each	100.00	300.00	INR Three Hundred Only
58	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	20.00	Cum	1200.00	24000.00	INR Twenty Four Thousand Only
59	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in-charge.	22.80	Cum	1200.00	27360.00	INR Twenty Seven Thousand Three Hundred & Sixty Only
60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	40.00	Cum	380.00	15200.00	INR Fifteen Thousand Two Hundred Only
61	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	30.00	Cum	1200.00	36000.00	INR Thirty Six Thousand Only
62	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50 metres lead.	4715.70	Sqm	5.00	23578.50	INR Twenty Three Thousand Five Hundred & Seventy Eight and Paise Fifty Only
63	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: G.S. Sheet	100.00	Sqm	50.00	5000.00	INR Five Thousand Only
64	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge.	176.38	Sqm	50.00	8819.00	INR Eight Thousand Eight Hundred & Nineteen Only
65	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	7.50	Cum	6000.00	45000.00	INR Forty Five Thousand Only

Signature
10/01/2025
SM(E-C)

Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
66	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	16.88	Cum	7500.00	126600.00	INR One Lakh Twenty Six Thousand Six Hundred Only
67	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	2.00	Each	6000.00	12000.00	INR Twelve Thousand Only
68	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid	3.00	Each	6000.00	18000.00	INR Eighteen Thousand Only
69	Providing and fixing white vitreous china flat back half stall urinal of size 580x380x350 mm with white PVC automatic flushing cistern, with fittings, standard size C.P. brass flush pipe, spreaders with unions and clamps (all in C.P. brass) with waste fitting as per IS : 2556, C.I. trap with outlet grating and other couplings in C.P. brass, including painting of fittings and cutting and making good the walls and floors wherever required : Single half stall urinal with 5 litre P.V.C. automatic flushing cistern	4.00	each	9000.00	36000.00	INR Thirty Six Thousand Only
70	Providing and fixing wash basin with CI brackets, 15mm brass pillar taps, 32mm CP brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever required.: White vitreous china wash basin size 630 mm x 450 mm with single 15mm CP brass pillar tap.	5.00	Each	3200.00	16000.00	INR Sixteen Thousand Only
71	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required : Kitchen sink with drain board: 510x1040 mm bowl depth 178 mm	1.00	each	5500.00	5500.00	INR Five Thousand Five Hundred Only
72	Providing and fixing P.V.C waste pipe for sink or wash basin including P.V.C waste fitting complete: Flexible pipe: 40 mm dia	3.00	Each	100.00	300.00	INR Three Hundred Only
73	Providing and fixing 600x450mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	3.00	Each	1200.00	3600.00	INR Three Thousand Six Hundred Only
74	Providing and fixing soil, waste and vent pipes: 100 mm dia Sand cast iron S&S pipe as per IS: 1729	20.00	Metre	900.00	18000.00	INR Eighteen Thousand Only

Kamlesh
 10/01/2025
 SM(E-C)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
75	Providing and fixing M.S. holder-bat clamps of approved design to Sand Cast iron/cast iron (spun) pipe embedded in and including cement concrete blocks 10x10x10 cm of 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), including cost of cutting holes and making good the walls etc. :For 100 mm dia pipe	8.00	Each	100.00	800.00	INR Eight Hundred Only
76	Providing and fixing bend of required degree with access door, insertion rubber washer 3 mm thick, bolts and nuts complete.: 100 mm dia Sand cast iron S&S as per IS - 1729	8.00	Each	300.00	2400.00	INR Two Thousand Four Hundred Only
77	Providing and fixing plain bend of required degree.:100 mm dia Sand cast iron S&S as per IS - 1729	8.00	Each	300.00	2400.00	INR Two Thousand Four Hundred Only
78	Providing and fixing heel rest sanitary bend: 100 mm dia Sand cast iron S&S as per IS - 1729	8.00	Each	300.00	2400.00	INR Two Thousand Four Hundred Only
79	Providing and fixing double equal junction of required degree with access door, insertion rubber washer 3 mm thick, bolts and nuts complete : 100x100x100x100 mm Sand cast iron S&S as per IS - 1729	8.00	Each	500.00	4000.00	INR Four Thousand Only
80	Providing and fixing single equal plain junction of required degree with access door, insertion rubber washer 3 mm thick, bolts and nuts complete.: 100x100x100 mm Sand cast iron S&S as per IS - 1729	8.00	Each	500.00	4000.00	INR Four Thousand Only
81	Providing and fixing terminal guard : 100 mm Sand cast iron S&S as per IS - 1729	8.00	Each	300.00	2400.00	INR Two Thousand Four Hundred Only
82	Providing and fixing collar : 100 mm Sand cast iron S&S as per IS - 1729	8.00	Each	300.00	2400.00	INR Two Thousand Four Hundred Only
83	Providing lead caulked joints to sand cast iron/centrifugally cast (spun) iron pipes and fittings of diameter : 100 mm	10.00	Each	300.00	3000.00	INR Three Thousand Only
84	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors : 100 mm inlet and 100 mm outlet Sand cast iron S&S as per IS: 1729	10.00	Each	800.00	8000.00	INR Eight Thousand Only
85	providing & fixing PTMT towel rail complete with brackets fixed to wooden cleats with cp brass screws with concealed fittings arrangement of approved quality and colour.: 450 mm long towel rail with total length of 495 mm. 78 mm wide and effective height of 88 mm, weighting not less than 170 gms.	2.00	Each	200.00	400.00	INR Four Hundred Only
86	Providing and fixing Chlorinate Polyvinyl Chloride (CPVC) pipes having thermal stability for hot & cold water supply including all (CPVC) plain & brass threaded fittings including fixing the pipe with clamps at 1.00 m spacing. This including jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of engineer in charge.: Internal Work - Exposed on Wall: 20 mm nominal outer dia pipes.	40.00	Metre	250.00	10000.00	INR Ten Thousand Only

Ramkesh
10/01/2025
SM(E-G)


Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
87	Providing and fixing Chlorinate Polyvinyl Chloride (CPVC) pipes having thermal stability for hot & cold water supply including all (CPVC) plain & brass threaded fittings including fixing the pipe with clamps at 1.00 m spacing. This including jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of engineer in charge.: Internal Work - Exposed on Wall: 25 mm nominal outer dia pipes.	35.00	Metre	300.00	10500.00	INR Ten Thousand Five Hundred Only
88	Providing and fixing Chlorinate Polyvinyl Chloride (CPVC) pipes having thermal stability for hot & cold water supply including all (CPVC) plain & brass threaded fittings including fixing the pipe with clamps at 1.00 m spacing. This including jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of engineer in charge.: Internal Work - Exposed on Wall: 32 mm nominal outer dia pipes.	35.00	Metre	400.00	14000.00	INR Fourteen Thousand Only
89	Providing and fixing Chlorinate Polyvinyl Chloride (CPVC) pipes having thermal stability for hot & cold water supply including all (CPVC) plain & brass threaded fittings including fixing the pipe with clamps at 1.00 m spacing. This including jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of engineer in charge.: Internal Work - Exposed on Wall: 40 mm nominal outer dia pipes.	17.00	Metre	500.00	8500.00	INR Eight Thousand Five Hundred Only
90	Providing and fixing Chlorinate Polyvinyl Chloride (CPVC) pipes having thermal stability for hot & cold water supply including all (CPVC) plain & brass threaded fittings including fixing the pipe with clamps at 1.00 m spacing. This including jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of engineer in charge.: Internal Work - Exposed on Wall: 50 mm nominal outer dia pipes.	12.50	Metre	700.00	8750.00	INR Eight Thousand Seven Hundred & Fifty Only
91	Providing and fixing Chlorinate Polyvinyl Chloride (CPVC) pipes having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This including jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the the same including testing of joints complete as per direction of engineer in charge: Concealed work including cutting chases and making good the walls etc: 20 mm nominal outer dia pipes	7.00	Metre	350.00	2450.00	INR Two Thousand Four Hundred & Fifty Only
92	Providing and fixing Chlorinate Polyvinyl Chloride (CPVC) pipes having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This including jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the the same including testing of joints complete as per direction of engineer in charge: Concealed work including cutting chases and making good the walls etc: 25 mm nominal outer dia pipes.	7.00	Metre	400.00	2800.00	INR Two Thousand Eight Hundred Only

Signature
10/01/2025
SM(E-C)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
93	Providing and fixing Chlorinate Polyvinyl Chloride (CPVC) pipes having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This including jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the the same including testing of joints complete as per direction of engineer in charge: Concealed work including cutting chases and making good the walls etc: 32 mm nominal outer dia pipes.	25.00	Metre	500.00	12500.00	INR Twelve Thousand Five Hundred Only
94	Providing and fixing brass stop cock of approved quality complete.: 15 mm nominal bore	10.00	Each	600.00	6000.00	INR Six Thousand Only
95	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end): 25 mm dia nominal bore	6.00	Each	600.00	3600.00	INR Three Thousand Six Hundred Only
96	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet : 150 mm diameter	1.00	Each	500.00	500.00	INR Five Hundred Only
97	Providing and placing on terrace (at all floor levels) Polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement amd making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	10000.00	Litre	8.00	80000.00	INR Eighty Thousand Only
98	Providing and fixing unplasticised P.V.C connection pipe with PTMT Nuts collar and bush of approved quality and colour.: 15mm nominal bore with 45cm length	6.00	Each	100.00	600.00	INR Six Hundred Only
99	Providing and laying cement concrete 1:5:10 (1 cement: 5 coarse sand: 10 graded stone aggregate 40 mm nominal size) all-round SW including bed concrete as per standard design.: 100mm diameter	25.00	Metre	400.00	10000.00	INR Ten Thousand Only
100	Providing and fixing square mouth SW gully trap class SP-1 complete with CI grating brick masonry chamber and water tight CI cover with frame of 300 x 300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg. as per standard design.: 180x150mm size P type: with common burnt clay F.P.S. (non modular) bricks of class designation 3.5	10.00	Each	1200.00	12000.00	INR Twelve Thousand Only
101	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : 300 mm dia. R.C.C. pipe	14.00	Metre	800.00	11200.00	INR Eleven Thousand Two Hundred Only
102	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : Powder coated aluminium (minimum thickness of powder coating 50 micron)	100.00	Kg	500.00	50000.00	INR Fifty Thousand Only

Signature
10/01/2025
SM(E-C)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
103	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) Powder coated aluminium (minimum thickness of powder coating 50 micron)	100.00	Kg	500.00	50000.00	INR Fifty Thousand Only
104	Providing and fixing 12mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. Pre-laminated particle board with decorative lamination on both sides.	30.00	Sqm	900.00	27000.00	INR Twenty Seven Thousand Only
105	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5.50 mm thickness	51.00	Sqm	1200.00	61200.00	INR Sixty One Thousand Two Hundred Only
106	Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS : 6315, having brand logo embossed on the body / plate with double spring mechanism and door weight upto 125 kg., for doors, including cost of cutting floors , embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charge. With stainless steel cover plate minimum 1.25 mm thickness.	15.00	Each	2400.00	36000.00	INR Thirty Six Thousand Only
107	Filling the gap in between aluminium frame & adjacent RCC/ Brick/ Stone work by providing weather silicon sealant over backer rod of approved quality as per architectural drawings and direction of Engineer-in-charge complete. Upto 5mm depth and 5 mm width	15.00	Sqm	50.00	750.00	INR Seven Hundred & Fifty Only
108	Providing and fixing aluminium tubular handle bar 32 mm outer dia, 3.0 mm thick & 2100 mm long with SS screws etc .complete as per direction of Engineer-in-Charge. Powder coated minimum thickness 50 micron aluminium tubular handle bar	15.00	Each	500.00	7500.00	INR Seven Thousand Five Hundred Only
109	Providing and fixing anodised aluminium grill (anodised transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P. brass/ stainless steel screws @ 200 mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, all complete as per requirement and direction of Engineer-in-charge. (Only weight of grill to be measured for payment).	50.00	Kg	500.00	25000.00	INR Twenty Five Thousand Only
110	Providing and fixing 12 mm thick frameless toughened glass door shutter of approved brand and manufacture, including providing and fixing top & bottom pivot & spring type fixing arrangement and making necessary holes etc. for fixing required door fittings, all complete as per direction of Engineer-in-charge (Door handle, lock and stopper etc.to be paid separately).	40.00	Sqm	6000.00	240000.00	INR Two Lakh Forty Thousand Only


 10/01/2025
 sm(E-C)


Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
111	Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc consisting of following operations: (a) Applying a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with water proofing compound conforming to IS. 2645 and approved by Engineer-in-charge over the RCC slab including adjoining walls upto 300 mm height including cleaning the surface before treatment. (b) Laying brick bats with mortar using broken bricks/brick bats 25 mm to 115 mm size with 50% of cement mortar 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge over 20 mm thick layer of cement mortar of mix 1:5 (1 cement :5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge to required slope and treating similarly the adjoining walls upto 300 mm height including rounding of junctions of walls and slabs. (c) After two days of proper curing applying a second coat of cement slurry using 2.75 kg/ sqm of cement admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge. (d) Finishing the surface with 20 mm thick jointless cement mortar of mix 1:4 (1 cement :4 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge including laying glass fibre cloth of approved quality in top layer of plaster and finally finishing the surface with trowel with neat cement slurry and making pattern of 300x300 mm square 3 mm deep. (e) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test."All above operations to be done in order and as directed and specified by the Engineer-in-Charge : With average thickness of 120 mm and minimum thickness at khurra as 65 mm.	77.12	Sqm	1300.00	100256.00	INR One Lakh Two Hundred & Fifty Six Only
112	Design and preparation of detailed working drawings for proposed renovation of interiors and exterior facade of various buildings in engineering complex and site developments along with the 3 d views for proposed developments by the Architect. The local architect from Nagpur with experience more than 10 years and with a valid registration with council of architecture is to be appointed taking approval from the engineer in charge. The appointed architect will supply required working drawings and will visit the site from time to time to supervise the execution of the proposed works and will certify the quality of works as per directed by the Engineer-In-Charge.	1.00	Job	240000.00	240000.00	INR Two Lakh Forty Thousand Only
113	Providing and fixing false ceiling with 7.5 mm thick PVC plain panel board ceiling of approved quality in aluminium frame work with necessary screws etc all complete as per directed by the Engineer-In-Charge.	704.52	Sqm	2000.00	1409040.00	INR Fourteen Lakh Nine Thousand & Forty Only
114	Carriage of excavated earth by mechanical transport including loading, unloading and stacking for lead upto 1 Kms complete as per directed by the Engineer-In-Charge.	150.00	cum	380.00	57000.00	INR Fifty Seven Thousand Only
115	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	250.00	Kg	630.00	157500.00	INR One Lakh Fifty Seven Thousand Five Hundred Only

Signature
10/01/2025
sm(E-C)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
116	Providing & fixing PVC multichamber profiled wall panelling sheet at all heights protruding from wall 50mm to 75mm or more or less as per site requirement including providing & fixing of framework made of special section, power pressed from M.S. sheets and galvanised with zinc coating and consisting of angle cleat of size 25mm wide x 0.6mm thick with appropriate flanges at 600mm c/c. one flange fixed to the wall with necessary fixtures using screws or dash fastener or nut bolts of required. size other flange of angle cleat fixed to the main trapezoidal sheet section of thickness not less than 0.4 mm with top 35mm and bottom expand upto 65mm spaced at 600 mm c/c. The perimeter edge of PVC profiled sheet / tiles shall covered by extruded PVC same colour corner bedding fixing with screws or with appropriate fixtures. The PVC multichamber hollow section of size 250mm x 6mm overall thick percisely engineered "Rib and Flute" or "Tongue and Groove" joint with concealed screws fixed on structure in such a way that no framework elements is visible from out sides as per manufacture's specification. Nothing extra payable for any extra fixtures or fitting material required for maintaining true line and level. The cost of making opening for light fittings, grills, diffusers, cut outs made with frame of perimeter channels suitably fixed, all complete as per satisfaction and direction of the Engineer in charge.	581.00	Sqm	2000.00	1162000.00	INR Eleven Lakh Sixty Two Thousand Only
117	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of M sand, compacting and proper embedding/laying of inter locking paver blocks into the M sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with M sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. 60mm thick cement concrete paver block of M-35 grade with approved colour, design & pattern.	532.00	Sqm	840.00	446880.00	INR Four Lakh Forty Six Thousand Eight Hundred & Eighty Only
118	Fixing available precoated galvanised iron profile sheets by using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	200.00	Sqm	400.00	80000.00	INR Eighty Thousand Only
119	Providing & Fixing in position with Table made up of 1. Top Panel in 25mm thick. Prelam Partical Board Matt Finished with pvc edge binding machine pressed from all sides. 2. Modesty (Full Height Modesty) in 18mm thick. Prelam Partical Board Matt Finished with pvc edge binding machine pressed from all sides. 3. Base Support CRCA Pipe frame 25x75x1.6mm Powder Coated. including neccessary Hardware etc. as per approved shade & colour. Cabin Type-A Table_(Width 1950mm x Height 750mm x Depth 900mm)	3.00	Each	17000.00	51000.00	INR Fifty One Thousand Only
120	Providing & Fixing in position with Credenza made up of 1. Top Panel in 25mm thick. Prelam Partical BoardMatt Finished with pvc edge binding machine pressed from all sides. 2. Shutter , Carcase & Drawer Facia in 18mm thick. Prelam Partical Board Matt Finished with pvc edge binding machine pressed from all sides. 3. Carcase Back & Drawer Bottom in 9mm thick. Prelam Partical Board Matt Finished. including neccessary Hardware Regular Handle , Drawer Lock , Regular Non-Soft Closed Hinges & Regular Non-Soft Closed Telescopic Rail etc. complete as per approved shade & colour. Side Credenza (3 Top Drawers & 3 Base Shutter)_(Width 1200 x Height 750 x Depth 430+20)	4.00	Each	10000.00	40000.00	INR Forty Thousand Only

Ramlesh
10/01/2025
SM(E-C)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
121	Providing & Fixing in position with Table made up of 1. Top Panel in 25mm thick. Prelam Partical Board Matt Finished with pvc edge binding machine pressed from all sides. 2. Modesty (Full Height Modesty) in 18mm thick. Prelam Partical Board Matt Finished with pvc edge binding machine pressed from all sides. 3. Base Support CRCA Pipe frame 25x75x1.6mm Powder Coated. including neccessary Hardware etc. as per approved shade & colour. Workstation Type-B & C Table_(Width 2100mm x Height 750mm x Depth 900mm)	4.00	Each	17000.00	68000.00	INR Sixty Eight Thousand Only
122	Providing & Fixing in position with Credenza made up of 1. Top Panel in 25mm thick. Prelam Partical Board Matt Finished with pvc edge binding machine pressed from all sides. 2. Shutter , Carcase & Drawer Facia in 18mm thick. Prelam Partical Board Matt Finished with pvc edge binding machine pressed from all sides. 3. Carcase Back & Drawer Bottom in 9mm thick. Prelam Partical Board Matt Finished. including neccessary Hardware Regular Handle , Drawer Lock , Regular Non-Soft Closed Hinges & Regular Non-Soft Closed Telescopic Rail etc. complete as per approved shade & colour. Side Credenza (2 Top Drawers & 2 Base Shutter)_(Width 820 x Height 750 x Depth 430+20)	4.00	Each	8000.00	32000.00	INR Thirty Two Thousand Only
123	Providing & Fixing in position with pedestal made up of 1. Top Panel in 18mm thick. Prelam Partical Board Matt Finished with pvc edge binding machine pressed from all sides. 2. Drawer Facia & Carcase in 18mm thick. Prelam Partical Board Matt Finished with pvc edge binding machine pressed from all sides. 3. Carcase Back & Drawer Bottom in 9mm thick. Prelam Partical Board Matt Finished. including neccessary Regular Handle , Multidrawer Lock , Regular Non-Soft ClosedTelescopic Rail etc. complete as per approved shade & colour. 3 Drawer Pedestal_(w400xh670xd430+20)	14.00	Each	6000.00	84000.00	INR Eighty Four Thousand Only
124	Base Shelf Unit (2 Shutter , Internal Shelf 1)_(Width 858 x Height 750 x Depth 580+20) Providing & Fixing in position with Base Shelf Unit made up of 1. Top Panel in 25mm thick. Prelam Partical Board Matt Finished with pvc edge binding machine pressed from all sides. 2. Shutter & Carcase in 18mm thick. Prelam Partical Board Matt Finished with pvc edge binding machine pressed from all sides. 3. Carcase Back in 9mm thick. Prelam Partical Board Matt Finished. Including neccessary Hardware Regular Handle , Regular Non-Soft Closed Hinges etc. complete as per approved shade & colour.	3.00	Each	6000.00	18000.00	INR Eighteen Thousand Only
125	Wall Cabinet (2 Shutter , Internal Shelf 1)_(Width 936 x Height 750 x Depth 350+20) Providing & Fixing in position with Wall Cabinet made up of 1. Shutter & Carcase in 18mm thick. Prelam Partical Board Matt Finished with pvc edge binding machine pressed from all sides. 2. Carcase Back in 9mm thick. Prelam Partical Board Matt Finished. Including neccessary Hardware Regular Bottom Profile for Handle Purpose , Regular Non-Soft Closed Hinges etc. complete as per approved shade & colour.	22.00	Each	6000.00	132000.00	INR One Lakh Thirty Two Thousand Only
126	Tall Shelf Unit (4 Shutter , Internal Shelf 5)_(Width 806 x Height 2100 x Depth 580+20) Providing & Fixing in position with Tall Shelf Unit made up of 1. Shutter & Carcase in 18mm thick. Prelam Partical Board Matt Finished with pvc edge binding machine pressed from all sides. 2. Carcase Back in 9mm thick. Prelam Partical Board Matt Finished. Including neccessary Hardware Regular Handle , Regular Non-Soft Closed Hinges etc. complete as per approved shade & colour.	6.00	Each	17000.00	102000.00	INR One Lakh Two Thousand Only


 10/01/2025
 SM(E-C)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
127	Providing and fixing Signage no.I (Main Gate) MS frame (18 gauge) mounted with 3mm ACP panelling (Any Colour) with 3 mm Acrylic letters 2" deep (any Colour) Letters and logo will have LED lights (ADS LED by Samsung with water proof water supply) inside.The test matter will be "Airports Authority of India" in English and Marathi/Hindi along with the "AAI logo". Each English Letter will be 16 inch in height.(Total 24 English Letters).Each Marathi/Hindi Letters height will be 22.5 inch (including Kanna matra) Logo height will be 36 inch at Engineering complex including Scaffolding and other materials all complete as per requirement and direction of Engineer-in-charge.	1.00	Job	100000.00	100000.00	INR One Lakh Only
128	Providing and fixing Signage no.III (Waiting room at New HR Building) MS frame (18 gauge) mounted with 3mm ACP panelling (Any Colour) with 3 mm Acrylic letters 2" deep (any Colour) Letters and logo will not have LED lights .The test matter will be "Airports Authority of India" in English and Marathi/Hindi along with the "AAI logo". Each English Letter will be 10 inch in height.(Total 24 English Letters).Each Marathi/Hindi Letters height will be 16 inch (including Kanna matra) Logo height will be 24 inch at Engineering complex including Scaffolding and other materials all complete as per requirement and direction of Engineer-in-charge.	1.00	Job	30000.00	30000.00	INR Thirty Thousand Only
129	Providing and fixing Signage no.II (Finance Section Building) Flat Acrylic Letters 12 mm deep/thick (any colour) directly mounted on wall (Any Colour). Letters and logo will not have LED lights inside.The test matter will be "Airports Authority of India" in English and Marathi/Hindi along with the "AAI logo". Each English Letter will be 6 inch in height.(Total 24 English Letters).Each Marathi/Hindi Letters height will be 8.5 inch (including Kanna matra) Logo height will be 14.5 inch at Engineering complex including Scaffolding and other materials all complete as per requirement and direction of Engineer-in-charge.	1.00	Job	30000.00	30000.00	INR Thirty Thousand Only
130	Dismantling the G.I. chain link fabric fencing by removing the necessary nuts, bolts, and washers, along with the angle truss of the required width, having mesh sizes of 50x50 mm with 3 mm diameter wire mesh (along a length of 210 meters) and angle size of 50x50x5 mm, completing the work as per the direction of the Engineer-in-charge.	1.00	Job	25000.00	25000.00	INR Twenty Five Thousand Only
131	Credit items value for old fencing wire mesh (Size 50x50 mm with 3 mm diameter) and angles (50x50x5 mm & 40x40x5mm) @50/Kg.completing the work as per the direction of the Engineer-in-charge.	2270.20	Kg	10.00	-22702.00	INR Minus Twenty Two Thousand Seven Hundred & Two Only
132	Providing and fixing C.P. brass two way bib cock (Kerovit,Cera and Hindware) of approved quality conforming to IS standards complete as per direction of Engineering in charege 15mm bonimal bore	13.00	Each	1200.00	15600.00	INR Fifteen Thousand Six Hundred Only
133	Preparation and submission of detailed analysis, Structural design and drawings of proposed New HR offices at Engg Complex. All drawings & designs to be submitted in 3 sets along with soft copy.Visit of consultant during each stage & as and when desired by EIC at the time of execution of work.	157.50	Sqm	500.00	78750.00	INR Seventy Eight Thousand Seven Hundred & Fifty Only
134	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineerin- charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	220.00	Sqm	600.00	132000.00	INR One Lakh Thirty Two Thousand Only

Signature
10/01/2025
SM(EC)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
135	SH : ELECTRICAL WORKS					
135.1	Wiring for light point / fan point / exhaust fan point / call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required.	168.00	Point	1140.00	191520.00	INR One Lakh Ninety One Thousand Five Hundred & Twenty Only
136	Wiring for group controlled (looped) light point / fan point / exhaust fan point / call bell point (without independent switch etc.) with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface / recessed PVC conduit, and earthing the point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc. as required.	63.00	Point	740.00	46620.00	INR Forty Six Thousand Six Hundred & Twenty Only
137	Wiring for circuit / submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.					
137.1	2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire.	681.00	Mtr.	270.00	183870.00	INR One Lakh Eighty Three Thousand Eight Hundred & Seventy Only
137.2	2 X 4 sq. mm + 1 X 4 sq. mm earth wire.	867.00	Mtr.	310.00	268770.00	INR Two Lakh Sixty Eight Thousand Seven Hundred & Seventy Only
138	Supplying and fixing following modular switch / socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.					
138.1	5/6 A switch.	50.00	Each	70.00	3500.00	INR Three Thousand Five Hundred Only
138.2	3 pin 5/6 A socket outlet.	50.00	Each	120.00	6000.00	INR Six Thousand Only
139	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	24.00	Each	340.00	8160.00	INR Eight Thousand One Hundred & Sixty Only
140	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as required.	76.00	Each	440.00	33440.00	INR Thirty Three Thousand Four Hundred & Forty Only
141	Supplying and fixing 20 amps, 240 volts, SPN industrial type, socket outlet, with 2 pole and earth, metal enclosed plug top alongwith 20 amps "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket outlet and complete with connections, testing and commissioning etc. as required.	22.00	Each	1220.00	26840.00	INR Twenty Six Thousand Eight Hundred & Forty Only
142	Supplying and drawing following pair 0.5 mm dia FRLS PVC insulated annealed copper conductor, unarmoured telephone cable in the existing surface / recessed steel / PVC conduit as required.					
142.1	2 Pair	645.00	Metre	33.00	21285.00	INR Twenty One Thousand Two Hundred & Eighty Five Only
143	Supplying and drawing of UTP 4 pair CAT 6 unarmoured LAN Cable in the existing surface / recessed Steel / PVC conduit as required.					
143.1	1 run of Cable	205.00	Metre	44.00	9020.00	INR Nine Thousand & Twenty Only
143.2	2 run of Cable	245.00	Metre	72.00	17640.00	INR Seventeen Thousand Six Hundred & Forty Only

Signature
10/10/2025
SM(EE)

Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
143.3	3 run of Cable	195.00	Metre	110.00	21450.00	INR Twenty One Thousand Four Hundred & Fifty Only
144	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface / recess including cutting the wall and making good the same in case of recessed conduit as required.					
144.1	25 mm	340.00	Metre	105.00	35700.00	INR Thirty Five Thousand Seven Hundred Only
145	Supplying and fixing Telephone socket outlet (RJ 11 Socket Outlet) alongwith 1 / 2 module metal box, 1 module modular base & cover plate in recess / on surface including connections etc. as required.	37.00	Each	200.00	7400.00	INR Seven Thousand Four Hundred Only
146	Supplying and fixing Computer Jack RJ 45 (Cat 6), 1 Module, alongwith 1/2 module metal box, 1 module modular base & cover plate in recess / on surface including connections etc. as required.	36.00	Each	450.00	16200.00	INR Sixteen Thousand Two Hundred Only
147	Supplying & Fixing Krone Connection box (IP 42 suitable for 10 pair RC Cable made out of 14 SWG MS Junction box with 10 pair incoming & 10 Pair outgoing) with Krone type disconnection module (Krone Connector) suitable for electronic exchange with proper locking arrangement etc. complete as required.	1.00	Job	2500.00	2500.00	INR Two Thousand Five Hundred Only
148	Supplying and fixing following way, horizontal / verticle type, three pole and neutral, sheet steel, MCB distribution board, 415 volts, on surface / recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)					
148.1	For 4 way (4 + 12), Double door TPN MCBDB	1.00	Each	7300.00	7300.00	INR Seven Thousand Three Hundred Only
148.2	For 6 way (4 + 18), Double door TPN MCBDB	1.00	Each	9300.00	9300.00	INR Nine Thousand Three Hundred Only
148.3	For 8 way (8 + 24), Double door TPN MCBDB	3.00	Each	11000.00	33000.00	INR Thirty Three Thousand Only
149	Supplying and fixing following rating, 240/415 volts, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
149.1	6 A to 32 A ratings, SP MCB.	92.00	Each	175.00	16100.00	INR Sixteen Thousand One Hundred Only
149.2	40 A ratings, FP MCB.	2.00	Each	1650.00	3300.00	INR Three Thousand Three Hundred Only
149.3	63 A ratings, FP MCB.	3.00	Each	2000.00	6000.00	INR Six Thousand Only
150	Supply of size 48" (1200 mm) Ceiling fan suitable for operating on 230V AC supply etc. as required.	24.00	Each	2200.00	52800.00	INR Fifty Two Thousand Eight Hundred Only
151	Installation, testing and commissioning of ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable etc. complete as required.	24.00	Each	150.00	3600.00	INR Three Thousand Six Hundred Only
152	Supply of 250 mm light duty Exhaust Fan with suitable louvers / shutters complete with frame operating on 230V AC etc. complete as required (Havells make Ventil Air DX Super White model FHVVEDXWHT10 or equivalent).	14.00	Each	2500.00	35000.00	INR Thirty Five Thousand Only
153	Installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. complete as required. (Upto 450 mm sweep).	14.00	Each	150.00	2100.00	INR Two Thousand One Hundred Only

Handwritten signature
10/01/2025
SM(E-C)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
154	Supply of 600mm x 600mm recess mounted LED fixture with high efficiency polymethyl methacrylate (PMMA) diffuser, complete with driver and accessories having luminaire efficacy not less than 100 Lumens / watt, suitable for indoor applications and as per technical specifications etc. as required. (Crompton Polaris Nio-I/II LCTLRNE-36-FO-CDL / Bajaj BZRSQ 36L LED GX WH or equivalent)	20.00	Each	2100.00	42000.00	INR Forty Two Thousand Only
155	Supply of recessed mounted 18 W LED round cool day light (CDL) panel light fixture made of aluminium die cast, i/c. necessary electronic driver, diffuser, LED lamp with minimum 100 lumen/watt efficiency suitable to operate on 230V AC power supply etc. as per specifications complete as required. (Havells LHEBADP7IZ1W018 / Bajaj BGSLO Sleek Recess RD 18W WH LED or equivalent)	97.00	Each	1230.00	119310.00	INR One Lakh Nineteen Thousand Three Hundred & Ten Only
156	Supply of 20 Watt Batten type LED tube light fitting having double side connection i/c. necessary electronic driver suitable to operate on 230V AC power supply as per specifications complete as required. (Crompton, Bright Linea CCS-100-20-65-HL2-DP-NWH / Bajaj BCLAB 20W LED P or equivalent).	20.00	Each	450.00	9000.00	INR Nine Thousand Only
157	Supply of 45 watt LED street light fitting made of aluminium die cast, system efficacy not less than 110 lumens per watt, weatherproof gasket for lamp, control gear accessories, suitable for mounting on existing bracket, electronic driver and accessories complete as per specifications etc. as required. (Crompton Wanderer plus Ref. TRP-417-45-57-SL-LM-NBK / Bajaj ENXT P 54L WH PO PC SD MT or equivalent)	4.00	Each	2500.00	10000.00	INR Ten Thousand Only
158	Supply of 200 Watt Flood LED Light fixture having minimum 110 lumen/watt output with powder coated pressure die-cast aluminium housing with toughened glass, high power LED's with IP 66 protection, weatherproof gasket for lamp and control gear accessories as per technical specifications etc. as required. (Crompton, Pluto Neo Aura TFS-507-200-57-NL-SL-GL-NSG / PRAZE F 240L WH NB-A5 TG SD or equivalent)	5.00	Each	6800.00	34000.00	INR Thirty Four Thousand Only
159	Supply of 40 watt suspended standalone luminaire i/c. aluminium die-cast housing with mounting arrangement on ceiling, driver and accessories having luminaire efficacy not less than 100 Lumens / watt, suitable for indoor applications and as per technical specifications etc. as required. (Bajaj BPCS 40W LED WH 4F or equivalent).	15.00	Each	3400.00	51000.00	INR Fifty One Thousand Only
160	SITC of 24 watt LED Profile / Strip light along with aluminium housing & capping, size 17 X 8 mm, 12 V 2A driver & accessories complete as required. (Havells Flex. Neo LED Strip 24 W 5 M or equivalent)	20.00	Metre	3400.00	68000.00	INR Sixty Eight Thousand Only
161	Installation, testing and commissioning of pre-wired, LED fitting / fluorescent fitting / compact fluorescent fitting of all types, complete with all accessories and tube etc. directly on ceiling/ wall, including connection with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	152.00	Each	150.00	22800.00	INR Twenty Two Thousand Eight Hundred Only
162	Supply of 400 mm size Wall Mounting Fan suitable to operate on 230V, 50 Hz, AC supply with all accessaires etc. compite as required.	10.00	Each	2400.00	24000.00	INR Twenty Four Thousand Only
163	Installation, testing and commissioning of wall mounted fan, including mounting arrangement with all accessaires etc. compite as required.	10.00	Each	100.00	1000.00	INR One Thousand Only

Samir
10/01/2025
SM(E-C)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
164	Supplying and fixing of 32 mm dia X 2.00 metres long G.I. pipe (medium class) bracket for mounting of LED/ fluorescent / HPMV / HPSV street light fitting on pole including bending the pipe to the required shape, 2 nos 40 mm X 3 mm flat iron clamps with nuts, bolts and washer, painting the flat iron with primer and finish paint etc. as required.	4.00	Each	1000.00	4000.00	INR Four Thousand Only
165	Supply & fixing of IP 66 weather proof loop in / loop out cable junction box suitable for outdoor installation, made out of thermoplastic polycarbonate (Make: Hensel CAT No. KF1616G (155 x 210 x 92 mm) or similar) with D-rail mounted terminals suitable for cable of size 10-16 Sqmm, with knockouts for cable entry, locking arrangement, 01 no earth terminal complete in all respect including fixing on wall / pole with suitable 2 mm thick GI clamps and nuts-bolts etc. complete as required.	6.00	Each	2400.00	14400.00	INR Fourteen Thousand Four Hundred Only
166	Installation, Testing and Commissioning of 30/45 W LED fitting on existing pole bracket / wall bracket including providing 3C x 1.5 sqmm PVC insulated copper conductor flexible cable of suitable length, connections etc. complete as required.	4.00	Job	200.00	800.00	INR Eight Hundred Only
167	Supply of following size XLPE/PVC insulated, PVC innersheathed, copper conductor armoured power cable of 1.1 KV grade as per IS 7098 (Part 1) 1988 with up to date amendments of approved make & as per technical specifications etc. complete as required.					
167.1	3 core X 2.5 sq.mm.	150.00	Metre	120.00	18000.00	INR Eighteen Thousand Only
168	Supply of following size XLPE/PVC insulated, PVC innersheathed, aluminium conductor armoured power cable of 1.1 KV grade as per IS 7098 (Part 1) 1988 with up to date amendments of approved make & as per technical specifications etc. complete as required.					
168.1	3.5 core X 70 sq.mm.	30.00	Metre	480.00	14400.00	INR Fourteen Thousand Four Hundred Only
168.2	4 core X 25 sq.mm.	130.00	Metre	210.00	27300.00	INR Twenty Seven Thousand Three Hundred Only
169	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade size up-to 35 sq.mm. in the existing RCC/HUME/Metal/DWC/GI pipe as required.	200.00	Metre	30.00	6000.00	INR Six Thousand Only
170	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of size above 35 sq.mm. and upto 95 sq.mm. in the existing RCC/HUME/Metal/DWC/GI pipe as required.	20.00	Metre	50.00	1000.00	INR One Thousand Only
171	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade up-to 35 sq.mm. size clamped with 1 mm thick saddle on wall surface etc. complete as required.	80.00	Metre	40.00	3200.00	INR Three Thousand Two Hundred Only
172	Supplying and making end termination with brass compression gland and copper lugs for following size of PVC insulated and PVC sheathed / XLPE Copper conductor cable of 1.1 KV grade etc. complete as required.					
172.1	3 core X 2.5 sq.mm.	12.00	Set	200.00	2400.00	INR Two Thousand Four Hundred Only
173	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE Aluminium conductor cable of 1.1 KV grade etc. complete as required.					
173.1	3.5 core X 95 sq.mm.	2.00	Set	500.00	1000.00	INR One Thousand Only

Ramkishan
10/01/2025
SM(E-C)


Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
173.2	3.5 core X 120 sq.mm.	3.00	Set	650.00	1950.00	INR One Thousand Nine Hundred & Fifty Only
173.3	4 core X 25 sq.mm.	6.00	Set	300.00	1800.00	INR One Thousand Eight Hundred Only
174	Supply of 50 mm size (OD-50 mm & ID-38 mm nominal) DWC HDPE pipe ISI marked along with all accessories like couplers etc. complete as required.	200.00	Metre	93.00	18600.00	INR Eighteen Thousand Six Hundred Only
175	Laying of 50 mm DWC HDPE pipe complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required.	200.00	Metre	98.00	19600.00	INR Nineteen Thousand Six Hundred Only
176	Providing, laying and fixing 100 mm dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc. as required.	24.00	Metre	1350.00	32400.00	INR Thirty Two Thousand Four Hundred Only
177	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia, B class including accessories, and providing masonry enclosure with cover plate having locking arrangement with charcoal/coke and salt etc. complete as required.	1.00	Set	7500.00	7500.00	INR Seven Thousand Five Hundred Only
178	Providing and laying earth connection from earth electrode with 6 SWG dia G.I. Wire in 15 mm dia B class G.I. pipe from earth electrode including connection with G.I. thimble excavation and re-filling etc. complete as required.	10.00	Metre	230.00	2300.00	INR Two Thousand Three Hundred Only
179	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and GI watering pipe, B class of 2.7 metre long etc. (with charcoal/ coke and salt) as required.	1.00	Set	7500.00	7500.00	INR Seven Thousand Five Hundred Only
180	Providing and fixing 25 mm X 5 mm GI strip in 40 mm dia B class G.I. pipe from earth electrode including connection with G.I. nut, bolt, spring, washer excavation and re-filling etc. as required.	20.00	Metre	600.00	12000.00	INR Twelve Thousand Only
181	Providing & fixing of 25 mm X 5 mm GI strip on surface or in recess for connections etc. as required.	5.00	Metre	180.00	900.00	INR Nine Hundred Only

Agmish
10/01/2025
SM(E-C)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
182	Design, Fabrication, Supply, Installation, Testing and Commissioning of cubicle type, IP-65 outdoor LT panel - floor mounting, free standing, suitable for 415V+/-10%, 3 Phase, 4 wire, 50 Hz AC supply system, fabricated in compartmentalized modular design from CRCA sheet steel of 1.6 mm thick for frame work and covers, 3 mm thick for gland plates i/c cleaning & finishing complete with 7 tank process for powder coating in approved shade, TPN Aluminium bus bars of high conductivity, SMC / DMC bus bar supports, with short circuit withstand capacity of 50 KA for 1 sec, bottom base channel of MS section not less than 100 mm x 75 mm x 5 mm thick, entire panel shall have a common Al. earth bus bar of suitable size at the rear end with 2 Nos. earth stud, solid / flexible connections from main bus bar to switchgears and from switchgear output to cable termination in cable alley with required size of Copper conductors / Aluminium bus bars and control wiring with 2.5 sqmm PVC insulated copper conductor cable (FRLS), cable alleys, cable gland plates in two half, complete with all accessories, interconnection, interlocking, earthing i/c providing following switchgears / accessories as per specifications. The panel shall be mounted on MS angle stand to be grouted in 1:2:4 concrete of 100 X 100 X 300 mm depth, providing & laying in position cement concrete (PCC) of specified grade around the panel (PCC Size 1Mtr X 1 Mtr X 0.25 Mtr) (1:2:4) (1 cement: 2 coarse sand: 4 graded stone aggregate 40mm nominal size) etc. as per technical specifications as required. A) Incomers & Bus coupler: i) 250 Amps, 36 kA, Four Pole MCCB (Ics = 100% Icu), with O/L and S/C Fault Protection with Adjustable Thermal and Adjustable Magnetic Releases + Ammeter with in-built selector switch, class-1 accuracy & suitable range of cast resin CTs (03 Nos) including connections etc. as required. - 3 Sets. (Incomer - 2 Nos. & Bus-Coupler - 1 No.)					
182.1	ii) Intelligent Digital Multi Function Meter to read V, A, kVA, KW, KVAR, PF, Hz, THD and individual order harmonics up to 31st Order etc. with communication facility (RS-485 port), CL-1.0, LED display with 03 Nos of CTs, 100/5, 1 VA, Class 1.0 and control circuit wiring with 2 Amps MCBs for controlling and protection. - 2 Sets. iii) 3 Phase 4 Wire kWh meter, CT op base mounting, class accuracy 0.5 sec. with suitable range of cast resin CTs (03 Nos) including connections of class 1.0 - 2 Sets. iv) R, Y, B Phase indicating lamps, LED type, with 2 Amp MCB for protection. - 2 Sets. v) 1 Set of Indication Lamps, LED type for MCCB 'ON', 'OFF', 'TRIP' with 02 Amps MCB for protection - 3 Sets. vi) Auxiliary contacts / contactors, auxiliary relays, shunt trip etc... for positive interlocking of the incomer MCCBs and bus coupler MCCB as required. - 1 Set. B) Main Busbars: TPN, high conductivity Aluminium main bus bars of minimum of 500 Amps. capacity with heat shrinkable coloured sleeves and i/c DMC / SMC bus bars cross section supports & their spacing etc... For withstanding fault level of 50 kA capacity for 1 sec. - 1 Set C) Outgoings: i) 63 Amps, 10 kA, Four Pole, 'C Curve' MCB. - 12 Nos. ii) 40 Amps, 10 kA, Four Pole, 'C Curve' MCB. - 4 Nos.	1.00	Job	340000.00	340000.00	INR Three Lakh Forty Thousand Only
183	Supply of Inverter type, 5 Star rating, 1.5 TR split air conditioner having rotary / scroll type compressor, 100% copper condenser, with cordless remote control, refrigerant type R-32, suitable for operation on 230 V AC, 50 Hz, 1-Ph power supply etc. complete as per technical specifications as reqd.	8.00	Each	4000.00	32000.00	INR Thirty Two Thousand Only
184	Supply of Inverter type, 5 Star rating, 2.0 TR split air conditioner having rotary / scroll type compressor, 100% copper condenser, with cordless remote control, refrigerant type R-32, suitable for operation on 230 V AC, 50 Hz, 1-Ph power supply etc. complete as per technical specifications as required.	10.00	Each	58000.00	580000.00	INR Five Lakh Eighty Thousand Only

Ramlesh
10/01/2025
SM(E-C)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (Excluding GST) To be entered by the Bidder in Rs. P	TOTAL AMOUNT (Excluding GST) in Rs. P	TOTAL AMOUNT (Excluding GST) In Words
1	2	4	5	13	53	55
185	Installation, testing & commissioning of 1.5/2 TR split air conditioner by fixing indoor unit on wall/ceiling/structure and outdoor unit on wall/stand including providing & fixing suitable size duly painted / powder coated M.S. / G.I. equal angle base frame (ODU Stand), providing and fixing suction/discharge refrigerant copper piping with elastomeric nitrile rubber insulation (Up to 4 Mtrs), control cabling (Up to 4 Mtrs) from indoor to outdoor unit, fasteners, charging of refrigerant gas i/c minor civil works and all accessories etc. complete as required.	18.00	Each	1800.00	32400.00	INR Thirty Two Thousand Four Hundred Only
186	Supply & fixing (Over and above 4 Mtrs included in Item No: 183 & 184) of suction/ discharge refrigerant copper piping for 1.5/2 TR split AC insulated elastomeric nitrile rubber between indoor and outdoor units with suitable size of clamp / MS hanger / MS support / MS angle as per site requirement and as per technical specifications as required.	60.00	Mtr.	1000.00	60000.00	INR Sixty Thousand Only
187	Supply & fixing 25 mm dia. UPVC drain pipe including cutting, jointing with solvent compound etc. complete as required.	50.00	Mtr.	100.00	5000.00	INR Five Thousand Only
188	Supply of 4 C x 2.5 Sq. mm PVC insulated, PVC sheathed unarmored multi stranded copper cable as per IS : 694 etc. as required.	100.00	Mtr.	150.00	15000.00	INR Fifteen Thousand Only
189	Dismantling of existing split air conditioners of 1.5 TR / 2.0 TR capacity & shifting the complete unit up to AAI's store or as directed by Engineer-in-charge.	8.00	Job	500.00	4000.00	INR Four Thousand Only
190	Dismantling of existing tower / mega split air conditioners of 2.5/3.0/3.5 TR capacity & shifting the complete unit up to AAI's store or as directed by Engineer-in-charge.	4.00	Job	500.00	2000.00	INR Two Thousand Only
191	Re-Installation, testing & commissioning of existing 1.0 / 1.5 / 2.0 TR split air conditioner by fixing indoor unit on wall / ceiling / structure and outdoor unit on floor / wall / stand including dehydration, providing charging of suitable refrigerant gas with leak testing, connections etc. complete as required.	8.00	Job	1800.00	14400.00	INR Fourteen Thousand Four Hundred Only
192	Re-Installation, testing & commissioning of existing 2.5 / 3.0 / 3.5 TR tower / mega split air conditioner by fixing indoor unit on wall / ceiling / structure and outdoor unit on floor / wall / stand including dehydration, providing charging of suitable refrigerant gas with leak testing, connections etc. complete as required.	3.00	Job	2500.00	7500.00	INR Seven Thousand Five Hundred Only
193	Supply, installation, testing & commissioning of Water cooler with in-built RO+UF purifier technology & having water storage tank capacity 20 Litres, purification capacity up-to 40 LPH, along with filter cartridges & RO Membrane of suitable rating, compressor with R134A refrigerant including all accessories, fittings etc. as required for installation & connection with existing water source point etc. complete as required. (Make: Kent, Model - Perk or similar)	1.00	Job	8000.00	8000.00	INR Eight Thousand Only
Total in Figures					15773778.90	INR One Crore Fifty Seven Lakh Seventy Three Thousand Seven Hundred & Seventy Eight and Paise Ninety Only
Quoted Rate in Words		INR One Crore Fifty Seven Lakh Seventy Three Thousand Seven Hundred & Seventy Eight and Paise Ninety Only				


 10/01/2025
 सूर्यवंशी
 Kamlesh Suryawanshi
 वरिष्ठ प्रबंधक (अभियंत्रिकी-सिविल)
 Senior Manager (Engg-Civil)
 भा.वि.प्र., डी.बी.ए.आई. विमानतल, नागपुर-45
 B.V.P., D.B.I.A. Airport, Nagpur-45