



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

भाविप्रा/वडोदरा/ई-सी/ Fire & MT Works/डब्ल्यू-274/2024-25/1148

दिनांक: 04/03/2025

AAI/Vadodara/E-C/ Fire & MT Works /W-274/2024-25

Date: 04/03/2025

सेवा में,

मेसर्स ओम कन्स्ट्रक्शन

311, मोहनदीप सोसायटी,

डभोली चार रास्ता के पास, वेद रोड,

सुरत - 395 004

To,

M/s. Om Construction

311, Mohandeep Society,

Near Dabholi Char Rasta, Ved Road,

Surat - 395 004

कार्य का नाम: सिविल एरोड्रम वडोदरा में एमटी पूल के पास रबर हटाने की मशीन के लिए पार्किंग शेड का प्रावधान तथा फायर स्टेशन की पहली मंजिल पर कमरों और शौचालय के नवीनीकरण का कार्य।

(निविदा आई. डी. - 2024_AAI_218922_1)

Name of Work: "Provision of parking shed for rubber removal machine near MT pool and rooms at 1st floor of fire station i/c toilet renovation at C.A. Vadodara."

(Tender ID - 2024_AAI_218922_1)

संदर्भ:- दिनांक 30/01/2025 को खोला गया आपका ई-टेंडर । (वित्तीय बोली)

Ref: Your e-tender opened on 30/01/2025 (Financial Bid)

महोदय/Sir,

- उपर्युक्त कार्य हेतु आपकी निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से, आपके द्वारा बताए गये मद दर मूल्यों पर निविदा की राशि कुल रु. 60,57,763.00 (रुपये साठ लाख सत्तावन हजार सात सौ तिरेसठ मात्र) (बगैर GST) स्वीकृत किया जाता है, जो कि निविदाकी अनुमानित लागत राशि रु. 75.28 Lakh (बगैर GST) से 19.53 % कम है।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs. 60,57,763.00 (Excluding GST) (Rupees Sixty Lakh Fifty-Seven Thousand Seven Hundred Sixty Three only), which is 19.53 % below the estimated cost put to tender of Rs. 75.28 Lakh (Excluding GST).

- सहायक महाप्रबंधक (अभि-सिविल), वडोदरा विमानक्षेत्र, वडोदरा कार्य प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप स्वयं या आपकी ओर से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 19.03.2025 तक सहायक महाप्रबंधक (अभि-सिविल), वडोदरा विमानक्षेत्र के कार्यालय में उपस्थित हो तथा करारनामे को पूरा करें। ठेके का करारनामा रु.300/- (रु. तीन सौ मात्र) के नोन ज्यूडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा स्टैम्प पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Assistant General Manager (Engg- Civil), Vadodara Airport, Vadodara shall be the Engineer-in-charge of the work. You are requested to attend or depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the office of the Assistant General Manager (Engg- Civil), Vadodara Airport by 19.03.2025 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.300/- (Rs. Three Hundred only) and the cost of the stamp paper shall be borne by you.

पवन नै. पारधी / PAWAN N. PARDHI

सहायक महाप्रबंधक (अभि-सि)
Asstt General Manager (E-C)

आर. विमान वडोदरा विमानक्षेत्र / AAI VADODARA AIRPORT

प्रमाणित
06.03.2025



3. इस पत्र के जारी होने की तारीख से 10 दिनों के भीतर सुरक्षा जमा राशि के लिए, **₹ 6,05,776.00 (रुपये छह लाख पांच हजार सात सौ छिहतर मात्र)** जमा करे जोकि अनुबंध मूल्य का 10% है। ऐसा न करने पर निविदा दस्तावेज़ के जीसीसी के खंड 1A पृष्ठ 16 के अनुसार यह राशि चालू खाता बिल से काट लिया जाएगा। आपके टेंडर के साथ प्राप्त ईएमडी राशि **₹. 1,50,560.00 (रुपये एक लाख पचास हजार पांच सौ साठ मात्र)** ऑनलाइन वापस कर दी जाएगी जब एसडी राशि ईएमडी से अधिक होगी।
Please deposit Rs. 6,05,776.00 (Rupees Six Lakh Five Thousand Seven Hundred Seventy - Six Only) i.e @10% of Contract value towards security deposit within 10 days from the date of issue of this letter, failing which the same shall be deducted from the Running Account Bills as per the Tender document Clause 1A GCC Page 16. The earnest money amount of **Rs 1,50,560.00 (Rupees One Lakh Fifty Thousand Five Hundred Sixty Only)**, received along with your tender shall be refunded online once SD amount exceeds the EMD
4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) 1971 केंद्रीय नियमों के प्रावधान का पालन करे, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण कार्यकर्ता (रोजगार का विनियमन और सेवा की शर्त) अधिनियम 1996, बिल्डिंग और अन्य निर्माण कार्यकर्ता कल्याण सेस अधिनियम 1996 जैसा कि निविदा के जीसीसी के खंड 19 पृष्ठ 49 और केंद्रीय तथा राज्य सरकार के नियमों में निर्दिष्ट है।
You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and Contract labour (Regulation and Abolition) Central rules 1971 Child labour (Prohibition and Regulation) Act 1986, Construction workers (Regulation of Employment and Condition of service) Act 1996, Building and other construction workers welfare cess act 1996 as specified in clause 19 page 49 of GCC of tender & minimum wage act and rules of Central and state government.
5. आपको निर्देश दिया जाता है कि आप तुरंत सहायक महाप्रबंधक (अभि-सिविल)/प्रबंधक(अभि-सिविल), वडोदरा विमानक्षेत्र से मिले वह आपको साइट सौंपने की व्यवस्था करेंगे। कृपया नोट कर ले कि काम करने का अनुमत समय **8 (आठ) महीना** जोकि बरसात के मौसम के 2 महीने सहित इस पत्र के जारी होने के दस दिन बाद से गिना जाएगा।
You are also directed to contact **Assistant General Manager (Engg-Civil) / Manager (Engg - Civil)** Vadodara Airport immediately who will arrange to hand over site to you. Please note that the time allowed for carrying out the work is **8 (Eight) Months i/c 2 month of Rainy season** which shall be reckoned from 10th days after the issuance of this letter.
6. इस ठेके के संबंध में आगे की कोई भी पत्राचार सहायक महाप्रबंधक (अभि-सिविल), वडोदरा विमानक्षेत्र, वडोदरा 390022 के पते पर किया जाए।
Any further correspondence in connection with the contract should normally be addressed to the Assistant General Manager (Engg- Civil) Vadodara Airport, Vadodara -390022.
7. उपरोक्त संदर्भित सभी पत्र इस ठेके का भाग होंगे।
All the letters referred above shall from part of contract.
8. उपर्युक्त कार्य के लिए त्रुटि दायित्व की अवधि **12 (बारह) महीने** होगी।
The defects liability period for the above-mentioned work is **12 (Twelve) months**.
9. यदि ठेकेदार सुरक्षा नियमों का भंग करेगा तो उनका कालियादी में सम्मिलित किया जाएगा एवं उचित कानूनी कार्यवाही के लिए भी जिम्मेदार होगा।
If Contractor is found Violate any of Security Regulations, he shall be Black listed and will be subjected to other Legal Proceedings.



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

10. स्वीकृति के प्रतीक के रूप में अधिसूचना में हस्ताक्षर करने के बाद कृपया इस पावती को स्वीकार करें और इस पत्र की नकल प्रतिलिपि वापस करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

11. यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण को सही रूप में लिया जाएगा ,
In case any discrepancy is found then English version will be taken as correct.

भवदीय /Yours faithfully

पवन नै. पारधी
04.03.2025

पवन नै. पारधी / PAWAN N. PARDHI

सहायक महाप्रबंधक (अभि-सि)

Asstt General Manager (E-C)

भा.वि.प्रा. वडोदरा विमानक्षेत्र /AAI, VADODARA AIRPORT

सहायक महाप्रबंधक (अभि-सिविल),

वडोदरा हवाईअड्डा, वडोदरा

कृतेअध्यक्ष,भारतीय विमानपत्तन प्राधिकरण

Assistant General Manager (Engg.-Civil),

Vadodara Airport, Vadodara

For and on behalf of Chairman

Airports Authority of India

Validate Print Help

Item Rate BoQ

Tender Inviting Authority: Assistant General Mangar (Engg. -Civil)

Name of Work: Provision of parking shed for rubber removal machine near MT pool and rooms at 1st floor of fire station i/c toilet renovation at C.A. Vadodara.

Contract No: 2024_AAI_218922_1

Name of the Bidder/ Bidding Firm / Company : OM CONSTRUCTION						
PRICE SCHEDULE						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	25.000	Cum	800.00	20000.00	INR Twenty Thousand & Paise Zero Only
2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead : For thickness of tiles 10 mm to 25 mm	245.000	Sqm	80.00	19600.00	INR Nineteen Thousand Six Hundred & Paise Zero Only
3	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	98.000	Sqm	80.00	7840.00	INR Seven Thousand Eight Hundred Forty & Paise Zero Only
4	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	5.000	Cum	1250.00	6250.00	INR Six Thousand Two Hundred Fifty & Paise Zero Only
5	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (including equivalent design mix)	3.600	Cum	800.00	2880.00	INR Two Thousand Eight Hundred Eighty & Paise Zero Only
6	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	3.000	Cum	800.00	2400.00	INR Two Thousand Four Hundred & Paise Zero Only
7	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : Of area 3 sq. metres and below	10.000	Each	260.00	2600.00	INR Two Thousand Six Hundred & Paise Zero Only
8	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of serviceable material with in 50 metres lead as directed by Engineer-in-charge.	8.000	Sqm	26.00	208.00	INR Two Hundred Eight & Paise Zero Only
9	Dismantling of WC & flushing cistern/Washbin / Urinal and its associated Plumbing fixture such as Bib Cock/Angle Cock of all types (C.I./PVC/Vitrious China/Brass/GI) including its pipe and other Fiting all including and stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	24.000	Each	80.00	1920.00	INR One Thousand Nine Hundred Twenty & Paise Zero Only

पवन नै. पारधी / PAWAN N. PARDHI
सहायक महाप्रबंधक (अभि-सि)
Asstt General Manager (E-C)
भा.नि.प्रा. वडोदरा विमानक्षेत्र /AAI, VADODARA AIRPORT

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
10	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	193.000	Cum	260.00	50180.00	INR Fifty Thousand One Hundred Eighty & Paise Zero Only
11	Extra for every additional lift of 1.5 m or part thereof in excavation / banking excavated or stacked materials. All kinds of soil.	40.000	Cum	260.00	10400.00	INR Ten Thousand Four Hundred & Paise Zero Only
12	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc, in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 and for all lift.	204.000	Cum	80.00	16320.00	INR Sixteen Thousand Three Hundred Twenty & Paise Zero Only
13	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	51.000	Cum	1700.00	86700.00	INR Eighty Six Thousand Seven Hundred & Paise Zero Only
14	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	31.000	Cum	5030.00	155930.00	INR One Lakh Fifty Five Thousand Nine Hundred Thirty & Paise Zero Only
15	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete	144.000	Sqm	170.00	24480.00	INR Twenty Four Thousand Four Hundred Eighty & Paise Zero Only
16	Centering and shuttering including strutting, propping etc. and removal of form for : Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc	48.000	Sqm	260.00	12480.00	INR Twelve Thousand Four Hundred Eighty & Paise Zero Only
17	Centering and shuttering including strutting, propping etc. and removal of form for : Columns, Pillars, Piers, Abutments, Posts and Struts	154.000	Sqm	260.00	40040.00	INR Forty Thousand Forty & Paise Zero Only
18	Centering and shuttering including strutting, propping etc. and removal of form for : Lintels, beams, plinth beams, girders, bressumers and cantilevers	127.000	Sqm	260.00	33020.00	INR Thirty Three Thousand Twenty & Paise Zero Only
19	Centering and shuttering including strutting, propping etc. and removal of form for : Suspended floors, roofs, landings, balconies and access platform	200.000	Sqm	260.00	52000.00	INR Fifty Two Thousand & Paise Zero Only
20	Centering and shuttering including strutting, propping etc. and removal of form for : Edges of slabs and breaks in floors and walls. Under 20 cm wide	92.000	Mtr	80.00	7360.00	INR Seven Thousand Three Hundred Sixty & Paise Zero Only

पवन नै. पार्धी
04.03.2025

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
21	Centering and shuttering including strutting, propping etc. and removal of form for Edges of slabs and breaks in floors and walls. Above 20 cm wide	56.000	Sqm	80.00	4480.00	INR Four Thousand Four Hundred Eighty & Paise Zero Only
22	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads, but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works upto plinth level Concrete of M25 grade with minimum cement content of 330 kg /cum	80.000	cum	8000.00	640000.00	INR Six Lakh Forty Thousand & Paise Zero Only
23	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads, but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works above plinth level upto floor V level Concrete of M25 grade with minimum cement content of 330 kg /cum	59.000	cum	8450.00	498550.00	INR Four Lakh Ninety Eight Thousand Five Hundred Fifty & Paise Zero Only
24	Add for using extra cement in the items of design mix over and above the specified cement content therein.	42.000	Qtl	620.00	26040.00	INR Twenty Six Thousand Forty & Paise Zero Only
25	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	6000.000	Kg	80.00	480000.00	INR Four Lakh Eighty Thousand & Paise Zero Only
26	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	5900.000	Kg	89.00	525100.00	INR Five Lakh Twenty Five Thousand One Hundred & Paise Zero Only


पवन नै. पारधी / PAWAN N. PARDHI
 सहायक महाप्रबंधक (अभि-सि)
 Asstt General Manager (E-C)
 भा. वि. प्र. वडोदरा विमानक्षेत्र / IAI, VADODARA AIRPORT

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
27	Brick work with clay flyash F.P.S. (non modular) brick of class designation 5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	18.000	Cum	6200.00	111600.00	INR One Lakh Eleven Thousand Six Hundred & Paise Zero Only
28	Brick work with clay flyash F.P.S. (non modular) brick of class designation 5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand)	56.000	Cum	7100.00	397600.00	INR Three Lakh Ninety Seven Thousand Six Hundred & Paise Zero Only
29	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	18.000	Sqm	980.00	17640.00	INR Seventeen Thousand Six Hundred Forty & Paise Zero Only
30	Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only. Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily. Glazed Vitrified tiles Matt/Antiskid finish : Size of Tile 600 x 600 mm	240.000	Sqm	1160.00	278400.00	INR Two Lakh Seventy Eight Thousand Four Hundred & Paise Zero Only
31	12 mm cement plaster of mix : 1:4 (1 cement: 4 coarse sand)	508.000	Sqm	350.00	177800.00	INR One Lakh Seventy Seven Thousand Eight Hundred & Paise Zero Only
32	15 mm cement plaster on rough side of single or half brick wall of mix: 1:4 (1 cement : 4 coarse sand)	377.000	Sqm	350.00	131950.00	INR One Lakh Thirty One Thousand Nine Hundred Fifty & Paise Zero Only
33	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	317.000	Sqm	350.00	110950.00	INR One Lakh Ten Thousand Nine Hundred Fifty & Paise Zero Only
34	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	201.000	Sqm	890.00	178890.00	INR One Lakh Seventy Eight Thousand Eight Hundred Ninety & Paise Zero Only
35	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content With water thinnable cement primer on wall surface having VOC content less than 50 grams/ litre	471.000	Sqm	80.00	37680.00	INR Thirty Seven Thousand Six Hundred Eighty & Paise Zero Only
36	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour Two coats	863.000	Sqm	125.00	107875.00	INR One Lakh Seven Thousand Eight Hundred Seventy Five & Paise Zero Only
37	Finishing walls with Acrylic Smooth exterior paint of required shade: New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm)	545.000	Sqm	125.00	68125.00	INR Sixty Eight Thousand One Hundred Twenty Five & Paise Zero Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
38	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete at all levels. Granite stone slab of colour black, Cherry/Ruby red Area of slab upto 0.50 sqm	28.000	Sqm	3050.00	85400.00	INR Eighty Five Thousand Four Hundred & Paise Zero Only
39	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Second class teak wood	0.250	cum	125000.00	31250.00	INR Thirty One Thousand Two Hundred Fifty & Paise Zero Only
40	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	21.000	Sqm	3500.00	73500.00	INR Seventy Three Thousand Five Hundred & Paise Zero Only
41	Extra for providing lipping with 2nd class teak wood battens 25 mm minimum depth on all edges of flush door shutters (over all area of door shutter to be measured).	26.000	Sqm	350.00	9100.00	INR Nine Thousand One Hundred & Paise Zero Only
42	Providing and Fixing factory made uPVC door frame, made of uPVC extruded sections, of size 65 mm x 55 mm with wall thickness 2.0 mm (± 0.2 mm), corners of the door frame to be mitred cut and jointed with plastic brackets and stainless steel screws, reinforcing hinge side vertical of the frames with PVC profile of Size 28 mm x 30 mm having wall thickness 2 mm (± 0.2 mm), including providing & fixing 3 nos of 125 mm long stainless steel hinges to the frame, fixing the frame with jamb with required number & size of anchor dash fasteners, all complete as per manufacturer's specification and direction of Engineer-in-charge.	52.000	Mtr	260.00	13520.00	INR Thirteen Thousand Five Hundred Twenty & Paise Zero Only
43	Providing and fixing 37 mm thick factory made PVC door shutter, styles and rails made of PVC hollow section of size 100 mm x 37 mm with wall thickness 2 mm (± 0.2 mm), with inbuilt bead on one side, styles and rails mitred cut and joint at the corners by means of 2 nos of plastic brackets of size 75 mm x 220 mm at each corner and stainless steel screws, reinforcing the hinge side of style by inserting PVC profile of size 28 mm x 30 mm, with wall thickness 2 mm (± 0.2 mm). Lockrail of size 100 mm x 37 mm, wall thickness 2 mm (± 0.2 mm) will be fixed to the vertical styles, Providing with PVC snapfit beads and panel of size 100 mm x 20 mm, and inserting 2 nos tie bar of 6 mm dia and fastening with nuts and washers complete, all as per manufacturer's specification and direction of Engineer-in-charge.	20.000	Sqm	2600.00	52000.00	INR Fifty Two Thousand & Paise Zero Only

पर्वणदी
 04.03.2025
 पवन नै. पारधी / PAWAN N. PARDHI
 सहायक महाप्रबंधक (अभि-सि)
 Asstt General Manager (E-C)
 भा. वि. प्रा. वडोदरा विमानक्षेत्र / AAI, VADODARA AIRPORT

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
44	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately). For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	125.000	Kg	440.00	55000.00	INR Fifty Five Thousand & Paise Zero Only
45	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately). For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	80.000	Kg	440.00	35200.00	INR Thirty Five Thousand Two Hundred & Paise Zero Only
46	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item). With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)	17.000	Sqm	1250.00	21250.00	INR Twenty One Thousand Two Hundred Fifty & Paise Zero Only
47	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI: IS : 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. complete.	9.000	Each	1700.00	15300.00	INR Fifteen Thousand Three Hundred & Paise Zero Only
48	Providing and fixing aluminium round shape handle of outer dia 100 mm with SS screws etc. complete as per direction of Engineer-in-charge Anodized (AC 15) aluminium	38.000	Each	260.00	9880.00	INR Nine Thousand Eight Hundred Eighty & Paise Zero Only
49	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete. 200x10 mm	22.000	Each	80.00	1760.00	INR One Thousand Seven Hundred Sixty & Paise Zero Only
50	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. Twin rubber stopper	19.000	Each	80.00	1520.00	INR One Thousand Five Hundred Twenty & Paise Zero Only


 04.03.2025
पवन नै. पारधी / PAWAN N. PARDHI
 सहायक महाप्रबंधक (अभि-सि)
 Asstt General Manager (E-C)
 भा.प्र.प्र. वडोदरा विमानक्षेत्र /AAI, VADODARA AIRPORT

Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
51	Providing and fixing water closet squatting pan (Indian type W.C pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: White Vitreous china Onssa pattern W.C. pan of size 580x440 mm with integral type foot rests	2.000	Each	3500.00	7000.00	INR Seven Thousand & Paise Zero Only
52	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid	6.000	Each	5300.00	31800.00	INR Thirty One Thousand Eight Hundred & Paise Zero Only
53	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	6.000	Each	4400.00	26400.00	INR Twenty Six Thousand Four Hundred & Paise Zero Only
54	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 15 mm nominal bore	12.000	Each	980.00	11760.00	INR Eleven Thousand Seven Hundred Sixty & Paise Zero Only
55	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15 mm nominal bore	16.000	Each	980.00	15680.00	INR Fifteen Thousand Six Hundred Eighty & Paise Zero Only
56	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	1000.000	Lit	12.50	12500.00	INR Twelve Thousand Five Hundred & Paise Zero Only
57	Providing and fixing white vitreous china flat back or wall corner type tipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I. clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : One urinal basin with 5 litre white P.V.C. automatic flushing cistern	8.000	Each	3500.00	28000.00	INR Twenty Eight Thousand & Paise Zero Only
58	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings and fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 32 mm nominal dia Pipes	10.000	Mtr	530.00	5300.00	INR Five Thousand Three Hundred & Paise Zero Only
59	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings and fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 25 mm nominal dia Pipes	40.000	Mtr	440.00	17600.00	INR Seventeen Thousand Six Hundred & Paise Zero Only

पर्वपार्थी
04.03.2025

पवन नै. पारधी / PAWAN N. PARDHI
सहायक महाप्रबंधक (अभि-सि)
Asstt General Manager (E-C)
भा.नि.प्रा. वडोदरा विमानक्षेत्र /AAI, VADODARA AIRPORT

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
60	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings and fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 15 mm nominal dia Pipes	30.000	Mtr	350.00	10500.00	INR Ten Thousand Five Hundred & Paise Zero Only
61	Providing and fixing soil, waste and vent pipes including cost for bends, union, junction, tee, Floor/nahani trap etc. complete - UPVC pipes of Astral, Supreme, Finolex Make of pressure rating SCH80 or Equivalent 75 mm Dia This includes jointing of pipes & fittings with solvent cement and the cost of cutting chases and making good the same wherever required including testing of joints all complete and as per direction of Engineer-In charge.	12.000	Mtr	350.00	4200.00	INR Four Thousand Two Hundred & Paise Zero Only
62	Providing and fixing soil, waste and vent pipes including cost for bends, union, junction, tee, Floor/nahani trap etc. complete - UPVC pipes of Astral, Supreme, Finolex Make of pressure rating SCH80 or Equivalent -160mm Dia This includes jointing of pipes & fittings with solvent cement and the cost of cutting chases and making good the same wherever required including testing of joints all complete and as per direction of Engineer-In charge.	50.000	Mtr	530.00	26500.00	INR Twenty Six Thousand Five Hundred & Paise Zero Only
63	Providing and fixing soil, waste and vent pipes including cost for bends, union, junction, tee, Floor/nahani trap etc. complete - UPVC pipes of Astral, Supreme, Finolex Make of pressure rating SCH80 or Equivalent-110 mm Dia This includes jointing of pipes & fittings with solvent cement and the cost of cutting chases and making good the same wherever required including testing of joints all complete and as per direction of Engineer-In charge.	40.000	Mtr	440.00	17600.00	INR Seventeen Thousand Six Hundred & Paise Zero Only
64	Providing and fixing P.V.C waste pipe for sink or washbasin including P.V.C waste fitting complete Flexible 32mm Dia	6.000	Each	125.00	750.00	INR Seven Hundred Fifty & Paise Zero Only
65	Providing and fixing PTMT grating of approved quality and colour :Rectangular type with openable circular lid 150 mm nominal size square 100 mm diameter of the inner hinged round grating	16.000	Each	125.00	2000.00	INR Two Thousand & Paise Zero Only
66	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing :Rectangular shape 1500x450 mm	2.000	Each	2600.00	5200.00	INR Five Thousand Two Hundred & Paise Zero Only
67	Providing and fixing uplasticsised PVC connection pipe with brass unions :45 cm length 15 mm nominal bore	6.000	Each	125.00	750.00	INR Seven Hundred Fifty & Paise Zero Only
68	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet :150 mm diameter	1.000	Each	800.00	800.00	INR Eight Hundred & Paise Zero Only
69	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge.	6.000	Each	1700.00	10200.00	INR Ten Thousand Two Hundred & Paise Zero Only


Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
70	Providing and fixing health faucet (Hand shower) with 1.20 to 1.50 mtr flexible Tube (Stainless Steel) of quality and make as approved by Engineer - in - charge.	8.000	Each	1700.00	13600.00	INR Thirteen Thousand Six Hundred & Paise Zero Only
71	Constructing masonry Chamber 30x30x50 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for stop cock, with C.I. surface box 100x100 x75 mm (inside) with hinged cover fixed in reinforced cement concrete slab 1:1.5:3 mix (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size), including necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12mm thick, finished with a floating coat of neat cement complete as per standard design. With common burnt clay F.P.S. (non modular) bricks of class designation 5.00.	4.000	Each	1250.00	5000.00	INR Five Thousand & Paise Zero Only
72	Making soak pit 2.5 m diameter 3.0 metre deep with 45 x 45 cm dry brick honey comb shaft with bricks and S.W. drain pipe 100 mm diameter, 1.8 m long complete as per standard design. With common burnt clay F.P.S. (non modular) bricks of class designation 5.00.	2.000	Each	23750.00	47500.00	INR Forty Seven Thousand Five Hundred & Paise Zero Only
73	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	1284.000	Kg	125.00	160500.00	INR One Lakh Sixty Thousand Five Hundred & Paise Zero Only
74	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	3435.000	Kg	116.00	398460.00	INR Three Lakh Ninety Eight Thousand Four Hundred Sixty & Paise Zero Only
75	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work.	178.000	Sqm	125.00	22250.00	INR Twenty Two Thousand Two Hundred Fifty & Paise Zero Only
76	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50mm (base metal of minimum 0.45mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5 x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	270.000	Sqm	620.00	167400.00	INR One Lakh Sixty Seven Thousand Four Hundred & Paise Zero Only
77	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc., of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge. 60mm thick cement concrete paver block of M-35 grade with approved colour, design & pattern.	20.000	Sqm	800.00	16000.00	INR Sixteen Thousand & Paise Zero Only

पवन नै. पारधी
04.03.2025

पवन नै. पारधी / PAWAN N. PARDHI
सहायक महाप्रबंधक (अभि-सि)
Asstt General Manager (E-C)
भा.नि.प्रा. वडोदा विमानक्षेत्र /AAI, VADODARA AIRPORT

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
78	Providing, laying and making kerb channel 30 cm wide and 50 mm thick with cement concrete 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size) over 75mm bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including finishing the top smooth etc. complete and as per direction of Engineer in-charge.	6.000	Sqm	800.00	4800.00	INR Four Thousand Eight Hundred & Paise Zero Only
79	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not be more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured to calculate volume for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	1.000	cum	12500.00	12500.00	INR Twelve Thousand Five Hundred & Paise Zero Only
80	Providing and placing in position 100 mm thick factory made machine batched & machine mixed Precast RCC Rectangular Covers on drains of footpath of various sizes, of M-25 grade cement concrete for RCC work, including cost of centering, shuttering, reinforcement of 8 mm dia TMT bars of Fe 500 grade @ maximum 100mm c/c on both ways, neat cement punning on finished surface, properly encased on all edges with 1.6 mm thick 100 mm wide MS sheet duly painted over priming coat, reinforcement to be welded at edges with MS sheet and providing 2 Nos. 12 mm dia bar for hooks etc. i/c cost of cartage, all leads & lift, handling at site etc. all complete as per direction of Engineer-in-Charge.	9.000	Sqm	890.00	8010.00	INR Eight Thousand Ten & Paise Zero Only
81	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone-II) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation leveling & dressing & finishing the top smooth.	45.000	Sqm	503.00	22635.00	INR Twenty Two Thousand Six Hundred Thirty Five & Paise Zero Only
82	Brick edging 7cm wide 11.4 cm deep to plinth protection with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 including grouting with cement mortar 1:4 (1 cement : 4 fine sand).	66.000	Mtr	80.00	5280.00	INR Five Thousand Two Hundred Eighty & Paise Zero Only
83	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings. This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 25 mm nominal outer dia. Pipes.	70.000	Mtr	440.00	30800.00	INR Thirty Thousand Eight Hundred & Paise Zero Only
84	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall 25 mm nominal outer dia. Pipes.	30.000	Mtr	350.00	10500.00	INR Ten Thousand Five Hundred & Paise Zero Only
85	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete : 25 mm nominal bore	2.000	Each	350.00	700.00	INR Seven Hundred & Paise Zero Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
86	Providing and fixing CPVC Ball valve of 25 mm nominal bore all complete as per direction of Engineer in Charge.	4.000	Each	800.00	3200.00	INR Three Thousand Two Hundred & Paise Zero Only
87	Providing, laying and jointing glazed stoneware pipes class SP-1 with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc.complete ;150 mm diameter	120.000	Mtr	503.00	60360.00	INR Sixty Thousand Three Hundred Sixty & Paise Zero Only
88	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete as per standard design : 150 mm diameter S.W. pipe	120.000	Mtr	602.00	72240.00	INR Seventy Two Thousand Two Hundred Forty & Paise Zero Only
89	Extra for providing and fixing wind ties of 40 x 6 mm flat iron section.	144.000	Meter	80.00	11520.00	INR Eleven Thousand Five Hundred Twenty & Paise Zero Only
Total in Figures					6057763.00	INR Sixty Lakh Fifty Seven Thousand Seven Hundred Sixty Three & Paise Zero Only
Quoted Rate in Words						INR Sixty Lakh Fifty Seven Thousand Seven Hundred Sixty Three & Paise Zero Only


 04.03.2025
पवन नै. पारधी / PAWAN N. PARDHI
 सहायक महाप्रबंधक (अमि-सि)
 Asstt General Manager (E-C)
 भा.वि.प्रा. वडोदरा विमानक्षेत्र /AAJ, VADODARA AIRPORT

Signature Not Verified

Digitally signed by PAWAN
 NAISHWARLAL PARDHI
 Date: 2025.07.15 17:16:10 IST
 Location: eProcurement System for
 Central PSUs