



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

भाविप्रा/वडोदरा/ई-सी/Recarpeting Perimeter Road/डब्ल्यू-273/2024-25/ 1147
AAI/Vadodara/E-C/ Recarpeting Perimeter Road/W -273/2024-25/

दिनांक: 11/02/2025

Date: 11/02/2025

सेवा मे,

M/s भयान कंस्ट्रक्शन कंपनी, हिसार.
ह.नं. 510, सेक्टर 4, हिसार,
हिसार, हरियाणा-125001

To,

M/s Bhyan Construction Company Hisar
H No. 510, Sector 4, Hisar,
Hisar, Haryana-125001.

कार्य का नाम: वडोदरा हवाई अड्डे पर परिधि सड़क की पुनः कालीन बिछाने और संबद्ध कार्य।
(निविदा आई. डी. - 2024_AAI_220060_1)

Name of Work: "Recarpeting of Perimeter road and allied work at Vadodara Airport."
(Tender ID - 2024_AAI_220060_1)

संदर्भ:- दिनांक 28/01/2025 को खोला गया आपका ई-टेंडर । (वित्तीय बोली)

Ref: Your e-tender opened on 28/01/2025 (Financial Bid)

महोदय/Sir,

- उपर्युक्त कार्य हेतु आपकी निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से, आपके द्वारा बताए गये मद दर मूल्यों पर निविदा की राशि कुल रु. 3,28,85,171.00 (रुपये तीन करोड़ अठ्ठाइस लाख पिच्चासी हजार एक सौ इकहतर मात्र) (बगैर GST) स्वीकृत किया जाता है, जो कि निविदाकी अनुमानित लागत राशि रु. 432.17 लाख (बगैर GST) से 23.91% कम है।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs. 3,28,85,171.00 (Excluding GST) (Rupees Three Crore Twenty-Eight Lakh Eighty-Five Thousand One Hundred Seventy-One only), which is 23.91 % below the estimated cost put to tender of Rs. 432.17 Lakh (Excluding GST).

- सहायक महाप्रबंधक (अभि-सिविल), वडोदरा विमानक्षेत्र, वडोदरा कार्य प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप स्वयं या आपकी ओर से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करे जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 26.02.2025 तक सहायक महाप्रबंधक (अभि-सिविल), वडोदरा विमानक्षेत्र के कार्यालय में उपस्थित हो तथा करारनामे को पूरा करे। ठेके का करारनामा रु.300/- (रु. तीन सौ मात्र) के नोन ज्यूडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा स्टैम्प पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Assistant General Manager (Engg- Civil), Vadodara Airport, Vadodara shall be the Engineer-in-charge of the work. You are requested to attend or depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the office of the Assistant General Manager (Engg- Civil), Vadodara Airport by 26.02.2025 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.300/- (Rs. Three Hundred only) and the cost of the stamp paper shall be borne by you.

पवन न. पारधी
11.02.2025

पवन न. पारधी / PAWAN N. PARDHI

सहायक महाप्रबंधक (अभि-सि)
Asstt General Manager (E-C)

भा.वि.प्रा. वडोदरा विमानक्षेत्र / AAI, VADODARA AIRPORT



3. इस पत्र के जारी होने की तारीख से 10 दिनों के भीतर सुरक्षा जमा राशि के लिए, **₹.32,88,517.00 (रुपये बत्तीस लाख अट्ठासी हजार पांच सौ सत्रह मात्र)** जमा करे जोकि अनुबंध मूल्य का 10% है। ऐसा न करने पर निविदा दस्तावेज़ के जीसीसी के खंड 1A पृष्ठ 16 के अनुसार यह राशि चालू खाता बिल से काट लिया जाएगा। आपके टेंडर के साथ प्राप्त ईएमडी राशि **₹. 8,64,340.00 (रुपये आठ लाख चौंसठ हजार तीन सौ चालीस मात्र)** ऑनलाइन वापस कर दी जाएगी जब एसडी राशि ईएमडी से अधिक होगी।

Please deposit **Rs. 32,88,517.00 (Rupees Thirty-Two Lakh Eighty-Eight Thousand Five Hundred Seventeen Only)** i.e @10% of Contract value towards security deposit within 10 days from the date of issue of this letter, failing which the same shall be deducted from the Running Account Bills as per the Tender document Clause 1A GCC Page 16. The earnest money amount of **Rs 8,64,340.00 (Rupees Eight Lakh Sixty-Four Thousand Three Hundred Forty Only)**, received along with your tender shall be refunded online once SD amount exceeds the EMD

4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) 1971 केंद्रीय नियमों के प्रावधान का पालन करे, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण कार्यकर्ता (रोजगार का विनियमन और सेवा की शर्त) अधिनियम 1996, बिल्डिंग और अन्य निर्माण कार्यकर्ता कल्याण सेस अधिनियम 1996 जैसा कि निविदा के जीसीसी के खंड 19 पृष्ठ 49 और केंद्रीय तथा राज्य सरकार के नियमों में निर्दिष्ट है।

You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and Contract labour (Regulation and Abolition) Central rules 1971 Child labour (Prohibition and Regulation) Act 1986, Construction workers (Regulation of Employment and Condition of service) Act 1996, Building and other construction workers welfare cess act 1996 as specified in clause 19 page 49 of GCC of tender & minimum wage act and rules of Central and state government.

5. आपको निर्देश दिया जाता है कि आप तुरंत सहायक महाप्रबंधक (अभि-सिविल)/प्रबंधक(अभि-सिविल), वडोदरा विमानक्षेत्र से मिले वह आपको साइट सौंपने की व्यवस्था करेंगे। कृपया नोट कर ले कि काम करने का अनुमत समय **8 (आठ) महीना** जोकि बरसात के मौसम के 2 महीने सहित इस पत्र के जारी होने के दस दिन बाद से गिना जाएगा।

You are also directed to contact **Assistant General Manager (Engg-Civil) / Manager (Engg – Civil)** Vadodara Airport immediately who will arrange to hand over site to you. Please note that the time allowed for carrying out the work is **8 (Eight) Months i/c 2 month of Rainy season** which shall be reckoned from 10th days after the issuance of this letter.

6. इस ठेके के संबंध में आगे की कोई भी पत्राचार सहायक महाप्रबंधक (अभि-सिविल), वडोदरा विमानक्षेत्र, वडोदरा 390022 के पते पर किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Assistant General Manager (Engg- Civil) Vadodara Airport, Vadodara -390022.

7. उपरोक्त संदर्भित सभी पत्र इस ठेके का भाग होंगे।

All the letters referred above shall form part of contract.

8. उपर्युक्त कार्य के लिए त्रुटि दायित्व की अवधि **12 (बारह) महीने** होगी।

The defects liability period for the above-mentioned work is **12 (Twelve)** months.

RECEIVED
11.02.2025
PAWAN N. PARDHI
सहायक महाप्रबंधक (अभि-सि)
Assit General Manager (E-C)
आर. विमान, वडोदरा विमानक्षेत्र / AAI, VADODARA AIRPORT

पवन नै. पारधी
11.02.2025
पवन नै. पारधी / PAWAN N. PARDHI
सहायक महाप्रबंधक (अभि-सि)
Assit General Manager (E-C)
आर. विमान, वडोदरा विमानक्षेत्र / AAI, VADODARA AIRPORT



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

9. यदि ठेकेदार सुरक्षा नियमों का भंग करेगा तो उनका कालियादी मे सम्मलित किया जाएगा एवं उचित कानूनी कार्यवाही के लिए भी जिम्मेदार होगा ।
If Contractor is found Violate any of Security Regulations, he shall be Black listed and will be subjected to other Legal Proceedings.
10. स्वीकृति के प्रतीक के रूप में अधिसूचना में हस्ताक्षर करने के बाद कृपया इस पावती को स्वीकार करें और इस पत्र की नकल प्रतिलिपि वापस करें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
11. यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण को सही रूप में लिया जाएगा ,
In case any discrepancy is found then English version will be taken as correct.

भवदीय /Yours faithfully

पवन नै. पारधी
11.02.2025

सहायक महाप्रबंधक (अभि-सिविल),
वडोदरा हवाईअड्डा, वडोदरा
कृतेअध्यक्ष, भारतीय विमानपत्तन प्राधिकरण
Assistant General Manager (Engg.-Civil),
Vadodara Airport, Vadodara
For and on behalf of Chairman
Airports Authority of India

पवन नै. पारधी / PAWAN N. PARDHI

सहायक महाप्रबंधक (अभि-सि)

Asstt General Manager (E-C)

आ.वि.प्रा. वडोदरा विमानक्षेत्र /AAI, VADODARA AIRPORT

Item Rate BoQ

Validate

Print

Help

Tender Inviting Authority: Assistant General Mangar (Engg. -Civil)

Name of Work: Recarpeting of Perimeter road and allied work at Vadodara Airport.

Contract No: 2024_AAL_220060_1

Name of the Bidder/ Bidding Firm / Company : Bhyan Construction Company Hisar

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	TEXT #
1	2	4	5	13	53	55	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in charge. All kinds of soil	729.000	Cum	96.00	69984.00	INR Sixty Nine Thousand Nine Hundred Eighty Four & Paise Zero Only	
2	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30	371.000	Cum	2100.00	779100.00	INR Seven Lakh Seventy Nine Thousand One Hundred & Paise Zero Only	
3	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paver finisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	414.000	Cum	2200.00	910800.00	INR Nine Lakh Ten Thousand Eight Hundred & Paise Zero Only	

पंजीकृत
11.02.2025

पवन नै. पार्थी / PAWAN N. PARDHI
सहायक महाप्रबंधक (अभि-सि)
Asstt General Manager (E-C)
आ. वि. पा. मंत्रालय विमानक्षेत्र /AAI, VADODARA AIRPORT

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
4	Providing and laying of Hot Mix Dense Bituminous Macadam (DBM) using crushed stone aggregate of quality, size and grading as specified and cement filler of quality as specified and Viscosity Grade Bitumen (supplied in bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-in-Charge including compacting with 8-10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [for tendering purpose VG-30 bitumen of grade shall be taken as 110 kg/m ³ of mix supplied in bulk produced by Govt. Refineries and 2 % cement by weight of aggregates as filler material.	1763.000	Cum	7200.00	12693600.00	INR One Crore Twenty Six Lakh Ninety Three Thousand Six Hundred & Paise Zero Only
5	Providing and laying of Hot Mix Semi Dense Asphaltic Concrete (SDAC) using crushed stone aggregate of quality, size and grading as specified and 2% cement by weight of aggregates as filler of quality as specified and Viscosity Grade Bitumen (supplied in bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-in-Charge including compacting with 8-10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [for tendering purpose VG bitumen of grade VG-30) content shall be taken as 120 kg/m ³ of mix supplied in bulk produced by Govt. Refineries and 2% cement by weight of aggregates as filler material.	1175.000	Cum	9100.00	10692500.00	INR One Crore Six Lakh Ninety Two Thousand Five Hundred & Paise Zero Only
6	Providing and applying tack coat using Bitumen Emulsion (Rapid Setting) complying with IS:8887, spraying the bitumen with mechanically operated spray unit at the rate specified below, cleaning and preparing the existing pavement surface as per specifications complete in all respects as per direction of Engineer-In-Charge. If the actual quantity of bitumen varies from the quantity specified, necessary cost adjustment for deviation in the quantity of bitumen shall be done as per rate in actual supply voucher from nearest refinery at the time of execution. The rate of bitumen exclusive of GST shall only be considered for payment. 0.20kg/ Sqm on existing bituminous surface.	47000.000	Sqm	16.00	752000.00	INR Seven Lakh Fifty Two Thousand & Paise Zero Only

पं. पा. र. धी
 11.02.2025
 पवन नै. पा. र. धी / PAWAN N. PARDHI
 सहायक महाप्रबंधक (अभि-सि)
 Asstt General Manager (E-C)
 भा. नि. प्रा. वडोदरा विमानक्षेत्र /AAI, VADODARA AIRPORT

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
7	Providing and laying design mix cement concrete of M-30 grade, in roads/ taxi tracks/ runways, using cement content as per design mix, using coarse sand and graded stone aggregate of 40 mm nominal size in appropriate proportions as per approved & specified design criteria, providing dowel bars with sleeve/ tie bars wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/ camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction/ expansion, construction & longitudinal joints (10 mm wide x 50 mm deep) by groove cutting machine, providing and filling joints with approved joint filler and sealants, complete all as per direction of Engineer-in-charge (Item of joint fillers, sealants, dowel bars with sleeve/ tie bars to be paid separately). Note:- Cement content considered in M-30 is @ 340 kg/cum. Excess/ less cement used as per design mix is payable/ recoverable separately. Cement concrete manufactured in automatic batching plant (RMC plant) i/c transportation to site in transit mixer	514.000	Cum	5900.00	3032600.00	INR Thirty Lakh Thirty Two Thousand Six Hundred & Paise Zero Only
8	Add for using extra cement in the items of design mix over and above the specified cement content therein.	155.000	Qtl	7200.00	1116000.00	INR Eleven Lakh Sixteen Thousand & Paise Zero Only
9	Providing and fixing pre-moulded joint filler in expansion joints of RCC roads / CC pavements after making the joints dust free with high pressure air jet cleaners, all complete as per direction of the Engineer-in-Charge. (Pre-moulded joint fillers shall be made of bitumen hot sealing compound impregnated fibre board having impregnation more than 35%, conforming to IS:1838 for fibre board and IS: 1834 for hot sealing bitumen compound grade A.)	6000.000	per cm width	49.00	294000.00	INR Two Lakh Ninety Four Thousand & Paise Zero Only
10	Providing and filling in position rubberized bitumen hot sealing compound for sealing of expansion joints in roads / pavements all complete as per direction of the Engineer-in-Charge. Using grade 'A' sealing compound conforming to IS: 1834.	1450.000	per cm width	69.00	100050.00	INR One Lakh Fifty & Paise Zero Only
11	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	284.000	Sqm	719.00	204196.00	INR Two Lakh Four Thousand One Hundred Ninety Six & Paise Zero Only
12	Excavating, supplying, stacking and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in foundation trenches, plinth, sides of foundation etc. complete for all lift.	320.000	Cum	356.00	113920.00	INR One Lakh Thirteen Thousand Nine Hundred Twenty & Paise Zero Only

पवन नै. पार्थी / PAWAN N. PARDHI

सहायक महाप्रबंधक (अभि-सि)
Asstt General Manager (E-C)

भा.वि.वा. वडोदरा विमानक्षेत्र /AAI, VADODARA AIRPORT

पैनर
11.02.2025

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
13	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 and for all lift.	729.000	Cum	119.00	86751.00	INR Eighty Six Thousand Seven Hundred Fifty One & Paise Zero Only
14	Providing and laying Non Pressure NP-3 class (Medium duty) R.C.C. pipes including collars/ spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 450 mm dia RCC pipes.	53.000	Mtr	3600.00	190800.00	INR One Lakh Ninety Thousand Eight Hundred & Paise Zero Only
15	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand/zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	29.000	Cum	4200.00	121800.00	INR One Lakh Twenty One Thousand Eight Hundred & Paise Zero Only
16	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	14.000	Cum	3600.00	50400.00	INR Fifty Thousand Four Hundred & Paise Zero Only
17	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete	109.000	Sqm	216.00	23544.00	INR Twenty Three Thousand Five Hundred Forty Four & Paise Zero Only
18	Brick work with clay flyash F.P.S. (non modular) brick of class designation 5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand) 12 mm cement plaster of mix : 1:4 (1 cement: 4 coarse sand)	9.000	cum	4900.00	44100.00	INR Forty Four Thousand One Hundred & Paise Zero Only
19		83.000	Sqm	291.00	24153.00	INR Twenty Four Thousand One Hundred Fifty Three & Paise Zero Only
20	Providing and applying 2.5 mm thick road marking strips (retro-reflective) of specified shade/ colour using hot thermoplastic material by fully semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications.	2662.000	Sqm	492.00	1309704.00	INR Thirteen Lakh Nine Thousand Seven Hundred Four & Paise Zero Only
21	Providing and laying LDPE Sheet of 300 microns Confirming to IS:2508 on the base course with overlaps of not less than 100 mm longitudinally and 150mm transversely complete as per specification and as directed by Engineer-In-Charge	2570.000	Sqm	90.00	231300.00	INR Two Lakh Thirty One Thousand Three Hundred & Paise Zero Only

पुनर्विचार
11.02.2025

पवन नै. पारधी / PAWAN N. PARDHI

सहायक महाप्रबंधक (अभि-सि)

Asstt General Manager (E-C)

भा. वि. प्रा. यशोदा विमानक्षेत्र /AAI, YASHODA AIRPORT

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
22	Providing, laying and making kerb channel 30 cm wide and 50 mm thick with cement concrete 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size) over 75mm bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including finishing the top smooth etc. complete and as per direction of Engineer in-charge.	51.000	Sqm	319.00	16269.00	INR Sixteen Thousand Two Hundred Sixty Nine & Paise Zero Only
23	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured to calculate volume for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	4.000	cum	6900.00	27600.00	INR Twenty Seven Thousand Six Hundred & Paise Zero Only
Total in Figures					32885171.00	INR Three Crore Twenty Eight Lakh Eighty Five Thousand One Hundred Seventy One & Paise Zero Only
Quoted Rate in Words	INR Three Crore Twenty Eight Lakh Eighty Five Thousand One Hundred Seventy One & Paise Zero Only					

पवन नै. पारधी / PAWAN N. PARDHI

सहायक महाप्रबंधक (अभि-रि)

Asstt General Manager (E-C)

भा.वि.प्र. चंडोदरा विमानक्षेत्र /AAI, VADODARA AIRPORT

युगपारधी
11-02-2025

Signature Not Verified

Digitally signed by PAWAN NAISHWARLAL PA
Date: 2025.06.26 17:24:30 IST
Location: eProcurement System for Central PS