



Lr. No. AAI/VIJ/DGM (ENGG-C)/Drain Repair works/2025

Dated: 11-02-2025.

To,

M/S V Group Infrastructures,
D.No: 56-11-13A, Sri Devi Complex,
Y V R Street, Patamata,
Vijayawada-520010
Contact: 9052909530
Email: vgroupinfrastructures@gmail.com

Name of work: "Improvement of drainage system at 26 end of runway at Vijayawada Airport. SH: Demolishing & Reconstruction of collapsed storm water drain and streamlining of drainage system at Bravo Taxiway in Operational area at Vijayawada Airport".

Ref: 1. Financial E-Bid for the above work opened on 17-01-2025
(Tender Reference No: AAI/VIJ/ENGG(C)/2024-25/Drain repairs works,
Tender ID no: 2024_AAI_220067_1).

Sir,

- 1) Your E-Tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to Rs. **69,19,400.00** (Rupees Sixty-Nine Lakhs Nineteen Thousand Four Hundred Only) **excluding GST** which is **23.97%** (Twenty-Three decimal Ninety-Seven Percent) **Below** the Estimated Cost put to tender of **Rs. 91,01,385/-** (Excluding GST).
- 2) Dy. Gen. Manager-Engg [C], AAI, Vijayawada Airport, Vijayawada, shall be the Engineer – in- charge of the work. You are requested to attend the office of Dy. General Manager-Engg [C], AAI, Vijayawada Airport within 15days (i.e.) from issue of this letter to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100.00 (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.
- 3) The earnest money amount of **Rs.1,82,028/-** (Rupees One Lakh Eighty-Two Thousand Twenty-Eight Only) received along with your tender in the form of online payment will be treated and converted as part of security deposit as per Clause 1(A) on Page No: GCC-17 of contract document. Please deposit **Rs. 5,09,912/-** (Rupees Five Lakhs Nine Thousand Nine Hundred and Twelve Only) towards Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted from your bill as per Clause no. 1(A) at page no. GCC-17 of Contract agreement.
- 4) You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and contract labour (Regulation and Abolition) Central rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause 19 on page no GCC-45 of tender

Continued...2



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
VIJAYAWADA AIRPORT, VIJAYAWADA - 521102

and minimum wages Act 1948 and Employees Provident Fund and Misc. Provision Act 1952 and ESI Act 1948 as specified in Clause 20 & Clause 20(A) on Page No GCC-51 & 58 and rules there of Central and State Governments.

5) You are also directed to contact **Asst. General Manager Engg [C], Vijayawada Airport - 521102**, immediately who will arrange to hand over the site to you.

6) Please note that the time allowed for carrying out the work shall be **04 (Four) Months** and same shall be reckoned from the 10th day after issue of this letter.

7) Any further correspondence in connection with the contract should normally be addressed to the Engineer - in -charge, AAI, Vijayawada Airport.

8) Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Encl: (Bill of Quantities)

Yours faithfully,

(Kadali.V.G. Suresh)

Dy. General Manager Engg [C]
For and on behalf of the Chairman,
Airports Authority of India
Vijayawada Airport.

Tender Inviting Authority: Asst General Manager (Engg-Civil)

Name of Work: Improvement of drainage system at 26 end of runway at Vijayawada Airport.
SH: Demolishing & Reconstruction of collapsed storm water drain and streamlining of drainage system at Bravo Taxiway in Operational area at Vijayawada Airport.

Contract No: 2024_AAI_220067_1

Name of the Bidder/ Bidding Firm / Company :	V GROUP INFRASTRUCTURES						
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	RATE In Figures with out GST To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST
1	2	3	4	5	6	7	8
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	250.00	CUM	INR	800.00	200000.00	INR Two Lakh Only
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-incharge. a) All kinds of soil	800.00	CUM	INR	350.00	280000.00	INR Two Lakh Eighty Thousand Only
3	Centering and shuttering including strutting, propping etc. and removal of form work for : a) Foundations, footings, bases for columns	380.00	SQM	INR	580.00	220400.00	INR Two Lakh Twenty Thousand Four Hundred Only
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a) 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	110.00	CUM	INR	8200.00	902000.00	INR Nine Lakh Two Thousand Only
5	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete a) 1200 mm dia RCC pipes. (Laying by manual/ machanical means)	310.00	METRE	INR	1000.00	310000.00	INR Three Lakh Ten Thousand Only
6	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete a) 450 mm dia RCC pipes	220.00	METRE	INR	3200.00	704000.00	INR Seven Lakh Four Thousand Only
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a) 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	130.00	CUM	INR	8500.00	1105000.00	INR Eleven Lakh Five Thousand Only

Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	RATE In Figures with out GST To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST
1	2	3	4	5	6	7	8
8	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 and for all lift.	810.00	CUM	INR	350.00	283500.00	INR Two Lakh Eighty Three Thousand Five Hundred Only
9	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. a) All works upto plinth level i) Concrete of M25 grade with minimum cement content of 330 kg /cum	70.00	CUM	INR	10300.00	721000.00	INR Seven Lakh Twenty One Thousand Only
10	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. a) Mild steel and Medium Tensile steel bars	7000.00	KG	INR	115.00	805000.00	INR Eight Lakh Five Thousand Only
11	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: a) Cement mortar 1:4 (1 cement : 4 coarse sand)	70.00	CUM	INR	8000.00	560000.00	INR Five Lakh Sixty Thousand Only
12	15 mm cement plaster on the rough side of single or half brick wall of mix : a) 1:4 (1 cement: 4 fine sand)	110.00	SQM	INR	450.00	49500.00	INR Forty Nine Thousand Five Hundred Only
13	Neat cement punning.	110.00	SQM	INR	450.00	49500.00	INR Forty Nine Thousand Five Hundred Only
14	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	2280.00	KG	INR	120.00	273600.00	INR Two Lakh Seventy Three Thousand Six Hundred Only
15	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. a) In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	3960.00	KG	INR	140.00	554400.00	INR Five Lakh Fifty Four Thousand Four Hundred Only
16	Painting with black anti-corrosive bitumastic paint of approved brand and manufacture to give an even shade : a) Two or more coats on new work	500.00	SQM	INR	140.00	70000.00	INR Seventy Thousand Only
17	Credit and taking away of steel reinforcement extracted from dismantling of RCC wall including transportation and loading charges etc. complete as per the directions of Engineer-in-charge. (Note: Since this item is credit item, the amount quoted by the bidder shall be negative)	16850.00	KG	INR	10.00	-168500.00	INR Minus One Lakh Sixty Eight Thousand Five Hundred Only
Total in Figures						6919400.00	INR Sixty Nine Lakh Nineteen Thousand Four Hundred Only
Quoted Rate in Words		INR Sixty Nine Lakh Nineteen Thousand Four Hundred Only					
Note:GST Applicable for this work shall be 18% (Eighteen Percentage)							

Signature Not Verified



Signature Not Verified

Digitally signed by S V S R K MOHAN MEDISETTY
Date: 2026.06.08 16:12:27 IST
Location: eProcurement System for Central PSUs

