

भाविप्रा/कोल्हापुर/अभि.-विद्युतीय /स.म.प्र.(ई)/सी.डब्ल्यू.-01/2025-26/ 03 दिनांक: 24/04/2025
AAI/Kolhapur/Engg.-Electrical/AGM (E)/CW-01/2025-26/ 03/692-709 Date: 24/04/2025

सेवा मे,
✓ मैसर्स. सन शाइन पावर लाइन्स,
703 डब्लूएनजी-सी जेनबाजी पार्क,
आरयूआई बारामती पुणे,
पुणे - 413102 .

To,
M/s. Sun Shine Power Lines,
703 WNG- C Genbaji Park,
RUI Baramati Pune,
Pune - 413102

कार्य का नाम : कोल्हापुर हवाई अड्डे पर परिधि प्रकाश व्यवस्था का प्रावधान (चरण - I)
Name of Work: Provision of perimeter lighting at Kolhapur Airport (Phase - I)

संदर्भ:- दिनांक 24/03/2025 को खोला गया आपका ई-टेंडर (ID: 2024_AAI_220386_1) (वित्तीय लिफाफा)।

Ref: - Your e-tender (ID: 2024_AAI_220386_1) (Financial bid) opened on 24/03/2025.

महोदय/Sir,

1. ऊपर उल्लेखित कार्य हेतु आपका टेंडर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है, आपके द्वारा बताए गए मद मूल्यों पर आपकी टेंडर राशि जीएसटी रहित कुल रु.57,74,444.00 (रुपये सत्तावन लाख चौहत्तर हजार चार सौ चौवालीस रुपये मात्र) है जो कि टेंडर की अनुमानित लागत राशि रु. 92,02,341.00 से 37.25% नीचे है।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you Excluding GST totalling to Rs. 57,74,444.00 (Rupees Fifty Seven Lakh Seventy Four Thousand Four Hundred Forty Four Only) which is 37.25% below the estimated cost put to tender of Rs. 92,02,341.00

2. सहा. महाप्रबंधक (इंजी-विद्युतीय), भारतीय विमानपत्तन प्राधिकरण, कोल्हापुर विमानक्षेत्र, कोल्हापुर कार्य प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप स्वयं या आपकी ओर से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 07/05/2025 तक सहा महाप्रबंधक (इंजी- विद्युतीय), भाविप्रा, कोल्हापुर विमानक्षेत्र के कार्यालय में उपस्थित हो तथा करारनामे को पूरा करें। ठेके का करारनामा रु. 100/- (रु. एक सौ मात्र) के नोन-ज्यूडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Assistant General Manager (Engg.- Electrical), Airports Authority of India, Kolhapur Airport, Kolhapur shall be the Engineer-in-charge of the work. You are requested to attend or depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the office of the Asst. General Manager (Engg- Elect), AAI, Kolhapur Airport by 04/05/2025 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rs. One Hundred only) and the cost of the stamp paper shall be borne by you.

3. इस निविदा के साथ मांगी गयी अग्रिम धन राशि रु. 1,84,047.00/- (रु रुपये एक लाख चौरासी हजार सैंतालीस मात्र) थी जो की आपके मूल खाते में प्राप्त हो जावेगी। कृपया, प्रतिभूति निक्षेप राशि रु.

Bidyut

Bidyut

Asst. Gen. Manager (Engg-E)

5,77,444.00/- (रुपये पांच लाख सतहत्तर हजार चार सौ चौवालीस मात्र) इस पत्र के निर्गत दिनांक से दस दिनों के भीतर जमा करें अन्यथा उक्त धनराशि की कटौती संविदा प्रपत्र की उक्त संदर्भित शर्त 1A पृष्ठ क्रमांक GCC-16 के अनुसार की जाएगी।

The earnest money deposit of **Rs. 1,84,047.00 (Rupees One Lakh Eighty Four Thousand and Forty Seven Only)** will be refunded back to your original account. Please deposit **Rs. 5,77,444.00/- (Rupees Five Lakh Seventy Seven Thousand Four Hundred and Forty Four Only)**, towards security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted as per condition of GCC Clause no. 1A at page 16 of GCC of tender document.

4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) 1971 केंद्रीय नियमों के प्रावधान का पालन करे, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण कार्यकर्ता (रोजगार का विनियमन और सेवा की शर्त) अधिनियम 1996, बिल्डिंग और अन्य निर्माण कार्यकर्ता कल्याण सेस अधिनियम 1996 जैसा कि निविदा के जीसीसी के खंड 19 पृष्ठ 49 और केंद्रीय तथा राज्य सरकार के नियमों में निर्दिष्ट है।

You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and Contract labour (Regulation and Abolition) Central rules 1971 Child labour (Prohibition and Regulation) Act 1986, Construction workers (Regulation of Employment and Condition of service) Act 1996, Building and other construction workers welfare cess act 1996 as specified in clause 19 page 49 of GCC of tender & minimum wage act and rules of Central and state government.

5. आपको निर्देश दिया जाता है कि आप तुरंत **प्रबंधक (इंजी-विद्युतीय)**, भाविप्रा, कोल्हापुर विमानक्षेत्र से मिले वह आपको साइट सौंपने की व्यवस्था करेंगे। कृपया नोट कर ले कि काम करने का अनुमत समय **03 (तीन) महीना** है जोकि इस पत्र के जारी करने के दसवे दिन से यानी दिनांक **04/05/2025** से गिना जायेगा।

You are also directed to contact **Manager (Engg.-Electrical)**, AAI, Kolhapur Airport immediately who will arrange to hand over site to you. Please note that, the time allowed for carrying out the work is **03 (Three) Months** which shall be reckoned from the tenth day issue of this letter i.e. date **04/05/2025**.

6. इस ठेके के संबंध में आगे की कोई भी पत्राचार **सहा. महाप्रबंधक (इंजी-विद्युतीय)**, भाविप्रा, कोल्हापुर विमानक्षेत्र, कोल्हापुर 416004 के पते पर किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the **Assistant General Manager (Engg.-Electrical)**, AAI, Kolhapur Airport, Kolhapur -416004.

7. उपरोक्त संदर्भित सभी पत्र इस ठेके का भाग होंगे।

All the letters referred above shall from part of contract.

8. उपरोक्त कार्य के लिए त्रुटि दायित्व की अवधि 12 (बारह) महीने होगी।

The defects liability period for the above-mentioned work is 12 (Twelve) months.

9. यदि ठेकेदार को किसी भी सुरक्षा नियम का उल्लंघन करते हुए पाया जाता है, तो वह ब्लैक लिस्टेड हो जाएगा और अन्य कानूनी कार्यवाही के लिए जिम्मेदार होगा।

If Contractor is found violate any of Security Regulations, he shall be Black listed and will be responsible subjected to other Legal Proceedings.

10. स्वीकृति के प्रतीक के रूप में अधिसूचना में हस्ताक्षर करने के बाद कृपया इस पावती को स्वीकार करें और इस पत्र की नकल प्रतिलिपि वापस करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

11. यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण को सही रूप में लिया जाएगा.

In case any discrepancy is found then English version will be taken as correct.

भवदीय /Yours faithfully



सहा महाप्रबंधक (अभि- विद्युतीय),

भाविप्रा, कोल्हापुर हवाईअड्डा, कोल्हापुर

कृते अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से

Asstt. General Manager (Engg.-Elect),

AAI, Kolhapur Airport, Kolhapur

For and on behalf of

Chairman, Airports Authority of India

विद्युत रॉय / Bidyut Roy

सहा. महाप्रबंधक (अभि.विद्युत)

Asst. Gen. Manager (Engg-E)

भा. वि. प्रा. कोल्हापुर हवाई अड्डा, कोल्हापुर

A. A. I. Kolhapur Airport, Kolhapur

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Asst. GENERAL MANAGER (ENGG-ELECT), AIRPORTS AUTHORITY OF INDIA, KOLHAPUR AIRPORT, KOLHAPUR.

Name of Work : Provision of Perimeter lighting at Kolhapur Airport (Phase-I).

Contract No: 2024_AAI_220386_1

Name of the Bidder/
Bidding Firm

M/s. SUNSHINE POWER LINES

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER	TEXT #	TEXT #	NUMBER #	NUMBER #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE(Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Excluding GST
1	2	4	5	12	13	53
1	Supply of 6 mtr height hot dip galvanised octagonal poles with 130 mm bottom (A/F) and 70 mm top (A/F) made of 3mm thick HT sheet along with base plate of size 200mm X 200mm X 12mm thick welded to bottom of the pole having lockable Terminal box, gasket along with 4 Nos. TS-600 foundation bolts including template, providing bakelite sheet with stud type 32 A heavy duty 4 pole connector, DIN Rail for mounting of MCB in the terminal box etc. complete as required.	82	Each	INR	8000.00	656000.00
2	Supplying and fixing of 1 metre long bracket with 300 mm long ERW pipe suitable to fix on 70 mm top (A/F) Octogonal pole and mounting 45 W LED street light fitting including welded cap, stiffner, nuts & bolts (3 Nos, M10 E.R.W.) and washer etc. complete as required. Single Arm	76	Each	INR	1200.00	91200.00
3	Supplying and fixing of 1 metre long bracket with 300 mm long ERW pipe suitable to fix on 70 mm top (A/F) Octogonal pole and mounting 45 W LED street light fitting including welded cap, stiffner, nuts & bolts (3 Nos, M10 E.R.W.) and washer etc. complete as required. Double Arm	6	Each	INR	1800.00	10800.00

Bidyut Roy

विद्युत रॉय / Bidyut Roy
सहा. महाप्रबंधक (अभि.विद्युत)
Asst. Gen. Manager (Engg-E)
भा. वि. प्रा. कोल्हापूर हवाई अड्डा, कोल्हापूर
A. A. I. Kolhapur Airport, Kolhapur


NUMBER #	TEXT #	NUMBER	TEXT #	TEXT #	NUMBER #	NUMBER #
SL. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE(Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Excluding GST
1	2	4	5	12	13	53
4	Supply of 45 W LED type Street Light Luminaire with control gear, made of pressure die cast aluminium housing with heat resistant toughened flat glass/polycarbonate cover and minimum IP 65 protection, suitable for operation in 140-270 V, 50 HZ AC supply and confirming to the specification specified in the tender document with all accessories etc. complete as required.	82	Each	INR	1400.00	114800.00
5	Supply of indoor surface mounting 10 W (nominal capacity), 600 mm length LED light fitting, complete with LED tube rod, accessories etc and suitable for use on 230 volts, 50 Hz, single phase, A.C. supply complete as required.	6	Each	INR	330.00	1980.00
6	Supply of surface mounting 10 W (nominal capacity), IP 65, Bulkhead LED light fitting, complete with accessories suitable for use on 230 volts, 50 Hz, single phase, A.C. supply complete as required.	6	Each	INR	1180.00	7080.00
7	Supply of 300 mm sweep wall fan having Aerodynamically designed, Balanced Blade, suitable for use on 230 volts, 50 Hz, single phase, A.C. supply etc. complete as required.	3	Each	INR	1500.00	4500.00
8	Supplying and fixing DP sheet steel enclosure on surface/ recess complete as required.	3	Each	INR	650.00	1950.00
9	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required. (a) Group C	18	Point	INR	900.00	16200.00
10	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. (a) 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	60	Mtr	INR	210.00	12600.00
11	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required.	6	Each	INR	800.00	4800.00
12	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. (a) Double pole	85	Each	INR	875.00	74375.00

Bidyut Roy
 बिद्युत रॉय / Bidyut Roy
 सहा. महाप्रबंधक (अभि. विद्युत)
 Asst. Gen. Manager (Engg-E)
 भा. वि. प्रा. कोल्हापूर हवाई अड्डा, कोल्हापूर
 A. A. I. Kolhapur Airport, Kolhapur

NUMBER #	TEXT #	NUMBER	TEXT #	TEXT #	NUMBER #	NUMBER #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE(Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Excluding GST
1	2	4	5	12	13	53
13	Erection of 6 mtr. height street light pole of above S.No.1 including making suitable cement concrete foundation, excavation and refilling etc. complete as required as per OEM approved design.	82	Job	INR	2900.00	237800.00
14	Installation, testing and commissioning of street light fixtures on existing street light pole of height not more than 6 mtr. complete with providing and laying of 3 x 1.5 sqmm PVC insulated flexible copper conductor cable from terminal box to fitting, connections etc. as required.	82	Each	INR	550.00	45100.00
15	Installation, testing and commissioning of wall bracket /ceiling fittings of all sizes and shapes containing upto two GLS/CFL/ LED lamps per fitting/wall fan, complete with all accessories including connections etc. as required.	15	Each	INR	90.00	1350.00
16	PTTA PANEL Design, manufacture, supply, installation, testing and commissioning of outdoor compartmentalized type Panel 50 kA short circuit breaking capacity, having panel of suitable size, bus bars with SMC/DMC supports, made of 14 SWG CRCA sheet steel, totally enclosed, IP-65, free standing, floor / wall mounting, powder coated painting, suitable to the existing space, operation on 3 phase and neutral, 415V, 50 Hz AC system with bus bars, G.I flat Earth strip on both side, Removable gland plates at bottom with suitable size of predrilled holes for cables, cable interconnections, wiring, earthing, rotary handles & spreader links to all MCCBs, powder coated painting etc. with following items and installation on suitable channels /elevated concrete foundation as per site requirement etc. complete as required. INCOMER (i) MCCB of 125 Amps, 35 kA, 4 pole, microprocessor based release with Rotary operating mechanism, shunt trip, auxiliary contact etc. 02 Nos (ii) Indication Lamps, LED type, R.Y.B and breaker 'ON', 'OFF', 'TRIP' lamps- 02 Sets (iii) Digital Mult functional meter suitable range for 3 phase, 4 wire with LED display and selector switch along with MCB of suitable ratings- 02 Sets,for 3 phase 4 wire with LED display and selector switch and cast resin CT ratio programmable and auto ranging along with 3 numbers of class 1.0, 15 VA suitable range CTs -02 Sets (iv) Electrical and mechanical interlocking arrangement between above 02 nos. incomers so that supply to busbar to be fed by only 01 incomer at a time. BUSBAR One set of 250 Amp TPN aluminium bus bars of 35 KA capacity OUTGOING (i) 03 Nos. FP, 63 A, 35 kA MCCB with extended terminal with real time timer of suitable rating, contactors and direct rotary handle etc as required (ii) 01 No. FP, 125 A, 35 kA MCCB with extended terminal & direct rotary handle etc as required (iii) 02 Nos. FP MCB 32 Amps, directly connected to bus bar in separate compartment	3	Job	INR	293500.00	880500.00

Bidyut Roy
 बिद्युत रॉय / Bidyut Roy
 सहा. महाप्रबंधक (अभि.विद्युत)
 Asst. Gen. Manager (Engg-E)
 शा. नि. प्रा. बोल्लपुर हवाई अड्डा कोलकाता
 W. A. 1 K. 100 300 400 500 600 700 800 900 1000

NUMBER #	TEXT #	NUMBER	TEXT #	TEXT #	NUMBER #	NUMBER #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE(Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Excluding GST
1	2	4	5	12	13	53
17	Supply of following sizes of XLPE insulated and PVC sheath XLPE aluminium conductor armoured cable of 1.1KV grade conforming to IS 7098 (Part-I) with up to date amendments as required. 4 X 16 Sq.mm	460	Mtr	INR	185.00	85100.00
18	Supply of following sizes of XLPE insulated and PVC sheath XLPE aluminium conductor armoured cable of 1.1KV grade conforming to IS 7098 (Part-I) with up to date amendments as required. 4 X 25 Sq.mm	2419	Mtr	INR	220.00	532180.00
19	Supply of following sizes of XLPE insulated and PVC sheath XLPE aluminium conductor armoured cable of 1.1KV grade conforming to IS 7098 (Part-I) with up to date amendments as required. 3.5 x 240 Sq.mm	1600	Mtr	INR	1200.00	1920000.00
20	Supply of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II etc. , complete as required 90 mm dia (OD-90 mm & ID-76 mm nominal)	1528	Mtr	INR	75.00	114600.00
21	Supply of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II etc. , complete as required 50 mm dia (OD -50mm & ID 40 mm nominal)	2606	Mtr	INR	40.00	104240.00
22	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required 100 mm dia.	42	Mtr	INR	1300.00	54600.00
23	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required 50 mm dia.	30	Mtr	INR	600.00	18000.00
24	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required. Above 185 sq. mm and upto 400 sq. mm	30	Mtr	INR	75.00	2250.00
25	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL / HDPE pipe as required. Upto 35 sq. mm	2666	Mtr	INR	30.00	79980.00
26	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL / HDPE pipe as required. Above 185 sq. mm and upto 400 sq. mm	1570	Mtr	INR	80.00	125600.00
27	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. Upto 35 sq. mm (clamped with 1mm thick saddle)	60	Mtr	INR	37.00	2220.00


 विद्युत रॉय / Bidyut Roy
 सहा. महाप्रबंधक (अभि. विद्युत)
 Asst. Gen. Manager (Engg-E)
 वि. प्रा. कोल्हापूर हवाई अड्डा कोल्हापूर
 V. P. R. Kolhapur Airport, Kolhapur

NUMBER #	TEXT #	NUMBER	TEXT #	TEXT #	NUMBER #	NUMBER #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE (Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Excluding GST
1	2	4	5	12	13	53
28	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed/ XLPE aluminium conductor cable of 1.1 KV grade as required. 4 X 16 sq. mm (28mm)	6	Set	INR	330.00	1980.00
29	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed/ XLPE aluminium conductor cable of 1.1 KV grade as required. 4 X 25 sq. mm (28mm)	6	Set	INR	520.00	3120.00
30	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed/ XLPE aluminium conductor cable of 1.1 KV grade as required. 4 X 25 sq. mm (Excluding Gland)	158	Set	INR	120.00	18960.00
31	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed/ XLPE aluminium conductor cable of 1.1 KV grade as required. 3.5 X 240 sq. mm (62mm)	5	Set	INR	2500.00	12500.00
32	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 3.5 X 240 sq. mm	3	Set	INR	7070.00	21210.00
33	Laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. 90 mm dia (OD-90 mm & ID-76 mm nominal)	1528	Mtr	INR	90.00	137520.00
34	Laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. 50 mm dia (OD -50mm & ID 40 mm nominal)	2606	Mtr	INR	75.00	195450.00
35	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/ coke and salt as required.	6	Each	INR	5000.00	30000.00
36	Providing and fixing 25 mm X 5 mm G.I. strip in 40 mm dia G.I. pipe from earth electrode including connection with G.I. nut, bolt, spring, washer excavation and re-filling etc. as required.	30	Mtr	INR	510.00	15300.00
37	Providing and fixing 25 mm X 5 mm G.I. strip on surface or in recess for connections etc. as required.	30	Mtr	INR	120.00	3600.00

Bidyut Roy

विद्युत रॉय / Bidyut Roy

सहा. महाप्रबंधक (अभि. विद्युत)

Asst. Gen. Manager (Engg-E)

भा. वि. प्रा. कोल्हापूर हवाई अड्डा, कोल्हापूर

A. A. I. Kolhapur Airport, Kolhapur

NUMBER #	TEXT #	NUMBER	TEXT #	TEXT #	NUMBER #	NUMBER #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE(Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Excluding GST
1	2	4	5	12	13	53
38	Providing and fixing 8 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ recessed conduit/ submain wiring/ cable as required.	2879	Mtr	INR	21.00	60459.00
39	Supplying and making cable route marker with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) of size 60 cm X 60 cm at the bottom and 50 cm X 50 cm at the top with a thickness of 10cm including inscription duly engraved as required	32	Each	INR	220.00	7040.00
40	Excavation for cable trenches in soft soil, depth upto 1.2 m including dressing of sides lift upto 1.5 m, including getting out the excavated soil, refilling with sand and or good soil after laying of cable/ pipe etc in layers of 20 cm, ramming, watering and disposal of surplus excavated soil as directed, within a lead of 50 metres.	20	Cum	INR	400.00	8000.00
41	Excavation of the cable trenches in hard rock not exceeding 1.5 metres in width, and lift upto 1.5 metres, including getting out the excavated soil and disposal of excavated soil as directed within a lead of 50 metres.	40	Cum	INR	800.00	32000.00
42	Providing and laying in position reinforced cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) in etc. as required (excluding reinforcement).	5	Cum	INR	3500.00	17500.00
43	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete.	20	Cum	INR	500.00	10000.00
Total in Figures						577444.00

Bidyut

Bidyut Roy
Asst. Gen. Manager (Engg-E)
सहा. महाप्रबंधक (अभि. विद्युत)
कोलकाता ईलाका, कोलकाता

Signature Not Verified

Digitally signed by BIDYUT ROY
Date: 2026.01.07 13:20:00 IST
Location: eProcurement System for Central PSUs

