



भारतीय विमानपत्तन प्राधिकरण,
Airports Authority of India
सिविल एन्क्लेव, बरेली-243122
Civil Enclave, Bareilly-243122

संख्या:-भाविप्रा/ वीएलवाई/ एजीएम (ई-ई) /पेरिमीटर लाइट / का0आ0-09/2024-25/

दिनांक :-11.02.2025

Ref:- AAI/BLY/AGM(E-E)/Perimeter Light/WO-09/2024-25/898-905

Date :- 11.02.2025

(By Speed Post/E-mail)

सेवा में

To,

मैसर्स अनु इंजीनियरिंग कारपोरेशन,
सी-36 दुग्गल कॉलोनी, खानपुर
देवली रोड, दिल्ली - 110062

M/s. Anu Engineering Corporation,
C-36 Duggal Colony, Khanpur
Devli Road, Delhi- 110062

कार्य का नाम :- वाइडनिंग एंड स्ट्रेंथनिंग ऑफ एप्रन एंड टैक्सी ट्रैक एट बरेली एयरपोर्ट।

सब हेड:- प्रोविजन ऑफ पेरिमीटर रोड लाइटिंग.

Name of Work:- Widening and Strengthening of Apron and Taxi Track at Bareilly Airport.

SH: Provision of Perimeter Road Lighting.

संदर्भ :- 1) आपका टेंडर आईडी (2024_AAI_220402_1) खोला गया दिनांक - 24.01.2025

Your tender ID. - (2024_AAI_220402_1) opened on dated - 24.01.2025

महोदय/Sir,

1. उपरोक्त कार्य हेतु आपका आफर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है, आपके द्वारा बताये गये मद मूल्यों पर आपका ऑफर कुल रुपये 28,42,650/- (रुपये अट्ठाईस लाख बयालीस हजार छह सौ पचास केवल) (जी0एस0टी0 अतिरिक्त) है। जोकि टैण्डर की अनुमानित/न्यायसंगत राशि रू0 39,45,370/- से 27.95 प्रतिशत कम है।

Your offer for the work mentioned above work is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs 28,42,650/- (Rupees Twenty Eight Lakhs Forty two Thousand Six Hundred Fifty Only) (GST Extra). Which is 27.95% Below the justified cost put to tender of Rs. 39,45,370/-

2. सहा0 महा0 प्रबन्धक (इंजी-विद्युत), भाविप्रा, सिविल एन्क्लेव, बरेली - 243122, कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप करारनामों पर हस्ताक्षर करने के लिए दिनांक 24.02.2025 तक अधोहस्ताक्षरकर्ता के कार्यालय में उपस्थित हो तथा करारनामों को पूरा करें। ठेके का करारनामा 100/-रुपये के नोनज्यूडिशियल स्टाम्प पेपर पर निष्पादित किया जाएगा, तथा स्टाम्प पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Asstt. General Manager (Engg.-Elect.), AAI, Civil Enclave, Bareilly - 243122, shall be the Engineer in charge of the work. You are requested to attend the office of undersigned by 24-02-2025 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees Hundred only) and the cost of the stamp paper shall be borne by you.

3. आपके इ-टेंडर के साथ प्राप्त धरोहर राशि रुपये 76,927/- ठेके के सामान्य भातों पर दी गयी शर्त 1(A) के अनुसार जमानत राशि में परिवर्तित कर दी जायेगी। कृपया इस पत्र के जारी होने के 15 दिनों के भीतर सिक्क्यूरिटी डिपोजिट के लिए रुपये 2,84,265/- (रु. दो लाख चौरासी हजार दो सौ पैसठ मात्र) जमा कर दे, अन्यथा ठेके के करारनामों में दी शर्त के अनुसार इतनी राशि आपके रनिंग बिलों से काट ली जाएगी।


11.2.2025
AAGM(E-E)

(3/2)

The earnest money amount of Rs. 76,927/- received along with your e-tender will be treated and converted as part of Security Deposit as per GCC Clause 1(A) of the contract document. Please deposit Rs 2,84,265/- (Rupees Two Lakh Eighty Four Thousand Two Hundred Sixty Five Only) towards security deposit within 15 days from the date of issue of this letter, failing which the same will be deducted from your running bills as per condition of the contract.

4. आपसे निवेदन है कि आप केन्द्रीय और राज्य सरकारों के 1970 के अधिनियम अनुबंध श्रम नियम तथा 1971 के केन्द्रीय नियम (रेगुलेशन एवं अबोलिशन) एवं न्यूनतम वेतन अधिनियम और नियमों के प्रावधानों का अब तक के संशोधन के साथ अनुपालन करें।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 and minimum wages act and rules thereof Central and State Governments with upto date amendments.

5. आपको निर्देश दिया जाता है कि आप तुरंत प्रबन्धक (इंजी-विधुत), भाविप्रा, सिविल एन्क्लेव, बरेली से मिलें वह आपको साईट सौंपने की व्यवस्था करेंगे। कृपया नोट कर ले कि काम करने का समय 03 महीना है जोकि दिनांक 18.02.2025 से गिना जाएगा।

You are also directed to contact Manager Engg. (E), AAI, Civil Enclave, Bareilly immediately who will arrange to hand over the site to you. Please note that the time allowed for carrying out the work shall be 03 months which shall be reckoned from dated 18.02.2025.

6. इस ठेके के संबंध में आगे का कोई भी पत्राचार सहायक महाप्रबन्धक (इंजी-विधुत), भाविप्रा, सिविल एन्क्लेव, बरेली - 243122, उत्तर प्रदेश के पते पर किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Asstt. Gen. Manager (Engg.-Elect.), AAI, Civil Enclave, Bareilly- 243122, Uttar Pradesh.

7. उक्त कार्य का त्रुटि दायित्व अवधि 12 (बारह) महीने होगी।

The defects liability period of the contract is 12 (Twelve) months.


8. कृपया पावती भेजें और स्वीकृति के टोकन के रूप में संलग्न इस पत्र की दूसरी प्रति हस्ताक्षर करके अधोहस्ताक्षरी को भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it, to the under signed as a token of acceptance

नोट : हिंदी या अंग्रेजी संस्करण में अंतर या अस्पष्टता के मामले में अंग्रेजी संस्करण मान्य होगा

Note : In case of difference or amguity in Hindi or English Version, the English version will Prevail.

भवदीय / Your's Faithfully,


11.02.2025

सहायक महाप्रबन्धक (अभि.-विधुत),

Asstt. General Manager (Engg.-Elect.),

कृते तथा ओर से अध्यक्ष,

For and on behalf of Chairman,

भारतीय विमानपत्तन प्राधिकरण

Airports Authority of India.

सिविल एन्क्लेव बरेली-243122

Civil Enclave Bareilly -243122

संलग्न/Enclosed – शेडयूल ऑफ क्वान्टटी (5 पेज)/SOQ (5 Pages) Schedule "A"

जारी /Contd...

SCHEDULE OF QUANTITY


Name Of Work:- Widening and Strengthening of Apron and Taxi Track at Bareilly Airport.
SH: Provision of Perimeter Road Lighting

Item No.	Description	Unit	Qty.	Rate (without GST)	Amount
1	2	3	4	5	6
1	Supply of 30 W LED road lighting luminaire consisting of single piece, integral, grey powder coated high pressure die-cast aluminium housing, connecting strip, including power driver should having surge protection upto 8KV complete as required suitable for operation on 230 V, 50 Hz AC supply. (Surya SLE UL 30W IP66 NGN OR EQUIVALENT as per list of Preferred make) Remark: 05 years guarantee shall be provided for complete fitting including driver by OEM in favour of AAI.	Each	125	1200.00	150000.00
2	Supply of 3.50 Meter Height hot dip galvanized octagonal poles with 130 mm Bottom dia , 70 mm top dia , 3 mm thick , base plate of size 200x200x 12 mm, having openable mechanism with L key set, with Single arm standard bracket (having 70 mm top) not less than 1500 mm length and made of 40 mm dia pipe having suitable nipple of size 32mm dia GI pipe to hold the fittings with tilt angle not more than 20 degree including in built arrangement for incoming cable termination with 63A 4P connector and 6A (B curve) SP MCB etc. complete as required as per EIC.	Each	73	6800.00	496400.00
3	Installation of the 3.5 Meter Height GI street light poles with 04 nos foundation bolts of M16X450mm long J type EN 8 grade along with template with 1:1.5:3 Cement concrete (0.45 mtr X 0.45 mtr X 1.10 mtr) to the required depth as per special conditions (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20mm	Job	73	4400.00	321200.00

[Signature]
11.02.2025
AGM (EE)


(3/7)

	nominal size) and necessary base concrete of 1:5:10 for 100mm thickness below the pole (1cement :5 fine sand:10graded stone aggregate 40mm nominal size) suitable finishing on surface above the ground level etc. complete as required including fixing of HDPE/DWC-HDPE pipe for cable entry.				
4	Supply of wall mounted Light Arm made of 40 mm Dia 'B' class G.I pipe having suitable straight and bend of length min 1.0 meter, tilt angle not more than 20 degree suitable for installation of Street light fittings etc. complete as required.	Each	39	450.00	17550.00
5	Providing & fixing of IP-66 SMC box of size 155mm x 210mm x 92 mm on the existing wall, including providing & fixing 01 no. 6A SP MCB and 01 no. four pole connector, connections etc. complete as required. (Make:Hensel, Model No : DK1616 G or equivalent)	Each	39	2800.00	109200.00
6	Installation of wall mounted Light Arm made of 40 mm Dia 'B' class G.I pipe having suitable straight and bend of length min 1.0 meter, tilt angle not more than 20 degree suitable for installation of Street light fittings with suitable clamps (min thickness 3 mm) and 04 nos. anchor fastner i/c fixing of SMC Box on wall for incoming and outgoing cable termination etc. complete as required.	Job	39	350.00	13650.00
7	Installation, Testing and Commissioning of LED (30 W) fitting on existing 3.50 mtr street light pole (straight and bend of length min 1.5 meter) with 3 x 1.5 sqmm PVC insulated copper conductor round cable from cable looping box to fitting etc. complete as required.	Job	73	100.00	7300.00
8	Installation, Testing and Commissioning of LED (30 W) fitting on existing wall mounted Light Arm (straight and bend of length min 1.0 meter) with 3 x 1.5 sqmm PVC insulated copper conductor round cable from SMC box to fitting etc. complete as required.	Job	39	100.00	3900.00

 11.02.2025
 AGM(EE)

(04/7)

9	SITC of outdoor type feeder pillar box with double door weather proof fabricated from 14 SWG MS sheet duly inhibited dust and vermin proof and powder coated complete with rubber gasket, hinged, to be accommodate having IP 65 protection, doors removable gland plate for cable entry. feeder pillar to be installed on the angle iron stand of size 50mmx5mm having four legs and to be mounted in CC base of suitable size etc i/c cement concrete foundation complete as required. 1) 200 A 4 Strip aluminium busbar chamber with DMC/SMC supporting insulators and MS shrouding - 1 set. 2) FP MCCB 125 A, 36KA - 1 No (For Incoming) 3) FP MCCB 125 A, 36KA -1 No , 4P MCB 63 A- 1 No, 4P MCB 32 A- 2 No, 2P MCB 16 A- 2 No (For outgoing) 4) 0-500V, 3 phase digital multi function Ammeter voltmeter meter. 5) CTs 200/5 - 1 set 6) R,Y,B Pilot indicating lamps (Cluster LED type) with 6 nos. control 6 Amp. SP MCB -1 Set for incommers. 7) (0-24 Hrs) Astronomical timer switch with 63A FP contactor-01 No.	Each	2	105000.00	210000.00
10	Supply of XLPE/PVC insulated, PVC sheathed aluminium conductor armoured power cable of 1.1KV grade confirming to IS 7098 (Part I) 1978 with upto date amendments etc as required for the following sizes.(Make : As per approved list.)				
10.1	3.5C x 70 sqmm	Mtr.	1350	440.00	594000.00
10.2	4C x 16 Sqmm.	Mtr.	2000	165.00	330000.00
11	Supplying and laying of 63 mm dia (OD- 63 mm & ID-51 mm nominal) DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level including excavation and	Mtr.	1750	170.00	297500.00

 11.02.2025
 AGM (EE)

(05/7)


	refilling the trench but excluding sand cushioning and protective covering etc., complete as required.				
12	Supplying and Laying of additional 63 mm dia (OD-63 mm & ID-51 mm nominal) DWC HDPE pipe along with all accessories like socket, bend, couplers etc. complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) in the same trench in one tier horizontal formation including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required.	Mtr.	500	150.00	75000.00
13	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				
13.1	3.5C x 70 sqmm	Each	4	200.00	800.00
13.2	4C x 16 Sqmm.	Each	224	150.00	33600.00
14	Laying of one number PVC insulated and PVC sheathed/XLPE power cable of 1.1 KV grade of following size in the existing RCC/HUME/Metal/DWC HDPE pipe as required. Above 35 sq. mm and upto 95 Sq.mm	Mtr.	1300	15.00	19500.00
15	Laying of one number PVC insulated and PVC sheathed/XLPE power cable of 1.1 KV grade of following size in the existing RCC/HUME/Metal/DWC HDPE pipe as required. Upto 35 sq. mm.	Mtr.	1050	15.00	15750.00
16	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. Upto 35 sq. mm (clamped with 1mm thick saddle)	Mtr.	500	90.00	45000.00
17	Providing, laying and fixing 80 mm dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required.	Mtr.	24	850.00	20400.00


 11.02.2025
 A GME EE/

(06/7)

18	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. (with charcoal/coke and salt) as required.	Job	7	4500.00	31500.00
19	Providing and laying earth connection from earth electrode with 6 SWG dia G.I. wire in 15 mm dia G.I. pipe from earth electrode including connection with G.I. thimble excavation and re-filling as required.	Mtr.	20	195.00	3900.00
20	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ recessed conduit/ submain wiring/ cable as required.	Mtr.	1550	30.00	46500.00
Total Rs.					28,42,650.00

(Rs. Twenty Eight Lakhs Fourty Two Thousand Six Hundred Fifty only)


11.02.2025

Asst. General Manager (Engg.-Elect.)
AAI, Civil Enclave Bareilly-243122

(07/7)