



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

संदर्भ संख्या: भा.वि.प्रा./ राजमुंदरी/ आईएलएस /2024-25/1435
Ref.No. AAI/RJY/Engg-Civil/ ILS /2024-25

दिनांक: 06.03.2025
Date: 06.03.2025

सेवा में
एम/एस. गगन सेल,
घर नंबर: 8-3-169/2A, सिद्धार्थनगर,
वेंगलाराव नगर,
हैदराबाद,
तेलंगाना - 500 038

To
M/S. GAGAN SAIL,
H. No: 8-3-169/2A, SIDDARTH NAGAR,
VENGALRAO NAGAR,
Hyderabad,
Telangana - 500 038.

कार्य का नाम : राजमुंदरी हवाई अड्डे पर आईएलएस की स्थापना, लोकलाइज़र और ग्लाइड पथ का निर्माण।
एसएच: सिविल और आंतरिक विद्युत कार्य।

Name of Work: **Installation of ILS-Construction of LLZ & GP at Rajahmundry Airport.**
SH: Civil and internal electrical works.

संदर्भ : ई-निविदा क्रमांक 2024_AAI_221634_1 के संदर्भ में विषयागत कार्य हेतु 07.02.2025 को खोली गई आपकी वित्तीय निविदा।

Ref : Your financial bid for the subject work in reference to Tender ID - 2024_AAI_221634_1, opened on 07.02.2025.

महोदय/Dear Sir,

- उपर्युक्त कार्य के लिए आपका ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आपके द्वारा उद्धृत कुल रु. 3,08,21,455.00 (मात्र तीन करोड़ आठ लाख इक्कीस हजार चार सौ पचपन रूपये) (जीएसटी को छोड़कर) की दर पर स्वीकार किया जाता है जो कि निविदा में रखी गई अनुमानित लागत रु. 4,42,98,747.00 से 30.42% कम है।

Your E-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India at the items rate quoted by you totalling to Rs. 3,08,21,455.00 (Rupees Three Crores Eight Lakh Twenty-one Thousand Four Hundred Fifty-five only) (Excl. GST) which is 30.42% below estimated cost put to tender of Rs. 4,42,98,747.00.

- सहायक महाप्रबंधक (इंजीनियरिंग-सिविल), एएआई राजमुंदरी हवाई अड्डा कार्य का प्रभारी इंजीनियर होगा। आपसे अनुरोध है कि समझौते पर हस्ताक्षर करने और पूरा करने के लिए 21.03.2025 तक सहायक महाप्रबंधक (इंजीनियरिंग-सिविल), एएआई, राजमुंदरी हवाई अड्डे के कार्यालय में उपस्थित हों। अनुबंध 100/- रुपये मूल्य के गैर-न्यायिक स्टॉप पेपर पर निष्पादित किया जाएगा और स्टॉप पेपर की लागत आपके द्वारा वहन की जाएगी।

Asst General Manager (Engg-Civil), AAI Rajahmundry Airport shall be the Engineer-in-charge of the work. You are requested to attend the office of Asst General Manager (Engg-Civil), AAI, Rajahmundry Airport by 21.03.2025 to sign and complete the agreement. The

6/3/25

विमानपत्तन निदेशक का कार्यालय, राजमुंदरी हवाई अड्डा, मधुरपूडि (पोस्ट), राजमुंदरी 533 102
O/o The Airport Director, Rajahmundry Airport, Madhurapudi (Post), Rajahmundry 533 102
दूरभाष / Phone: 0883 - 2007838, फैक्स / FAX: 0883 - 2487852
राजमुंदरी / RAJAHMUNDY-533 102.



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

contract agreement shall be executed on a non-judicial stamp paper of value of Rs.100/- and the cost of the stamp paper shall be borne by you.

3. इस पत्र के जारी होने की तारीख से 10 दिनों के भीतर सुरक्षा जमा राशि के रूप में रुपये 30,82,145/- (मात्र तीस लाख बयासी हजार एक सौ पैतालीस रुपये) कृपया जमा करें, ऐसा न करने पर, अनुबंध दस्तावेज़ के पृष्ठ GCC-17 पर खंड 1A की शर्त के अनुसार कटौती की जाएगी।

Please deposit Rs. 30,82,145/- (Rupees Thirty lakhs eighty-two thousand one hundred forty-five only) towards security deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted as per condition of Clause 1A on Page GCC-17 of the Contract Document.

4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार का विनियमन और शर्त) के प्रावधानों का अनुपालन करें। सेवा) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 जैसा कि खंड संख्या में निर्दिष्ट है। 19 पेज नं. केंद्र और राज्य सरकारों की निविदा और उसके नियमों की जीसीसी की धारा 45।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act of 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971, Child Labour (Prohibition and Regulation) Act 1986, Construction Workers (Regulation of Employment and condition of Service) Act 1996, Building and other construction workers Welfare cess Act 1996 as specified in clause no. 19 at page no. 45 of GCC of tender and rules thereof Central and State Governments.

5. आपको तुरंत एएआई राजमुंदरी हवाई अड्डे के सहायक महाप्रबंधक (इंजीनियरिंग-सिविल) से संपर्क करने का भी निर्देश दिया जाता है, जो आपको साइट सौंपने की व्यवस्था करेंगे।


You are also directed to contact Asst. General Manager (Engg-Civil), AAI Rajahmundry Airport immediately who will arrange to handover the site to you.

6. कृपया ध्यान दें कि कार्य को पूरा करने के लिए अनुमत समय 09 (नौ) महीने (बारिश के लिए विचार किए गए 02 महीने सहित) होगा जिसकी गणना इस पत्र के जारी होने के दसवें दिन से की जाएगी।

Please note that the time allowed for carrying out the work shall be 09 (Nine) Months (Including 02 Month(s) considered for rains) which shall be reckoned from tenth day after issue of this letter.

7. इस अनुबंध के संबंध में कोई भी आगे का पत्राचार सामान्यतः प्रभारी अभियंता को संबोधित किया जाना चाहिए।

Any further correspondence in connection with this contract should normally be addressed to the Engineer-in-Charge.


सहायक महा प्रबंधक (इंजीनियरिंग-सिविल)
Asst. Gen Manager (Engg-Civil)



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

8. कृपया पावती भेजें तथा इसके साथ संलग्नित इस पत्र की दूसरी प्रति पर विधिवत हस्ताक्षर करने के उपरांत प्राप्ति के प्रमाणस्वरूप में इसे अधोहस्ताक्षरी को वापस भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after duly signing it to the undersigned as a token of acceptance.

भवदीय / Yours faithfully,

(के कनकराज) / (K. KANAKARAJ)

सहायक महाप्रबंधक (अभि-सि.), / Asst. General Manager (Engg-Civil)

भा.वि.प्रा. राजमंड्री हवाई अड्डा / AAI, Rajahmundry Airport

अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण के लिए व उनकी तरफ से

For and on Behalf of the Chairman, Airports Authority of India.

संलग्न/Encl.: अनुसूची ऐ /Schedule A

सहायक महा प्रबंधक (इंजी-सिविल)

Asst. Gen Manager (Engg-Civil)

भारतीय विमानपत्तन प्राधिकरण/AAI
राजमंड्री हवाई अड्डा / RAJAHMUNDRY AIRPORT

राजमंड्री/ RAJAHMUNDRY-533 102.

9.

Validate

Print

Help


Item Rate BoQ

Tender Inviting Authority: Asst. Gen. Manger (Engg-C), AAI, Rajahmundry Airport


Name of Work: Installation of ILS-Construction of LLZ & GP at Rajahmundry Airport. SH: Civil and internal electrical works.

Contract No: 2024_AAI_221634_1

Name of the Bidder/ Bidding Firm / Company :	GAGAN SAIL							
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)								
NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST.
1	2	3	3	4	5	6	7	8
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in- Charge: All kinds of soil.	SH-1/1	7962.50	sqm	INR	36.00	286650.00	INR Two Lakh Eighty Six Thousand Six Hundred & Fifty Only
2	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge.All kinds of soil.	SH-1/2	100.00	cum	INR	90.00	9000.00	INR Nine Thousand Only
3	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge. Ordinary rock.	SH-1/3	100.00	cum	INR	150.00	15000.00	INR Fifteen Thousand Only
4	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth upto 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m :Pipes, cables etc. exceeding 80 mm dia. but not exceeding 300 mm dia	SH-1/4	100.00	mtr	INR	117.00	11700.00	INR Eleven Thousand Seven Hundred Only
5	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil.	SH-1/5	89410.00	sqm	INR	5.50	491755.00	INR Four Lakh Ninety One Thousand Seven Hundred & Fifty Five Only


 महाप्रबन्धक महा प्रबंधक (इंजी-सिविल)
 Asst. Gen Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण/AAI
 राजमंड्री हवाई अड्डा / RAJAHMUNDY AIRPORT

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST.
1	2	3	3	4	5	6	7	8
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources).	SH-1/6	44.00	cum	INR	4959.00	218196.00	INR Two Lakh Eighteen Thousand One Hundred & Ninety Six Only
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :M-10 or 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources).	SH-1/7	573.00	cum	INR	3753.00	2150469.00	INR Twenty One Lakh Fifty Thousand Four Hundred & Sixty Nine Only
8	P/L in position ready mixed or site batched design mix cement concrete for plain cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana/Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering and finishing as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra above the minimum specified cement content in design mix shall be payable separately. All works upto plinth level : Concrete of M25 grade with minimum cement content of 300 kg /cum.	SH-1/8	38.00	cum	INR	5499.00	208962.00	INR Two Lakh Eight Thousand Nine Hundred & Sixty Two Only
9	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete.	SH-1/9	139.00	sqm	INR	320.00	44480.00	INR Forty Four Thousand Four Hundred & Eighty Only
10	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform	SH-1/10	15.00	sqm	INR	380.00	5700.00	INR Five Thousand Seven Hundred Only
11	Centering and shuttering including strutting, propping etc. and removal of form for Edges of slabs and breaks in floors and walls above 20 cm wide.	SH-1/11	7.00	sqm	INR	450.00	3150.00	INR Three Thousand One Hundred & Fifty Only
12	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	SH-1/12	8000.00	kg	INR	90.00	720000.00	INR Seven Lakh Twenty Thousand Only


 सहायक महा प्रबंधक (इंजीनियरिंग)
 Asst. Gen Manager (Engg-Civil)
 भाग्यनीय विमानपत्तन प्राधिकरण/AAI
 राजमंडी हवाई अड्डा / RAJAHMUNDRY AIRPORT
 राजमंडी/ RAJAHMUNDRY-533 102.

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT in Words without GST.
1	2	3	3	4	5	6	7	8
13	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement above the minimum specified cement content in design mix shall be payable separately. All works upto plinth level Concrete of M25 grade with minimum cement content of 330 kg /cum	SH-1/13	100.00	cum	INR	5589.00	558900.00	INR Five Lakh Fifty Eight Thousand Nine Hundred Only
14	Add for using extra cement in the items of design mix over and above the specified cement content therein.	SH-1/14	480.00	qtl	INR	549.00	263520.00	INR Two Lakh Sixty Three Thousand Five Hundred & Twenty Only
15	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 5.0 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand).	SH-1/15	10.00	cum	INR	6000.00	60000.00	INR Sixty Thousand Only
16	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	SH-1/16	148.00	kg	INR	135.00	19980.00	INR Nineteen Thousand Nine Hundred & Eighty Only
17	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete.	SH-1/17	423.00	kg	INR	115.00	48645.00	INR Forty Eight Thousand Six Hundred & Forty Five Only
18	Providing and laying Vitriified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in allcolours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement:4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm includinggrouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only . Laying oftiles will be done with the notch trowel, plier, wedge, clips of requiredthickness, leveling system and rubber mallet for placing the tiles gentlyand easily Glazed Vitriified tiles Matt/Antiskid finish of size Size of Tile 600 x 600 mm.	SH-1/18	80.00	sqm	INR	1120.00	89600.00	INR Eighty Nine Thousand Six Hundred Only

महायक महा प्रबंधक (इंजीनियरिंग)
 Asst. Gen Manager (Engg.Civil)
 भारतीय विमानपत्तन प्राधिकरण/AAI
 राजमंडी हवाई अड्डा / RAJAHMUNDY AIRPORT
 राजमंडी RAJAHMUNDY-533 102.


NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST.
1	2	3	3	4	5	6	7	8
19	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion - Single socketed pipes 75 mm diameter.	SH-1/19	100.00	metre	INR	145.00	14500.00	INR Fourteen Thousand Five Hundred Only
20	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion - Single socketed pipes 110 mm diameter.	SH-1/20	200.00	metre	INR	225.00	45000.00	INR Forty Five Thousand Only
21	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Bend 87.5° 75 mm bend.	SH-1/21	1.00	Each	INR	150.00	150.00	INR One Hundred & Fifty Only
22	12 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand).	SH-1/22	33.00	sqm	INR	280.00	9240.00	INR Nine Thousand Two Hundred & Forty Only
23	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 metres.	SH-1/23	5050.00	sqm	INR	45.00	227250.00	INR Two Lakh Twenty Seven Thousand Two Hundred & Fifty Only
24	Construction of dry lean cement concrete sub base over a prepared sub- grade with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per specifications, cement content not to be less than 150 Kg/cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, for all leads & lifts, laid with a mechanical paver, compacting with 8-10 tonne vibratory roller, finishing and curing etc. complete as per direction of Engineer-in- charge.	SH-1/24	488.00	cum	INR	2799.00	1365912.00	INR Thirteen Lakh Sixty Five Thousand Nine Hundred & Twelve Only
25	Providing and filling in position rubberized bitumen hot sealing compound for sealing of expansion joints in roads / pavements all complete as per direction of the engineer in charge.	SH-1/25	1215.00	per cm depth per cm width per metre length	INR	10.00	12150.00	INR Twelve Thousand One Hundred & Fifty Only

सहायक महा प्रबंधक (इंजीनियरिंग)
 Asst. Gen Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण/AAI
 राजमंडी हवाई अड्डा / RAJAHMUNDY AIRPORT
 522 102

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST.
1	2	3	3	4	5	6	7	8
26	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	SH-1/26	8040.00	sqm	INR	684.00	5499360.00	INR Fifty Four Lakh Ninety Nine Thousand Three Hundred & Sixty Only
27	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer- in-Charge. With material conforming to Grade-II (size range 53 mm to 0.075 mm) having CBR Value-25.	SH-1/27	1515.00	cum	INR	1359.00	2058885.00	INR Twenty Lakh Fifty Eight Thousand Eight Hundred & Eighty Five Only
28	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid.	SH-1/28	2.00	Each	INR	5000.00	10000.00	INR Ten Thousand Only
29	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Flat back wash basin size 450 x 300 mm with single 15mm C.P. brass pillar tap.	SH-1/29	2.00	Each	INR	1200.00	2400.00	INR Two Thousand Four Hundred Only
30	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete, Flexible pipe 32 mm dia.	SH-1/30	2.00	Each	INR	100.00	200.00	INR Two Hundred Only
31	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing: Rectangular shape 453 x 357 mm.	SH-1/31	2.00	Each	INR	1200.00	2400.00	INR Two Thousand Four Hundred Only
32	Providing and fixing uplasticised PVC connection pipe with brass unions 45 cm length 15 mm nominal bore.	SH-1/32	4.00	Each	INR	200.00	800.00	INR Eight Hundred Only
33	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 : 15 mm nominal bore.	SH-1/33	2.00	Each	INR	1200.00	2400.00	INR Two Thousand Four Hundred Only
34	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 : 15 mm nominal bore.	SH-1/34	4.00	Each	INR	600.00	2400.00	INR Two Thousand Four Hundred Only

6/3/25
 सहायक महा प्रबंधक (इंजीनियरिंग)
 Asst. Gen Manager (Engg-Civil)
 AIRPORT


NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST.
1	2	3	3	4	5	6	7	8
35	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings. This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 20 mm nominal dia Pipes.	SH-1/35	20.00	metre	INR	300.00	6000.00	INR Six Thousand Only
36	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings. This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 50 mm nominal dia Pipes.	SH-1/36	40.00	metre	INR	700.00	28000.00	INR Twenty Eight Thousand Only
37	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 20 mm dia nominal bore.	SH-1/37	100.00	metre	INR	400.00	40000.00	INR Forty Thousand Only
38	Providing and fixing gun metal non- return valve of approved quality (screwed end) : 40 mm nominal bore Horizontal.	SH-1/38	2.00	Each	INR	4080.00	8160.00	INR Eight Thousand One Hundred & Sixty Only
39	Providing and fixing rectangular high density polyethylene water storage loft tank with cover, conforming to ISI : 12701, colour of opaque white or as approved by Engineer-in-charge. The rate includes making necessary holes for inlet, outlet & over flow pipes. (The base support i/c fittings & fixtures for tank shall be paid separately).	SH-1/39	500.00	litre	INR	10.00	5000.00	INR Five Thousand Only
40	Constructing brick masonry road gully chamber/ Normal Chamber 50 x 45 x 60 cm with bricks in cement mortar 1:4 (1 cement : 4 coarse sand) including 500 x 450 mm pre-cast R.C.C. horizontal grating or cover with frame complete as per standard design: With common burnt clay F.P.S. (non modular) bricks of class designation 3.5.	SH-1/40	4.00	Each	INR	2800.00	11200.00	INR Eleven Thousand Two Hundred Only
41	Making soak pit 2.5 m diameter 3.0 metre deep with 45 x 45 cm dry brick honey comb shaft with bricks and S.W. drain pipe 100 mm diameter, 1.8 m long complete as per standard design. With common burnt clay F.P.S. (non modular) bricks of class designation 3.5 to 7.5.	SH-1/41	2.00	Each	INR	24300.00	48600.00	INR Forty Eight Thousand Six Hundred Only
42	Boring/drilling bore well of required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/ bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge, upto 90 metre depth below ground level. All types of soil 300 mm dia.	SH-1/42	180.00	metre	INR	1500.00	270000.00	INR Two Lakh Seventy Thousand Only


 सहायक महा प्रबंधक (इंजी-सिविल)
 Asst. Gen Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण/AAI
 राजमंडी हवाई अड्डा / RAJAHMUNDY AIRPORT
 राजमंडी/ RAJAHMUNDY-533 102.

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST.
1	2	3	3	4	5	6	7	8
43	Boring/drilling bore well of required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/ bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer -in-charge, beyond 90 metre & upto 150 metre depth below ground level. All types of soil 300 mm dia.	SH-1/43	40.00	metre	INR	1800.00	72000.00	INR Seventy Two Thousand Only
44	Supplying, assembling, lowering and fixing in vertical position in bore well, unplasticized PVC medium well casing (CM) pipe of required dia, conforming to IS: 12818, including required hire and labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer -in-charge. 200 mm nominal size dia.	SH-1/44	180.00	metre	INR	1400.00	252000.00	INR Two Lakh Fifty Two Thousand Only
45	Supplying, assembling, lowering and fixing in vertical position in bore well unplasticized PVC medium well screen (RMS) pipes with ribs, conforming to IS: 12818, including hire & labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer-in-charge 200 mm nominal size dia.	SH-1/45	40.00	metre	INR	1800.00	72000.00	INR Seventy Two Thousand Only
46	Supplying, filling, spreading & leveling stone boulders of size range 5 cm to 20 cm, in recharge pit, in the required thickness, for all leads & lifts, all complete as per direction of Engineer-in-charge.	SH-1/46	10.00	cum	INR	1800.00	18000.00	INR Eighteen Thousand Only
47	Supplying, filling, spreading & leveling gravels of size range 5 mm to 10 mm, in the recharge pit, over the existing layer of boulders, in required thickness, for all leads & lifts, all complete as per direction of Engineer-in-charge.	SH-1/47	10.00	cum	INR	1800.00	18000.00	INR Eighteen Thousand Only
48	Supplying, filling, spreading & leveling coarse sand of size range 1.5 mm to 2 mm in recharge pit, in required thickness over gravel layer, for all leads & lifts, all complete as per direction of Engineer -in-charge.	SH-1/48	10.00	cum	INR	1800.00	18000.00	INR Eighteen Thousand Only
49	Gravel packing in tubewell construction in accordance with IS: 4097, including providing gravel fine/ medium/ coarse, in required grading & sizes as per actual requirement, all complete as per direction of Engineer-in-charge.	SH-1/49	10.00	cum	INR	1950.00	19500.00	INR Nineteen Thousand Five Hundred Only


 सहायक महा प्रबंधक (इंजी-सिविल)
 Asst. Gen Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण/AAI
 राजमंडी हवाई अड्डा / RAJAHMUNDRI AIRPORT
 राजमंडी/ RAJAHMUNDRI-533 102.


NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST.
1	2	3	3	4	5	6	7	8
50	Development of tube well in accordance with IS : 2800 (part I) and IS: 11189, to establish maximum rate of usable water yield without sand content (beyond permissible limit), with required capacity air compressor, running the compressor for required time till well is fully developed, measuring yield of well by "V" notch method or any other approved method, measuring static level & draw down etc. by step draw down method, collecting water samples & getting tested in approved laboratory, i/c disinfection of tubewell, all complete, including hire & labour charges of air compressor, tools & accessories etc., all as per requirement and direction of Engineer-in-charge.	SH-1/50	50.00	hour	INR	900.00	45000.00	INR Forty Five Thousand Only
51	Providing and fixing suitable size threaded mild steel cap or spot welded plate to the top of bore well housing/ casing pipe, removable as per requirement, all complete for borewell of: 200 mm dia.	SH-1/51	2.00	Each	INR	500.00	1000.00	INR One Thousand Only
52	Providing and fixing M.S. clamp of required dia to the top of casing/ housing pipe of tubewell as per IS: 2800 (part I), including necessary bolts & nuts of required size complete. 200 mm clamp.	SH-1/52	2.00	Each	INR	2000.00	4000.00	INR Four Thousand Only
53	Providing and fixing Bail plug/ Bottom plug of required dia to the bottom of pipe assembly of tubewell as per IS:2800 (part I). 200 mm dia.	SH-1/53	2.00	Each	INR	500.00	1000.00	INR One Thousand Only
54	Extra for disposal of excavated earth upto 1000 mt lead over and above the base earth work items. (measurement will be based on truck capacity after deduction of voides as per CPWD specifications)	SH-1/54	300.00	cum	INR	150.00	45000.00	INR Forty Five Thousand Only
55	Providing and installing Fire Retardant Water proof Frangible Hut (Wall and Roof 50mm thick with both sides FRP Sheet 2 mm thick) Hut Size 8.0 Mtr x 5.0 Mtr x 3.5 Mtr., having one Partition and 2 nos. doors. And toilet block Size: 2.0 Mtr. X 2.0 Mtr. X 3.5 Mtr. Having one door.PUF Density: - 40±2 Kg/M³. Design and details drawing have to be vetted and certified from Government engineering college for complying under ICAO norms "ICAO AERODROME DESIGN MANUAL (Doc. No.9157, Part -6 Frangibility) and as per the product technical specifications.	SH-1/55	2.00	Each	INR	2430000.00	4860000.00	INR Forty Eight Lakh Sixty Thousand Only


 सहयक महा प्रबंधक (इंजीनियरिंग)
 Asst. Gen Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण/AAI
 राजमंडी हवाई अड्डा / RAJAHMUNDY AIRPORT
 राजमंडी/ RAJAHMUNDY-533 102.

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST.
1	2	3	3	4	5	6	7	8
56	Providing and fixing Medium B class G.I. pipes painted with anti corrosive bitumastic paint complete with G.I. fittings or joining with welding including trenching, filling sand of grading zone V or coarser grade, allround and refilling etc. The rate shall be inclusive of all fittings and specials such as bends, couplings, elbows or welding, earth work, laying, painting G.I. pipes and fittings with two coats of anti-corrosive bitumastic paint of approved quality, providing and filling sand of coarser grade, allround. The minimum depth of cutting shall be 600mm unless restricted due to site conditions. External work: Painting G.I. pipes and fittings with two coats of anti-corrosive bitumastic paint of approved quality : Providing and filling sand of grading zone V or coarser grade, allround the G.I. pipes in external work : 150 mm dia.	SH-1/56	1155.00	metre	INR	1629.00	1881495.00	INR Eighteen Lakh Eighty One Thousand Four Hundred & Ninety Five Only
57	Providing and laying polythene sheet 400 micron thick confirming to IS 2508 anti friction layer on the surface course complete as per specifications with specified overlaps between adjacent and transverse strips, only plan area will be measured for payment as directed by the engineer in charge.	SH-1/57	4875.00	sqm	INR	45.00	219375.00	INR Two Lakh Nineteen Thousand Three Hundred & Seventy Five Only
58	Providing and laying in position ready mixed or site batched design mix cement concrete M 30 grade in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping making provision for contraction/ expansion, construction & longitudinal joints (10 mm wide x 50 mm deep) by groove cutting machine complete. Note: Extra cement above minimum specified cement content in design mix shall be payable separately. All works upto plinth level Concrete of M30 grade with minimum cement content of 350 kg /cum.	SH-1/58	1219.00	cum	INR	6039.00	7361541.00	INR Seventy Three Lakh Sixty One Thousand Five Hundred & Forty One Only
59	Providing and fixing PVC/polyethylene bio septic tank, of approved make, with necessary fittings for inlet and outlet and as per the manufacturer specifications. Earth work required will be paid separately in earthwork item.	SH-1/59	4000.00	Litre	INR	25.00	100000.00	INR One Lakh Only
60	Providing and Fixing SWR PVC pipes specially designed and manufactured using high grade raw material for removal of waste in the drainage system for non-pressure plumbing applications, such as transportation of soil, waste and waste discharge systems. SWR pipes type B for soil and waste discharge. Pipes shall confirm to IS 13592 and Fittings shall confirm to IS 14735. 110mm dia.	SH-1/60	20.00	Mtr	INR	350.00	7000.00	INR Seven Thousand Only

6/3/24
 महायक महा प्रबंधक (इंजीनियरिंग)
 Asst. Gen Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण/AAI
 राजमंडी हवाई अड्डा / RAJAHMUNDRY AIRPORT
 राजमंडी RAJAHMUNDRY-533 102.


NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST.
1	2	3	3	4	5	6	7	8
61	Providing and Fixing SWR PVC pipes specially designed and manufactured using high grade raw material for removal of waste in the drainage system for non-pressure plumbing applications, such as transportation of soil, waste and waste discharge systems. SWR pipes type B for soil and waste discharge. Pipes shall confirm to IS 13592 and Fittings shall confirm to IS 14735. 75mm dia.	SH-1/61	20.00	Mtr	INR	210.00	4200.00	INR Four Thousand Two Hundred Only
62	Providing and Fixing SWR PVC fittings specially designed and manufactured using high grade raw material for removal of waste in the drainage system for non-pressure plumbing applications, such as transportation of soil, waste and waste discharge systems. SWR pipes type B for soil and waste discharge. Pipes shall confirm to IS 13592 and Fittings shall confirm to IS 14735. 110mm dia Bend.	SH-1/62	8.00	Each	INR	120.00	960.00	INR Nine Hundred & Sixty Only
63	Providing and Fixing SWR PVC fittings specially designed and manufactured using high grade raw material for removal of waste in the drainage system for non-pressure plumbing applications, such as transportation of soil, waste and waste discharge systems. SWR pipes type B for soil and waste discharge. Pipes shall confirm to IS 13592 and Fittings shall confirm to IS 14735. 75mm dia Bend.	SH-1/63	8.00	Each	INR	80.00	640.00	INR Six Hundred & Forty Only
64	Providing and Fixing SWR PVC fittings specially designed and manufactured using high grade raw material for removal of waste in the drainage system for non-pressure plumbing applications, such as transportation of soil, waste and waste discharge systems. SWR pipes type B for soil and waste discharge. Pipes shall confirm to IS 13592 and Fittings shall confirm to IS 14735. 110mm dia door Bend.	SH-1/64	4.00	Each	INR	150.00	600.00	INR Six Hundred Only
65	Providing and Fixing SWR PVC fittings specially designed and manufactured using high grade raw material for removal of waste in the drainage system for non-pressure plumbing applications, such as transportation of soil, waste and waste discharge systems. SWR pipes type B for soil and waste discharge. Pipes shall confirm to IS 13592 and Fittings shall confirm to IS 14735. 75mm dia door Bend.	SH-1/65	4.00	Each	INR	90.00	360.00	INR Three Hundred & Sixty Only
66	Providing and Fixing SWR PVC fittings specially designed and manufactured using high grade raw material for removal of waste in the drainage system for non-pressure plumbing applications, such as transportation of soil, waste and waste discharge systems. SWR pipes type B for soil and waste discharge. Pipes shall confirm to IS 13592 and Fittings shall confirm to IS 14735. 110mm dia Tee.	SH-1/66	4.00	Each	INR	150.00	600.00	INR Six Hundred Only


 सहायक महा प्रबंधक (इंजी-सिविल)
 Asst. Gen Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण/AAI
 गान्धारी हवाई अड्डा / RAJAHMUNDY AIRPORT
 RAJAHMUNDY AIRPORT


NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST.
1	2	3	3	4	5	6	7	8
67	Providing and Fixing SWR PVC fittings specially designed and manufactured using high grade raw material for removal of waste in the drainage system for non-pressure plumbing applications, such as transportation of soil, waste and waste discharge systems. SWR pipes type B for soil and waste discharge. Pipes shall confirm to IS 13592 and Fittings shall confirm to IS 14735. 75mm dia Tee.	SH-1/67	4.00	Each	INR	120.00	480.00	INR Four Hundred & Eighty Only
68	Providing and Fixing SWR PVC fittings specially designed and manufactured using high grade raw material for removal of waste in the drainage system for non-pressure plumbing applications, such as transportation of soil, waste and waste discharge systems. SWR pipes type B for soil and waste discharge. Pipes shall confirm to IS 13592 and Fittings shall confirm to IS 14735. 110mm dia Door Tee.	SH-1/68	2.00	Each	INR	180.00	360.00	INR Three Hundred & Sixty Only
69	Providing and Fixing SWR PVC fittings specially designed and manufactured using high grade raw material for removal of waste in the drainage system for non-pressure plumbing applications, such as transportation of soil, waste and waste discharge systems. SWR pipes type B for soil and waste discharge. Pipes shall confirm to IS 13592 and Fittings shall confirm to IS 14735. 75mm dia Door Tee.	SH-1/69	2.00	Each	INR	120.00	240.00	INR Two Hundred & Forty Only
70	Providing and Fixing SWR PVC fittings specially designed and manufactured using high grade raw material for removal of waste in the drainage system for non-pressure plumbing applications, such as transportation of soil, waste and waste discharge systems. SWR pipes type B for soil and waste discharge. Pipes shall confirm to IS 13592 and Fittings shall confirm to IS 14735. 110mm dia Coupler.	SH-1/70	2.00	Each	INR	90.00	180.00	INR One Hundred & Eighty Only
71	Providing and Fixing SWR PVC fittings specially designed and manufactured using high grade raw material for removal of waste in the drainage system for non-pressure plumbing applications, such as transportation of soil, waste and waste discharge systems. SWR pipes type B for soil and waste discharge. Pipes shall confirm to IS 13592 and Fittings shall confirm to IS 14735. 75mm dia Coupler.	SH-1/71	2.00	Each	INR	60.00	120.00	INR One Hundred & Twenty Only
72	Providing and Fixing SWR PVC fittings specially designed and manufactured using high grade raw material for removal of waste in the drainage system for non-pressure plumbing applications, such as transportation of soil, waste and waste discharge systems. SWR pipes type B for soil and waste discharge. Pipes shall confirm to IS 13592 and Fittings shall confirm to IS 14735. 100mmx75mm dia floor trap.	SH-1/72	2.00	Each	INR	150.00	300.00	INR Three Hundred Only


 सहायक महा प्रबंधक (इंजीनियरिंग)
 Asst. Gen Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण / AAI
 राजमंडी हवाई अड्डा / RAJAHMUNDY AIRPORT
 RAJAHMUNDY-533 102.


NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST.
1	2	3	3	4	5	6	7	8
73	Providing and Fixing SWR PVC fittings specially designed and manufactured using high grade raw material for removal of waste in the drainage system for non-pressure plumbing applications, such as transportation of soil, waste and waste discharge systems. SWR pipes type B for soil and waste discharge. Pipes shall confirm to IS 13592 and Fittings shall confirm to IS 14735. Gully Trap.	SH-1/73	2.00	Each	INR	500.00	1000.00	INR One Thousand Only
74	Supply & Providing health faucet ISI marked (Hand Shower) with 1.2mt long flexible tube with wall hook complete as per satisfaction of Engineer-in-Charge. Jaquar or equivalent	SH-1/74	2.00	Each	INR	900.00	1800.00	INR One Thousand Eight Hundred Only
75	Providing and fixing 100 mm stainless steel grating for floor trap.	SH-1/75	2.00	Each	INR	500.00	1000.00	INR One Thousand Only
76	Providing and fixing brass gate valve of ZOLOTO or equivalent in water supply line, all complete as per direction of Engineer-in-Charge. 50 mm nominal bore.	SH-1/76	2.00	Each	INR	5000.00	10000.00	INR Ten Thousand Only
77	Providing and fixing brass gate valve of ZOLOTO or equivalent in water supply line, all complete as per direction of Engineer-in-Charge. 20 mm nominal bore.	SH-1/77	2.00	Each	INR	1200.00	2400.00	INR Two Thousand Four Hundred Only
78	Providing unskilled workers for temporary nature of works/works unsusceptible to measure as and when required including necessary T&P as directed by Engineer-in-Charge.	SH-1/78	40.00	Each	INR	900.00	36000.00	INR Thirty Six Thousand Only
79	Supply of High robust Industrial box type Channel made of Powder coated CRCA Sheet Steel including 1 x 20 W Retrofit LED T8 Tube light with PC diffuser, Aluminum extrusion and integral control driver & metal heat sink, operates on 230V, 50Hz, Single Phase AC supply etc. complete as required.	SH-2/1	34.00	Each	INR	990.00	33660.00	INR Thirty Three Thousand Six Hundred & Sixty Only
80	Supply of 45 watts LED outdoor type light fitting with pressure die cast aluminum housing, heat resistant glass, High power LEDs with Secondary optics lens, IP66 protection including integral control driver with top opening driver cover operates on single phase, 230 Volts, 50HZ, AC power supply etc. complete as required.	SH-2/2	16.00	Each	INR	4200.00	67200.00	INR Sixty Seven Thousand Two Hundred Only
81	Supply of 1200 mm sweep, 5 Star rated Ceiling fan, double ball bearing, standard down rod and other standard accessories etc. without regulator suitable for operation on 230 V, 50 Hz, AC supply etc. complete as required.	SH-2/3	2.00	Each	INR	2000.00	4000.00	INR Four Thousand Only
82	Supply of 300mm dia, 900RPM heavy duty exhaust fan suitable for single phase 230 volt, 50 Hz AC supply complete with motor, capacitor, louvers/shutters and all accessories etc. complete as required.	SH-2/4	2.00	Each	INR	1800.00	3600.00	INR Three Thousand Six Hundred Only


 सहायक महा प्रबंधक (इंजीनियरिंग)
 Asst. Gen Manager (Engg-Civil)
 सिविल इंजीनियरिंग प्राधिकरण/AAI
 CHANDIGARH AIRPORT


NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST.
1	2	3	3	4	5	6	7	8
83	Wiring for light Point/ fan Point/ exhaust fan Point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface/recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing Point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc. complete as required.(GROUP C)	SH-2/5	50.00	Point	INR	1750.00	87500.00	INR Eighty Seven Thousand Five Hundred Only
84	Wiring for circuit/ submain / power plug wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed Steel conduit etc. complete as required. 3 X 6 sq. mm + 1 X 6 sq. mm earth wire	SH-2/6	60.00	Mtr	INR	580.00	34800.00	INR Thirty Four Thousand Eight Hundred Only
85	Wiring for circuit/ submain / power plug wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed Steel conduit etc. complete as required. 2 X 4 sq. mm + 1 X 4 sq. mm earth wire	SH-2/7	670.00	Mtr	INR	450.00	301500.00	INR Three Lakh One Thousand Five Hundred Only
86	Wiring for circuit/ submain / power plug wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed Steel conduit etc. complete as required. 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	SH-2/8	90.00	Mtr	INR	375.00	33750.00	INR Thirty Three Thousand Seven Hundred & Fifty Only
87	Supplying and fixing two module 05 Step Electronic fan regulator including modular GI Box with modular base & cover plate including connections etc. complete as required.	SH-2/9	2.00	Each	INR	500.00	1000.00	INR One Thousand Only
88	Supplying and fixing of suitable size GI box with modular base plate and cover plate in front on surface or in recess including providing and fixing 3 pin 6 A modular socket outlet and 6 A modular switch and connections etc. complete as required.	SH-2/10	10.00	Each	INR	400.00	4000.00	INR Four Thousand Only
89	Supplying and fixing of suitable size GI box with modular base plate and cover plate in front on surface or in recess including providing and fixing shuttered type 6/16 A modular socket outlet and 16 A modular switch with LED indicator (red), connections etc. complete as required.	SH-2/11	70.00	Each	INR	580.00	40600.00	INR Forty Thousand Six Hundred Only
90	Supplying and fixing of Surface mounting, Water proof 3 module enclosure with 6/16 A modular socket outlet and 16 A modular switch, IP 55 protection including connections etc. complete as required.	SH-2/12	4.00	Each	INR	980.00	3920.00	INR Three Thousand Nine Hundred & Twenty Only
91	Installation, testing and commissioning of 20 Watt LED tube light with fitting of all types complete with all accessories etc. direct on wall /ceiling including connections etc., complete as required.	SH-2/13	32.00	Each	INR	200.00	6400.00	INR Six Thousand Four Hundred Only


 सहायक महा प्रबंधक (इंजीनियरिंग)
 Asst. Gen Manager (Engg.Civil)
 भारतीय विमानपत्तन प्राधिकरण/AAI
 राजमंडी हवाई अड्डा / RAJAHMUNDY AIRPORT
 राजमंडी/ RAJAHMUNDY-533 102.

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST.
1	2	3	3	4	5	6	7	8
92	Installation, testing & commissioning of 45 W LED type outdoor light fixture on single arm G.I Pipe bracket including providing suitable size and length G.I Pipe bracket to be fixed on the outside corners of the building with necessary clamps & accessories including connections with 3C x 1.5 sq.mm FRLS PVC sheathed copper conductor cables etc., complete as required.	SH-2/14	14.00	Each	INR	880.00	12320.00	INR Twelve Thousand Three Hundred & Twenty Only
93	Installation, testing and commissioning of the 1200 mm sweep ceiling fan, including providing necessary accessories for the ceiling to fix the ceiling fan, wiring the down rods of standard length (upto 30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable etc. complete as required	SH-2/15	2.00	Each	INR	300.00	600.00	INR Six Hundred Only
94	Installation, testing and commissioning of 300mm Sweep, High Speed, Powder coated robust metallic exhaust fan with bird guard, including necessary accessories, wiring with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable etc. complete as required	SH-2/16	2.00	Each	INR	150.00	300.00	INR Three Hundred Only
95	Supplying and fixing 4 pole MCB sheet steel enclosure with powder coated on surface/ recess along with 01 No. 63 A "C" curve, 10 KA, FP MCB complete with connections, testing and commissioning etc. complete as required.	SH-2/17	5.00	Each	INR	2300.00	11500.00	INR Eleven Thousand Five Hundred Only
96	Supplying and fixing 20 A, 240 V, SPN Industrial type socket outlet, with 2 pole and earth, metal enclosed plug top along with 20 A "C" curve, 10 KA, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. complete as required.	SH-2/18	12.00	Each	INR	1300.00	15600.00	INR Fifteen Thousand Six Hundred Only
97	Supplying and fixing of surface/ recess mounting, 20 Way SPN Double door MCB distribution board of sheet steel, dust protected, IP 43, duly powder coated/painted inclusive of earth bar, din bar for mounting MCB's (but without MCB's and incomer), wiring, connections etc. complete as required.	SH-2/19	8.00	Each	INR	5000.00	40000.00	INR Forty Thousand Only
98	Supplying and fixing of surface/ recess mounting, 8 Way SPN Double door MCB distribution board of sheet steel, dust protected, IP 65, duly powder coated/painted inclusive of earth bar, din bar for mounting MCB's (but without MCB's and incomer), wiring, connections etc. complete as required.	SH-2/20	1.00	Each	INR	2300.00	2300.00	INR Two Thousand Three Hundred Only
99	Supplying and fixing of 6A to 32 A rating, 10 kA, "C" curve, Double Pole MCB in the existing MCB DB complete with connections, testing and commissioning etc. as required.	SH-2/21	64.00	Each	INR	675.00	43200.00	INR Forty Three Thousand Two Hundred Only
100	Supplying and fixing following rating RCBO in the existing MCB DB complete with connections, testing and commissioning etc., as required. 32A, 100 mA, Double Pole RCBO.	SH-2/22	6.00	Each	INR	3580.00	21480.00	INR Twenty One Thousand Four Hundred & Eighty Only


 मसौदा मंत्र प्रबंधक (इंजीनियरिंग)
 (Engineering Civil)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
SI. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	RATE (inclusive of all taxes but exclusive of GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without GST in Rs. P	TOTAL AMOUNT In Words without GST.
1	2	3	3	4	5	6	7	8
101	Supplying and fixing following rating MCB in the existing MCB DB complete with connections, testing and commissioning etc., as required. 63A, 10 KA, DP MCB	SH-2/23	2.00	Each	INR	1180.00	2360.00	INR Two Thousand Three Hundred & Sixty Only
102	Supply ,installation, testing, commissioning of 4" dia submersible borewell type pump of 60 LPM discharge (minimum) at 88 mtr head, multi stage, Noryl impeller suitable for 150 mm borewell with 2 HP motor suitable for operation on 230V, Single phase power supply etc, complete as required. (Make: Kirloskar KS4C-2016 or its equivalent from list of AAI approved makes).	SH-2/24	2.00	Each	INR	28000.00	56000.00	INR Fifty Six Thousand Only
103	Supply , Installation, Testing & commissioning of IP54 protected Sheet Steel Enclosure with powder coated DOL starter panel having Digital ammeter & Voltmeter, Motor ON/Trip indications, protection of Overload, Single Phasing, Phase reversal & phase imbalance suitable for single phase, 2 HP submersible Borewell pump, interconnected wiring etc. as required.	SH-2/25	2.00	Each	INR	6000.00	12000.00	INR Twelve Thousand Only
104	Providing and fixing of 40 mm Dia HDPE Pipe having PE 80 and PN 10 suitable for 2 HPsubmersible pump delivery line including joint fittings complete etc.as required.	SH-2/26	200.00	Mtrs	INR	120.00	24000.00	INR Twenty Four Thousand Only
105	Supply and laying of 3C X 2.5 Sqmm PVC insulated and PVC sheathed copper conductor flat submersible cable in the existing GI pipe /PVC conduit / duct or surface of wall/HDPE pipe etc complete as required.	SH-2/27	200.00	Mtrs	INR	130.00	26000.00	INR Twenty Six Thousand Only
Total in Figures							30821455.00	INR Three Crore Eight Lakh Twenty One Thousand Four Hundred & Fifty Five Only
Quoted Rate in Words	INR Three Crore Eight Lakh Twenty One Thousand Four Hundred & Fifty Five Only							


 सहायक महा प्रबंधक (इंजी-सिविल)
 Asst. Gen Manager (Engg-Civil)
 भारतीय विमानपत्तन प्राधिकरण / AAI
 राजमंड्री हवाई अड्डा / RAJAHMUNDRY AIRPORT
 राजमंड्री / RAJAHMUNDRY-533 102.

Signature Not Verified

Digitally signed by Ruthala Satyanarayana Murthy
 Date: 2025.09.20 13:51:27 IST
 Location: eProcurement System for Central PSUs

