

ACCEPTANCE LETTER No: MINUTES OF CWC - I HELD ON 07-06-2024

To

S. VINAYAGAMURTHY,
No. 1201, TNHB, KAKALUR SCHEME,
THIRUVALLUR - 602001

Dear Sirs,

Type of Work: ITEM RATE

Sub: **EXTENSION OF BALCONY IN TYPE - V 2/4 QUARTERS AT HVF ESTATE**

Ref: (i) Fy Tender No. HVF/TE/13025/CEO/2023-24/78, dated 05-03-2024 with Tender ID: 2024_AVNL_189807_1

(ii) Your Bid:693410 in this tender and Price revisions offered vide emails and letters dt 10-05-2024 & 30-05-2024.

For and on behalf of the President of India, I hereby convey the acceptance of your tender by the competent financial authority for the above mentioned work for a total value of **Rs. 6,05,725 /-** (Rupees Six Lakhs Five Thousand Seven Hundred and Twenty Five Only) and order the services detailed in the schedule enclosed herewith at the item rates quoted by you in Schedule 'A' of the Tender documents as per the terms, conditions and specifications laid therein. List of items, to be issued by factory, is given in Schedule 'B'.

2. The contract is allotted with No. **HVF/CE/07/2024-25/CAP., dated 25-06-2024** which will have to be quoted by you in all future correspondence in connection with this contract.

3. In accordance with condition No. 22 of the General Condition of Contract (IAFW-2249), please submit the security deposit of Rs. 15,200 /- (Rupees Fifteen Thousand and Two Hundred Only) in favour of "The Chief General Manager, Heavy Vehicle Factory, Avadi" as mentioned in tender condition.


. The maturity date of security Deposit shall be minimum 12 months from date of the completion of contract.

4. The contract shall be governed by the terms and conditions as per the contract documents enclosed and general condition of contract MES IAFW 2249. The deviation limit shall be as per the clause No.19.1.1 & 19.1.2 of MES Contract Manual (latest revision).

5. Shri.K.Ravichandran, JWM(SG)/IMS/CE(E) is nominated as Engineer-in-Charge for the subject work and Shri.S.Vijayakumar, JWM/IMS/CE(E) is nominated as Site In-charge for the subject work.

6. You are requested to contact the Engineer-in-Charge within 7 days of receipt of this letter for taking over of site and to make time and progress chart. You will also maintain wage-cum-muster roll and all other records as required in Contract Labour Rules and Acts.

7. Please acknowledge receipt of this letter and return two copies duly signed by you in proof of acceptance within seven days from the date of receipt of this communication.



(K. TULASI RAO)

JT. GENERAL MANAGER / IMS

For CHIEF GENERAL MANAGER / HVF

For And On Behalf Of THE PRESIDENT OF INDIA

Copy to :

1. GM / HR, F&A, IMS, HVF, Avadi, Chennai - 600054
2. Shri.K.Ravichandran, JWM(SG)/IMS/CE(E) - Engineer -In Charge
3. Shri.S.Vijayakumar, JWM/IMS/CE(E) - Site -In Charge
4. Shri. G. Ananda kumar, WM / IMS - Technical Examiner

IN LIEU OF IAFW-1823(REVISED)
CONTRACTORS' ORDER SHEET

Work Order/Deviation Order No	HVF/CE/07/2024-25/CAP., dated 25-06-2024
Acceptance letter No.	MINUTES OF CWC - I HELD ON 07-06-2024
Contractor's Name	S. VINAYAGAMURTHY
Name of the work	EXTENSION OF BALCONY IN TYPE - V 2/4 QUARTERS AT HVF ESTATE
CA amount	Rs. 6,05,725 /-

PARTICULARS

1. Authority	CWC decision of Fy. LEVEL CWC - I
2. Brief Description of work to be carried out	As per details in sheet attached and adhering to your firm Bid No 693410 & Price revisions offered vide emails and letters dated 10-05-2024 and 30-05-2024 in HVF Tender: HVF/TE/13025/CEO /2023-24/78, dated 05-03-2024 with Tender ID: 2024_AVNL_189807_1 for all Terms & Conditions therein & rate quoted in Schedule 'A' enclosed with tender documents.
3. Time effect	
a. Date of handing over of the site	02/07/2024
b. Date of commencement of work	02/07/2024
c. Date of Completion as per contract	30/09/2024
d. Date for completion shown in previous Orders	NA
e. Revised date of completion	NA
4. Financial effect (Rs.)	
a. Present order	Rs. 6,05,725 /-
b. Contract amount as adjusted by previous orders	NA
c. Contract amount adjusted up to and including this order	NA
5. Expenditure to be booked under code Head No	920 / 34 (Capital Civil Works Grant)
6. Certified that no special rate is involved	
7. Technical Examiner	Shri. G. Ananda Kumar, WM / IMS
8. Approved	Shri. K. Tulasi Rao, Jt.GM / IMS
9. Accepted	S. VINAYAGAMURTHY



(K. TULASI RAO)
JT. GENERAL MANAGER / IMS
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA

Distribution to :--

- 1) S. VINAYAGAMURTHY
- 2) GM / HR, F&A, IMS, HVF, Avadi, Chennai – 600054
- 3) Sr. Security Officer
- 4) Shri.K.Ravichandran, JWM(SG)/IMS/CE(E) - Engineer -In Charge
- 5) Shri.S.Vijayakumar, JWM/IMS/CE(E) - Site -In Charge
- 6) Shri. G. Ananda Kumar, WM / IMS - Technical Examiner
- 7) HOS/Safety, 8) HOS/Internal Audit cell, 9) HOS/Test Audit, 10) ALWC,
- 11) Chief Commissioner of Central Excise, 26/1, Mahatma Gandhi Road, Nungambakkam, Chennai – 600034.
- 12) Dy.Chief Labour Commissioner(c), No:26, III Block, 5thfloor,Shastri Bhavan, Haddows Road, Nungambakkam,Chennai – 600006.


Name of the work: **EXTENSION OF BALCONY IN TYPE - V 2/4 QUARTERS AT HVF ESTATE**

Contract Agreement No: **HVF/CE/07/2024-25/CAP., dated 24-06-2024**

SCHEDULE – “A”					
Item Code	Item Description	Quantity	Unit	Rate/Unit	Total Cost
1	Earthwork excavation in hard/dense soil in trenches width and depth not exceeding 1.50 m and getting out.	16.00	CuM	853.00	13648.00
2	Material and labour for sand filling in foundation including watering and consolidation.	4.00	CuM	2490.00	9960.00
3	Material & Labour for PCC 1:3:6 type C2 using 40mm graded aggregate for foundation.	4.00	CuM	7180.00	28720.00
4	Material and labour for cement concrete 1:2:4 Type B1 20mm graded aggregate in foundation filling and mass concrete.	13.00	CuM	8240.00	107120.00
5	Supply and fixing of mild steel reinforcement deformed or twisted bars including bending, cranking, hooking and tying with mild steel wire not less than 0.90mm dia. Used RINL-VIZAG Steel / SAIL / TATA-TISCON / "BIS"MARKED (or) Suitably Equivalent make.	1100.00	Kg	103.00	113300.00
6	M & L for form work to side of RCC Member such as columns, pillars etc., and the finishing shall be of fair finished surface.	75.00	SqM	765.00	57375.00
7	M & L for Brick work built in CM.1:6 using good quality modular bricks / solid Concrete bricks. Bricks, straight or curved on plan exc 6m mean radius.	4.00	CuM	6220.00	24880.00
8	M & L for plastering in CM 1:4, 15mm thick on fair faces of brick work and concrete surfaces.	90.00	SqM	310.00	27900.00
9	M & L for plastering in CM 1:4, 12mm thick on RCC Ceiling.	25.00	SqM	320.00	8000.00
10	Material and Labour for fixing Light shade Vitrified ceramic tiles 10mm thick (Square/rectangle) polished area of each tile not exceeding 0.36 Sqm in floors etc., set and jointed in neat cement slurry and pointed in white or colored cement to match including screed bed in cement mortar 1:4, 15mm thick complete.	35.00	SqM	1610.00	56350.00
11	S & F of Framed work as in doors or gates of angle or other section with gusset plates, rails, braces, etc., complete, drilled for fixing of steel sheeting or other covering. Doors, etc. to be prepared for hanging or sliding with and including either hooks and hinges or steel hanging door fittings (exclusive of steel sheeting or other covering, running rails and guides) and hanging; also fastening and fixing complete.	750.00	Kg	130.00	97500.00
12	M & L for painting to steel surfaces of any description over 10cm width or girth with two coats of synthetic enamel paint over a coat of primer including preparing new surfaces.	25.00	SqM	148.00	3700.00
13	Material and Labour for white washing on ceiling with two coats including preparation of old ceiling surfaces.	20.00	SqM	28.00	560.00
14	Material and Labour for applying two coats of plastic emulsion as directed by EIC.	98.00	SqM	128.00	12544.00

Item Code	Item Description	Quantity	Unit	Rate/Unit	Total Cost
15	S & F of PVC 110mm dia Pipes single socketed, in any length with rubber ring joints, Fixed to walls.	30.00	RM	245.00	7350.00
16	Returning / refilling of soil / loose including spreading, leveling, watering and well ramming in layers not exceeding 25cm.	15.00	CuM	160.00	2400.00
17	Material and labour for Point wiring with 1.5sqmm FRLS PVC insulated sheathed single core cable 1100V grade confirming to IS 694 multi strand copper conductor along with 2mm thick PVC conduit accessories run on wall / roof / L angle including M.S. switch box concealed in the wall (made out of 3mm thick sheet) and laminated sun mica sheet 3mm thick cover for housing the switches, regulators and plug socket etc. mount on a wall / roof etc. including 16SWG bare or 1.5/2.5 stranded copper earth continuity wire. (Make: Finolux / Havells / Polycab / Kundan / Orbit or suitably equivalent make as approved by EIC). a) One light point controlled by one switch light / fan."	10.00	Point	1090.00	10900.00
18	Material and labour for Point wiring with 1.5sqmm FRLS PVC insulated sheathed single core cable 1100V grade confirming to IS 694 multi strand copper conductor along with 2mm thick PVC conduit accessories run on wall / roof / L angle including M.S. switch box concealed in the wall (made out of 3mm thick sheet) and laminated sun mica sheet 3mm thick cover for housing the switches, regulators and plug socket etc. mount on a wall / roof etc. including 16SWG bare or 1.5/2.5 stranded copper earth continuity wire. (Make: Finolux / Havells / Polycab / Kundan / Orbit or suitably equivalent make as approved by EIC). b) One 3 pin plug socket with switches flush type 5A on same board with 2.5sqmm cable."	2.00	Point	315.00	630.00
19	Material and labour for Point wiring with 1.5sqmm FRLS PVC insulated sheathed single core cable 1100V grade confirming to IS 694 multi strand copper conductor along with 2mm thick PVC conduit accessories run on wall / roof / L angle including M.S. switch box concealed in the wall (made out of 3mm thick sheet) and laminated sun mica sheet 3mm thick cover for housing the switches, regulators and plug socket etc. mount on a wall / roof etc. including 16SWG bare or 1.5/2.5 stranded copper earth continuity wire. (Make: Finolux / Havells / Polycab / Kundan / Orbit or suitably equivalent make as approved by EIC). c) One 3 pin plug socket with switches flush type 5A on independent board with 2.5sqmm cable.	1.00	Point	1190.00	1190.00
20	Supply & fixing of switch piano, flush type single pole one way 6 amps. (ANCHOR / LEGRAND/ HAVELLS or suitably equivalent make as approved by EIC).	10.00	Each	135.00	1350.00
21	Supply & fixing of Switch socket combination 2 in 1, 6A flush type (ANCHOR / LEGRAND/ HAVELLS or suitably equivalent make as approved by EIC).	2.00	Each	399.00	798.00
22	Material & Labour for ceiling rose, 3 Phase/PVC / Polycarbonate, isolated body (ANCHOR / LEGRAND/ HAVELLS or suitably equivalent make as approved by EIC).	6.00	Each	67.00	402.00

Item Code	Item Description	Quantity	Unit	Rate/Unit	Total Cost
23	Supply and fixing LED lights fitting 1x 20W, 220V, AC decorative box type with driver, holder including LED tube light connecting up with three core flexible copper conductor cable of suitable size from ceiling rose complete. Make: Philips / Wipro / CG / Havells or suitably equivalent make as approved by EIC.	4.00	Each	1450.00	5800.00
24	Supply & Fixing LED light fitting 1x9W / 1X10W bulkhead luminaires including LED light driver holder connecting up with three core flexible copper conductor cable of suitable size. Make: Philips / Wipro / CG / Havells or suitably equivalent make as approved by EIC.	1.00	Each	1430.00	1430.00
25	Material & Labour for wiring with two runs of FRLS PVC insulated sheathed single core copper cable upto 1100 volts grade confirming to IS 694 multistrand with copper conductor along with PVC conduit and conduit accessories run on wall/roof one run of copper cable as earth wire. (Make: Finolux / Havells / Polycab / Kundan / Orbit or suitably equivalent make as approved by EIC). a) 2x2.5 sq.mm + 1x2.5 sq.mm earth wire.	10.00	RM	230.00	2300.00
26	Supply & fixing sheet metal enclosures for DB's when MCBs to be use, single pole and neutral, 8 way with 200 amps rated bus bar, double door.	1.00	Each	2418.00	2418.00
27	Supply and fixing of TP 25 To 63 AMP 415V 10KA 'B' curve miniature circuit breaker (MCB) of following poles and current carrying capacity in the DB complete with connection testing and commissioning. (Make: STANDARD / LEGRAND / HAVELLS / ABB / Schneider or suitably equivalent make as approved by EIC).	2.00	Each	1900.00	3800.00
28	Supply and fixing 240V, 10 KA 'B' curve miniature circuit breaker (MCB) of single poles and current carrying capacity 6 to 32 AMP, in the MCB DB Complete with connection testing and commissioning. (Make: STANDARD / LEGRAND / HAVELLS / ABB / Schneider or suitably equivalent make as approved by EIC).	10.00	Each	340.00	3400.00
Gross Total of Items				Rs. 6,05,725.00 /-	



(K. TULASI RAO)

JT. GENERAL MANAGER / IMS

For CHIEF GENERAL MANAGER / HVF

For And On Behalf Of THE PRESIDENT OF INDIA

TERMS & CONDITIONS:

1 Special Condition: The Material required for the subject work which be brought inside the factory by the contractors, should be noted along with challan / vouchers etc., and a copy of the same are to be given to the engineering office for record and copy to be submitted to the contractors along with the bill while claiming the payment.

2 Payment Clause: The contractor has to pay the minimum daily wages to the skilled/semi skilled/unskilled labourers engaged in their work as has been specified by the Government, latest rate and displayed in the wages notice Board at factory.

3 Safety Clause: Annexure-B of MES Safety Code, IAFW 2249 must be observed in general. Work Permit shall be obtained for overhead/hazardous work condition. All the safety precautions/measures have to be taken by the contractor. However, a few points of safety measures to be followed for working at height and on the roof are mentioned hereby :

Use of safety belt and helmet of proper quality is mandatory for all workers working on roofs at height of above 5.00 meters and also in the underground areas. Safety belt with life line should be properly tied at some firm support.

(i) In case any difficulty is faced in proper fastening and securing of safety belt, a safety net may be provided below the work spot so that in case of accident fall, there might not be any fatality.

(ii) A crawling ladder or roof walker must be used for movement on Asbestos/CGI roofing.

(iii) Work Permit system should be followed in proper spirit. Contractors shall start the work after obtaining the Work Permit, wherever applicable. Contractor's supervisor and site-in-charge should brief on safety precautions to be observed by the workmen before start of the work. The workers should be clearly explained about the danger of standing or sitting on an apparently stout & new and neat looking asbestos/CGI sheet which is intrinsically weak.

(iv) The contractor shall clear the site after completion of work.

(v) The contractor must employ the labour force duly insured against life risk.

(vi) The contractors shall ensure compliance of all applicable statutory rules and regulations.

4 DEVIATION CLAUSE:

(i) $\pm 25\%$ of value of individual item other than freakishly rate quoted items.

(ii) For freakishly higher or lower rate quoted items it shall be $\pm 5\%$.

(iii) 20% of Work Order value (Contract value maximum Rs.10 lakhs)

10% of Work Order value (Contract value exceeding Rs.10 lakhs)



(K. TULASI RAO)

JT. GENERAL MANAGER / IMS

For CHIEF GENERAL MANAGER / HVF

For And On Behalf Of THE PRESIDENT OF INDIA