

ACCEPTANCE LETTER No : MINUTES OF CWC – I HELD ON 20-06-2024

To

SRI SELLIAMMAN & CO
No. 80, C BLOCK, 4G, YUGA KALPATARU,
PILLAYAR KOIL STREET, PADIKUPPAM,
KOYAMBEDU, CHENNAI – 600 107

Dear Sirs,

Type of Work: ITEM RATE

Sub : **REPAIRS / RE-CARPETING OF BRANCH ROADS INSIDE HVF ESTATE, AVADI.**

Ref: (i) HVF Tender No. HVF/TE/13025/CEO/2023-24/90, Dt. 27-03-2024 with Tender ID: 2024_AVNL_192476_1
(ii) Your Bid No: 695513 in this tender and Price Reduction & Confirmation offered vide your E.Mail
and letter Dt. 11-06-2024.

For and on behalf of The President of India, I hereby convey the acceptance of your tender by the competent financial authority for the above mentioned work for a total value of **Rs. 3,40,49,677 /- (Rupees Three Crore Forty Lakh Forty Nine Thousand Six Hundred and Seventy Seven Only)** and order the services detailed in the schedule enclosed herewith at the item rates quoted by you in Schedule 'A' of the Tender documents as per the terms, conditions and specifications laid therein. List of items, to be issued by factory, is given in Schedule 'B'.

2. The contract is allotted with No. **HVF/CE/08/2024-25/CAP, Dated. 27-06-2024** which will have to be quoted by you in all future correspondence in connection with this contract.

3. In accordance with condition No. 22 of the General Condition of Contract (IAFW-2249), please submit the security deposit of Rs. 5,19,400 /- (Rupees Five Lakh Nineteen Thousand and Four Hundred Only) in favour of " The Chief General Manager, Heavy Vehicle Factory, Avadi" as mentioned in tender condition.

The maturity date of security Deposit shall be minimum 12 months from date of the completion of contract.

4. The contract shall be governed by the terms and conditions as per the contract documents enclosed and general condition of contract MES IAFW 2249. The deviation limit shall be as per the clause No.19.1.1 & 19.1.2 of MES Contract Manual (latest revision).

5. Shri. G. Anandakumar, WM / IMS , is nominated as Engineer-in-Charge and Shri. K. Ravichandran, JWM (SG) / IMS / CE (Estate) & Shri. S. Arunachalam, JWM / IMS / CE (Estate) are nominated as Site In-charges for the subject work respectively.

6. You are requested to contact the Engineer-in-Charge within 7 days of receipt of this letter for taking over of site and to make time and progress chart. You will also maintain wage-cum-muster roll and all other records as required in Contract Labour Rules and Acts.

7. Please acknowledge receipt of this letter and return two copies duly signed by you in proof of acceptance within seven days from the date of receipt of this communication.



(K. TULASI RAO)

JT. GENERAL MANAGER / IMS

For CHIEF GENERAL MANAGER / HVF

For And On Behalf Of THE PRESIDENT OF INDIA

Copy to :

- | | | |
|--|---|--------------------|
| 1. GM / HR, F&A, IMS, HVF, Avadi, Chennai – 600054 | - | Engineer-in-Charge |
| 2. Shri. G. Ananda Kumar, WM / IMS | - | Site-in-Charge |
| 3. Shri. K. Ravichandran, JWM (SG) / IMS / CE (Estate) | - | Site-in-Charge |
| 4. Shri. S. Arunachalam, JWM / IMS / CE (Estate) | - | Site-in-Charge |
| 5. Shri. Pranjit Bhagabati, DGM / IMS | - | Technical Examiner |

IN LIEU OF IAFW-1823(REVISED)
CONTRACTORS' ORDER SHEET

Work Order/Deviation Order No	HVF/CE/08/2024-25/CAP., Dated 27-06-2024
Acceptance letter No.	MINUTES OF CWC – I HELD ON 20-06-2024
Contractor's Name	SRI SELLIAMMAN & CO
Name of the work	REPAIRS / RE-CARPETING OF BRANCH ROADS INSIDE HVF ESTATE, AVADI.
CA amount	Rs. 3,40,49,677 /=-

PARTICULARS

1. Authority	CWC decision of Fy. LEVEL CWC - I
2. Brief Description of work to be carried out	As per details in sheet attached and adhering to your firm Bid No. 695513 in this tender and Price Reduction & Confirmation offered vide your E.Mail & Letter Dt. 11-06-2024 in T.E No. HVF/TE/13025/CEO/2023-24/90, Dt. 27-03-2024 with Tender ID: 2024_AVNL_192476_1 for all Terms & Conditions therein & rate quoted in Schedule 'A' enclosed with tender documents.
3. Time effect	
a. Date of handing over of the site	08/07/2024
b. Date of commencement of work	08/07/2024
c. Date of Completion as per contract	08/07/2025
d. Date for completion shown in previous Orders	NA
e. Revised date of completion	NA
4. Financial effect (Rs.)	
a. Present order	Rs. 3,40,49,677 /=-
b. Contract amount as adjusted by previous orders	NA
c. Contract amount adjusted up to including this order	NA
5. Expenditure to be booked under code Head No	920 / 34 (CAPITAL GRANT)
6. Certified that no special rate is involved	
7. Technical Examiner	Shri. Pranjit Bhagabati, DGM / IMS
8. Approved	Shri. K. Tulasi Rao, Jt.GM / IMS
9. Accepted	SRI SELLIAMMAN & CO


(K. TULASI RAO)

JT. GENERAL MANAGER / IMS
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA

Distribution to :-

1. SRI SELLIAMMAN & CO
2. GM / HR, F&A, IMS, HVF, Avadi, Chennai – 600054
3. SR. SECURITY OFFICER
4. Shri. G. Ananda Kumar, WM / IMS - Engineer-in-Charge
5. Shri. K. Ravichandran, JWM (SG) / IMS / CE (Estate) - Site-in-Charge
6. Shri. S. Arunachalam, JWM / IMS / CE (Estate) - Site-in-Charge
7. Shri. Pranjit Bhagabati, DGM / IMS - Technical Examiner.
8. HOS/Safety, 9. HOS/Internal Audit cell, 10. HOS/Test Audit, 11. ALWC,
12. Chief Commissioner of Central Excise, 26/1, Mahatma Gandhi Road, Nungambakkam, Chennai – 600034
13. Dy. Chief Labour Commissioner(c), No: 26, III Block, 5th floor, Shastri Bhavan, Haddows Road, Nungambakkam, Chennai – 600006.

**NAME OF THE WORK : REPAIRS / RE-CARPETING OF BRANCH ROADS INSIDE
HVF ESTATE, AVADI**

CONTRACT AGREEMENT No : HVF/CE/08/2024-25/CAP, Dated 27-06-2024

SCHEDULE – "A"

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
01	Preparing black top surfaces by brushing with wire brushes for removing caked mud etc., sweeping with brooms and finally fanning the cleaned surface with gunny bags to remove all loose dirt etc.,	Per 10 SQM	8300.00	25.00	207500.00
02	M & L for applying evenly prime/tack coat with Paving bituminous emulsion at 5.00 Kg per 10 Sqm using paving bitumen.	Per 10 SQM	8300.00	50.00	415000.00
03	Material and labour for premix bituminous macadam using 4% binder content by weight of total mixlaid /rolled and completed to required gradient and camber using paving bitumen any penetration Consolidated thickness 75mm and below.	CUM	200.00	7200.00	1440000.00
04	Material and labour for Bituminous premix asphaltic dense concrete 40mm consolidated thickness with 6% binder content by weight of total mix, rolled and compacted to required camber, gradient complete using paving bitumen. The mixture is to be premixed in central hot mix plant, screening, sorting and spreading with self propelled mechanical paver consolidation with power and vibratory rollers of 80 to 100KN static weight to achieve specified value of compaction. The static roller of 8-12 tonne capacity shall be used for rolling the finished layer to have a uniform surface as per the direction of the EIC.	Per 10 SQM	8300.00	3600.00	29880000.00
05	M & L for laying hot applied thermoplastic compound 2.5 mm thick including reflecting glass beads of 250Gms per Sq.m area thickness 2.5mm is exclusive of surfaces applied glass beads as per IRC35.The finished surface to be level uniform and free from streaks and holes etc., complete as per the MORTH specification also the width of thermoplastic will be 3" or 4" based on the site conditions as directed by EIC .	SQM	3000.00	410.00	1230000.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
06	Repair to potholes any depth, not exc 1 sq m each including sweeping free from dust and mud, or water, scoring sunken surfaces in roads, paths, etc. cutting around edges to at least 25 mm in depth, making good by filling in screened & graded road metal, watering and well ramming (including supply of road metal)	Per 10 SQM	500.00	500.00	250000.00
07	Supply & Fixing of two way acrylic road studs as per guidelines approved by IRC using necessary nailing, drilling, fixing using adhesives etc.as direct to EIC.	Nos.	933.00	219.00	204327.00
08	M & L for Providing Precast Cement concrete 1:2:4 B1 Type Using 20 mm graded aggregate in solid building Blocks or slabs or kerb 7.5 cm thick (with plain or interlocking joints as directed) setting in 1:4 Cement Mortar, Complete in Walls / Kerbs, etc	SQM	300.00	1020.00	306000.00
09	M & L for Moorum / red bajri filling in floors or pavings, laid in layers n exc. 15 cm thick, spread, levelled and rammed including watering.	CUM	95.00	1230.00	116850.00
Gross Total of Items (Rs.)			3,40,49,677 /=-		


 (K. TULASI RAO)
 JT. GENERAL MANAGER / IMS
 For CHIEF GENERAL MANAGER / HVF
 For And On Behalf Of THE PRESIDENT OF INDIA

TERMS & CONDITIONS:

1 Special Condition: The Material required for the subject work which be brought inside the factory by the contractors, should be noted along with challan / vouchers etc., and a copy of the same are to be given to the engineering office for record and copy to be submitted to the contractors along with the bill while claiming the payment.

2 Payment Clause: The contractor has to pay the minimum daily wages to the skilled/semi skilled/unskilled labourers engaged in their work as has been specified by the Government, latest rate and displayed in the wages notice Board at factory.

3 Safety Clause: Annexure-B of MES Safety Code, IAFW 2249 must be observed in general. Work Permit shall be obtained for overhead/hazardous work condition. All the safety precautions/measures have to be taken by the contractor. However, a few points of safety measures to be followed for working at height and on the roof are mentioned hereby :

Use of safety belt and helmet of proper quality is mandatory for all workers working on roofs at height of above 5.00 meters and also in the underground areas. Safety belt with life line should be properly tied at some firm support.

(i) In case any difficulty is faced in proper fastening and securing of safety belt, a safety net may be provided below the workspot so that in case of accident fall, there might not be any fatality.

(ii) A crawling ladder or roof walker must be used for movement on Asbestos/CGI roofing.

(iii) Work Permit system should be followed in proper spirit. Contractors shall start the work after obtaining the Work Permit, wherever applicable. Contractor's supervisor and site-in-charge should brief on safety precautions to be observed by the workmen before start of the work. The workers should be clearly explained about the danger of standing or sitting on an apparently stout & new and neat looking asbestos/CGI sheet which is intrinsically weak.

(iv) The contractor shall clear the site after completion of work.

(v) The contractor must employ the labour force duly insured against life risk.

(vi) The contractors shall ensure compliance of all applicable statutory rules and regulations.


4 DEVIATION CLAUSE:

(i) $\pm 25\%$ of value of individual item other than freakishly rate quoted items.

(ii) For freakishly higher or lower rate quoted items it shall be $\pm 5\%$.

(iii) 20% of Work Order value (Contract value maximum Rs.10 lakhs)

10% of Work Order value (Contract value exceeding Rs.10 lakhs)



(K. TULASI RAO)

JT. GENERAL MANAGER / IMS

For CHIEF GENERAL MANAGER / HVF

For And On Behalf Of THE PRESIDENT OF INDIA