

आर्मर्ड व्हीकल्स निगम लिमिटेड
वाहन निर्माणी जबलपुर
भारत सरकार का उद्यम
रक्षा मंत्रालय



ARMoured VEHICLES NIGAM LIMITED
VEHICLE FACTORY JABALPUR
A GOVT. OF INDIA ENTERPRISE
MINISTRY OF DEFENCE
CIN-U35990TN2021GOI145504

Vehicle Factory Jabalpur
Jabalpur State-Madhya Pradesh, Pin-482009

ACCEPTANCE LETTER No: 208/ND 2310/2024-25/EOC/VFJ

To,
M/s M/s Kamal Kishore Garg,
A - 89/S - 1, Ward No 27,
Kamla Nagar,
Kotara Sultanabad,
Bhopal, MP - 462003

Dear Sir,

Type of Work: Item Rate

Sub: - Provision of High Mast Lighting Arrangement 34M height with LED Luminaries in VFJ Stadium (04 Nos.).

Ref: - Tender Ref. No: ND-2310/VFJ and Tender ID No. 2024_AVNL_192566_1

For and on behalf of the President of India, I hereby convey the acceptance of your tender by the competent financial authority for the above mentioned work for a total value of Rs. 1,31,99,450.00 (**Rupees One Crore Thirty-One Lakhs Ninety-Nine Thousands Four Hundred Fifty Point Zero Zero only**) and order the services detailed in the schedule enclosed herewith at the item rates quoted by you in Schedule 'A' of the Tender documents as per the terms, conditions and specifications laid therein. List of items, to be issued by factory, is given in Schedule 'B'.

- The contract is allotted with No. 07/Engg/VFJ/24-25/EOC Dated 28/06/24 which will have to be quoted by you in all future correspondence in connection with this contract.
- In accordance with condition No. 22 of the General Condition of Contract (IAFW-2249), please submit the security deposit of Rs. 2,74,500.00 (Rupees Two Lakhs Seventy Four Thousands Five Hundred Only) in favour of "AVNL, Vehicle Factory Jabalpur" as mentioned in tender condition.
The maturity date of Security Deposit shall be minimum 24 + 02 = 26 months from date of the completion of contract.
- The contract shall be governed by the terms and conditions as per the contract documents enclosed and general condition of contract MES IAFW 2249. The deviation limit shall be as per the clause No.19.1.1 & 19.1.2 of MES Contract Manual (latest revision).
- Shri Shailendra Kumar Mishra, WM and Shri Arvind Kumar Patel, JWM nominated as Engineer-in-Charge and Site in-charge for the subject work respectively.
- You are requested to contact the Engineer-in-Charge immediately after the receipt of this letter for taking over of site and to make time and progress chart. You will also maintain wage-cum-muster roll and all other records as required in Contract Labour Rules and Acts.
- Please acknowledge receipt of this letter and return two copies duly signed by you in proof of acceptance within seven (07) days from the date of receipt of this communication.

Copy to:

- F & A Section
- Shri Shailendra Kumar Mishra, WM
- Shri Arvind Kumar Patel, JWM

कमल विश्व
मेसर्स कमल किशोर गार्ग, भोपाल
(ठेकेदार)

(डी.एन. कोशल)
जारीकर्ता अधिकारी, उपमहाप्रबंधक
कृते मुख्य महाप्रबंधक



Unit Address: Vehicle Factory Jabalpur, MP -482009
PHONE NO: 0761-2793000, 2793001, 2330520
FAX NO. 0761-2330436, EMAIL: vfj.ofb@nic.in

Regd. Address: C/o Armoured Vehicles Headquarters,
HVF Road, Bhaktavatsalapuram, Avadi, Chennai, TN 600054, INDIA
PHONE NO: 044-26383601, 26384784, FAX NO. 044-26383653

1

आर्मर्ड व्हीकल्स निगम लिमिटेड
वाहन निर्माणो जबलपुर
भारत सरकार का उद्यम
रक्षा मंत्रालय



ARMOURED VEHICLES NIGAM LIMITED
VEHICLE FACTORY JABALPUR
A GOVT. OF INDIA ENTERPRISE
MINISTRY OF DEFENCE
CIN-U35990TN2021GOI145504

IN LIEU OF IAFW-1823(REVISED)
CONTRACTORS' ORDER SHEET

Work Order/Deviation Order No.	/24-25
Acceptance letter No.	208/ND 2310/2024-25/EOC/VFJ
Contractor's Name	M/s Kamal Kishore Garg, Bhopal
Name of the work	Provision of High Mast Lighting Arrangement 34M height with LED Luminaries in VFJ Stadium (04 Nos.).
CA amount	1,31,99,450.00

PARTICULARS

1. Authority	CWC decision No. CWC-I
2. Time effect	
a. Date of handing over of the site	01/07/2024
b. Date of commencement of work	01/07/2024
c. Date of Completion as per contract	27/12/2024
d. Date for completion shown in previous Orders	NA
e. Revised date of completion	NA
3. Financial effect (Rs.)	
a. Present order	1,31,99,450.00
b. Contract amount as adjusted by previous orders	NA
c. Contract amount adjusted up to and including this order	NA
4. Expenditure to be booked under code Head No	920/34
5. Certified that no special rate is involved	
6. Technical Examiner	Shri Pranav Priyank, DGM
7. Approved	Shri D N Kaushal, DGM
8. Accepted	M/s Kamal Kishore Garg, Bhopal

Distribution to: -

1. M/s Kamal Kishore Garg, Bhopal
2. F&A section
3. Sr. Security Officer
4. Shri Pranav Priyank, DGM (TE)
5. Shri Shailendra Kumar Mishra, WM (EIC)
6. Shri Arvind Kumar Patel, JWM (SIC)
7. Internal Audit cell, Test Audit, ALWC
8. Safety Officer
9. JWM/PCS
10. DO/EM

कमल किशोर
मेसर्स कमल किशोर गार्ग, भोपाल
(ठेकेदार)

(डी.एन. कौशल)
जारीकर्ता अधिकारी, उपमहाप्रबंधक
कृते मुख्य महाप्रबंधक



Unit Address: Vehicle Factory Jabalpur, MP -482009
PHONE NO: 0761-2793000, 2793001, 2330520
FAX NO. 0761-2330436, EMAIL: vfj.off@nic.in

Regd. Address: C/o Armoured Vehicles Headquarters,
HVF Road, Bhaktavatsalapuram, Avadi, Chennai, TN 600054, INDIA
PHONE NO: 044-26383601, 26384784, FAX NO. 044-26383653



SCHEDULE – "A"					
Item Code	Item description	Quantity	Unit	Rate / Unit	Total Cost
1	"Excavating in trenches, n exc 1.5 m wide and n exc 1.5 m in depth; for foundation, etc. or for afts, wells, cesspits, manholes, pierholes, etc n exc 10 sqm on plan and n exc 1.5m in depth and getting out in hard dense soil.	544.50	Cum	650.00	353925.00
2	Fine aggregate (sand) for concrete	135.00	Cum	1600.00	216000.00
3	M&L XLPE insulated, armoured heavy duty electric cable with aluminium conductor, 1100 volts grade, cross-sectional area 120 sq. mm, 3.5 core.	600.00	RM	850.00	510000.00
4	M&L for XLPE insulated, screened, PVC bedded, galvanised steel strip or wire armoured, electric power cables (heavy duty) with aluminium conductor, 11000 volts Earthed, grade cross sectional area 120 sq. mm, 3 core	300.00	RM	1100.00	330000.00
5	Returning refilling in, including spreading leveling watering and well ramming in layers not ex 25cm.	544.50	Cum	130.00	70785.00
6	M&L for Supplying and laying un-reinforced precast concrete cable cover, class LV, type 2 with peak, flat, size 300mm x 180mm x 40mm.	5000.00	Each	125.00	625000.00
7	M&L Earthing complete with Copper earth plate electrode 60×60cm ×3.15mm thick electrode and copper strip as earthing lead, buried directly in ground (earth pit not less than 2.25 metres deep below ground level) with top edge of the plate not less than 1.5 metres below normal ground level, connected to copper strip 20×3mm as earth lead by means of bolts, nuts, check nuts and washers of galvanised iron or steel all as shown in electrical plate No. 3 connected to earthing test point all as specified or indicated including testing on completion.	2.00	Each set	15000.00	30000.00
8	Supplied & Installed Transformer, step-down, 11/0.433 KVA complete, outdoor/indoor, copper wound capacity 250 KVA, L-3	1.00	Each	950000.00	950000.00
9	M&L for Cross arms, bracings, supports, clamps and back plates fabricated from structural steel sections including nuts, bolts, washers, welding, bending cold or hot, drilling holes for bolts, in any shape or size as indicated or directed and inclusive of one primer coat, one under coat and one finishing coat of paint.	5.00	Per Qtl.	15000.00	75000.00
10	M&L for Earth continuity conductor or main earthing lead fixed to wall on batten or recess or chases or buried in ground or drawn in conduit/pipe or fixed to poles or any other indicated situation for loop earthing etc. as required 4mm dia galvanised iron or steel wire.	100.00	RM	100.00	10000.00
11	M&L for Air break (switch) insulator for 11000 volts for outdoor use Suitable for current rating of 200 amp.	2.00	Each	24000.00	48000.00
12	M&L for Triple pole, mechanically operated, mounted on insulator and steel frame, with operating mechanism worked from ground level, for current rating upto 200 amps, 11000 Volts.	1.00	Each	13000.00	13000.00
13	M&L for Expulsion fuse single pole upto 25A, 6.6KV	3.00	Each	900.00	2700.00
14	M&L for Cable jointing kit for 11 KV (Earthed) grade cable for outdoor termination heat shrink type joint complete with jointing material and accessories suitable for 3 core XLPE armoured aluminium conductor cable of size 120 to 185 sqmm.	1.00	Each	6500.00	6500.00
15	M&L for Lightning arresters expulsion type complete with all fittings, transmission class, discharge capacity 65 kilo amp suitable for 11000 volts.	1.00	per set	10000.00	10000.00
16	M&L for Steel tubular swaged poles complete with cast iron base plate, final taper plug, bolts, nuts & screws as specified type 410 SP-64 (12.0metres long)	2.00	Each	21500.00	43000.00
17	Supply installation & commissioning of 34 mtrs high mast tower with complete accessories with 800 watt led flood light (40 nos each tower) details enclosed	1.00	01 WJ	9750000.00	9750000.00
18	I. LT Power Panel-200 Kw Supply of outdoor type Complete Power Panel,	1.00	Each	155540.00	155540.00

कमल
मेसर्स कमल किशोर गार्स भोपाल

(डी.एन. कोशल)
जारीकर्ता अधिकारी, उपमहाप्रबंधक
कृते मुख्य महाप्रबंधक

 Unit Address: Vehicle Factory Jabalpur, MP-482009
PHONE NO: 0761-2793000, 2793001, 2330520
FAX NO. 0761-2330436, EMAIL: vfi.ofb@nic.in

Regd. Address: C/o Armoured Vehicles Headquarters,
HVF Road, Bhaktavatsalapuram, Avadi, Chennai, TN 600054, INDIA
PHONE NO: 044-26383601, 26384784, FAX NO. 044-26383653

आर्मर्ड व्हीकल्स निगम लिमिटेड
वाहन निर्माणी जबलपुर
भारत सरकार का उद्यम
रक्षा मंत्रालय



ARMOURED VEHICLES NIGAM LIMITED
VEHICLE FACTORY JABALPUR
A GOVT. OF INDIA ENTERPRISE
MINISTRY OF DEFENCE
CIN-U35990TN2021GOI145504

capacity 200KW 3-Phase 440 V ,50Hz supply, installation & commissioning with following Parameters:-Powder Coated Enclosure 1.6 mm CRCA Stainless steel. - Doors and covers shall be provided with PU gasket. -Horizontal & vertical Incoming & outgoing. - Aluminum bus bar of rating 400Amp. - indication lights, LED Type, RYB 230 V AC. - Panel size-60x60x15 inches(Min.). To control 3-phase power supply incoming, & out going as: -Main Incomer supply through 400A MCCB-01 No, -Outgoing supply through 200A MCCB -04 Nos -Outgoing supply through 63A MCCB -02 Nos. -Outgoing supply through 32A MCCB -02 Nos. -Outgoing supply through 16A MCB -02 Nos. -incoming/outgoing Ckt with proper control. -Aluminum bus bar & MCCBs to control LT power supply. -Accessories Make -Scheinider/C&S/HPL/Seimens/Havells ONLY. -followed all safety norms in ckt connections.				
Total value of Items Rs.				1,31,99,450.00
Add Taxes as applicable Rs.				0.00
Gross Rs.				1,31,99,450.00

TERMS & CONDITIONS:

1. Special Condition: The Material required for the subject work which be brought inside the factory by the contractors, should be noted along with challan/ vouchers etc. and a copy of the same are to be given to the engineering office for record and copy to be submitted to the contractors along with the bill while claiming the payment.
2. Payment Clause: The contractor has to pay the minimum daily wages to the High skilled/skilled/ semi-skilled/ unskilled labourer engaged in their work as specified by the Government, latest rate and displayed in the wages notice Board at factory. Contractor has to maintain a record of worker's attendance and wages paid to them.
3. Safety Clause: Annexure-B of MES Safety Code, IAFW 2249 must be observed in general. Work Permit shall be obtained for overhead/hazardous work condition. All the safety precautions/measures have to be taken by the contractor. However, a few points of safety measures to be followed for working at height and on the roof are mentioned hereby: -

Use of safety belt and helmet of proper quality is mandatory for all workers working on roofs at height of above 5.00 meters and also in the underground areas. Safety belt with life line should be properly tied at some firm support in

- i. In case any difficulty is faced in proper fastening and securing of safety belt, a safety net may be provided below the workspot so that in case of accident fall, there might not be any fatality.
- ii. A crawling ladder or roof walker must be used for movement on Asbestos/CGI roofing.
- iii. Work Permit system should be followed in proper spirit. Contractors shall start the work after obtaining the Work Permit, wherever applicable. Contractor's supervisor and site-in-charge should brief on safety precautions to be observed by the workmen before start of the work. The workers should be clearly explained about the danger of standing or sitting on an apparently stout & new and neat looking asbestos/CGI sheet which is intrinsically weak.
- iv. The contractor shall clear the site after completion of work.
- v. The contractor must employ the labour force duly insured against life risk.
- vi. The contractor shall ensure compliance of all applicable statutory rules and regulations.

4. DEVIATION CLAUSE:

- (i) $\pm 25\%$ of value of individual item other than freakishly rate quoted items.
- (ii) For freakishly higher or lower rate quoted items it shall be $\pm 5\%$.
- (iii) 20% of Work Order value (Contract value maximum Rs.10 lakhs)
10% of Work Order value (Contract value exceeding Rs.10 lakhs)


मेसर्स कमल किशोर गर्ग, भोपाल
(ठेकेदार)
प्रामाणिक


(डी.एन. किशोर)
जारीकर्ता अधिकारी, उपमहाप्रबंधक
कृते मुख्य महाप्रबंधक


Unit Address: Vehicle Factory Jabalpur, MP -482009
PHONE NO: 0761-2793000, 2793001, 2330520
FAX NO. 0761-2330436, EMAIL: vfj.ofb@nic.in

Regd. Address: C/o Armoured Vehicles Headquarters,
HVF Road, Bhaktavatsalapuram, Avadi, Chennai, TN 600054, INDIA
PHONE NO: 044-26383601, 26384784, FAX NO. 044-26383653

(4)

सी.ए. क्र. 07/इजी/वा.नि.ज./2024-25/ई.ओ.(सिविल)


1. Scope of Work:

This contract covers all works described in schedule "A" and as specified in particular specifications. This work lies in restricted area of Vehicle Factory/Factory Estate of VFJ.

2. General Notes:

- I. The normal deviation limit of this contract of items of any individual trade included in the contract shall be plus/minus 25%. The total deviation of contract shall not exceed 20 % for the work up to 10 lakhs, and not exceeding 10% for the works costing more than 10 lakhs as per condition 7 of IAFW-2249, list of building included in scope of work can be changed at any time but quantity will be restricted as per condition 7 of IAFW-2249.
 - II. Water charges will be deducted at Rs. 6.00 per Rs. 1000/- from the bill.
 - III. Income Tax @ 2.0 % will be deducted from the bill.
 - IV. The contract value is inclusive of GST and no extra payment will be made to the contractor for GST.
 - V. GST will be applicable as per Rule and Tax slab. In this regard discretion of accepting officer will be final and binding to the contractor.
 - VI. The contractor will submit GST invoice with filed status of GSTR-1 (B2B) report along with each bill. Bill for Payment will be forwarded to F&A section only when the particulars of the GST Invoice submitted by contractor, correctly appear on GSTR-2B portal of Vehicle factory Jabalpur. Such particulars should be correct in respect of invoice no, invoice date, taxable amount, GST amount and any other field of such Tax Invoice. Such particulars should appear with 'Filed' status if the GSTR 1 filing periodicity in relation to such tax invoice(s) of the supplier has expired or else the factory shall have the right to withhold the future payments of the firm.
 - VII. Contractor should have to deposit EPF amount of workmen under their control directly to EPF office and will send a copy of receipt of challan along with attendance sheet to EO (Civil) every month through EIC/SIC. Same will be verified with attendance sheet and EPFO website. In Case of any ambiguity payment will not be processed and action as deemed fit shall be taken against the firm.
In addition, the contractor will also have to submit an undertaking that the payment due to EPF, has been made in respective offices by him for the particular months in favour of the workmen employed by him in VFJ only.
 - VIII. Contractor has to deposit ESIC amount of workmen under their control directly to ESIC office and will send a copy of receipt of challan along with attendance sheet to EO (Civil) every month through EIC/SIC. Same will be verified with attendance sheet.
In addition, the contractor will also have to submit an undertaking that the payment due to ESIC, has been made in respective offices by him for the particular months in favour of the workmen employed by him in VFJ only.
 - IX. The contractors, who are going to execute the work at height, should make arrangement for group Insurance for persons who will be executing the work to cover compensation charges an eventuality of any accident, if occurred.
 - X. As per The Building and Other Construction Workers (Regulation of employment & condition of service) Act 1996, a Registration Certificate to be obtained from the labour Commission (Central), Jabalpur or Shram Suvidha Portal. The above is a statutory requirement & the contractor has to submit the Registration number.
 - XI. Contractor shall be liable to pay element for "Building & Other Construction Workers Welfare Cess" as admissible, at the prevailing rates (presently 01% of the completion cost) and the quoted rates shall be deemed to be inclusive of this element and the same will be deducted from contractor's bill.
 - XII. All other taxes imposed by Central/State Govt. from time to time will be paid by the Contractor.
 - XIII. The electric supply will be provided by factory on request by the contractor. The contractor has to make arrangement for electric meter, cable, fittings etc. at site. The electricity charges will be deducted from the contractor's bill at the prevailing rate.
 - XIV. Detailed measurement of the work will be taken and entered in the Measurement book (IAFW-2261) in the usual manner.
 - XV. Day to day progress, persons engaged and material used should be recorded in work diary. The work diary must be signed by contractor or his representative and Site-in-charge on day to day basis.
- 3. Period of Completion:**
Entire contract is to be completed within **180 Days** from the date of commencement of work as indicated in Contract. Time of completion is the essence of contract. Normally, the time of completion as mentioned in contract will not be extended, however time of completion will be extended with **compensation for delay** only as per general condition of contracts IAFW- 2249.
- 4. Defect liability period:**
Defect liability period will be 24 months Years from the date of completion of work.
- 5. Deviation Limit:**
a. Deviation Limit for freakily higher Item No. 06 & 10 shall be restricted up to (+) 5% of quantities against normal deviation limit stated above.
b. There is no freak Low item.


मेसमस कमल किशोर गर्ग, भोपाल
(ठेकेदार)


(डी.एन. किशोर)
जारीकर्ता अधिकारी, उपमहाप्रबंधक
कृते मुख्य महाप्रबंधक

(5)

Signature Not Verified

Digitally signed by Teekaram Maravi
Date: 2024.06.29 16:14:13 IST
Location: eProcurement System for Central
PSUs