

ACCEPTANCE LETTER No : MINUTES OF CWC - I HELD ON 30-08-2024

To

M/S. SANTHOSH INFRASTRUCTURE,
NO. 18, RAM BHARATHI STREET,
KRISHNAPURAM, AMBATTUR, CHENNAI – 600 053.

Dear Sir,

Type of Work: ITEM RATE

Sub : CONSTRUCTION OF SMART CLASS ROOM IN FIRST FLOOR ABOVE LIBRARY BUILDING IN IOLAV AT HVF ESTATE.

Ref: (i) HVF Tender No. HVF/TE/13025/CEO/2024-25/17 Dt.04.07.2024, Tender ID : 2024_AVNL_200186_1
(ii) Your Bid No: 721744 in this tender and confirmation for quality and price revision offered vide email dated.28.08.2024.

For and on behalf of The President of India, I hereby convey the acceptance of your tender by the competent financial authority for the above mentioned work for a total value of **Rs. 31,06,068.20/- (Rupees Thirty One Lakh Six Thousand Sixty Eight and Paise Twenty Only)** and order the services detailed in the schedule enclosed herewith at the item rates quoted by you in Schedule 'A' of the Tender documents as per the terms, conditions and specifications laid therein. List of items, to be issued by factory, is given in Schedule 'B'.

2. The contract is allotted with No. **HVF/CE/14/2024-25/CAP, Dated. 23-09-2024** which will have to be quoted by you in all future correspondence in connection with this contract.

3. In accordance with condition No. 22 of the General Condition of Contract (IAFW-2249), please submit the security deposit of Rs. 78,000 /- (Rupees Seventy Eight Thousand Only) in favour of "Chief General Manager, Heavy Vehicle Factory, Avadi" as mentioned in tender condition. The maturity date of security Deposit shall be minimum 12 months from date of the completion of contract.

4. The contract shall be governed by the terms and conditions as per the contract documents enclosed and general condition of contract MES IAFW 2249. The deviation limit shall be as per the clause No.19.1.1 & 19.1.2 of MES Contract Manual (latest revision).

5. Shri. G. Ananda Kumar, WM / IMS is nominated as Engineer-in-Charge and Shri. S. Arunachalam, JWM/IMS/ CE(E) is nominated as Site In-charge for the subject work respectively.

6. You are requested to contact the Engineer-in-Charge within 7 days of receipt of this letter for taking over of site and to make time and progress chart. You will also maintain wage-cum-muster roll and all other records as required in Contract Labour Rules and Acts.

7. Please acknowledge receipt of this letter and return two copies duly signed by you in proof of acceptance within seven days from the date of receipt of this communication.



(K. TULASI RAO)

JT. GENERAL MANAGER / IMS

For CHIEF GENERAL MANAGER / HVF

For And On Behalf Of THE PRESIDENT OF INDIA

Copy to :


1. GM / HR, F&A, IMS, HVF, Avadi, Chennai – 600054
2. Shri. Pranjit Bhagabati, DGM / IMS - Technical Examiner
3. Shri. G. Anandakumar, WM / IMS - Engineer –In- Charge
4. Shri. S. Arunachalam, JWM/IMS / CE(E) - Site –In- Charge

IN LIEU OF IAFW-1823(REVISED)
CONTRACTORS' ORDER SHEET

Work Order/Deviation Order No	HVF/CE/14/2024-25/CAP., dated 23-09-2024
Acceptance letter No.	MINUTES OF CWC – I HELD ON 30-08-2024
Contractor's Name	M/S. SANTHOSH INFRASTRUCTURE
Name of the work	CONSTRUCTION OF SMART CLASS ROOM IN FIRST FLOOR ABOVE LIBRARY BUILDING IN IOLAV AT HVF ESTATE.
CA amount	Rs. 31,06,068.20 /-

PARTICULARS

1. Authority	CWC decision of Fy. LEVEL CWC - I
2. Brief Description of work to be carried out	As per details in sheet attached and adhering to your firm Bid No. 721744 in this tender in HVF/TE/13025/CEO/2024-25/17 Dt.04.07.24, Tender ID : 2024_AVNL_200186_1 price revision vide email dt.28.08.2024 for all Terms & Conditions therein & rate quoted in Schedule 'A' enclosed with tender documents.
3. Time effect	
a. Date of handing over of the site	01/10/2024
b. Date of commencement of work	01/10/2024
c. Date of Completion as per contract	29/05/2025
d. Date for completion shown in previous Orders	NA
e. Revised date of completion	NA
4. Financial effect (Rs.)	
a. Present order	Rs. 31,06,068.20 /-
b. Contract amount as adjusted by previous orders	NA
c. Contract amount adjusted up to and including this order	NA
5. Expenditure to be booked under code Head No	920 / 34 (Under Capital Civil Works Grant)
6. Certified that no special rate is involved	
7. Technical Examiner	Shri. Pranjit Bhagabati, DGM / IMS
8. Approved	Shri. K. Tulasi Rao, Jt.GM / IMS
9. Accepted	M/S. SANTHOSH INFRASTRUCTURE


(K. TULASI RAO)

JT. GENERAL MANAGER / IMS
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA

Distribution to :--

1. M/S. SANTHOSH INFRASTRUCTURE, Chennai
2. GM / HR, F&A,IMS, HVF, Avadi, Chennai - 600054
3. Sr. Security Officer
4. Shri. Pranjit Bhagabati, DGM / IMS - Technical Examiner
5. Shri. G. Anandakumar, WM / IMS - Engineer –In- Charge
6. Shri. S. Arunachalam, JWM/IMS / CE(E) - Site –In- Charge
7. HOS/Safety, 8. HOS/Internal Audit cell, 9. HOS/Test Audit, 10. ALWC, 11.GM/IOLAV
12. Chief Commissioner of Central Excise, 26/1, Mahatma Gandhi Road, Nungambakkam, Chennai – 600034
13. Dy. Chief Labour Commissioner(c), No: 26, III Block, 5th floor, Shastri Bhavan, Haddows Road, Nungambakkam, Chennai – 600006.

SCHEDULE – "A"					
Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
1	Demolition of concrete structure of any description	CUM	1.10	2072.00	2279.20
2	M & L for R.C.C A1 Type, 1: 1.5: 3 M20, 20mm graded aggregate in columns, pillars, piers, posts and struts etc	CUM	7.00	6100.00	42700.00
3	M & L for R.C.C A1 Type, 1: 1.5: 3 M20, 20mm graded aggregate in beams, cantilevers, bressummers, lintels over 1.50m span etc., (concrete work should be use of Ready Mix Concrete (RMC) (minimum cement conetent shall be 350kg per cum).	CUM	20.00	6100.00	122000.00
4	M & L for R.C.C A1 Type, 1: 1.5: 3 M20, 20mm graded aggregate in Slabs supported on walls,beams and columns in floors,roofs, landings, balconies,canopies, deck slabs and in shelves and the like.etc.(concrete work should be use of Ready Mix Concrete (RMC)(minimum cement conetent shall be 350kg per cum)	CUM	30.00	6100.00	183000.00
5	Supply and fixing of mild steel reinforcement deformed or twisted bars including bending, cranking, hooking and tying with mild steel wire not less than 0.90mm dia. Used RINL-VIZAG Steel/SAIL/TATA-TISCON/"BIS"MARKED or Similar Suitable Make.	KG	5700.00	93.00	530100.00
6	M & L for Flat form work to sides and soffits of floor or roof beam, beam, lintels, cantilevers, shelves, columns, slabs including supports, overhangs etc., and the finishing shall be of fair finished surface.	SQM	210.00	500.00	105000.00
7	M & L for Flat form work to soffits rough finish surfaces of suspended slabs such as roof slabs, floor slabs, landings and similar work not exceeding 200mm thick (Horizontal or sloping) and the finishing shall be of fair finished surface.	SQM	200.00	500.00	100000.00
8	M & L for Brick Work built in CM 1:6 using Sub class "B" Bricks straight or curved on plan exc 6m mean radius.	CUM	45.00	6100.00	274500.00
9	M & L for plastering in CM 1:4, 15mm thick on fair faces of brick work and concrete surfaces.	SQM	550.00	280.00	154000.00
10	M & L for plastering in CM 1:4, 12mm thick on RCC Ceiling.	SQM	350.00	280.00	98000.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
11	Material and labour for precast cement concrete B-0 type (1:2:4) jallies 35 mm thick and set in cement mortar 1:6.	SQM	3.00	800.00	2400.00
12	S & F of PVC 110mm dia Pipes single socketed, in any length with rubber ring joints fixed to walls.	RM	42.00	550.00	23100.00
13	S & F of PVC Bend 110mm dia any radius.	Each	8.00	125.00	1000.00
14	PVC (SWR) reducers 110mm dia any radius.	Each	4.00	155.00	620.00
15	S & F of II class hard wood door frame, wrought framed rebated on the solid rounded or chamfered put together with glue pined at joints.	CUM	0.10	95300.00	9530.00
16	S & F of plain, framed, paneled door shutters 40mm thick made out of II class hard wood.	SQM	5.00	2575.00	12875.00
17	S & F of 125mm Butt hinges, extruded aluminium alloy with foregoing items if brass hinge pin, anodised and fixed, type B- 21.	Each	6.00	320.00	1920.00
18	S & F of Alluminium drop bolt 300mm long with hasp, staple (Bolt type) and fixing clips.	Each	2.00	480.00	960.00
19	S & F of 200mm Aluminium anodized barrel tower bolt.	Each	4.00	100.00	400.00
20	S & F of 150mm Aluminium anodized bow handle.	Each	4.00	85.00	340.00
21	Supply and Fixing of door stopper 150mm of aluminium alloy body and tongue, anodised, with hard drawn steel spring	EACH	2.00	115.00	230.00
22	M & L for painting to wooden surfaces of any description over 10cm width or girth with two coats of synthetic enamel paint over a coat of pink primer including preparing new wooden surfaces.	SQM	7.00	160.00	1120.00
23	M & L for painting to wooden surfaces of any description over 10cm width or girth with two coats of synthetic enamel paint over a coat of pink primer including preparing old wooden surfaces.	SQM	20.00	165.00	3300.00
24	Material and labour for two coats of exterior emulsion paint on surfaces of any description over 10cm girth or width, not otherwise described including preparation of new painted surface with one coat of primer. ASIAN/NEROLAC/BERGER or Similar Suitable Make.	SQM	350.00	162.00	56700.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
25	Material and labour for two coats of exterior emulsion paint on surfaces of any description over 10cm girth or width, not otherwise described including preparation of old painted surface with one coat of primer. (ASIAN/NEROLAC/BERGER or Similar Suitable Make.)	SQM	260.00	175.00	45500.00
26	M & L for interior emulsion two coats on walls after preparing the new painted surfaces with one coat of alkali resistant primer (ASIAN/NEROLAC/BERGER or Similar Suitable Make.)	SQM	150.00	111.00	16650.00
27	M & L for interior emulsion two coats on walls after preparing the old painted surfaces with one coat of alkali resistant primer. (ASIAN/NEROLAC/BERGER or Similar Suitable Make.)	SQM	150.00	115.00	17250.00
28	M & L for white washing two coats on ceiling on newly prepared wall surfaces. (ASIAN/NEROLAC/BERGER or Similar Suitable Make.)	SQM	330.00	25.00	8250.00
29	Cutting holes in brick walls built in cement mortar Exc. half brick work but not exc. one brick for inserting hold fasts and making good dismantled portion in cement mortar 1:3 or cement concrete 1:2:4 type B1 as required.	Each	8.00	375.00	3000.00
30	Providing and fixing factory made UPVC white colour sliding window three track made of extruded profiles with wall thickness of 2.3 mm (1.0.2mm) window profile with hollow section with multi chamber. Frame(88mm x 52mm) sliding sash (42mm x 57mm) Sliding Interlock(one vertical length in each shutter)(45.5 mm x 28 mm) Glazing bead(24.5mm x 16 mm) will be mitred cut and fusion welded at all corners including railing of holes for fixing hardware and drainage of water etc., making arrangement for fixing hardware. EPDM gasket. 1.2 to 0.2 mm thick galvanised steel frame(30 mm x 18 mm) 2 nos. sliding sash (30 mm x 18 mm), Sliding mesh sash (26 mm x 10 mm) profile to be inserted in required profile frame will be fixed to the wall with 8mm x 100mm long fasteners. Hardware Touch Lock of Zinc alloyed (white powder coated). steel roller system. Stainless steel wire cloth 0.36mm nominal dia of wire and average width of aperture 1.40mm and required accessories.(Note The unit rate quoted by contractor excludes cost of glass and includes all other connected accessories. net opening will be measured for payment purpose.(a) area n exc 2.00 Sqm each) and as approved and as directed.	sqm	20.00	11200.00	224000.00
31	M & L for painting to steel surfaces of any description over 10cm width or girth with two coats of synthetic enamel paint over a coat of Red Oxide primer including preparing old surfaces.	SQM	15.00	169.00	2535.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
32	Supply and Fixing of sheet Glass 5.50mm quality and glazing with oil putty in square exc 0.5Sqm in each pare ground or obscured or tinted on one side and as approved and as directed by EIC.	SQM	15.00	1470.00	22050.00
33	Supply and fixing of stainless steel 304 grade hand rail top rail 50mm dia, stiffner 20mm, 32mm square bar with wall thickness 1.2mm with necessary flanges, holding clamps with complete buffing and polishing all complete . and as approved and as directed by EIC .	KG	265.00	740.00	196100.00
34	Material and Labour for fixing Light shade Vitrified ceramic tiles 10mm thick square/rectangle) polished area of each tiles not exceeding 0.36 Sqm in floors etc set and jointed in neat cement slurry and pointed in white or colored cement to match including screed bed in cement mortar 1:4, 15mm thick complete.	SQM	160.00	1700.00	272000.00
35	Material and Labour for 20mm thick Granite (of any type) work (table rubbed and polished) for wall lining (veneering to wall) 12mm thick in cement mortar (1:3) and pointing with white cement (1:2) using marble dust with admixture of pigment to match with shade of granite.	SQM	40.00	4500.00	180000.00
36	Material and labour for Point wiring with FRLS PVC insulated sheathed single core cable 1100V grade confirming to IS 694 multi strand copper conductor along with 2mm thick PVC conduit accessories run on wall or roof including M.S. switch box concealed in the wall(made out of 3mm thick sheet) and laminated sun mica sheet 3mm thick cover for housing the switches, regulators and plug socket etc. mount on a wall/roof etc. including multistrand copper earth continuity wire. (Make: Finolex/Orbit/ Kundan/ Havells/ Polycab or suitably equivalent make)a)one light / fan point controlled by one switch, with cables 1.5 sq.mm size.	Each	40.00	1000.00	40000.00
37	Material and labour for Point wiring with FRLS PVC insulated sheathed single core cable 1100V grade confirming to IS 694 multi strand copper conductor along with 2mm thick PVC conduuit accessories run on wall or roof including M.S. switch box concealed in the wall(made out of 3mm thick sheet) and laminated sun mica sheet 3mm thick cover for housing the switches, regulators and plug socket etc. mount on a wall/roof etc. including multistrand copper earth continuity wire. (Make: Finolex/Orbit/ Kundan/ Havells/ Polycab or suitably equivalent make) b) One light point controlled by two 2 - way switches , with cables1.5 sq. mm size	Each	3.00	1560.00	4680.00


Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
38	Material and labour for Point wiring with FRLS PVC insulated sheathed single core cable 1100V grade confirming to IS 694 multi strand copper conductor along with 2mm thick PVC conduit accessories run on wall or roof including M.S. switch box concealed in the wall(made out of 3mm thick sheet) and laminated sun mica sheet 3mm thick cover for housing the switches, regulators and plug socket etc. mount on a wall/roof etc. including multistrand copper earth continuity wire. (Make: Finolex/Orbit/ Kundan/ Havells/ Polycab or suitably equivalent make)c)One 3 pin plug socket with switches flush type 5A on same board with other switches, with 2.5sqmm cable	Each	32.00	325.00	10400.00
39	Material and labour for Point wiring with FRLS PVC insulated sheathed single core cable 1100V grade confirming to IS 694 multi strand copper conductor along with 2mm thick PVC conduit accessories run on wall or roof including M.S. switch box concealed in the wall(made out of 3mm thick sheet) and laminated sun mica sheet 3mm thick cover for housing the switches, regulators and plug socket etc. mount on a wall/roof etc. including multistrand copper earth continuity wire. (Make: Finolex/Orbit/ Kundan/ Havells/ Polycab or suitably equivalent make) d)One 3 pin plug socket with switches flush type 5A on Independent board with 2.5sqmm cable	Each	8.00	1250.00	10000.00
40	Supply fixing and connecting to the system modular type switches 10A single pole one way (Make:,LEGRAND MYRIUS/ Litaski/ Crabtree or suitably equivalent make)	Each	72.00	300.00	21600.00
41	Supply fixing and connecting to the system modular type switches 10A Two way, 1 module (Make:,LEGRAND MYRIUS/ Litaski/ Crabtree or suitably equivalent make)	Each	6.00	360.00	2160.00
42	Supply, fixing and connecting to the system of socket, 6A-2/3 pin combined modular type, 2 module(Make:,LEGRAND MYRIUS/ Litaski/ Crabtree or suitably equivalent make)	Each	32.00	380.00	12160.00
43	Supply, fixing and connecting to the system of socket, 6A/16A-2/3 pin combined modular type 2 module(Make:,LEGRAND MYRIUS/ Litaski/ Crabtree or suitably equivalent make)	Each	22.00	575.00	12650.00
44	Supply, fixing and connecting to the system modular type switch one way 16A, 1 module (Make:,LEGRAND MYRIUS/ Litaski/ Crabtree or suitably equivalent make)	Each	16.00	382.00	6112.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
45	Material & Labour for ceiling rose, 3 Phase/PVC/polycarbonate, isolated body (ANCHOR / LEGRAND/ HAVELLS or suitably equivalent make)	Each	15.00	73.00	1095.00
46	Supply & fixing of modular white cover plate with frame 2 module	Each	16.00	215.00	3440.00
47	Supply & fixing metal flush box for 2 module plate	Each	16.00	200.00	3200.00
48	Supply & fixing of 4 module modular white cover plate with frame	Each	4.00	273.00	1092.00
49	Supply & fixing of metal flush box for 4 module plate	Each	4.00	234.00	936.00
50	Supply & fixing of 6 module modular white cover plate with frame	Each	5.00	340.00	1700.00
51	Supply & fixing of metal flush box for 6 module plate	Each	5.00	313.00	1565.00
52	Supply & fixing of 8 module plate with frame	Each	1.00	420.00	420.00
53	Supply, fixing & connecting to the system of Sheet metal enclosures with double door DB's 415 V when MCB'S to be used Triple pole & neutral 4 way with 200 Amps rated busbar, (Make: Legrand/Havells/ABB or suitably equivalent make)	Each	1.00	2907.00	2907.00
54	Supply and fixing 415V 10KA 'B' curve miniature circuit breaker (MCB) of following poles and current carrying capacity in the DB complete with connection testing and commissioning. TP (Triple pole) 25 To 63 AMP (Make: Legrand/Havells/ABB or suitably equivalent make)	Each	2.00	1865.00	3730.00
55	Supply and fixing 240V, 10 KA 'B' curve miniature circuit breaker (MCB) of single poles and current carrying capacity 6 to 32 AMP, in the MCB DB Complete with connection testing and commissioning. (Make: ABB/LeGrand/ Havells or suitably equivalent make)	Each	21.00	300.00	6300.00
56	Supply & Fixing of MCCB 3 Pole, 415 V, fixed type, 125 Amps with breaking capacity of 16 KA. (Make: ABB/LeGrand/ Havells or suitably equivalent make)	Each	1.00	3940.00	3940.00
57	Material & Labour for wiring with two runs of PVC insulated sheathed single core copper cable upto 1100 volts grade conforming to IS 694 multistrand with copper conductor along with PVC conduit and conduit accessories run on wall/roof one run of copper cable as earth wire. (Make: Finolux/Havells/Polycab/ Kundan or suitably equivalent make) a) 2x2.5 sq.mm+1x2.5 sq.mm earth wire	RM	125.00	200.00	25000.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
58	Material & Labour for wiring with two runs of PVC insulated sheathed single core copper cable upto 1100 volts grade confirming to IS 694 multistrand with copper conductor along with PVC conduit and conduit accessories run on wall/roof one run of copper cable as earth wire. (Make: Finolux/Havells/Polycab/ Kundan or suitably equivalent make)b) 2x4.0 sq.mm+1x4.0 sq.mm earth wire	RM	130.00	235.00	30550.00
59	Material & Labour for wiring with two runs of PVC insulated sheathed single core copper cable upto 1100 volts grade confirming to IS 694 multistrand with copper conductor along with PVC conduit and conduit accessories run on wall/roof one run of copper cable as earth wire. (Make: Finolux/Havells/Polycab/ Kundan or suitably equivalent make)c) 4x10.0 sq.mm+ 1x10.0 sq.mm earth wire	RM	30.00	600.00	18000.00
60	Material and labour for Brick walls cutting chases, pinning in, making good to facing where required and pointing in cement mortar 1:3 to ends and cutting chases for concealed conduit wiring, etc., and making good, cutting exc. 10 cm but not exc. 20 cm grith.	RM	180.00	58.00	10440.00
61	Supply and fixing ceiling fans complete with blades, down rods, electronic regulator and accessories, 230 V, 1200 mm sweep. Min air delivery 210 CFM with service value 6.00 BEE. Five star rated with brushless direct current motor (BLDC) (Make:Usha/ crompton/ atomberg/ havells/ orient or suitably equivalent make)	Each	8.00	2900.00	23200.00
62	Supply and fixing LED luminaire 600 mm x 600 mm, 35/36 watt, 220 V AC recessed type with high efficiency PMMA diffuser soft glare free light complete with driver, holders & LED lamp suitable for roof ceiling including connecting up with driver three core flexible copper conductor cases of suitable size complete. (Make: PHILIPS/Bajaj/CG / Havells /Wipro or suitably equivalent make)	Each	12.00	4600.00	55200.00
63	Supply and fixing of LED lights fitting 1x 20W, 220V, AC decorative box type with driver, holder including LED tube light connecting up with three core flexible copper conductor cable of suitable size from ceiling rose complete. (Make: PHILIPS / CG /Havells / Wipro / Klite/ Bajaj/ Luker or suitably equivalent make)	Each	10.00	1430.00	14300.00
64	Supply and fixing of LED light fitting mirror type with high out put diffuser 2 feet, 10 watt 220 V AC decorative type with driver holder and LED lamp including connecting up with three core flexible copper conductor cable of suitable size complete (Make: PHILIPS / Bajaj /CG /Havells / Wipro or suitably equivalent make)	RM	1.00	1495.00	1495.00

Heavy Vehicles Factory,
Avadi, Chennai, TamilNadu-600054

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
65	Supply and fix exhaust fan, steel body AC single Phase. 230V of size 300mm sweep with, blades, and frame and louvers (Make: Almonard/Kaithan / crompton or suitably equivalent make)	Each	1.00	3912.00	3912.00
66	Supply & fixing of MCBDB 4 way(DPX160+12) legrand make as per legrand 2010 catalogue No.607790. or Havells/ Hager/ L&T/ ABB or suitably equivalent make)	Each	1.00	10235.00	10235.00
67	Supply & Fixing of Modular type MCB 20A, 240V, Single pole, in the MCB DB complete with connection testing and commissioning (Make: LegrandHavells/ Hager/ L&T/ ABB or suitably equivalent make)	Each	8.00	2800.00	22400.00
68	Supply and fixing of LED ceiling/Recessed mounting fitting complete with suitable LED lamp and accessories, Wattage 24 to 30 watts and minimum system output 1800 lumens. (Make: PHILIPS / Bajaj /CG /Havells / Wipro or suitably equivalent make)	Each	6.00	3700.00	22200.00
69	Supply & fixing metal flush box for 8 module plate	Each	1.00	125.00	125.00
70	Supply & fixing of 12 module plate with frame and metal flush box	Each	8.00	455.00	3640.00
71	Supply & fixing of 16 module plate with frame and metal flush box	Each	3.00	500.00	1500.00
72	Supply & fixing of modular type Dummy plate	Each	15.00	25.00	375.00
Gross Total of Items (Rs.)				Rs.31,06,068.20/-	


 (K. TULASI RAO)
 JT. GENERAL MANAGER / IMS
 For CHIEF GENERAL MANAGER / HVF
 For And On Behalf Of THE PRESIDENT OF INDIA

TERMS & CONDITIONS:

1 Special Condition: The Material required for the subject work which be brought inside the factory by the contractors, should be noted along with challan / vouchers etc., and a copy of the same are to be given to the engineering office for record and copy to be submitted to the contractors along with the bill while claiming the payment.

2 Payment Clause: The contractor has to pay the minimum daily wages to the skilled/semi skilled/unskilled labourers engaged in their work as has been specified by the Government, latest rate and displayed in the wages notice Board at factory.

3 Safety Clause: Annexure-B of MES Safety Code, IAFW 2249 must be observed in general. Work Permit shall be obtained for overhead/hazardous work condition. All the safety precautions/measures have to be taken by the contractor. However, a few points of safety measures to be followed for working at height and on the roof are mentioned hereby :

Use of safety belt and helmet of proper quality is mandatory for all workers working on roofs at height of above 5.00 meters and also in the underground areas. Safety belt with life line should be properly tied at some firm support.

(i) In case any difficulty is faced in proper fastening and securing of safety belt, a safety net may be provided below the workspot so that in case of accident fall, there might not be any fatality.

(ii) A crawling ladder or roof walker must be used for movement on Asbestos/CGI roofing.

(iii) Work Permit system should be followed in proper spirit. Contractors shall start the work after obtaining the Work Permit, wherever applicable. Contractor's supervisor and site-in-charge should brief on safety precautions to be observed by the workmen before start of the work. The workers should be clearly explained about the danger of standing or sitting on an apparently stout & new and neat looking asbestos/CGI sheet which is intrinsically weak.

(iv) The contractor shall clear the site after completion of work.

(v) The contractor must employ the labour force duly insured against life risk.

(vi) The contractors shall ensure compliance of all applicable statutory rules and regulations.


4 DEVIATION CLAUSE:

(i) $\pm 25\%$ of value of individual item other than freakishly rate quoted items.

(ii) For freakishly higher or lower rate quoted items it shall be $\pm 5\%$.

(iii) 20% of Work Order value (Contract value maximum Rs.10 lakhs)

10% of Work Order value (Contract value exceeding Rs.10 lakhs)



(K. TULASI RAO)
JT. GENERAL MANAGER / IMS
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA