

ACCEPTANCE LETTER No : MINUTES OF CWC – II HELD ON 22-08-2024

To

M/S MSK CONSTRUCTION
No. 120, FIRST STREET, SANIPOONDI,
TIRUVANNAMALAI TALUK
TAMIL NADU – 606 755

Dear Sirs,

Type of Work: ITEM RATE

Sub : **REPAIRS TO DAMAGED FENCING AND COMPOUND WALL OF POL GODOWN IN OLD FACILITY
AT HVF, AVADI.**

Ref: (i) HVF Tender No. HVF/TE/13025/CEO/2024-25/18, Dt. 04-07-2024 with Tender ID: 2024_AVNL_200234_1
(ii) Your Bid No: 721864 in this tender and Price Reduction & Confirmation offered vide your letter
Dt. 14-08-2024 and Rate revision sheet received vide e-mail Dt. 14-08-2024

For and on behalf of The President of India, I hereby convey the acceptance of your tender by the competent financial authority for the above mentioned work for a total value of **Rs. 10,35,555 /- (Rupees Ten Lakhs Thirty Five Thousand Five Hundred and Fifty Five Only)** and order the services detailed in the schedule enclosed herewith at the item rates quoted by you in Schedule 'A' of the Tender documents as per the terms, conditions and specifications laid therein. List of items, to be issued by factory, is given in Schedule 'B'.

2. The contract is allotted with No. **HVF/CE/17/2024-25/MAINT, Dated. 29-08-2024** which will have to be quoted by you in all future correspondence in connection with this contract.

3. In accordance with condition No. 22 of the General Condition of Contract (IAFW-2249), please submit the security deposit of Rs. 26,000 /- (Rupees Twenty Six Thousand Only) in favour of " The Chief General Manager, Heavy Vehicles Factory, Avadi" as mentioned in tender condition.


The maturity date of security Deposit shall be minimum 12 months from date of the completion of contract.

4. The contract shall be governed by the terms and conditions as per the contract documents enclosed and general condition of contract MES IAFW 2249. The deviation limit shall be as per the clause No.19.1.1 & 19.1.2 of MES Contract Manual (latest revision).

5. Shri. P. Neelakandan, JWM (SG) / IMS / CE (FY), is nominated as Engineer-in-Charge and Shri. E. Uma Sankar, JWM / IMS / CE (FY) is nominated as Site In-charge for the subject work respectively.

6. You are requested to contact the Engineer-in-Charge within 7 days of receipt of this letter for taking over of site and to make time and progress chart. You will also maintain wage-cum-muster roll and all other records as required in Contract Labour Rules and Acts.

7. Please acknowledge receipt of this letter and return two copies duly signed by you in proof of acceptance within seven days from the date of receipt of this communication.



(K. TULASI RAO)

JT. GENERAL MANAGER / IMS

For CHIEF GENERAL MANAGER / HVF

For And On Behalf Of THE PRESIDENT OF INDIA

Copy to :

- | | |
|--|----------------------|
| 1. GM / HR, F&A, IMS, HVF, Avadi, Chennai – 600054 | |
| 2. Shri. P. Neelakandan, JWM (SG) / IMS / CE (FY) | - Engineer-in-Charge |
| 3. Shri. E. Uma Sankar, JWM / IMS / CE (FY) | - Site-in-Charge |
| 4. Shri. P.G. Harish Kumar, JWM / CEO | - Technical Examiner |

IN LIEU OF IAFW-1823(REVISED)
CONTRACTORS' ORDER SHEET

Work Order/Deviation Order No	HVF/CE/17/2024-25/MAINT, Dated 29-08-2024
Acceptance letter No.	MINUTES OF CWC – II HELD ON 22-08-2024
Contractor's Name	M/S MSK CONSTRUCTION
Name of the work	REPAIRS TO DAMAGED FENCING AND COMPOUND WALL OF POL GODOWN IN OLD FACILITY AT HVF, AVADI
CA amount	Rs. 10,35,555 /=-

PARTICULARS

1. Authority	CWC decision of Fy. LEVEL CWC - II As per details in sheet attached and adhering to your firm Bid No. 721864 in this tender and Price Reductions & Confirmation offered vide your Letter Dt. 14-08-2024 and Rate Revision Sheet received vide e.mail Dt. 14-08-2024 in T.E No. HVF/TE/13025/CEO/2024-25/18, Dt. 04-07-2024 with Tender ID: 2024_AVNL_200234_1 for all Terms & Conditions therein & rate quoted in Schedule 'A' enclosed with tender documents.
2. Brief Description of work to be carried out	
3. Time effect	
a. Date of handing over of the site	09/09/2024
b. Date of commencement of work	09/09/2024
c. Date of Completion as per contract	07/01/2025
d. Date for completion shown in previous Orders	NA
e. Revised date of completion	NA
4. Financial effect (Rs.)	
a. Present order	Rs. 10,35,555 /=-
b. Contract amount as adjusted by previous orders	NA
c. Contract amount adjusted up to including this order	NA
5. Expenditure to be booked under code Head No	809 / 01 (REVENUE GRANT)
6. Certified that no special rate is involved	
7. Technical Examiner	Shri. P.G. Harish Kumar, JWM / CEO
8. Approved	Shri. K. Tulasi Rao, Jt.GM / IMS
9. Accepted	M/S MSK CONSTRUCTION


(K. TULASI RAO)

JT. GENERAL MANAGER / IMS
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA

Distribution to :--

1. M/s MSK Construction.
2. GM / HR, F&A, IMS, HVF, Avadi, Chennai – 600054
3. Sr. Security Officer
4. Shri. P. Neelakandan, JWM (SG) / IMS / CE (Fy) - Engineer-in-Charge
5. Shri. E. Uma Sankar, JWM / IMS / CE (Fy) - Site-in-Charge
6. Shri. P.G. Harish Kumar, JWM / CEO - Technical Examiner.
7. AWM / STORES. 8. HOS/Safety, 9. HOS/Internal Audit cell, 10. HOS/Test Audit, 11. ALWC,
12. Chief Commissioner of Central Excise, 26/1, Mahatma Gandhi Road, Nungambakkam, Chennai – 600034
13. Dy. Chief Labour Commissioner(c), No: 26, III Block, 5th floor, Shastri Bhavan, Haddows Road, Nungambakkam, Chennai – 600006.

**NAME OF THE WORK : REPAIRS TO DAMAGED FENCING AND COMPOUND WALL OF POL
GODOWN IN OLD FACILITY AT HVF, AVADI.**

CONTRACT AGREEMENT No : HVF/CE/17/2024-25/MAINT, Dated. 29-08-2024

SCHEDULE – "A"


Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
01	Demolition of Brick work built in cement mortar of any description including removal of the debris to a lead exceeding 1.5 KM.	CUM	16.00	1095.00	17520.00
02	Earth work excavation in hard/ dense soil in trenches width and depth not exceeding 1.50m and getting out.	CUM	33.00	723.00	23859.00
03	Dismantling posts or struts Concrete, brick work, masonry, etc.(wood, steel or R.C.C.) any section, embedded in concrete, masonry or brick mortar including taking out embedded portion and making good disturbed ground as directed by EIC	RM	275.00	44.00	12100.00
04	Material and Labour for Bush Cutting ,Cutting/Trimming of trees branches falling on the existing /proposed Fencing area complete as directed by the EIC and handed over to Y&E Wood Scrap Godown.	WJ	1.00	5100.00	5100.00
05	Dismantling structural steel work including doors, gates but excluding framed truss etc.,	Quintal	10.50	664.00	6972.00
06	M&L for Excavating in post holes hard/dense (or similar holes) each n exc 0.5 cu. m, getting out returning, filling in and ramming earth or broken rubble mixed with earth around, in layers not exceeding 25 cm,	EACH	70.00	410.00	28700.00
07	Surface Excavation soft /loose soil not exceeding 30 cm deep and averaging 15cm deep and getting out as directed by EIC.	SQM	100.00	57.00	5700.00
08	M&L for sand filling under foundations, flooring, etc, including watering and consolidation.	CUM	4.50	2112.00	9504.00
09	M & L for P.C.C 1:4:8, D2 type using 40mm graded aggregated Cement concrete in foundations, filling and mass concrete in foundation.	CUM	4.50	6000.00	27000.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
10	M&L for cement concrete in foundation ,filling and mass concrete typeB1 1:2:4 using 20mm aggregate.	CUM	16.50	8250.00	136125.00
11	M&L for Reinforced cement concrete type B1 1:2:4 using 20 mm graded aggregate(nominal mix) in Foundations, including rafts, Footings, foundation beams, plinth beams; bases for columns,etc.;basement slabs under-reamed piles and columns.	CUM	10.00	6994.80	69948.00
12	M & L for providing reinforced cement concrete type B1. 1:2:4 mix 20mm graded aggregate in pre-cast posts, fencing posts, straining or terminal posts struts etc., for fencing, average sectional area exceeding 100 sq cm and not exceeding 250 sq.cm with or without chamfered angles and flat, splayed, rounded or mitered tops as directed and fixed.	CUM	11.00	12265.00	134915.00
13	Material and labour for flat Form work to sides of concrete foundations, footings, bases of columns, raft and raft beams, sides and soffits (if any) of foundation and plinth beams, columns and similar work; vertical and the finishing shall be of smooth and fair finish.	SQM	53.00	360.00	19080.00
14	S&F of mild steel reinforcement deformed or twisted bars 10 mm dia and over, cut to length, bent to shape required, including cranking, bending spirally for hooping for columns, hooking ends and binding with and including mild steel wire (annealed) not less than 0.9mm dia or securing with clips.	KG	900.00	95.00	85500.00
15	S&F of mild steel reinforcement deformed or twisted bars 6 to 8 mm dia, cut to length, bent to shape required, including cranking, bending spirally for hooping for columns, hooking ends and binding with and including mild steel wire (annealed) not less than 0.9mm dia or securing with clips .	KG	650.00	96.00	62400.00
16	Supply and fixing of Hand rails, half round or other steel section or core for wooden hand-rail straight portion, drilled and countersunk for balusters running bars, for doors, balusters, nosing to steps including embedding in concrete and screwing etc. wind ties for roof including securing bolts; posts and struts in fencing including cutting tops to shape as directed, drilling holes, notching for wire, etc.; flat iron fillets (for securing wire mesh etc.) including all necessary drilling, bolting or riveting, etc., and similar work conforming to Fe-290 Gde E-165.	KG	550.00	120.00	66000.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
17	Material and labour for painting steel surfaces of any description over 10cm width or girth with two coats of synthetic enamel paint over a coat of red oxide primer including preparing new steel surfaces.	SQM	60.00	130.00	7800.00
18	Material and labour for chain link fencing made of 8 gauge G.I. Wire with 3" aperture and height as directed.	SQM	400.00	388.52	155408.00
19	Supply and fixing of galvanized 2 strand steel barbed wire 2.24mm dia barbed with 2mm dia barbs at 75mm spacings and straining and fixing to any type of standard rails straining bolts including securing or tying at crossings with and provision of galvanised mild steel wire staples or steel pins etc., as directed (each line wire to be measured).	Per 100 RM	6.00	1650.00	9900.00
20	M & L for white washing two coats on new concrete surfaces including preparation of new surfaces.	SQM	200.00	21.00	4200.00
21	M & L for Brick work in CM 1:6 using sub class 'B' Bricks.	CUM	16.00	6000.00	96000.00
22	M&L for Plastering with 1:4,15mm thick on faces of new brick work and concrete surfaces.	SQM	154.00	281.00	43274.00
23	Returning / refilling of soil / loose including spreading, leveling, watering and well ramming in layers not exceeding 25cm.	CUM	15.00	150.00	2250.00
24	Removal of excavated soils exceeding 250m but not exceeding 500mm and depositing where directed.	CUM	18.00	350.00	6300.00

Gross Total of Items (Rs.)

10,35,555 /-


(K. TULASI RAO)

JT. GENERAL MANAGER / IMS
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA

TERMS & CONDITIONS:

1 Special Condition: The Material required for the subject work which be brought inside the factory by the contractors, should be noted along with challan / vouchers etc., and a copy of the same are to be given to the engineering office for record and copy to be submitted to the contractors along with the bill while claiming the payment.

2 Payment Clause: The contractor has to pay the minimum daily wages to the skilled/semi skilled/unskilled labourers engaged in their work as has been specified by the Government, latest rate and displayed in the wages notice Board at factory.

3 Safety Clause: Annexure-B of MES Safety Code, IAFW 2249 must be observed in general. Work Permit shall be obtained for overhead/hazardous work condition. All the safety precautions/measures have to be taken by the contractor. However, a few points of safety measures to be followed for working at height and on the roof are mentioned hereby :

Use of safety belt and helmet of proper quality is mandatory for all workers working on roofs at height of above 5.00 meters and also in the underground areas. Safety belt with life line should be properly tied at some firm support.

(i) In case any difficulty is faced in proper fastening and securing of safety belt, a safety net may be provided below the workspot so that in case of accident fall, there might not be any fatality.

(ii) A crawling ladder or roof walker must be used for movement on Asbestos/CGI roofing.

(iii) Work Permit system should be followed in proper spirit. Contractors shall start the work after obtaining the Work Permit, wherever applicable. Contractor's supervisor and site-in-charge should brief on safety precautions to be observed by the workmen before start of the work. The workers should be clearly explained about the danger of standing or sitting on an apparently stout & new and neat looking asbestos/CGI sheet which is intrinsically weak.

(iv) The contractor shall clear the site after completion of work.

(v) The contractor must employ the labour force duly insured against life risk.

(vi) The contractors shall ensure compliance of all applicable statutory rules and regulations.


4 DEVIATION CLAUSE:

(i) $\pm 25\%$ of value of individual item other than freakishly rate quoted items.

(ii) For freakishly higher or lower rate quoted items it shall be $\pm 5\%$.

(iii) 20% of Work Order value (Contract value maximum Rs.10 lakhs)

10% of Work Order value (Contract value exceeding Rs.10 lakhs)



(K. TULASI RAO)

JT. GENERAL MANAGER / IMS

For CHIEF GENERAL MANAGER / HVF

For And On Behalf Of THE PRESIDENT OF INDIA