

ACCEPTANCE LETTER No: MINUTES OF CWC HELD ON 19-08-2024

To

SANTHOSH INFRASTRUCTURE,
No. 18, RAM BHARATHI STREET, KRISHNAPURAM,
AMBATTUR, CHENNAI - 600053

Dear Sirs,

Type of Work: ITEM RATE

Sub : **PROVISION OF INTERLOCKING TILES, REPAIRS TO THE DAMAGED COMPOUND WALL AND ENTRANCE GATE IN URC AT HVF ESTATE**

Ref: (i) Tender No. HVF/TE/URC/REPAIRS/PW/2024-25/03, Dt. 04-07-2024 with Tender ID:2024_AVNL_200255_1
(ii) Your Bid No: 721738 in this tender.

For and on behalf of the Chairman / Unit Run Canteen, HVF Estate, Avadi, I hereby convey the acceptance of your tender by the competent financial authority for the above mentioned work for a total value of **Rs. 19,15,642 /-** (Rupees Nineteen Lakhs Fifteen Thousand Six Hundred and Forty Two Only) and order the services detailed in the schedule enclosed herewith at the item rates quoted by you in Schedule 'A' of the Tender documents as per the terms, conditions and specifications laid therein. List of items, to be issued, is given in Schedule 'B'.

2. The contract is allotted with No. **HVF/CE/URC/REPAIRS/PW/02/2024-25., dated 28-08-2024** which will have to be quoted by you in all future correspondence in connection with this contract.

3. In accordance with condition No. 22 of the General Condition of Contract (IAFW-2249), please submit the security deposit of Rs. 47,900 /- (Rupees Forty Seven Thousand and Nine Hundred Only) in favour of "The Chief General Manager, Heavy Vehicle Factory, Avadi" as mentioned in tender condition.


The maturity date of security Deposit shall be minimum 12 months from date of the completion of contract.

4. The contract shall be governed by the terms and conditions as per the contract documents enclosed and general condition of contract MES IAFW 2249. The deviation limit shall be as per the clause No.19.1.1 & 19.1.2 of MES Contract Manual (latest revision).

5. Shri. K.Ravichandran, JWM(SG)/IMS/CE(E) is nominated as Engineer-in-Charge and Shri. S.Arunachalam, JWM/IMS/CE(E) is nominated as Site In-charge for the subject work.

6. You are requested to contact the Engineer-in-Charge within 7 days of receipt of this letter for taking over of site and to make time and progress chart. You will also maintain wage-cum-muster roll and all other records as required in Contract Labour Rules and Acts.

7. Please acknowledge receipt of this letter and return two copies duly signed by you in proof of acceptance within seven days from the date of receipt of this communication.



(K. TULASI RAO)

JT. GENERAL MANAGER / IMS
For CHIEF GENERAL MANAGER / HVF

Copy to :

1. Chairman / Unit Run Canteen, HVF Estate, Avadi,
2. Shri. K.Ravichandran, JWM(SG)/IMS/CE(E) - Engineer -In Charge
3. Shri.S.Arunachalam, JWM/IMS/CE(E) - Site -In Charge
4. Shri. P.G. Harish Kumar, JWM / CEO - Technical Examiner

IN LIEU OF IAFW-1823(REVISED)
CONTRACTORS' ORDER SHEET

Work Order/Deviation Order No	<u>HVF/CE/URC/REPAIRS/PW/02/2024-25., dated 28-08-2024</u>
Acceptance letter No.	MINUTES OF CWC HELD ON 19-08-2024
Contractor's Name	SANTHOSH INFRASTRUCTURE
Name of the work	PROVISION OF INTERLOCKING TILES, REPAIRS TO THE DAMAGED COMPOUND WALL AND ENTRANCE GATE IN URC AT HVF ESTATE
CA amount	Rs. 19,15,642 /-

PARTICULARS

1. Authority	CWC decision of HVF CWC.
2. Brief Description of work to be carried out	As per details in sheet attached and adhering to your firm Bid No. 721738 in HVF Tender; HVF/TE/URC/REPAIRS/PW/2024-25/03, Dt. 04-07-2024 with Tender ID:2024_AVNL_200255_1 for all Terms & Conditions therein & rate quoted in Schedule 'A' enclosed with tender documents.
3. Time effect	
a. Date of handing over of the site	04/09/2024
b. Date of commencement of work	04/09/2024
c. Date of Completion as per contract	03/12/2024
d. Date for completion shown in previous Orders	NA
e. Revised date of completion	NA
4. Financial effect (Rs.)	
a. Present order	Rs. 19,15,642 /-
b. Contract amount as adjusted by previous orders	NA
c. Contract amount adjusted up to and including this order	NA
5. Expenditure to be booked under code Head No	HVF Unit Run Canteen Fund
6. Certified that no special rate is involved	
7. Technical Examiner	Shri. P.G. Harish Kumar, JWM / CEO
8. Approved	Shri. K. Tulasi Rao, Jt.GM / IMS
9. Accepted	SANTHOSH INFRASTRUCTURE


(K. TULASI RAO)

JT. GENERAL MANAGER / IMS
For CHIEF GENERAL MANAGER / HVF

Distribution to :--

- 1) SANTHOSH INFRASTRUCTURE
- 2) Chairman / Unit Run Canteen, HVF Estate, Avadi,
- 3) Sr. Security Officer
- 4) Shri.K.Ravichandran, JWM(SG)/IMS/CE(E) - Engineer -In Charge
- 5) Shri. S.Arunachalam, JWM/IMS/CE(E) - Site -In Charge
- 6) Shri. P.G. Harish Kumar, JWM / CEO - Technical Examiner
- 7) HOS/Safety, 9) HOS/Internal Audit cell, 10) HOS/Test Audit, 11) ALWC,
- 12) Chief Commissioner of Central Excise, 26/1, Mahatma Gandhi Road, Nungambakkam, Chennai – 600034.
- 13) Dy.Chief Labour Commissioner(c), No:26, III Block, 5thfloor,Shastri Bhavan, Haddows Road, Nungambakkam,Chennai – 600006.

Name of the work: **PROVISION OF INTERLOCKING TILES, REPAIRS TO THE DAMAGED COMPOUND WALL AND ENTRANCE GATE IN URC AT HVF ESTATE**

Contract Agreement No: **HVF/CE/URC/REPAIRS/PW/02/2024-25., dated 28-08-2024**

SCHEDULE – “A”					
Item Code	Item Description	Quantity	Unit	Rate/Unit	Total Cost
1	Surface Dressing in hard / dense soil n. exc 15 cm deep.	800.00	SqM	37.00	29600.00
2	Demolition of brick work built in Cement Mortar.	10.00	CuM	1807.00	18070.00
3	Dismantling of Structural steel work including Doors, Gates but excluding framed truss etc.,	2.00	Per Quintal	686.00	1372.00
4	Earth Work excavation in Soft / Loose soil in trenches width and depth not exceeding 1.50 m and getting out.	50.00	CuM	422.00	21100.00
5	Material and labour for Removing and Re-fixing of Precast Concrete slabs etc., complete as directed by EIC.	35.00	SqM	550.00	19250.00
6	Demolition of Un-reinforced Cement concrete in ground floors and pavings not exceeding 15 cm thick.	11.00	CuM	1517.00	16687.00
7	Material and Labour for sand filling in foundation including watering and consolidation.	80.00	CuM	1500.00	120000.00
8	Material and labour for PCC 1:3:6 type C2 using 40 mm graded aggregate for foundation.	82.00	CuM	5500.00	451000.00
9	Material and labour for Pre-cast cement concrete block Type B1 1:2:4 (using 20mm graded aggregates) masonry with solid blocks, exc. 10 cm in width and setting in CM 1:4, complete as directed by EIC.	12.00	CuM	9000.00	108000.00
10	Material and labour for plastering in CM 1:4, 15 mm thick on fair faces of brick work and concrete surfaces.	165.00	SqM	250.00	41250.00
11	Supply and fixing of Rubber Mould Machine pressed precast concrete interlocking paver block with grey cement and colour pigment any shape and size confirming to IS 15658 - 2006 of 60 mm thickness M-35 Grade set in River sand cushion / bed, as per site condition the sand should be free from dust, pebbles, roots, vegetation etc., all complete as approved and as directed by EIC (Make as approved by EIC). The rate includes interlocking paver block and labour for laying but excluding river sand, which will be measured and paid separately.	850.00	SqM	740.00	629000.00
12	Supply and fixing of mild steel reinforcement deformed or twisted bars 10 mm dia and over including bending, cranking, hooking and tying with mild steel wire not less than 0.90 mm dia.	1150.00	Kg	91.00	104650.00

Item Code	Item Description	Quantity	Unit	Rate/Unit	Total Cost
13	Material and labour for R.C.C 1:1.5:3 M20, B1 type using 20 mm graded aggregate in foundation and flooring etc., as directed by EIC.	12.00	CuM	6628.00	79536.00
14	Material and labour for flat form work to side and soffit of RCC Member such as foundation, plinth beam etc., and the finishing shall be of fair finished surfaces.	55.00	SqM	400.00	22000.00
15	Supply and fixing of Ornamental Gate work such as grills, gratings etc., with ends of bars shouldered and / or riveted, or forged into spikes; framed guard bars; barred iron doors; ladders; framed balusters; walk ways; railings; frame work of water tanks and similar work conforming to Fe.290.Gde-E-165.	1100.00	Kg	200.00	220000.00
16	Material and labour for Metallic painting on steel surfaces of any description, with 2 coats of synthetic enamel paint and one coat of primer Red Oxide and preparation of new surfaces etc., as directed.	20.00	SqM	850.00	17000.00
17	Material and labour for applying two coats of plastic emulsion over one coat of primer including preparation of new surfaces as directed by EIC.	80.00	SqM	158.00	12640.00
18	Removal of excavated soils exceeding 250 m but not exceeding 500 m and depositing where directed.	7.00	CuM	641.00	4487.00
Gross Total of Items			Rs. 19,15,642.00 /-		


(K. TULASI RAO)

JT. GENERAL MANAGER / IMS
For CHIEF GENERAL MANAGER / HVF

TERMS & CONDITIONS:

1 Special Condition: The Material required for the subject work which be brought inside the factory by the contractors, should be noted along with challan / vouchers etc., and a copy of the same are to be given to the engineering office for record and copy to be submitted to the contractors along with the bill while claiming the payment.

2 Payment Clause: The contractor has to pay the minimum daily wages to the skilled/semi-skilled/unskilled labourers engaged in their work as has been specified by the Government, latest rate and displayed in the wages notice Board at factory.

3 Safety Clause: Annexure-B of MES Safety Code, IAFW 2249 must be observed in general. Work Permit shall be obtained for overhead/hazardous work condition. All the safety precautions/measures have to be taken by the contractor. However, a few points of safety measures to be followed for working at height and on the roof are mentioned hereby:

Use of safety belt and helmet of proper quality is mandatory for all workers working on roofs at height of above 5.00 meters and also in the underground areas. Safety belt with life line should be properly tied at some firm support.

(i) In case any difficulty is faced in proper fastening and securing of safety belt, a safety net may be provided below the work spot so that in case of accident fall, there might not be any fatality.

(ii) A crawling ladder or roof walker must be used for movement on Asbestos/CGI roofing.

(iii) Work Permit system should be followed in proper spirit. Contractors shall start the work after obtaining the Work Permit, wherever applicable. Contractor's supervisor and site-in-charge should brief on safety precautions to be observed by the workmen before start of the work. The workers should be clearly explained about the danger of standing or sitting on an apparently stout & new and neat looking asbestos/CGI sheet which is intrinsically weak.

(iv) The contractor shall clear the site after completion of work.

(v) The contractor must employ the labour force duly insured against life risk.

(vi) The contractors shall ensure compliance of all applicable statutory rules and regulations.


4 DEVIATION CLAUSE:

(i) $\pm 25\%$ of value of individual item other than freakishly rate quoted items.

(ii) For freakishly higher or lower rate quoted items it shall be $\pm 5\%$.

(iii) 20% of Work Order value (Contract value maximum Rs.10 lakhs)

10% of Work Order value (Contract value exceeding Rs.10 lakhs)



(K. TULASI RAO)

JT. GENERAL MANAGER / IMS
For CHIEF GENERAL MANAGER / HVF