

ACCEPTANCE LETTER No : MINUTES OF CWC – I HELD ON 18-10-2024

To

S. VINAYAGAMURTHY
No. 1201, TNHB, KAKALUR SCHEME,
THIRUVALLUR – 602 001

Dear Sirs,

Type of Work: ITEM RATE

Sub : **PROVISION OF COMPOUND WALL AROUND MAIN WATER PUMP HOUSE, G-TYPE, E-TYPE, NURSERY WATER TANK AND SPECIAL REPAIRS TO THE DAMAGED PERIMETER WALL AROUND HVF ESTATE AREA.**

Ref: (i) HVF Tender No. HVF/TE/13025/CEO/2024-25/26, Dt. 13-08-2024 with Tender ID: 2024_AVNL_204710_1
(ii) Your Bid No: 738703 in this tender and Price Reduction Offered vide your negotiated Bid opened on 14-10-2024 and Confirmations Offered vide your letter Dt. 08-10-2024

For and on behalf of The President of India, I hereby convey the acceptance of your tender by the competent financial authority for the above mentioned work for a total value of **Rs. 70,92,966 /- (Rupees Seventy Lakhs Ninety Two Thousand Nine Hundred and Sixty Six Only)** and order the services detailed in the schedule enclosed herewith at the item rates quoted by you in Schedule 'A' of the Tender documents as per the terms, conditions and specifications laid therein. List of items, to be issued by factory, is given in Schedule 'B'.

2. The contract is allotted with No. **HVF/CE/17/2024-25/CAP, Dated. 30-10-2024** which will have to be quoted by you in all future correspondence in connection with this contract.

3. In accordance with condition No. 22 of the General Condition of Contract (IAFW-2249), please submit the security deposit of Rs. 1,64,300 /- (Rupees One Lakh Sixty Four Thousand and Three Hundred Only) in favour of " The Chief General Manager, Heavy Vehicles Factory, Avadi" as mentioned in tender condition.

The maturity date of security Deposit shall be minimum 12 months from date of the completion of contract.

4. The contract shall be governed by the terms and conditions as per the contract documents enclosed and general condition of contract MES IAFW 2249. The deviation limit shall be as per the clause No.19.1.1 & 19.1.2 of MES Contract Manual (latest revision).

5. Shri. G. Anandakumar, WM / IMS, is nominated as Engineer-in-Charge and Shri. K. Ravichandran, JWM (SG) / IMS / CE (Estate) is nominated as Site In-charge for the subject work respectively.

6. You are requested to contact the Engineer-in-Charge within 7 days of receipt of this letter for taking over of site and to make time and progress chart. You will also maintain wage-cum-muster roll and all other records as required in Contract Labour Rules and Acts.

7. Please acknowledge receipt of this letter and return two copies duly signed by you in proof of acceptance within seven days from the date of receipt of this communication.



(K. TULASI RAO)

GENERAL MANAGER

For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA

Copy to :

- | | | |
|---|---|--------------------|
| 1. GM / HR, F&A, IMS, HVF, Avadi, Chennai – 600054 | - | Technical Examiner |
| 2. Shri. Pranjit Bhagabati, DGM / IMS | - | Engineer-in-Charge |
| 3. Shri. G. Ananda Kumar, WM / IMS | - | Site-in-Charge |
| 4. Shri. K. Ravichandran, JWM (SG)/ IMS / CE (Estate) | - | |

IN LIEU OF IAFW-1823(REVISED)
CONTRACTORS' ORDER SHEET

Work Order/Deviation Order No	HVF/CE/17/2024-25/CAP, Dated 30-10-2024
Acceptance letter No.	MINUTES OF CWC – I HELD ON 18-10-2024
Contractor's Name	S VINAYAGAMURTHY
Name of the work	PROVISION OF COMPOUND WALL AROUND MAIN WATER PUMP HOUSE, G-TYPE, E-TYPE, NURSERY WATER TANK AND SPECIAL REPAIRS TO THE DAMAGED PERIMETER WALL AROUND HVF ESTATE AREA.
CA amount	Rs. 70,92,966 /=-

PARTICULARS

1. Authority	CWC decision of Fy. LEVEL CWC - I
2. Brief Description of work to be carried out	As per details in sheet attached and adhering to your firm Bid No. 738703 in this tender and Price Reduction offered vide your negotiated bid opened on 14-10-2024 and confirmations offered vide your letter Dt. 08-10-2024 in T.E No. HVF/TE/13025/CEO/2024-25/26, Dt. 13-08-2024 with Tender ID: 2024_AVNL_204710_1 for all Terms & Conditions therein & rate quoted in Schedule 'A' enclosed with tender documents.
3. Time effect	
a. Date of handing over of the site	11/11/2024
b. Date of commencement of work	11/11/2024
c. Date of Completion as per contract	11/11/2025
d. Date for completion shown in previous Orders	NA
e. Revised date of completion	NA
4. Financial effect (Rs.)	
a. Present order	Rs. 70,92,966 /=-
b. Contract amount as adjusted by previous orders	NA
c. Contract amount adjusted up to including this order	NA
5. Expenditure to be booked under code Head No	920 / 34 (CAPITAL GRANT)
6. Certified that no special rate is involved	
7. Technical Examiner	Shri. Pranjit Bhagabati, DGM / IMS
8. Approved	Shri. K. Tulasi Rao, General Manager
9. Accepted	S VINAYAGAMURTHY


(K. TULASI RAO)

GENERAL MANAGER

For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA

Distribution to :-

1. M/s S. VINAYAGAMURTHY.
2. GM / HR, F&A, IMS, HVF, Avadi, Chennai – 600054
3. Sr. Security Officer
4. Shri. Pranjit Bhagabati, DGM / IMS - Technical Examiner
5. Shri. G. Anandakumar, WM / IMS - Engineer Incharge
6. Shri. K. Ravichandran, JWM (SG) / IMS / CE (Estate) - Site In-charge.
7. HOS/Safety, 8. HOS/Internal Audit cell, 9. HOS/Test Audit, 10. ALWC,
11. Chief Commissioner of Central Excise, 26/1, Mahatma Gandhi Road, Nungambakkam, Chennai – 600034
12. Dy. Chief Labour Commissioner(c), No: 26, III Block, 5th floor, Shastri Bhavan, Haddows Road, Nungambakkam, Chennai – 600006.

NAME OF THE WORK	PROVISION OF COMPOUND WALL AROUND MAIN WATER PUMP HOUSE, G-TYPE, E-TYPE, NURSERY WATER TANK AND SPECIAL REPAIRS TO THE DAMAGED PERIMETER WALL AROUND HVF ESTATE AREA.
CONTRACT AGREEMENT NO	HVF/CE/17/2024-25/CAP, Dated 30-10-2024


SCHEDULE – “A”					
Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
01	A Grubbing up tree trunk including cutting of trunk portion protruding over ground , digging out roots, filling holes and leveling off ground, stacking of serviceable material and removing of unserviceable material to a distance not exceeding 50 m and clearing site, girth of tree exceeding 150 cm and not exceeding 200 cm.	Each	6.00	1900.00	11400.00
02	Removal of bushes/shrubs around.	RM	650.00	5.90	3835.00
03	Dismantling posts or struts (R.C.C.) any section, including taking out embedded portion and making good disturbed ground. Concrete, brick work, masonry, etc	RM	300.00	37.00	11100.00
04	Surface dressing n exc 15 cm deep Hard/dense soil	SQM	600.00	30.00	18000.00
05	Demolition of Brick work built in cement mortor of any description	CUM	90.00	370.00	33300.00
06	Demolition of reinforced Concrete structure of any description.	CUM	1.00	1850.00	1850.00
07	Earth work excavation in hard/ dense soil in trenches width and depth not exceeding 1.50m and getting out.	CUM	450.00	498.00	224100.00
08	Material and labour for sand filling under foundation including watering and consolidation.	CUM	30.00	1797.00	53910.00
09	Material and labour for PCC Type B1 1:2:4 20mm graded aggregate in flooring.	CUM	65.00	6305.00	409825.00
10	M & L for PCC 1:3:6, C2 Type using 40mm graded aggregated in flooring.	CUM	70.00	5599.00	391930.00
11	M & L for providing reinforcement cement concrete in Footings, piles, Plinth beam with cement concrete A1 Type, 1:1.5:3 mix using M20 (20mm graded aggregated.)	CUM	145.00	6790.00	984550.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
12	M & L for providing reinforcement cement concrete in column, pillars and struts with cement concrete A1 Type, 1:1.5:3 mix using M20(20mm graded aggregated).	CUM	28.00	7695.00	215460.00
13	M & L for form work to sides of concrete foundation, bases of column, beam sides and soffits of foundation, Fair Finish and plinth beams.	SQM	600.00	380.00	228000.00
14	M & L for form work fair finish to RCC members such as columns, pillars etc., square, rectangular or polygonal	SQM	500.00	550.00	275000.00
15	Supply and fixing of twisted MS Bars 10mm dia and over, cut to length bent to shape required including cranking, bending, spiraling for hoping for columns, hooking ends and binding with MS Wire not less than 0.9mm dia or securing with clips.	KG	6000.00	91.00	546000.00
16	Supply and fixing of twisted MS Bars 6mm dia up to 8mm dia cut to length bent to shape required including cranking, bending, spiraling for hoping for columns, hooking ends and binding with MS Wire not less than 0.9mm dia or securing with clips.	KG	3700.00	92.00	340400.00
17	M & L for Brick work built in CM.1:6 using Sub-Class "B" Bricks, straight or curved on plan exc 6m mean radius built in .	CUM	190.00	7002.00	1330380.00
18	M & L for providing plastering in CM 1:4, 15mm thick on brick / concrete surface.	SQM	2260.00	284.00	641840.00
19	M & L for Extra over rendering or plastering for work in isolated widths or in widths not forming part of general plastering such as in bands, sunk panels, cornices, skirtings, drip moulds and similar work not exc 15 cm in width or girth; including cutting to edges, all mitres and stopped ends, etc.	RM	1000.00	49.00	49000.00
20	M & L for cement paint two coats over a coat of primer paint on newly prepared wall surfaces.	SQM	2325.00	95.00	220875.00
21	Returning / refilling of soil / loose including spreading, leveling, watering and well ramming in layers not exceeding 25cm.	CUM	305.00	104.00	31720.00
22	Removal of excavated soils exceeding 250 m but not exceeding 500 m and depositing where directed.	CUM	300.00	195.00	58500.00

Item Code	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
23	Cutting holes in brick walls built in cement mortar Exc.half brick work but not exc.one brick for inserting hold fasts and making good dismantled portion in cement mortar 1:3 or cement concrete 1:2:4 type B1 as required.	Each	530.00	166.00	87980.00
24	S & F of Framed work such as grills, gratings, etc.. with ends of bars shouldered and/or riveted, or forged into spikes; framed guard bars; and hung gates including pintle hinges stops hand made sliding bolts etc similar work conforming to Fe.290.Gde-E-165 including removal of existing damaged gate .	KG	4600.00	170.00	782000.00
25	S & F of galvanized, 2 strand steel barbed wire 2.24mm dia barbed with 2mm dia barbs at 75mm spacings and straining and fixing to any type of standard rails, straining bolts including securing or tying at crossings with and provision of galvanized mild steel wire, staples or steel pins etc., as directed (each line wire to be measured).	100 RM	15.00	1115.00	16725.00
26	S & F of GI Concertina wire of 600mm dia made of high tensile wire of 2.50mm having a strength of 165Kgs/Sq.mtr and the razor barb type of 0.52mm thick with barb width of 12mm and length of 10mm and weight 43.47 gm/M coated Zinc 120gsm/sqmt having 45-50 loops with 3 clips per loop giving a coverage of 5.5 to 6.0meter per coil.	RM	230.00	350.00	80500.00
27	M & L for painting to steel surfaces of any description, over 10cm in width or girth,with two coats of synthetic enamel paint over a coat of primer Red oxide, zinc chrome including preparing new surfaces.	SQM	133.00	142.00	18886.00
28	Material and labour for Precast cement concrete Type B1. 1:2:4 20 mm graded aggregate set in cement mortar 1:6 in landings, cover slabs, manholes chullah hoods, chajjas water troughs, mangers, shelves and similar articles with plain faces (cover slab)	CUM	2.00	10900.00	21800.00
29	S & F of PVC 110mm dia Pipes single socketed, in any length with rubber ring joints laid in trenches or in floors.	RM	20.00	205.00	4100.00

Gross Total of Items (Rs.)

70,92,966 /-



(K. TULASI RAO)

GENERAL MANAGER

For CHIEF GENERAL MANAGER / HVF

For And On Behalf Of THE PRESIDENT OF INDIA

TERMS & CONDITIONS:

1 Special Condition: The Material required for the subject work which be brought inside the factory by the contractors, should be noted along with challan / vouchers etc., and a copy of the same are to be given to the engineering office for record and copy to be submitted to the contractors along with the bill while claiming the payment.

2 Payment Clause: The contractor has to pay the minimum daily wages to the skilled/semi skilled/unskilled labourers engaged in their work as has been specified by the Government, latest rate and displayed in the wages notice Board at factory.

3 Safety Clause: Annexure-B of MES Safety Code, IAFW 2249 must be observed in general. Work Permit shall be obtained for overhead/hazardous work condition. All the safety precautions/measures have to be taken by the contractor. However, a few points of safety measures to be followed for working at height and on the roof are mentioned hereby :

Use of safety belt and helmet of proper quality is mandatory for all workers working on roofs at height of above 5.00 meters and also in the underground areas. Safety belt with life line should be properly tied at some firm support.

(i) In case any difficulty is faced in proper fastening and securing of safety belt, a safety net may be provided below the workspot so that in case of accident fall, there might not be any fatality.

(ii) A crawling ladder or roof walker must be used for movement on Asbestos/CGI roofing.

(iii) Work Permit system should be followed in proper spirit. Contractors shall start the work after obtaining the Work Permit, wherever applicable. Contractor's supervisor and site-in-charge should brief on safety precautions to be observed by the workmen before start of the work. The workers should be clearly explained about the danger of standing or sitting on an apparently stout & new and neat looking asbestos/CGI sheet which is intrinsically weak.

(iv) The contractor shall clear the site after completion of work.

(v) The contractor must employ the labour force duly insured against life risk.

(vi) The contractors shall ensure compliance of all applicable statutory rules and regulations.

4 DEVIATION CLAUSE:

(i) $\pm 25\%$ of value of individual item other than freakishly rate quoted items.

(ii) For freakishly higher or lower rate quoted items it shall be $\pm 5\%$.

(iii) 20% of Work Order value (Contract value maximum Rs.10 lakhs)

10% of Work Order value (Contract value exceeding Rs.10 lakhs)



(K. TULASI RAO)

GENERAL MANAGER

For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA