

ACCEPTANCE LETTER No : MINUTES OF CWC HELD ON 04-02-2025

To

M/S. SANTHOSH INFRASTRUCTURE,
NO. 18, RAM BHARATHI STREET,
KRISHNAPURAM, AMBATTUR, CHENNAI – 600 053.

Dear Sir,


Type of Work: ITEM RATE

Sub : CONSTRUCTION OF URC DOOM SHED AND PROVISION OF HARD STANDING IN FRONT OF URC/HVF (OFFICERS COUNTER) IN HVF ESTATE.

Ref: (i) HVF Tender No. HVF/TE/13025/CEO/URC/24-25/04, Dt.05.11.2024 Tender ID : 2024_AVNL_213432_1
(ii) Your Bid No: 771193 in this tender and your quality confirmation mail dated.20.02.2025.

For and on behalf of The President of India, I hereby convey the acceptance of your tender by the competent financial authority for the above mentioned work for a total value of **Rs. 38,91,220/- (Rupees Thirty Eight Lakh Ninety One Thousand Two Hundred and Twenty Only)** and order the services detailed in the schedule enclosed herewith at the item rates quoted by you in Schedule 'A' of the Tender documents as per the terms, conditions and specifications laid therein. List of items, to be issued by factory, is given in Schedule 'B'.

2. The contract is allotted with No. HVF/CE/URC/DOOMSHED/PW/04/2024-25, Dated. 21-02-2025 which will have to be quoted by you in all future correspondence in connection with this contract.
3. In accordance with condition No. 22 of the General Condition of Contract (IAFW-2249), please submit the security deposit of Rs. 98,000 /- (Rupees Ninety Eight Thousand Only) in favour of "Chief General Manager, Heavy Vehicle Factory, Avadi" as mentioned in tender condition. The maturity date of security Deposit shall be minimum 12 months from date of the completion of contract.
4. The contract shall be governed by the terms and conditions as per the contract documents enclosed and general condition of contract MES IAFW 2249. The deviation limit shall be as per the clause No.19.1.1 & 19.1.2 of MES Contract Manual (latest revision).
5. Shri. K. Ravichandran, JWM(SG)/IMS(E) is nominated as Engineer-in-Charge and Shri. Amarjit kumar, JWM/IMS(E) is nominated as Site In-charge's for the subject work respectively.
6. You are requested to contact the Engineer-in-Charge within 7 days of receipt of this letter for taking over of site and to make time and progress chart. You will also maintain wage-cum-muster roll and all other records as required in Contract Labour Rules and Acts.
7. Please acknowledge receipt of this letter and return two copies duly signed by you in proof of acceptance within seven days from the date of receipt of this communication.


(K. TULASI RAO)

GENERAL MANAGER / CEO & QA
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA

Copy to :

- | | |
|--|------------------------|
| 1. GM / HR, F&A, IMS, HVF, Avadi, Chennai – 600054 | |
| 2. Shri. G. Anandakumar, WM/IMS | - Technical Examiner |
| 3. Shri. K. Ravichandran, JWM(SG)/IMS(E) | - Engineer –In- Charge |
| 4. Shri. Amarjit kumar, JWM/IMS(E) | - Site –In- Charge |

IN LIEU OF IAFW-1823(REVISED)
CONTRACTORS' ORDER SHEET

Work Order/Deviation Order No	HVF/CE/URC/DOOMSHED/PW/04/2024-25, Dated. 21-02-2025
Acceptance letter No.	MINUTES OF CWC HELD ON 04-02-2025
Contractor's Name	M/s. SANTHOSH INFRASTRUCTURE, CHENNAI
Name of the work	CONSTRUCTION OF URC DOOM SHED AND PROVISION OF HARD STANDING IN FRONT OF URC/HVF (OFFICERS COUNTER) IN HVF ESTATE
CA amount	Rs. 38,91,220/-

PARTICULARS

1. Authority	CWC decision of Fy. LEVEL CWC
2. Brief Description of work to be carried out	As per details in sheet attached and adhering to your firm Bid No. 771193, Tender ID : 2024_AVNL_213432_1 and your quality confirmation mail dated.20.02.2025 for all Terms & Conditions therein & rate quoted in Schedule 'A' enclosed with tender documents.
3. Time effect	
a. Date of handing over of the site	28/02/2025
b. Date of commencement of work	28/02/2025
c. Date of Completion as per contract	27/08/2025
d. Date for completion shown in previous Orders	NA
e. Revised date of completion	NA
4. Financial effect (Rs.)	
a. Present order	Rs. 38,91,220 /-
b. Contract amount as adjusted by previous orders	NA
c. Contract amount adjusted up to and including this order	NA
5. Expenditure to be booked under code Head No	HVF URC FUND
6. Certified that no special rate is involved	
7. Technical Examiner	Shri. G. Anandakumar, WM/IMS
8. Approved	Shri. K. Tulasi Rao, GM / CEO & QA
9. Accepted	M/s. Santhosh Infrastructure


(K. TULASI RAO)

GENERAL MANAGER / CEO & QA
For CHIEF GENERAL MANAGER / HVF
For And On Behalf Of THE PRESIDENT OF INDIA

Distribution to :--

1. M/s. Santhosh Infrastructure, Chennai
2. GM / HR, F&A,IMS, HVF, Avadi, Chennai - 600054
3. Sr. Security Officer
4. Shri. G.Anandakumar, WM/IMS - Technical Examiner
5. Shri. K. Ravichandran, JWM(SG)/IMS(E) - Engineer -In- Charge
6. Shri. Amarjit kumar, JWM/IMS(E) - Site -In- Charge
7. HOS/Safety, 8 . HOS/Internal Audit cell, 9. HOS/Test Audit, 10. ALWC,
11. Chief Commissioner of Central Excise, 26/1, Mahatma Gandhi Road, Nungambakkam, Chennai – 600034
12. Dy. Chief Labour Commissioner(c), No: 26, III Block, 5th floor, Shastri Bhavan, Haddows Road, Nungambakkam, Chennai – 600006.

NAME OF WORK: CONSTRUCTION OF URC DOOM SHED AND PROVISION OF HARD STANDING IN FRONT OF URC/HVF (OFFICERS COUNTER) IN HVF ESTATE.

C.A. NO. HVF/CE/URC/DOOMSHED/PW/04/2024-25, Dated. 21-02-2025

SCHEDULE – "A"

Sl.No	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
1	M & L for R.C.C A1 Type, 1: 1.5: 3 M20, 20mm graded aggregate in foundations, including rafts, footings, column, beam, plinth beams, roof slab etc.,	CUM	6.00	7000.00	42000.00
2	Supply and fixing of twisted MS Bars 10mm dia and over, cut to length bent to shape required including cranking, bending, spiraling for hoping for columns, hooking ends and binding with MS Wire not less than 0.9mm dia or securing with clips.	KG	400.00	91.00	36400.00
3	Supply and fixing of deformed or twisted MS Bars 6mm dia up to 8mm dia cut to length bent to shape required including cranking, bending, spiraling for hoping for columns, hooking ends and binding with MS Wire not less than 0.9mm dia or securing with clips.	KG	250.00	92.00	23000.00
4	M & L for form work to side of RCC Members, Square/rectangular /polygonal such as columns, pillars etc., and the finishing shall be of fair finished surface.	SQM	20.00	781.00	15620.00
5	M & L for Brick work built in CM.1:6 using Good quality modular bricks / solid Concrete bricks straight or curved on plan exc 6m mean radius.	CUM	2.00	6500.00	13000.00
6	M & L for plastering in CM 1:4, 15mm thick on fair faces of brick work and concrete wall surfaces.	SQM	100.00	280.00	28000.00
7	Material and labour for applying two coats of Plastic emulsion on internal wall surfaces including preparation of new wall surfaces complete all as directed.	SQM	120.00	130.00	15600.00
8	M&L for painting two coats of exterior emulsion (Make APEX ULTIMA of ASIAN PAINTS) including one coat of priming paint applies after preparation of the new existing treatment	SQM	180.00	120.00	21600.00
9	Supply and Fixing of Fiber glass reinforced translucent corrugated sheeting of 2mm thick with two corrugations side lap fixed with coach screw and washer in roof, wall etc complete all as directed.	SQM	350.00	1250.00	437500.00
10	Supply and fixing of framed work using Fe410 W(Gde-E-250) A quality mild rolled steel tube , angles , plates etc . Inculding cutting , welding etc complete as directed by EIC.	KG	6200.00	120.00	744000.00

Sl. No.	Item Description	Unit	Quantity	Rate/Unit (Rs.)	Total Cost (Rs.)
11	S & F of PVC 110mm dia Pipes single socketed, in any length with rubber ring joints laid in trenches or in floors.	RM	120.00	170.00	20400.00
12	S & F of PVC Bend 110mm dia any radius.	Each	20.00	145.00	2900.00
13	M & L for painting to steel surfaces of any description over 10cm width or girth with two coats of synthetic enamel paint over a coat of Red Oxide primer including preparing new surfaces.	SQM	400.00	130.00	52000.00
14	Bending charges for MS pipes of Framed/Tubular Trusses including handling and necessary transport charges etc complete as directed.	KG	1800.00	80.00	144000.00
15	Getting Structural design for Doom shed of size 16.00Mts x 16.00Mts resting of the existing old building from Reputed structural engineer /Designer.	WJ	1.00	83000.00	83000.00
16	Surface excavation in hard/ dense soil not exc.30 cm deep and averaging 15cm deep and getting out.	SQM	1320.00	50.00	66000.00
17	Material and labour for sand filling in foundation including watering and consolidation.	CUM	101.00	1200.00	121200.00
18	Material & Labour for PCC 1:3:6 type C2 using 40mm graded aggregate cement concrete in foundations , filling and mass concrete	CUM	135.00	5000.00	675000.00
19	Material & Labour for PCC 1:2:4 mix,20mm graded aggregate e in foundations, filling and mass concrete	CUM	135.00	6000.00	810000.00
20	M & L for Forming 12mm thick expansion joints filled with performed bituminous filter and top 30mm primed and sealed with sealing compound Grade-B thickness of concrete slab is 150mm.	RM	900.00	600.00	540000.00
Gross Total of Items (Rs.)					38,91,220/-


 (K. TULASI RAO)
 GENERAL MANAGER / CEO & QA
 For CHIEF GENERAL MANAGER / HVF
 For And On Behalf Of THE PRESIDENT OF INDIA

TERMS & CONDITIONS:

1 Special Condition: The Material required for the subject work which be brought inside the factory by the contractors, should be noted along with challan / vouchers etc., and a copy of the same are to be given to the engineering office for record and copy to be submitted to the contractors along with the bill while claiming the payment.

2 Payment Clause: The contractor has to pay the minimum daily wages to the skilled/semi skilled/unskilled labourers engaged in their work as has been specified by the Government, latest rate and displayed in the wages notice Board at factory.

3 Safety Clause: Annexure-B of MES Safety Code, IAFW 2249 must be observed in general. Work Permit shall be obtained for overhead/hazardous work condition. All the safety precautions/measures have to be taken by the contractor. However, a few points of safety measures to be followed for working at height and on the roof are mentioned hereby :

Use of safety belt and helmet of proper quality is mandatory for all workers working on roofs at height of above 5.00 meters and also in the underground areas. Safety belt with life line should be properly tied at some firm support.

(i) In case any difficulty is faced in proper fastening and securing of safety belt, a safety net may be provided below the workspot so that in case of accident fall, there might not be any fatality.

(ii) A crawling ladder or roof walker must be used for movement on Asbestos/CGI roofing.

(iii) Work Permit system should be followed in proper spirit. Contractors shall start the work after obtaining the Work Permit, wherever applicable. Contractor's supervisor and site-in-charge should brief on safety precautions to be observed by the workmen before start of the work. The workers should be clearly explained about the danger of standing or sitting on an apparently stout & new and neat looking asbestos/CGI sheet which is intrinsically weak.

(iv) The contractor shall clear the site after completion of work.

(v) The contractor must employ the labour force duly insured against life risk.

(vi) The contractors shall ensure compliance of all applicable statutory rules and regulations.

4 DEVIATION CLAUSE:

(i) $\pm 25\%$ of value of individual item other than freakishly rate quoted items.

(ii) For freakishly higher or lower rate quoted items it shall be $\pm 5\%$.

(iii) 20% of Work Order value (Contract value maximum Rs.10 lakhs)

10% of Work Order value (Contract value exceeding Rs.10 lakhs)



(K. TULASI RAO)

GENERAL MANAGER / CEO & QA

For CHIEF GENERAL MANAGER / HVF

For And On Behalf Of THE PRESIDENT OF INDIA