



भारतीय अन्तर्देशीय जलमार्ग प्राधिकरण

(पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार)

INLAND WATERWAYS AUTHORITY OF INDIA

(Ministry of Ports, Shipping and Waterways, Govt. of India)

क्षेत्रीय कार्यालय : पी-७८, गार्डनरीच रोड, कोलकाता - ७०० ०४३ (प० ब०)

REGIONAL OFFICE : P-78, Garden Reach Road, Kolkata - 700 043 (W.B.)

दूरभाष : 2439 0393 / 5577 / 6055, फैक्स : 2439 5570



SAGARMALA
PORT-LED PROSPERITY

E-mail : iwaical@yahoo.com
dirkol.iwai@nic.in

IWAI/KOL/MM/92/VOL-II/20-21/ 767

28.08.2024

To,

M/s Sabita Udyog

10/7, Kasundia 2nd bye lane,

Howrah.

Sub: Award of Work for "Annual/Afloat repair of IWAI vessel AB Dhawalgiri for the year 2024-25"-reg.

Ref: 1) E-procurement tender id. 2024_IWAI_815847_4
2) E-procurement bidder bid no- 3061856

Sir,

Kindly refer to above reference for Annual/Afloat repair of IWAI vessel AB Dhawalgiri for the year 2024-25, we are pleased to place a work order to you at a total cost of Rs. 05,20,695.00 /- (Five Lakh Twenty Thousand Six Hundred Ninety Five Only) wherein Labour charges Rs. 03,10,695/- Excluding GST and cost of spares Rs 2,10,000/- (tentative) and excluding of GST as applicable, as per enclosed bill of quantity in accordance with the tender terms & conditions. Cost of spares on actual + 10 % basis to be paid subject to spares fitted and supplied within estimated cost. Incremental spare cost to be approved by Competent Authority.

The total cost of work shall be Rs. 05,20,695/- excluding of GST as applicable, as per item wise rate mentioned in the enclosed BOQ subject to variation of quantity of work actually executed and certified by the EIC. The above-mentioned total cost is inclusive of taxes, duties and other levies etc., excluding GST as specified in tender. The payment shall be made on submission of bill after certification of the E.I.C for the actual quantity executed. The work shall be completed within 30 (Thirty) days from the date of placement of vessel in the yard/received of vessel. As per tender Technical and Special Conditions no.11 all statutory survey by surveyor of IWT, State Government shall be arranged by the contractor on behalf of the Authority and survey fees, third-party insurance and any other endorsement/documentation as claimed by the IWT surveyor will only be reimbursed by Authority.

As per tender clause no. 18 under technical specification and special conditions, the inspection of vessels during execution of repairing of IWAI vessels shall be carried out by IRS and arranged by the contractor on behalf of the Authority. The payment of IRS visits, during repairing of the vessels at yard/repair place shall be paid by the repairer. However, this amount shall be re-imbursed to the repairer on submission of proof of bill raised by the IRS and payment made by the repairer.

o/c

Cont. page-2

Head Office : Jalmarg Bhawan, A-13, Sector-1, NOIDA - 201 301 (U.P.)

Phone : +91-120-2544036, 2543972, 2527667, 2448101, Fax : +91-120-244009, 2544041, 2521764, 2543973

Website : www.iwai.gov.in / www.iwai.nic.in Email : iwainoi@nic.in

You are requested to deposit an amount of Rs. 26,035/- (Rupees Twenty Six Thousand Thirty Five Only) i.e. the 5% of contract value of the work order value and in addition also to deposit an amount of Rs. 99,600/- (Rupees Ninety Nine Thousand Six Hundred Only) i.e., the 20% as per clause no. 3(3.2a) bid price offered the selected bidder is lower than 10% but upto 20% either in the form of RTGS/ NEFT through scheduled / nationalized banks in the favor of "Inland Waterways Authority of India Fund" payable at Kolkata (or) in the form of irrevocable bank guarantee of any scheduled bank towards performance Guarantee within 10 days of the issue of this work order as per terms & conditions of the tender document. In addition to the above, a security deposit equivalent to 5% of the contract value (i.e. Rs. 26,035/- (Rupees Twenty Six Thousand Thirty Five Only) will be deducted from RA bills as per Clause 4 of the General Conditions of Contract.

In case of delay in completion of the repair work of the vessel and delivery thereafter, liquidated damages as per the Clause no. 35 will be applicable @ 1.5% per month of delay for delay of work to be computed on per day basis subject to a maximum 10% on the total value of the contract.

A list of the additional work which is considered necessary as per recommendation of the EIC and or those which are directed during the course of repairs for satisfactory completion of repairs and subsequent commissioning of vessel should be prepared jointly by EIC and contractor. Thereafter, contractor shall furnish quotation for those items of work for which rate would be derived from the agreement or afresh as the case may be in force along with extra time required for completion of all the additional work. The rate for the additional work shall be approved as provided in clause No. 12 of Technical & Special Conditions of contract and clause no. 16 of the General Condition of contract for execution.

The work executed all items of work attended and spare etc. supplied by the contractor shall have Guarantee period of minimum 12 months or manufacturer warrantee whichever is more from the date of delivery of the vessel after repair.


The work plan to be submitted within 7 days of issue of work order.

An agreement shall be entered between this Authority and Firm in the approved format within 12 days from the date of receipt of work order. You are requested to attend this office with 2 non-Judicial stamp papers of Rs 100/- each for signing of contract agreement and integrity.

It is requested to convey your acceptance for this work order by signing the copy of this letter immediately.

Enc.: As Stated,

Yours faithfully,


(R.K. Singh)
DIRECTOR

Copy to:

1. Chief Engineer (Tech), IWA, Noida.
2. Sr. A.O, IWA, Kolkata

BOQ FOR ANNUAL AFLOAT REPAIR OF AB DHAWALGIRI FOR THE YEAR 2024-25

L - 26.50 M x B - 9.00 M X D - 2.2 M

SL. NO	DESCRIPTION OF WORK	UNIT	QTY	RATE(₹)	AMOUNT(₹)
1.00	Complete Overhauling of Harbour genset engine (Make Kirloskar, model no. 3R1040, power 42 BHP) is to be done as lube oil leakage observed from exhaust manifold, servicing/calibration/renewal of liner, piston, rings, valves, heads, fuel pump, injectors, sea water and fresh water pump, crank thrust clearance, self starter, dianamo and cleaning of all coolers etc. along with renewal of spares e.g. meters, gauges, V-belts, hose pipes etc. servicing of self starter, dynamo, checking/rectification of all safety systems, cleaning of heat exchanger & coolers as required as per direction fo EIC/ surveyor.				
1.02	Labour charges	Comp. Job	2	21,787.50	43,575.00
1.02	Cost of spares(actual + 10%)				
2.00	Genset alernator (Make-Crompton Greaves), 25KVA, 34A, 415V, Insulation Class ST&HT-F, EX-B are to be serviced, heat varnished and megger testing etc with renewal of spare parts to make operational as required as per direction fo EIC/ Surveyor.				
2.01	Labour charges	Comp. Job	1	24,750.00	24,750.00
2.02	Cost of spares(actual + 10%)				
3.00	Entire electrical/electronics, AC/DC line, panel of engine room, navigation lights, accomodateion (lights, fans etc), engine room, emergency lights, deck, general alarm bell, D.C. horn, switch boards, sensor, lighting, invertor, battery chargers, serarch light, fire alarm, horn, bed light, table light, light cover, chimney, lightings, Solar panel system & other fittings etc. are to be checked and rectify the defects as required with renewal of required materials. Line & wiring to be checked and serviced/repared. Renewal of required materials as per direction of EIC/ Surveyor.				
3.01	Labour charges	Comp. Job	1	52,500.00	52,500.00
3.02	Cost of spares(actual + 10%)				

4.00	The entire ship side shell plate from LWL to main deck, deck plate, bathroom, galley inside, engine room and outside along with other fitment etc, are to be proper cleaned, scrapped, wire brushed, chipped and painted by 3 coats of existing colour marine paint. (1 coat zinc chromate primer, followed by two coats of existing colour of marine paints). All pipe lines should be coloured as per marine colour code. After it name of vessel, dept. and logo to be made by fluorescent sticker as required as per direction of EIC/ Surveyor.	Sqm	800	252.00	2,01,600.00
5.00	Polyvinyl sheet is broken and damage at various location inside the vessel. The same ot be renewed with reputed polyvinyl sheet as required as per direction of IWT Surveyor/EIC.	Sqm	30	1,144.00	34,320.00
6.00	Replacement of existing metal tank with installation of one PVC fresh water tank and one PVC sea water tank of capacity 1000 Liters each with modification of foundation, pipeline etc.				
6.01	Labour charges	Comp. Job	1	21,000.00	21,000.00
6.01	Cost of spares(actual + 10%)				
	LABOUR COST(Excluding GST)				3,77,745.00
		LESS	17.75%		67,049.74
	Sub Total (in Rs.)				3,10,695.00
	Cost of Tantative SPARES (in Rs.)				2,10,000.00
	GRAND TOTAL(Excluding GST) (in Rs.)				5,20,695.00

Rupees Five Lakh Twenty Thousand Six Hundred NinetyFive Only
(GST extra as applicable)