



भारतीय अन्तर्देशीय जलमार्ग प्राधिकरण

(पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार)

INLAND WATERWAYS AUTHORITY OF INDIA

(Ministry of Ports, Shipping and Waterways, Govt. of India)

क्षेत्रीय कार्यालय : पी-७८, गार्डनरीच रोड, कोलकाता - ७०० ०४३ (प० ब०)

REGIONAL OFFICE : P-78, Garden Reach Road, Kolkata - 700 043 (W.B.)

दूरभाष : 2439 0393 / 5577 / 6055, फैक्स : 2439 5570



SAGARMALA
PORT-LED PROSPERITY

E-mail : iwaical@yahoo.com
dirkol.iwai@nic.in

IWAI/Kol/MM/92/2022-23/ AB Devprayag

13.01.2025

To,

M/s. Ghosh Enterprise,
21/2, Baje Shibpur,
2nd bye lane, Shibpur,
Howrah - 711102

Sub: Award of Work for "Dry Dock repair of AB Devprayag FOR THE YEAR 2024-25"-reg.

Ref: 1) E-procurement tender id. 2024_IWAI_829207_2
2) E-procurement bidder bid no- 3107828

Sir,

Kindly refer to e-tender no. 2024_IWAI_829207_2 for Dry Dock repair of IWAI vessel AB Devprayag FOR THE YEAR 2024-25, we are pleased to place a work order to M/s. Ghosh Enterprise at a total cost of Rs. 12,31,328.00 /- (Rupees Twelve Lakh Thirty One Thousand Three Hundred Twenty Eight Only) Excluding GST and Cost of spares on actual + 10 % basis to be paid subject to spares fitted and supplied.

The total cost of work shall be Rs.12,31,328.00 /- excluding of GST as applicable, as per item wise rate mentioned in the enclosed BOQ subject to variation of quantity of work actually executed and certified by the EIC. The above-mentioned total cost is inclusive of taxes, duties and other levies etc., excluding GST as specified in tender. The payment shall be made on submission of bill after certification of the E.I.C for the actual quantity executed. The work shall be completed within 60 (Sixty) days from the date of placement of vessel in the yard. As per tender Technical and Special Conditions no.11 all statutory survey by surveyor of IWT, State Government shall be arranged by the contractor on behalf of the Authority and survey fees, third-party insurance and any other endorsement/documentation as claimed by the IWT surveyor will only be reimbursed by Authority.

As per tender clause no. 18 under technical specification and special conditions, the inspection of vessels during execution of repairing of IWAI vessels shall be carried out by IRS and arranged by the contractor on behalf of the Authority. The payment of IRS visits, plate stamping and testing during repairing of the vessels at yard shall be paid by the repairer. However, this amount shall be re-imbursed to the repairer on submission of proof of bill raised by the IRS and payment made by the repairer.

Cont. to page 2

You are requested to deposit an amount Rs. 61,567.00/- (Rupees Sixty-One Thousand Five Hundred Sixty-Seven Only) i.e., the 5% of the contract value of the work order either in the form of RTGS/ NEFT through scheduled / nationalized banks in the favor of "Inland Waterways Authority of India Fund" payable at Kolkata (or) in the form of irrevocable bank guarantee of any scheduled bank towards performance Guarantee within 10 days of the issue of this work order as per terms & conditions of the tender document. In addition to the above, a security deposit equivalent to 5% of the contract value (i.e. Rs. 61,567.00/- (Rupees Sixty-One Thousand Five Hundred Sixty-Seven Only) will be deducted from RA bills as per Clause 4 of the General Conditions of Contract.

As per tender clause no. 35 LD (liquidity damages) will be imposed accordingly.

A list of the additional work which is considered necessary as per recommendation of the EIC and or those which are directed during the course of repairs for satisfactory completion of repairs and subsequent commissioning of vessel should be prepared jointly by EIC and contractor. Thereafter, contractor shall furnish quotation for those items of work for which rate would be derived from the agreement or afresh as the case may be in force along with extra time required for completion of all the additional work. The rate for the additional work shall be approved as provided in clause No. 12 of Technical & Special Conditions of contract and clause no. 16 of the General Condition of contract for execution.

The work executed all items of work attended and spare etc. supplied by the contractor shall have Guarantee period of minimum 12 months or manufacturer warrantee whichever is more from the date of delivery of the vessel after repair.

The work plan to be submitted within 7 days of issue of work order.

An agreement shall be entered between this Authority and Firm in the approved format within 12 days from the date of receipt of work order. You are requested to attend this office with 2 non-Judicial stamp papers of Rs 100/- each for signing of contract agreement and integrity.


It is requested to convey your acceptance for this work order by signing the copy of this letter immediately.

Enc.: As Stated,

Copy to: -

1. Chief Engineer (Tech), IWAI, Noida.
2. A.O, IWAI, Kolkata

Yours faithfully,


(R.K. Singh)
DIRECTOR



BOQ FOR DRY DOCK REPAIR OF AB DEVPRAYAG FOR THE YEAR 2024-25

(Length- 26.5 M,Breadth-9.00 M,Depth- 2.2M)

SL. NO	DESCRIPTION OF WORK	UNIT	QTY	RATE(₹)	AMOUNT(₹)
1.0	Beaching , blocking, unblocking including dock hire / mooring charges for repair of vessel as required as per direction of EIC/Surveyor.	Comp. Job	1	1,65,150.00	1,65,150.00
2.0	Ultrasonic testing to be done of hull, deck plate & LWL ship side plate, etc for checking of thickness as per direction of Surveyor/EIC.	Spot	300	66.00	19,800.00
3.0	cropping & renewal of under water & deck plate to be done etc as required after ultrasonic testing & its report and aslo anchor windless hand operation handle missing, guard rails found damaged wasted in various locations throughout vessel, vessel name plate found broken same to be fabricated /repaired as required as per direction of Surveyor/EIC.	Ton	1	1,32,048.00	1,32,048.00
4.0	All Sea chest, Mud Box, Stainer, sea water valves to be checked, repaired, cleaned and painted as required as per direction of Surveyor/EIC.	Comp. Job	1	16,500.00	16,500.00
5.0	Engine room pipin system (F.O, Bilge, fresh water & sea main) including vlves & fittings found leakage at various locations same to be serviced and all Sea chest valves, OBD valves, sea water/ Bilge/GS line valves to be overhauled pressure tested and pipe line to be operationally tested as required as per direction of EIC / surveyor.	Comp. Job	1	71,500.00	71,500.00
6.0	Under water hull plate & side plate to be scraped & chipped & wire brushed from keel to LWL to remove fouling and old paints. Painting of hull plate & side plate to be done by three coat as per painting scheme from keel to water level as per direction of Surveyor/ EIC.	sq-m	400	264.00	1,05,600.00

7.0	The entire ship from LWL to main deck, deck plate, bathroom, galley anchors, anchor rake, engine room, store rooms, fresh water tanks 2 nos. (15 KL) etc, are to be proper cleaned, scrapped, wire brushed, chipped and painted by 3 coats of existing colour marine paint. (1 coat zinc chromate primer, followed by two coats of existing colour of marine paints). All pipe lines should be coloured as per marine colour code. After it name of vessel, dept. logo, all door's lock opening and closing indication mark to be made by fluorescent sticker as required as per direction of EIC/ Surveyor.	Sqm	1550	253.00	3,92,150.00
8.0	Crew accomodation 10 nos. fan found non functional, emergency light throughout the vessel found non-fuctional same to be repaired / rectified and all other entire electrical/electronics, AC/DC line with all equipments to be checked and serviced/ repaired. Renewal of required materials as per direction of EIC/ Surveyor.				
8.1	Labour charges	Comp. Job	1	55,020.00	55,020.00
8.2	Cost of spares (actual + 10%)				
9.0	Crew accomodation all bathroom tap, valve, flushing found non fuctional same to be rectified/ repaired and all attach bathroom's other accessories i.e taps, showers, comode top & cover, flush tank, door & locker locks, valves, flushing tank pipe, complete wash basin, mirror, jet, exhaust window, towell rail etc and fitments etc to be checked and repaired/renewed as required and ensure leakage proof of water as required as per direction of EIC/Surveyor.				
9.1	Labour charges	Comp. Job	1	28,750.00	28,750.00
9.2	Cost of spares (actual + 10%)				
10.0	Crew accomodation ventilation mushroom head flap handle 4 nos. found jammed same to be make operational and All blowers/ ventilation fans/ exhaust fans to be serviced including repair & renewal of spares as required as per direction of EIC/ Surveyor.				
10.1	Labour charges	Comp. Job	1	24,750.00	24,750.00
10.2	Cost of spares (actual + 10%)				



11.0	Engine room door and engine room ventilation hatch (P & S) and all hatch weather tight rubber gaskets found wasted/ deteriorated and hardened, all void tank manhole rubber packing found damaged/ missing/ hardened same to be renewed and all others Manhole covers with damaged rubber packing/beading, Nuts , Bolts & Studs same to be repaired/ Renewed By good quality of Rubber beading & SS fittings respectively				
11.1	Labour charges	Comp. Job	1	17,600.00	17,600.00
11.2	Cost of spares (actual + 10 % basis)				
12.0	Engine room found with oily bilges / dirty water / soft mud and Cleaning and painting of bilge to be done with one coat primer and 2 coats of marine quality paints as per direction of EIC/Surveyor.	Comp. Job	1	93,500.00	93,500.00
13.0	Crew accommodation window 2 nos. glass broken, 1 no. scuttle glass broken same to be renewed /repaired as required as per direction of EIC/ Surveyor.				
13.1	Labour charges	Comp. Job	1	6,000.00	6,000.00
13.2	Cost of spares (actual + 10 % basis)				
14.0	Emergency fire pump connecting hose to be made operational and Portable emergency fire pump found non operational and same to be made operational with engine and others as required as per direction of EIC/ Surveyor.				
14.1	Labour charges	Comp. Job	1	7,700.00	7,700.00
14.2	Cost of spares(actual + 10%)				
15.0	D/G (S) radiator water tank found water leakage same to be rectified/ repaired and Running routine maintenance has to be done of (S) side Genset engine (Make: Kirloskar oil engine, Model: 3R1040 ,) through renewal of all filters, coolants, lube oil, V- belts and checking and repairing of tapped clearance . sea water & fresh water pumps, self starter, Dynamo, electrical safety system etc. cleaning of all coolers & heat exchanger as required as per the direction of Surveyor/EIC.				
15.1	Labour charges	Comp. Job	1	21,788.00	21,788.00
15.2	Cost of spares(actual + 10%)				



16.0	D/G (P) radiator cap found missing, local panel self start found non functional same to rectified/ repaired and Running routine maintenance has to be done of (P) side Genset engine (Make: Kirloskar oil engine, Model: 3R1040 ,) through renewal of all filters, coolants, lube oil, V- belts and checking and repairing of tapped clearance , sea water & fresh water pumps, self starter, Dynamo, electrical safety system etc. cleaning of all coolers & heat exchanger as required as per the direction of Surveyor/EIC.				
16.1	Labour charges	Comp. Job	1	21,788.00	21,788.00
16.2	Cost of spares(actual + 10%)				
17.0	Servicing of all quick closing valves and make operational with levelling indication mark of all valves as required as per direction of Surveyor /EIC.	Comp. Job	1	10,017.00	10,017.00
18.0	Fresh water tank (P) hand pump handle found broken, F.O pump, Fresh water pump, bilge/fire/GS pump etc. to be repaired/serviced and all other pump & motors are to be overhauled, repaired varnished to be done as required as per direction of EIC /Surveyor.				
18.1	Labour charges	Comp. Job	1	38,500.00	38,500.00
18.2	Cost of spares(actual + 10%)				
19.0	Fire hydrant valve (3 nos.) connection with o ring found damaged/ defective and all Fire hydrant valves, nozzles, fire hose box, couplings etc. to be serviced/ renewed and have to make leak free operation as required as per direction of EIC / Surveyor.				
19.1	Labour charges	Comp. Job	1	4,400.00	4,400.00
19.2	Cost of spares (actual + 10%)				
	LABOUR COST(Excluding GST)				12,32,561.00
	LESS			0.10%	1,232.56
	GRAND TOTAL(Excluding GST) (in Rs.)				12,31,328.00

Rupees Twelve Lakh ThirtyOne Thousand Three Hundred TwentyEight Only

***Cost of spares on (actual + 10%)**

***(GST extra as applicable)**


DIRECTOR

