

LETTER OF ACCEPTANCE/LETTER OF AWARD

To

M/s Satish Aggarwal & Co,
H No. 592, Basant Avenue,
Amritsar.
satishaggarwal99@yahoo.com

No. 1364

Dated: - 15.03.2024

Subject: - SHORT-TERM MAINTENANCE OF TARN TARAN KAPURTHALA ROAD (NH-703AA) AT KM 0.00 TO 50.25 IN DISTT. TARN TARAN AND KAPURTHALA.

This is to notify you that your bid date: 07.03.2024 for the work amounting to Rs **2,61,87,660.52/- (Rs Two Crore Sixty One Lacs Eighty Seven Thousand Six Hundred Sixty and Fifty Two Paise Only)** is here by accepted by Chief Engineer (NH), Punjab PWD B&R, Patiala Memo No: 910/NH dated: 15.03.2024 with a time limit of (12) ~~Two~~ **Five** months coupled with the terms and conditions exhibited in the approved DNIT at the following rates:-

Sr. No.	Description of Work / Item(s)	Units	Rates (excluding GST)
0	Bill No. 1 Road Maintenance		
1	Dismantling of flexible pavements and disposal of dismantled materials up to a lead of 1000 metres, stacking serviceable and unserviceable materials separately		
1.01	Bituminous courses	Cum	436.11
1.02	Granular Course (Av. Depth)	Cum	66.78
2	Construction of dry lean cement concrete Sub- base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing.	Cum	2261.83

For Satish Aggarwal & Co.

Sg-1/2

Partner

3	Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement @ 310 kg per cum, coarse and fine aggregate conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing	Cum	4149.34
4	Providing and applying tack coat with bitumen emulsion (R.S) using emulsion pressure distributor at the rate of 0.25 kg per sqm on the prepared bituminous surface treated with prime coat after cleaning the surface complete as per technical clauses 503 of MORTH&H specification.	Sqm	7.74
5	Providing and laying dense graded bituminous macadam with higher capacity batch type HMP using crushed aggregates of specified grading, premixed with VG-40 bituminous binder @ 4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 505 complete in all respects.	Cum	6936.86
6	Providing and applying tack coat with bitumen emulsion (R.S) using emulsion pressure distributor at the rate of 0.25 kg per sqm on the prepared bituminous surface treated with prime coat after cleaning the surface complete as per technical clauses 503 of MORTH&H specification.	Sqm	7.74
7	Providing and laying bituminous concrete with higher capacity batch type hot mix plant using crushed aggregates of specified grading, premixed with VG-40 bituminous binder @ 5.4 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects	Cum	8202.91
8	BILLNO.2: ROAD PROPERTY MAINTENANCE		
9	Not Applicable		
10	BILLNO.3: PAVEMENT REPAIRS		
11	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm with VG – 40 Grade Bitumen . Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with hot bituminous material as per clause 504, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2.	Per Month	123026.41

For Satish Aggarwal & Co.


 Partner

Note:- (i) GST applicable @18% extra shall be payable to the contractor on amount against the work executed.

The work will be executed as per approved DNIT and also subject to the financial, technical administrative & legal regularities and strict compliance of the specifications as included in the tender and execution of the work as per MORT&H specifications & approved DNIT, estimate including ensuring of quality throughout the execution of the work.

You are hereby requested to furnish the **Additional Performance security for unbalance items as per DNIT Clause 28.2 of ITB for an amount of Rs 5,72,265/- & Performance Security in form detailed in Para 34.1 of ITB for an amount of Rs 7,85,630/-** within 21 days of the receipt of this letter of acceptance valid upto 28 days from the date of expiry of defects liability period of the conditions of contract.

DA/X


Executive Engineer,
National Highway Division,
PWD (B&R) Branch; Amritsar.

Endst No. 1365-68

Dated: 15.03.2024


Copy of above forwarded to following for information & necessary action:-

- 1) Superintending Engineer, National Highway Circle, Amritsar w.r.t. his Endst No: 3094 dated: 15.03.2024.
- 2) Sub Divisional Engineer, National Highway Sub Division No:3, Amritsar.
- 3) Divisional Accounts Officer, Amritsar.
- 4) Agreement.

DA/X


Executive Engineer,
National Highway Division,
PWD (B&R) Branch; Amritsar

For Satish Aggarwal & Co.


Partner
Signature Not Verified

Digitally signed by Simranjeet Singh Gill
Date: 2026.01.08 14:16:03 IST
Location: eProcure-EPROC