



न्यूक्लियर पावर कॉर्पोरेशन ऑफ इंडिया लिमिटेड

Nuclear Power Corporation of India Limited

(भारत सरकार का उद्यम Government of India Enterprise)

कैगा स्थल KAIGA SITE

CENTRALISED TENDER CELL केंद्रीय नीविदा प्रकोष्ठ

Corporate Identification No. U40104MH1987GOI149458

Phone: +91 8382 264002, Fax: +91 8382 264025, sdileep@npcil.co.in Website: www.npcil.nic.in

Head, CTC, NPCIL, Kaiga Site, Kaiga-581 400, Tq: Karwar, Dist: Uttara Kannada, State: Karnataka



Ref: NPCIL/KGS/CTC/CPMP-019/WO/2024/1004

Date: 27-09-2024

To

M/s Abhilash N. Vasavan,
KPC Colony, Kadra,
Karnataka
Pin: 581 396

Cell No.: 9448405352

e-mail id: nvasavanabhilash@gmail.com

Work Order No.	:	700803
S.L. Code	:	A0121700803
Account Code	:	14211
Charge Code	:	6253
MSME	:	NA

WORK ORDER NO.: 2024_NPCIL_192300_2/WO

Name of work: "Providing brick wall partition to the enclosed area at 3rd floor of O&M building at Kaiga Generating Station 3&4, Kaiga."

- Ref: 1) Tender No.: NPCIL/KGS/CTC/C&SM-3&4/CPMP/2024/019
2) Last date of submission of tender is 16.07.2024
3) Negotiation MOM No.: NPCIL/KGS/CTC/2024/MOM/355, dated: 22.08.2024

Dear Sir,

1) BID ACCEPTANCE:

- 1.1 This is to inform you that, the bid submitted by you subsequently modified as referred above (Ref.3) has been accepted for and on behalf of NPCIL, for the items of work shown in the enclosed schedule of quantities and rates for a total value of ₹. **50,05,908/-** (Rupees Fifty Lakhs, Five thousand nine hundred and eight only) inclusive of all applicable taxes and including 18% GST.

2) QUANTITIES & RATES

- 2.1 You may note that the rates are for complete items of work including supply of all materials (unless otherwise specified), consumables, all temporary arrangements, all labours, all prevailing duties, taxes including GST.
- 2.2 Please note that, you have agreed [vide MOM No.: NPCIL/KGS/CTC/2024/MOM/355, dated: 22.08.2024] to offer an overall rebate of 5.78% . AHR Items: Nil & ALR Item: Nil
- 2.3 Payment to the manpower deployed for this work shall be made as specified in the tender.

[Signature]
23/09/24

3) **CONTRACT PRICE ADJUSTMENT:**

Escalation of payment shall be applicable as per **Sl. No.: 21** of Schedule – A.

4) **EXECUTION OF WORK:**

The work shall be carried out strictly in accordance with the terms, conditions, specifications and drawings stipulated in the tender and also in best work man like manner. You shall employ and maintain qualified engineers / supervisors in the job at all times. You shall also bring to the site and employ such machinery and equipment and other materials as are necessary for the satisfactory completion of this work.

5) **CONTRACT PERIOD:**

5.1 **Schedule completion Period:**

The work shall be completed in all respect within **365 calendar days (including monsoon period)** from the date of commencement. The date of commencement of work will be reckoned within **Seven (07) days** from the **date of issue of Work Order**. The time shall be essence of the contract and the work shall be completed as per approved program of work.

5.2 **Defect Liability Period:**

The Defect Liability Period is 12 Months - **Sl. No.: 18** of Schedule - A.

6) **AUTHORISED OFFICIALS:**

6.1 You are requested to inform the name of the authorized representative who will deal with all matter relating to the contract and the Power of Attorney in his favour duly executed on stamped paper of an appropriate value shall be furnished.

6.2 During the execution of the contract and until completion certificate is issued you will be fully liable to compensate all concerned for any loss, damage or destruction of work, structure, property etc. including third party risk arising due to causes attributable to you which will be decided by the engineer-in-charge whose decision in this regard will be final.

7) **INSURANCE:**

You are required to take out following insurance policies applicable to this contract at your cost immediately after receipt of this work order from the date of commencement of work to the **end of the Defect Liability Period** for the whole contract value inclusive of GST.

- a) **CAR policy for the whole contract value** – Applicable as per Schedule A
- b) **The Insurance amount should cover THIRD PARTY LIABILITY to 10% of Contract value subjected to maximum of Rs. 50.00 Lakhs.** – Applicable as per Schedule A
- c) **Employees State Insurances for contract workers.** – Applicable as per Schedule A
- d) **Wherever ESI Act not covers the contract worker based on monthly wage / salary, contractor shall obtain the employees / Workmen compensation for such workers.**

You may note that all insurance policies taken under 7 (a), (b) & (d) are to be in Joint names of Corporation and the contractor and specific to work by mentioning the name of work and Work Order Number in the policies and all Policies in Original should be submitted to the


12/10/14

engineer-in-charge before the date of commencement of work. Copy of ESI registration certificate shall be submitted to **engineer-in-charge of work**, before commencement of the work.

8) TAXES & DUTIES:

For tax related compliance (including TDS) refer Supplement/ Amendment to GCC (Additional document pg no.:291/346).

9) ENGINEER-IN-CHARGE:

Shri Rahul Mundotiya, SO/D, C&SM-3&4, will be the **Engineer-in-charge** of this work. You may make necessary arrangements for commencing the work immediately in consultation with Engineer-in-Charge.

10) SECURITY DEPOSIT:

Security Deposit shall be @ **10 %** of the contract value will be ₹. **5,00,591/-** (including GST), (Rupees Five Lakhs, Five hundred and ninety-one only)

10.1 Performance Guarantee: (This clause revised on 09.12.2022)

As per **Clause No.: 4.2.3** of GCC you shall submit a performance guarantee for ₹. **2,50,295/-** (50% of Security Deposit) to the Corporation within 30 days after issue of work order. It should cover the contract period plus Defects Liability period. In case, the Bank Guarantee need to be submitted as per the format given in tender document.

10.2 Retention Money:

As per **Clause No.: 4.2.5** of GCC, the remaining amount (50% of Security Deposit) of Security Deposit of ₹. **2,50,296/-** will be deducted as a Retention money from the RA bill / final bill at the rate of 6% of each bill amount. Security Deposit amount will not bear any interest.

10.3 Refund of Security Deposit:

Refund of Security deposit will be regularized as per **General Condition of Contract**.

11) APPLICABLE LAWS & ACTS:

11.1 You shall comply with various provisions of the contract labour (Regulations & Abolition) Act 1970 and rules framed thereafter from time to time. In case, the Contract Labour Act does not apply to your organization you should intimate the Engineer-in-Charge of this work accordingly before commencing the work. Further you shall also comply with the provisions of other laws such as Workmen's Compensation Act 1923, Minimum Wages Act 1948, E.P.F. Act, ESI Act, Gratuity Act and other labor laws as applicable to your organization. In case, NPCIL is required to incur any expenses as principal employer under the provisions of the various laws, NPC shall be entitled to recover the same from you / your bills.

11.2 You have to give request for the issue of Principal Employer's Certificate for obtaining labour license based on the maximum number of workmen you proposed to employ for this work. You may please note that within 14 days from the date of issue of this work order, you will have to apply for a labour license to the Asstt. Labour Commissioner, of the area, for the maximum number of workers you had indicated to engage on the work.


28/9/24

11.3 The contractor shall make the payment to all its labours on or before 7th of succeeding month and as per special condition of contract.

11.4 Labour License (if applicable),

12) PAYMENT TERMS:

12.1 The progressive monthly payment for the work completed and accepted by Engineer-in-charge shall be made through Running Account bills once in a month on submission of measurement / bill by the contractor. Submission of bills on monthly basis shall be ensured by the contractor.

12.2 Payment of bills will be processed on submission of GST invoice duly supported with Annexure-8 (Declaration form for GST).

12.3 In addition to above, first Running Account bill will be processed only on submission of Intimation from Tender Section regarding Work order acceptance & agreement signed by the contractor, Insurance Policies, copy of PAN, GST Registration Certificate, cancelled cheque for bank account details etc., to the Engineer-in-charge.

13) PENALTY & LIQUIDATED DAMAGES CLAUSE:

Penalties imposed by Engineer-in-charge for non-compliance or violation of certain conditions of contract, Liquidated Damages for delay in execution and any other penalty in the nature of fine imposed during execution of work will be recovered along with applicable GST there on from bills of the contractor before release of payment.

14) SECURITY, SAFETY & HOUSEKEEPING:

You may have to comply all Security, Safety rules & regulations, Environmental measure as defined in the Contract.

You shall submit the Police Verification Certificate [PVC] for you, your staff and labour; as a pre-condition to issue of RFID cards / Gate Passes [if applicable].

15) TRANSPORT & ACCOMMODATION:

Contractor shall make his own arrangement for Accommodation & Transportation of manpower deployed for this work.

16) AGREEMENT:

A formal agreement incorporating all the terms and conditions agreed between NPCIL and M/s Abhilash N. Vasavan, will be executed within the period from the date of issue of this work order. Till a **formal agreement** is executed the original tender together with letters under reference and this work order shall form the binding contract between NPCIL and M/s Abhilash N. Vasavan.

Kindly acknowledge receipt of this Work Order.

Thanking you,

Yours faithfully
For and on behalf of NPCIL

अनुरक्षण अधीक्षक, (केजीएस # 3 व 4)
Maintenance Superintendent, (KGS # 3&4)

NUCLEAR POWER CORPORATION OF INDIA LIMITED

(A Government of India Enterprise)

Kaiga Generating Station

Schedule Of Quantities And Rates



Print Date: 23-Sep-2024

Name of Work: Providing brick wall partition to the enclosed area at 3rd floor of O&M building at Kaiga Generating Station 3&4, Kaiga. WO / SOQR Number : 700803								Agency Name : M/s Abhilash N. Vasavan	
Co									
Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹		
Schedule : SMU-ACivilworks									
1	Dismantling, breaking, chiseling, removing PCC / IPS, RCC with suitable tools including collecting, shifting, loading, carriage, and disposing un wanted debris to the lead of 3000 mtrs. from the place of work including providig, fixing & removing staging, platform wherever, required, complete all as per standard technical specifications and as directed by the Engineer -in-charge at all locations & at all height.	CuM	5	1150	-	-	5,750.00		
		Rupees One Thousand One Hundreds Fifty Only							
2	Providing & Constructing Burnt Brick Masonry of 230 mm thick in CM 1:5 using well Burnt Bricks of standard size & compressive strength should not be less than 35Kg/cm2 for Super Structure, plinth and all other Miscellaneous Masonry Works, including simultaneous flush pointing, curing, preparation of base properly, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification and as directed by Engineer-in-charge at all locations and at all lift & height.	CuM	118	9200	-	-	10,85,600.00		
		Rupees Nine Thousand Two Hundreds Only							
3	Providing and laying Internal Cement Plaster 15 mm thick in CM 1:5 to the masonry & concrete surfaces etc., rubbed perfectly so as to obtain smooth & even finish including preparation of base by racking out all the masonry joints & close hacking the concrete surfaces for proper bonding, curing, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification and as directed by Engineer-in-charge at all locations and at all lift & height.	SqM	1460	450	-	-	6,57,000.00		
		Rupees Four Hundreds Fifty Only							
4	Providing and applying One Coat of Interior Grade Primer [of superior 1st quality & of standard make] and Two Coats of Interior Grade Acrylic Plastic Emulsion Paint [superior 1st quality & of standard make], of shade /colour [as per site requirement & as selected by Engineer-In-Charge], over the interior surface of newly plastered / concrete or masonry wall, RCC members such as columns; beams & other concrete surfaces, including providing & applying Two Coats of Acrylic Putty, [of superior 1st quality & of standard make] to the entire surface, preparation of surfaces by sand papering properly before application of putty; primer & paint. Putty, Primer & Paint shall be confirming to relevant BIS specification of latest edition, providing; fixing & removing necessary staging / platform / scaffolding / ladder, collecting & disposing the generated & construction waste, up to a lead of 2 - 3 kms. from the place of work & cleaning the work area, etc. complete all as per standard & manufacturers technical specification, drawing and as directed by Engineer-In-Charge at all locations & lifts.	SqM	2100	225	-	-	4,72,500.00		
		Rupees Two Hundreds Twenty Five Only							

[Signature]
23/9/24

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
5	Providing and laying Double Charge Vitrified Tiles of reputed make, approved shade / colour & thickness of tile shall be 8 mm to 8.9 mm for rooms & passages flooring with 20 mm thick in CM 1:4 [bedding] and for Skirting with 12 mm thick in CM 1:3 [backing] or using approved Adhesive [for Flooring & Skirting] pasting the Vitrified tiles on concrete or on masonry or on plastered surfaces, close jointed [with or without spacers] as directed, grout filling in the joints with matching pigmented cement slurry, finished to true line & levels / slope / plumb etc., including cutting of tiles, recommended acid washing, including preparation of base by closed hacking / chipping the concrete / plastered surfaces, racking out the adjoining masonry joints and cleaning, curing, providing; fixing removing staging / platform, collecting and disposing the generated waste up to a lead of 3000 meters from the place of work & cleaning the work area etc., complete all as per standard & manufacturers technical specification and as directed by the Engineer-in-charge at all locations and at all lifts/heights. Note: Basic rate of material shall be minimum Rs. 45/- per Sq.ft [excluding GST]	SqM	515	1450	-	-	7,46,750.00
		Rupees One Thousand Four Hundreds Fifty Only					
6	Providing and laying 18 mm to 20 mm thick, mirror polished Granite slab [Jet black / Ruby red / cat eye] for Kitchen platform, landing slab, selves & wash basin etc. over a bedding of 20 mm thick, in CM 1:4 using approved quality, granite stones shall be closely jointed properly, grout filling in the joints with matching pigmented cement slurry [@ 5.0 kgs. of cement / Sqm.], mirror polishing the joints, finished to true line & levels / slope / plumb etc., including preparation of base by close hacking / chipping the concrete / plastered surfaces, racking out the adjoining masonry joints & cleaning, machine cutting, smooth rounding all the exposed corners & edges and fixing in wall up to a depth of 75 mm by making the groove of size 75 mm [wide] X 75 mm [deep] in the BB wall / CC wall, providing & filling the gap in PCC 1:2:4 [after fixing the Granite Stone Slab in position to the true line; level & plumb] & finishing smooth, curing, providing; fixing & removing necessary staging / platform / ladder, collecting & disposing the generated waste up to a lead of 2 to 3 kms. from the place of work & cleaning the work area, etc. complete all as per standard technical specification, drawing [if any] and as directed by Engineer-in-charge at all locations and at all lift / height. Note: Basic rate of 18 - 20 mm thick mirror polished Granite Stone Slab shall not be less than Rs.1400.00 per Sqm. (excluding GST).	SqM	25	3100	-	-	77,500.00
		Rupees Three Thousand One Hundreds Only					
7	Providing and laying ceramic tiles for flooring/ Dado's in washroom areas by using decorative combination tiles [standard make] of size & shade / colour [as per site requirement & as selected by Engineer-in-charge] & thickness of tile shall be 5 mm to 6 mm, for flooring with 20 mm thick in CM 1:4 [bedding], Skirting & Dado with 12 mm thick in CM 1:3 [backing] or using approved Adhesive [Skirting & Dado] pasting the Ceramic tiles on concrete or on masonry or on plastered surfaces, cement slurry shall be used @ 3.3 Kgs / Sqm. of area, close jointed [with or without spacers] as directed, grout filling in the joints with matching pigmented cement slurry, finished to true line & levels / slope / plumb etc., including cutting of tiles, recommended washing, preparation of base by close hacking / chipping the old concrete & plastered surface, racking out the masonry joints roughening of existing base & cleaning, collecting & disposing the generated waste, up to a lead of 2000 mtrs. from the place of work & cleaning the work area, etc. complete all as per standard & manufacturers technical specification, drawing [if any] and as directed by Engineer-in-charge at all locations & lifts / heights.	SqM	117	1950	-	-	2,28,150.00
		Rupees One Thousand Nine Hundreds Fifty Only					

Handwritten signature and date: 28/12/14

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
8	Providing and laying/fixing Decorative with architectural finish suspended false ceiling using first quality PVC Boards of size 300mmX300mm X6mm of approved make with GI Grid Work of 600mm X 600mm made out of Perimeter channels [MF6A], Ceiling Sections [MF5 : placing at 475 mm (maximum) C/C], ceiling angles 25mm X 25mm Size [placing @ 1220mm (maximum) C/C] including Screws, soffit cleets, nuts & bolts, connecting clips and all other required miscellaneous materials & consumables of approved first quality/make etc., all material shall be confirming to relevant BIS specification of latest edition , providing; fixing & removing necessary staging / platform, cleaning the work area, collecting and disposing the generated waste & all unwanted materials upto lead of 2000meters from place of work etc., complete all as per standards / manufacturer specification and as directed by Engineer-In-Charge at all locations & all lift/heights.	SqM	560	2150	-	-	12,04,000.00
		Rupees Two Thousand One Hundreds Fifty Only					
9	Providing and fixing Single Rebate Door frames made out of 110 X 65 mm hollow metal pressed steel section [all materials shall be confirming to the BIS 513 of the latest edition] of 1.66 mm thick, galvanized as per BIS 277 of the latest edition with Zinc @ 120 gm. per Sqm., of approved make including preparation of base, providing & fixing four numbers of heavy duty, MS Oxidised Hinges of 125 mm long, three numbers of hold fastes of MS Flats 25 mm X 3 mm X 300 mm long on each side of frame or three numbers of 10 mm dia suitable length anchor fasteners by the side of column [wherever required / as directed], making provision for fixing required hardware fixtures, door closers & fittings, filling the hollow section & embedding the hold fasts using PCC 1:3:6 [using 20 mm down graded stone aggregates with curing], providing & applying metal putty [wherever required], Providing & painting with One Coat of Red oxide Primer / Zinc phosphate Primer & Two Coats 1st Quality Synthetic Enamel Paint [of asian / beger make, of approved shade / colour] on the all faces of frame, providing; fixing & removing necessary staging / platform, collecting & disposing the generated waste, up to a lead of 500 mtrs. from the place of work & cleaning the work area, etc. complete all as per standard technical specification, drawing, manufacturers technical specification and as directed by Engineer-in-charge at all locations & lifts / heights.	RM	110	990	-	-	1,08,900.00
		Rupees Nine Hundreds Ninety Only					
10	Providing and fixing in position the Factory Made, 30 mm thick, Single / Double Leaf, Flush Door Shutters of boiled water proof solid core block board with 30 X 20 mm external teak wood lipping all-round, bonded with phenol formaldehyde synthetic resin, hot pressed including providing & fixing approved make, [for each shutter] One number of 300 mm long & 16 mm dia Aldrop, One number of 200 mm long & 10 mm dia Tower Bolt; Two numbers of 125 mm grip 'D' handles, One / Two Number of Door Stopper, One / Two Numbers of Door Bush [Aldrop, Tower Bolts, 'D' handles, Door Stoppers & Door Bushes shall be of reputed make aluminium powder coated], providing, fixing & removing necessary staging / platform, Providing & painting with One Coat of Wood Primer, One Coat of wooden Putty & Two Coats of first quality Synthetic Enamel Paint to the entire shutter, collecting & disposing the generated waste up to a lead of 3000 mtrs.. from the place of work & cleaning the work area, etc. complete all as per standard & manufacturers technical specification and as directed by Engineer-in-charge at all locations and at all lift / height.	SqM	41	3150	-	-	1,29,150.00
		Rupees Three Thousand One Hundreds Fifty Only					

[Signature] 25/09/24

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
				Rate in Words			
11	Providing and laying PCC, 1:2:4 using 20 mm & downsize, clean, crushed, well graded, cubical shape, sharp edged aggregates of hard, durable & approved quality stones / rubbles for plinth, floor & drain bedding & all other various miscellaneous PCC works including preparation of base by closed hacking / chipping the concrete / plastered surfaces; racking out the adjoining masonry joints and cleaning, machine mixing, transporting, laying, spreading, consolidation, leveling, finishing, curing, providing, fixing removing staging / platform, providing; fixing & removing formwork, collecting and disposing the generated waste upto a lead of 3000 meters from the place of work & cleaning the work area etc., complete all as per standard technical specification and as directed by the Engineer-in-charge at all locations and at all lifts/heights. Note: OPC 43 Grade cement of reputed brand shall be used for executing this item.	CuM	2.5	9920	-	-	24,800.00
			Rupees Nine Thousand Nine Hundreds Twenty Only				
12	Providing and laying RCC, 1:1.5:3, using 20 mm & downsize, clean, crushed, well graded of hard, durable and approved quality for RCC works including mixing [Valumetric / as directed by Engineer-in-charge] including preparation of base by closed hacking / chipping the concrete / plastered surfaces; racking out the adjoining masonry joints and cleaning, machine mixing, transporting, laying, spreading, consolidation, leveling, finishing, curing, providing; fixing removing staging / platform, collecting and disposing the generated waste upto a lead of 3000 meters from the place of work & cleaning the work area etc., complete all as per standard technical specification and as directed by the Engineer-in-charge at all locations and at all lifts/heights. Note: OPC 43 Grade cement of reputed brand shall be used for executing this item.	CuM	8	10950	-	-	87,600.00
			Rupees Ten Thousand Nine Hundreds Fifty Only				
13	Providing and laying reputed make high yield strength deformed Reinforcement Bars of all diameters confirming to grade D-500 of IS:1786 [latest edition] including preparation of base, cutting, bending, transporting, placing in position & providing & tying using binding wire of suitable gauge [soft annealed binding wire] for all insitu concrete works and all other miscellaneous RCC works, providing & placing spacer bars, cover blocks [cover blocks shall be cast in same grade of concrete & cured properly], providing, fixing removing staging / platform, collecting and disposing the generated waste upto a lead of 3000 meters from the place of work & cleaning the work area etc., complete all as per standard & manufacturers technical specification and as directed by the Engineer-in-charge at all locations and at all lifts/heights.	Kgs	1000	110	-	-	1,10,000.00
			Rupees One Hundred Ten Only				
14	Providing, placing and removing formwork for all in-situ concrete works including providing, fixing & removing centering, shuttering, supports, brackets, clips, preparation of surface etc, providing, fixing removing staging / platform, collecting and disposing the generated waste upto a lead of 3000 meters from the place of work & cleaning the work area etc., complete all as per standard technical specification and as directed by the Engineer-in-charge at all locations and at all lifts/heights. Note: The measurement shall be made for the form work in contact with concrete surface.	SqM	130	610	-	-	79,300.00
			Rupees Six Hundreds Ten Only				
15	Providing and fixing Vertical Venetian Blinds [of superior 1st quality, of standard make & confirming to relevant BIS specification of latest edition] with all necessary fittings, fixturers & self threaded screws [of superior 1st quality, of standard make & confirming to relevant BIS specification of latest edition], shade / colour and size / length [as per site requirement & as selected by Engineer-in-charge] & width [width of strip shall be as per manufacturers specification] including preparation of base, providing; fixing & removing necessary staging / platform / ladder / scaffolding [if required], collecting & disposing the construction & generated waste up to a lead of 2 to 3 kms. from the place of work & cleaning the work area, etc. complete all as per standard & manufacturers technical specification, drawing [if any] and as directed by Engineer-in-charge at all locations and at all lifts / heights.	SqM	58	1550	-	-	89,900.00
			Rupees One Thousand Five Hundreds Fifty Only				

23/08/24

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
Schedule : SMU:BWatersupply&Sanit							
1	Providing and fixing in position White Indian Water Closet, ORISSA PAN of size 580 mm X 440 mm X 300 mm of standard make with 'P'or 'S' trap [all maerials shall be of superior 1st quality & of reputed make & confirming to relavent BIS specification of latest edition] with or without vent with all jointing materials, including necessary excavation, breaking of floor / PCC & other finishes etc. & cleaning the area, making hole in masonry & making good the same, encasing the pan & trap with PCC & backfilling extra space with river sand of good quality, curing, finishing the same & ensuring smooth functioning, collecting & disposing the generated waste, up to a lead of 3000 mtrs. from the place of work & cleaning the work area, etc. complete all as per standard & manufacturers technical specification and as directed by Engineer-in-charge at all locations & lift / heights Note: 1) Providing & placing of PCC 1:2:4 will be paid under relevant PCC Item 12A. 2) For Type, Size, Shape and Pattern Parryware White Indian Water Closet Model No. C0117 is to be referred	Each	1	4250	-	-	4,250.00
		Rupees Four Thousand Two Hundreds Fifty Only					
2	Providing and fixing white vitreous china Wall Mounting type water closet (European type) with seat and lid, 10 litre Capacity low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, Standard health faucet , overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required, ensuring smooth functioning including preparation of base, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the costruction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification, as per manufacturer's technical specification and as directed by Engineer-in-charge at all locations and at all lift & height.	Each	2	10382	-	-	20,764.00
		Rupees Ten Thousand Three Hundreds Eighty Two Only					
3	Providing and fixing in position Hindware / Parryware make white vitreous china Hand Wash Basin of size 550 X 400 mm with Plain Rims. One number 15 NB CP brass stop cock [weighing not less than 450 gm.], One number of 15 NB CP brass Piller cock [weighing not less than 450 gm.], One number one meter long PVC waste pipe, One number of 32 NB CP brass Waste Coupling, One number [450 mm long] 15 NB PVC Inlet Connector, One Pair brackets [brackets shall be painted with One Coat of Red Oxide Primer and Two Coats of approved synthetic enamel paint of approved shade / colour. All materials shall be of approved quality including chipping the wall / making hole in the wall for fixing the brackets in position, finishing the same & ensuring smooth functioning, prepartation of base, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the costruction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification, as per manufacturer's technical specification and as directed by Engineer-in-charge at all locations and at all lift & height.	Each	6	4785	-	-	28,710.00
		Rupees Four Thousand Seven Hundreds Eighty Five Only					
4	Providing and fixing "SEIKO make", 15 NB C.P Brass clutch head Long body Bib tap with all its required accessories and ensuring smooth functioning including preparation of base, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the costruction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification, as per manufacturer's technical specification and as directed by Engineer-in-charge at all locations and at all lift & height.	Each	7	1050	-	-	7,350.00
		Rupees One Thousand Fifty Only					

[Signature] 22/07/2024

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
				Rate in Words			
5	Providing and fixing "SEIKO make", 15 NB C.P Brass clutch head Short body Bib tap with all its required accessories and ensuring smooth functioning including preparation of base, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification, as per manufacturer's technical specification and as directed by Engineer-in-charge at all locations and at all lift & height.	Each	3	550	-	-	1,650.00
				Rupees Five Hundreds Fifty Only			
6	Providing and laying / fixing CPVC Pipes (SDR 11) with its all required plain & brass threaded fittings (Such as collars, elbows, tees, unions, coupling, reducers, enlargers, bends, nipples and all other fittings required for completing the job, as per code of practice for water supply to the buildings [BIS 2065 of the latest edition] of Ashirvad / Finolex / Supreme make including concealing in the wall (Makinf groove of 75 mm deep in wall with suitable width and finishing same with PCC 1:2: 4 - Using 6 mm downsize aggregate & plastering in cm 1:5) with suitable GI clamps, joining the pipes & fittings using CPVC solvent, cost of all material like white or red lead, clamps, cement, sand, tools & tackles, testing the pipe with clean water (As per specification) and ensuring smooth functioning, providing , fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification, as per manufacturer's technical specification and as directed by Engineer-in-charge at all locations and at all lift & height.	RM	20	550	-	-	11,000.00
				Rupees Five Hundreds Fifty Only			
6.1	15 mm	RM	15	625	-	-	9,375.00
				Rupees Six Hundreds Twenty Five Only			
6.2	20 mm	RM	20	700	-	-	14,000.00
				Rupees Seven Hundreds Only			
6.3	25 mm	RM	15	850	-	-	12,750.00
				Rupees Eight Hundreds Fifty Only			
6.4	32 mm	RM	10	625	-	-	6,250.00
				Rupees Six Hundreds Twenty Five Only			
7	Providing and fixing PVC heavy duty Nahani Trap (SWR Fittings IS:14735) [floor trap] 100 X 75mm of self cleaning design with 75 mm. outlet having a minimum water seal of 50 mm of Approved Brand / make with PVC grating of 125 mm dia [of approved quality & make], finishing neatly, curing, ensuring smooth functioning including preparation of base, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification, as per manufacturer's technical specification and as directed by Engineer-in-charge at all locations and at all lift & height.	Each	10	625	-	-	6,250.00
				Rupees Six Hundreds Twenty Five Only			

23/01/24

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
		Rate in Words					
8	Providing and fixing "SEIKO make", 15 NB C.P Brass clutch head Pillar taps with all its required accessories and ensuring smooth functioning including preparation of base, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification, as per manufacturer's technical specification and as directed by Engineer-in-charge at all locations and at all lift & height.	Each	7	1050	-	-	7,350.00
		Rupees One Thousand Fifty Only					
9	Providing and fixing SEIKO make 15 NB C.P Brass clutch head Angle taps with all its required accessories and ensuring smooth functioning including preparation of base, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification, as per manufacturer's technical specification and as directed by Engineer-in-charge at all locations and at all lift & height.	Each	3	850	-	-	2,550.00
		Rupees Eight Hundred Fifty Only					
10	Providing and fixing in position 10 Litres Capacity [of parry ware make (cat. No. C - 8090)]; Automatic white Flushing Cistern with all internal fittings & accessories, assembling the cistern components including providing and fixing One Number of 15 NB Angle Cook / Valve and One Number of 15 NB PVC Inlet Connector; 600 mm. long [of Kohinoor / Symet make] with brass checknuts at both ends & with 'X' Nipple, necessary PVC Flush bend, washer, suitable tools & tackles and required consumables etc. complete as per specifications conforming to IS 2556-1970 with all necessary jointing materials, chasing / making holes in masonry, making good the surface, providing 25 mm. dia GI [medium duty] over flow pipe embedded in wall, brought up to 150 mm. above floor level, with brass mosquito proof net at end, preparation of base properly, ensuring smooth functioning including preparation of base, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification, as per manufacturer's technical specification and as directed by Engineer-in-charge at all locations and at all lift & height.	Each	3	5500	-	-	16,500.00
		Rupees Five Thousand Five Hundreds Only					
11	Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS : 8329, 100 mm dia Ductile Iron Class LA pipes with all specials [such as Tees; bends; junction with or without doors; flanges and all other required fittings etc.] including providing & fixing necessary clamps, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification, as per manufacturer's technical specification and as directed by Engineer-in-charge at all locations and at all lift & height.	RM	12	2050	-	-	24,600.00
		Rupees Two Thousand Fifty Only					
12	Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS : 8329, 150 mm dia Ductile Iron Class LA pipes with all specials [such as Tees; bends; junction with or without doors; flanges and all other required fittings etc.] including providing & fixing necessary clamps, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification, as per manufacturer's technical specification and as directed by Engineer-in-charge at all locations and at all lift & height.	RM	12	3250	-	-	39,000.00
		Rupees Three Thousand Two Hundred Fifty Only					

Note: All Item Rates are considered to be in Indian Rupees unless otherwise explicitly specified and in which case shall be always converted appropriately to arrive at the amount in Indian Rupees.

Work Order Total	Rs. 53,12,999.00
Overall Rebate (%)	5.78
Work Order Value After Overall Rebate in Figure	Rs. 50,05,908.00
Work Order Value After Overall Rebate in Words	Rupees Fifty Lakh Five Thousand Nine Hundreds Eight Only

23/10/24

Head, CTC

23/10/24
KAS-344

Signature Not Verified

Digitally signed by BASA NAGOUDA
SHIVAGOUDA NAGANURI
Date: 2024.10.04 12:00:01 IST
Location: eProcurement System for
Central PSUs