



न्यूक्लियर पावर कॉर्पोरेशन ऑफ इंडिया लिमिटेड

Nuclear Power Corporation of India Limited

(भारत सरकार का उद्यम Government of India Enterprise)

कैगा स्थल KAIGA SITE

CENTRALISED TENDER CELL केंद्रीय नीविदा प्रकोष्ठ

Corporate Identification No. U40104MH1987GOI149458

Phone: +91 8382 264002, Fax: +91 8382 264025, vkthakur@npcil.co.in Website: www.npcil.nic.in

Head, CTC, NPCIL, Kaiga Site, Kaiga-581 400, Tq: Karwar, Dist: Uttara Kannada, State: Karnataka



Ref: NPCIL/KGS/CTC/CPMP-024/WO/2024/980

Date: 22-08-2024

To:

M/s Ravi S. Halagatti,
T – 4, 14/1, KPC Colony,
Kadra, Tq: Karwar
Dist: Uttara Kannada,
Pin 581 396

Kind Atten: Shri Ravi S. Halagatti
Cell No.: 94482 50384
E-mail ID: rshalagatti@gmail.com

Work Order No.	:	102115
S.L. Code	:	R0065102115
Account Code	:	14390
Charge Code	:	6153
MSME	:	NA

WORK ORDER NO.: 2024_NPCIL_193550_1/WO

Name of work: "Construction of CS Drum storage at WMCF at Kaiga Generating Station 1&2, Kaiga Site Kaiga."

Ref: 1) Tender No.: NPCIL/KGS/CTC/E&US-CIVIL-INFRA WORKS/CPMP/2024/024/193550_1
2) Last date of submission of tender is 09.05.2024

Dear Sir,

1) BID ACCEPTANCE:

1.1 This is to inform you that, the bid submitted by you as referred above has been accepted for and on behalf of NPCIL, for the items of work shown in the enclosed schedule of quantities and rates for a total value of **₹. 48,61,340.00** (Rupees Forty-eight Lakhs, Sixty-one thousand three hundred forty only) inclusive of all applicable taxes and including 18% GST.

2) QUANTITIES & RATES

2.1 You may note that the rates are for complete items of work including supply of all materials (unless otherwise specified), consumables, all temporary arrangements, all labours, all prevailing duties, taxes including GST.

2.2 AHR Items: Nil & ALR Item: Item Nos.: 7.2 & 19 (2Nos.)

2.3 Payment to the manpower deployed for this work shall be made as specified in the tender.

22/08/24

3) CONTRACT PRICE ADJUSTMENT:

Escalation of payment shall be applicable as per **Sl. No.: 21** of Schedule – A.

4) EXECUTION OF WORK:

The work shall be carried out strictly in accordance with the terms, conditions, specifications and drawings stipulated in the tender and also in best work man like manner. You shall employ and maintain qualified engineers / supervisors in the job at all times. You shall also bring to the site and employ such machinery and equipment and other materials as are necessary for the satisfactory completion of this work.

5) CONTRACT PERIOD:

5.1 Schedule completion Period:

The work shall be completed in all respect within **365 calendar days (including monsoon period)** from the date of commencement. The date of commencement of work will be reckoned within **Seven (07) days** from the **date of issue of Work Order**. The time shall be essence of the contract and the work shall be completed as per approved program of work.

5.2 Defect Liability Period:

The Defect Liability Period is 12 months - **Sl. No.: 18** of Schedule - A.

6) AUTHORISED OFFICIALS:

6.1 You are requested to inform the name of the authorized representative who will deal with all matter relating to the contract and the Power of Attorney in his favour duly executed on stamped paper of an appropriate value shall be furnished.

6.2 During the execution of the contract and until completion certificate is issued you will be fully liable to compensate all concerned for any loss, damage or destruction of work, structure, property etc. including third party risk arising due to causes attributable to you which will be decided by the engineer-in-charge whose decision in this regard will be final.

7) INSURANCE:

You are required to take out following insurance policies applicable to this contract at your cost immediately after receipt of this work order from the date of commencement of work to the **end of the Defect Liability Period** for the whole contract value inclusive of GST.

- a) **CAR policy for the whole contract value** – Applicable as per Schedule A
- b) **The Insurance amount should cover THIRD PARTY LIABILITY to 10% of Contract value subjected to maximum of Rs. 50.00 Lakhs.** – Applicable as per Schedule A
- c) **Employees State Insurances for contract workers.** – Applicable as per Schedule A
- d) **Wherever ESI Act not covers the contract worker based on monthly wage / salary, contractor shall obtain the employees / Workmen compensation for such workers.**

You may note that all insurance policies taken under 7 (a), (b) & (d) are to be in Joint names of Corporation and the contractor and specific to work by mentioning the name of work and

Handwritten signature and date:
12/05/24

Work Order Number in the policies and all Policies in Original should be submitted to the engineer-in-charge before the date of commencement of work. Copy of ESI registration certificate shall be submitted to **engineer-in-charge of work**, before commencement of the work.

8) TAXES & DUTIES:

For tax related compliance (including TDS) refer Supplement/ Amendment to GCC (Additional document pg no.:291/346).

9) ENGINEER-IN-CHARGE:

Shri Brijesh Meena, SO/C, Civil-Infra-Works, will be the **Engineer-in-charge** of this work. You may make necessary arrangements for commencing the work immediately in consultation with Engineer-in-Charge.

10) SECURITY DEPOSIT:

Security Deposit shall be @ **10 %** of the contract value will be ₹. **4,86,134/-** (including GST), (Rupees Four Lakhs, Eighty-six thousand One hundred and thirty-four only)

10.1 Performance Guarantee: (This clause revised on 09.12.2022)

As per **Clause No.: 4.2.3** of **GCC** you shall submit a performance guarantee for ₹. **2,43,067/-** (50% of Security Deposit) to the Corporation within 30 days after issue of work order. It should cover the contract period plus Defects Liability period. In case, the Bank Guarantee need to be submitted as per the format given in tender document.

10.2 Retention Money:

As per **Clause No.: 4.2.5** of **GCC**, the remaining amount (50% of Security Deposit) of Security Deposit of ₹. **2,43,067/-** will be deducted as a Retention money from the RA bill / final bill at the rate of 6% of each bill amount. Security Deposit amount will not bear any interest.

10.3 Refund of Security Deposit:

Refund of Security deposit will be regularized as per **General Condition of Contract**.

11) APPLICABLE LAWS & ACTS:

11.1 You shall comply with various provisions of the contract labour (Regulations & Abolition) Act 1970 and rules framed thereafter from time to time. In case, the Contract Labour Act does not apply to your organization you should intimate the Engineer-in-Charge of this work accordingly before commencing the work. Further you shall also comply with the provisions of other laws such as Workmen's Compensation Act 1923, Minimum Wages Act 1948, E.P.F. Act, ESI Act, Gratuity Act and other labor laws as applicable to your organization. In case, NPCIL is required to incur any expenses as principal employer under the provisions of the various laws, NPC shall be entitled to recover the same from you / your bills.

11.2 You have to give request for the issue of Principal Employer's Certificate for obtaining labour license based on the maximum number of workmen you proposed to employ for this work. You may please note that within 14 days from the date of issue of this work order, you will

[Handwritten signature]
21.8/24

have to apply for a labour license to the Asstt. Labour Commissioner, of the area, for the maximum number of workers you had indicated to engage on the work.

11.3 The contractor shall make the payment to all its labours on or before 7th of succeeding month and as per special condition of contract.

11.4 Labour License (if applicable),

12) PAYMENT TERMS:

12.1 The progressive monthly payment for the work completed and accepted by Engineer-in-charge shall be made through Running Account bills once in a month on submission of measurement / bill by the contractor. Submission of bills on monthly basis shall be ensured by the contractor.

12.2 Payment of bills will be processed on submission of GST invoice duly supported with Annexure-8 (Declaration form for GST).

12.3 In addition to above, first Running Account bill will be processed only on submission of Intimation from Tender Section regarding Work order acceptance & agreement signed by the contractor, Insurance Policies, copy of PAN, GST Registration Certificate, cancelled cheque for bank account details etc., to the Engineer-in-charge.

13) PENALTY & LIQUIDATED DAMAGES CLAUSE:

Penalties imposed by Engineer-in-charge for non-compliance or violation of certain conditions of contract, Liquidated Damages for delay in execution and any other penalty in the nature of fine imposed during execution of work will be recovered along with applicable GST there on from bills of the contractor before release of payment.


14) SECURITY, SAFETY & HOUSEKEEPING:

You may have to comply all Security, Safety rules & regulations, Environmental measure as defined in the Contract.

You shall submit the Police Verification Certificate [PVC] for you, your staff and labour; as a pre-condition to issue of RFID cards / Gate Passes [if applicable].

15) TRANSPORT & ACCOMMODATION:

Contractor shall make his own arrangement for Accommodation & Transportation of manpower deployed for this work.



16) AGREEMENT:

A formal agreement incorporating all the terms and conditions agreed between NPCIL and **M/s Ravi S. Halagatti**, will be executed within the period from the date of issue of this work order. Till a **formal agreement** is executed the original tender together with letters under reference and this work order shall form the binding contract between NPCIL and **M/s Ravi S. Halagatti**.

Kindly acknowledge receipt of this Work Order.

Thanking you,

Yours faithfully
For and on behalf of NPCIL


20/08/24


21/08/2024


21.8.24
अपर मुख्य अभियंता, (ई&युएस)
Additional Chief Engineer, (E&US)

NUCLEAR POWER CORPORATION OF INDIA LIMITED

(A Government of India Enterprise)

Kaiga Generating Station

Schedule Of Quantities And Rates



Print Date: 20-Aug-2024

Co		Name of Work: Construction of CS Drum storage at WMCF at Kaiga Generating Station 1&2, Kaiga Site, Kaiga. WO / SOQR Number : 102115			Agency Name : RAVI S HALAGATTI		
Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
Schedule : E&US:NA		Rate in Words					
1	Earthwork Excavation in all Sorts of Soil for foundation trenches, walls, drains, plinths, footings, pedestals, columns and for all other miscellaneous foundation works etc., including Cutting / removing & clearance of jungle, bushes, grass & all other unwanted plants, creepers, which are obstructing for excavation work etc. Shoring, strutting, bailing out water if necessary, dressing, leveling & hand ramming properly the bottom of foundations using wooden hand rammer with proper watering, refilling the sides of the foundation with excavated available good quality of Soil, leveling & hand ramming properly the sides of foundations using wooden hand rammer with proper watering, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification and as directed by Engineer-In-Charge at all locations and at all lift & height.						
1.1	Excavation from Ground level to 1.50 meters depth.	CuM	142	430	-	-	61,060.00
		Rupees Four Hundreds Thirty Only					
1.2	Excavation from 1.50 to 3.00 meters depth.	CuM	58	500	-	-	29,000.00
		Rupees Five Hundreds Only					
2	Earthwork Excavation in Soft Rock for foundation trenches, walls, drains, plinths, footings, pedestals, columns and for all other miscellaneous foundation works etc., including Cutting / removing & clearance of jungle, bushes, grass & all other unwanted plants, creepers, which are obstructing for excavation work etc. Shoring, strutting, bailing out water if necessary, dressing, leveling & hand ramming properly the bottom of foundations using wooden hand rammer with proper watering, refilling the sides of the foundation with excavated available good quality of Soil, leveling & hand ramming properly the sides of foundations using wooden hand rammer with proper watering, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification and as directed by Engineer-In-Charge at all locations and at all lift & height.						
		CuM	30	750	-	-	22,500.00
		Rupees Seven Hundreds Fifty Only					

[Signature]
20/08/24

Co		Name of Work: Construction of CS Drum storage at WMCF at Kaiga Generating Station 1&2, Kaiga Site, Kaiga. WO / SOQR Number : 102115				Agency Name : RAVI S HALAGATTI		
Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹	
				Rate in Words				
3	Filling in Plinth using selected excavated earth & earth brought from pits [excluding soft rock & rock muck] including Cutting / removing & clearance of jungle, bushes, grass and all other unwanted plants / creepers (from the filling area, filling earth shall be free from roots, stones, pebbles, leaves, unwanted materials and filling in layers not exceeding 200 mm thick, breaking the clods, levelling, dressing to required line, level, slope / gradient & watering and compacting the each layer. Using suitable weight hand rammer, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification and as directed by Engineer-In-Charge at all locations and at all lift & height.				-	-		
3.1	Using excavated available earth	CuM	79	170	-	-	13,430.00	
			Rupees One Hundreds Seventy Only					
3.2	Using earth brought from borrow pit	CuM	50	400	-	-	20,000.00	
			Rupees Four Hundreds Only					
4	Providing and laying 230 mm. thick soling , granite aggregated using hard; durable & approved quality stones of 40 mm. size including preparation of bed properly by proper leveling; dressing & proper watering, providing & filling / fixing interstices using small size stones / chips, providing & spreading binding materials such as crushed granite stone powder , base shall be fully neat; clean & slightly wet before laying stone filling , cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification and as directed by Engineer-In-Charge at all locations and at all lift & height.	CuM	82	3200	-	-	2,62,400.00	
			Rupees Three Thousand Two Hundreds Only					
5	Providing and laying PCC 1:3:6 using 40 mm & downsize clean, crushed, well graded, aggregates of hard, durable & approved quality for foundation, plinth, bedding, platforms, pathways, walkways & all other miscellaneous works including preparation of base, mixing, transporting, laying, spreading, consolidation, levelling, finishing curing, providing ; fixing & removing necessary form work, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification and as directed by Engineer-In-Charge at all locations and at all lift & height. NOTE: 43 Grade OPC cement shall be used.	CuM	28	7800	-	-	2,18,400.00	
			Rupees Seven Thousand Eight Hundreds Only					
6	Providing and laying RCC M30 Grade using 20 mm & downsize clean, crushed, well graded, aggregates of hard, durable & approved quality for foundation, rafts, footings, plinth, columns, beams, slabs, Chejjas, Lintels, bedding, platform, pathways, walkways and all insitu concrete works including preparation of base, mechanical mixing, transporting, laying, spreading, consolidation, levelling, finishing & curing, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification and as directed by Engineer-In-Charge at all locations and at all lift & height. NOTE: Reinforcement will be measured & paid under item no.: 8 formwork will be measured & paid under item no.: 7 43 Grade OPC cement shall be used.	CuM	84	9800	-	-	8,23,200.00	
			Rupees Nine Thousand Eight Hundreds Only					

[Signature]

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
							Rate in Words
7	Providing, placing and removing formwork for all in-situ concrete works such as foundation, raft, columns, beams, slab, footings, all other miscellaneous RCC works including providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification and as directed by Engineer-In-Charge at all locations and at all lift & height. Note: The measurement for the form work will be actual area of form in contact with the concrete surfaces.				-	-	-
7.1	For footing, foundation column below plinth & plinth beam - Sub structures	SqM	100	350	-	-	35,000.00
				Rupees Three Hundreds Fifty Only			
7.2	For column, floor / roof beams, slabs, lintels, lofts, chejja & staircase etc., Super Structures	SqM	110	550	-	-	60,500.00
				Rupees Five Hundreds Fifty Only			
8	Providing and laying approved make high yield strength deformed Reinforcement bars of all dia meters conforming to grade Fe-415 of IS:1786 [latest edition] including cutting, bending, transporting, placing in position & binding with suitable gauge soft annealed binding wire for all insitu concrete works and all other miscellaneous RCC works, providing & placing spacer bars, cover blocks [cover blocks shall be cast in same grade of concrete & cured properly. Providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification, as per manufacturer's technical specification and as directed by Engineer-In-Charge at all locations and at all lift & height. Note: The rate shall include the cost of Binding wire and cover blocks.	MT	5.6	102000	-	-	5,71,200.00
				Rupees One Lakh Two Thousand Only			
9	Providing & Constructing Burnt Brick Masonry of 230 mm thick in CM 1:5 using well Burnt Bricks of standard size & compressive strength of not less than 35Kg/cm2 for Super Structure, plinth and all other Miscellaneous Masonry Works, including simultaneous flush pointing, curing, preparation of base properly, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification and as directed by Engineer-In-Charge at all locations and at all lift & height.	CuM	17	10000	-	-	1,70,000.00
				Rupees Ten Thousand Only			
10	Providing and laying Internal Cement Plaster 15 mm thick in CM 1:5 to the masonry & concrete surfaces etc., rubbed perfectly so as to obtain smooth & even finish including preparation of base by racking out all the masonry joints & close hacking the concrete surfaces for proper bonding, curing, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification and as directed by Engineer-In-Charge at all locations and at all lift & height.	SqM	75	350	-	-	26,250.00
				Rupees Three Hundreds Fifty Only			

Co		Name of Work: Construction of CS Drum storage at WMCF at Kaiga Generating Station 1&2, Kaiga Site, Kaiga. WO / SOQR Number : 102115			Agency Name : RAVI S HALAGATTI		
Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
					Rate in Words		
11	Providing and laying External Cement Plaster 18 mm thick in Two Coats. Base coat shall be 12 mm thick in CM 1:5 & finishing coat shall be 6 mm thick in CM 1:3 (sponge finished) with Non-Shrink Water Proofing Compound [confirming to the BIS 2645 of the latest edition] @ 2 % by the weight of cement / as per the recommendation of the manufacturer to the Masonry surfaces & concrete surfaces etc. rubbed perfectly so as to obtain smooth & even finish including preparation of base by racking out all the masonry joints & close hacking the concrete surfaces for proper bonding, curing, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification and as directed by Engineer-In-Charge at all locations and at all lift & height.	Sqm	100	430	-	-	43,000.00
					Rupees Four Hundreds Thirty Only		
12	Providing, fabricating and erecting Mild Steel Structures using various MS Sections such as channels, angles, 'I' sections, rails, MS pipes, flats, plates, GI Gratings, GI Pipes, MS & Reinforcement rods and other approved sections etc. & transporting to the work place, including loading, unloading, cutting, fabricating the MS gates, MS grills, ladders, hand rails, angle frames, pannels, struts, tubular space frames, columns, beams, purlins, rafters, fencing posts, EP Plates, EP Flats & all other required miscellaneous structural steel works and fixing / erecting the same in position as directed. including providing & applying One Coat of Zinc Phosphate Primer & Two Coats of 1st quality Synthetic Enamel Paint of approved shade / colour [Promer & Paint shall of Asian Paints / Berger Paints], providing & fixing wherever required suitable anchor fasteners, of approved quality, preparation of base, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per technical specification, as per manufacturer's technical specification, fabrication as per drawing (if any) and as directed by Engineer-In-Charge at all locations and at all lift & height.	MT	8	120000	-	-	9,60,000.00
					Rupees One Lakh Twenty Thousand Only		
13	Collecting MS structural steel from Main store, transporting to WMP & Fabricating gates, hand rails, frames of panels, doors, windows & shutters, rafters, purlins, rafters, horizontal / vertical / cross members, columns, beams and all other miscellaneous new & modification to existing structure/s executing this work and fixing / erecting the same in position to true line level & plumb, preparation of base, providing & fixing hilly bolts [of approved quality] of suitable dia. & length, preparation of base, providing & painting One Coat of approved Zinc Phosphate Primer of asian paints / berger make and Two Coats of first quality synthetic enamel paint of asian paints / berger make, of approved shade / colour etc., providing; fixing & removing staging / platform / ladder, collecting & disposing the generated waste up to a lead of 2 to 3 kms. from the place of work & cleaning the work area, etc. complete all as per standard & manufacturers technical specification, drawing [if any] and as directed by Engineer-In-Charge at all locations and at all lift / height.	MT	8	38000	-	-	3,04,000.00
					Rupees Thirty Eight Thousand Only		
14	Providing, erecting and fixing curved / plain roof sheets of Galvalum Roofing sheets with Coating: AZ - 150/550 mpa, Paint: RMP (Regular Modified Polymer) Topcoat - 18-20 Microns, Bottom; 5-7 Microns. Tropezoidal Profile 0.47 MM Thick at Pitch 200 MM, Width 1060 MM and 6000 MM in Length ALUMINIUM-ZINC STEEL SHEETS(Galvalume Base) 55% ALUMINIUM,43% ZINC, 1.60% SILICON With Tensile Strength of 345 TO 550 mpa including preparation of base, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification, as per manufacturer's technical specification and as directed by Engineer-In-Charge at all locations and at all lift & height.	Sqm	680	630	-	-	4,28,400.00
					Rupees Six Hundreds Thirty Only		

10/2/2018

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
							Rate in Words
15	Providing and applying One Coat of Exterior Grade Primer of Asian Paints / Berger Paints / Dulux Paint / Nerolac Paints and Two Coats of Exterior Grade weather Proof Paint, of Asian Paints [Such as Apex Altima] / Berger Paints [Such as weather coat alguard] / Dulux Paint [Such as weather shield max] / Nerolac Paints [Such as Excel Total], of approved shade / colour for new surfaces of concrete or masonry wall, RCC members such as columns; beams & other concrete surfaces including providing & filling creack sealing compound in the cracks of approve make & quality, preparation of surfaces by sand papering, cleaning the surface, surface shall be neat; clean & dry before application of creack sealing compound; Primer & Paint, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification, as per manufacturer's technical specification and as directed by Engineer-In-Charge at all locations and at all lift & height.	SqM	100	200	-	-	20,000.00
							Rupees Two Hundreds Only
16	Providing and applying Two Coat of Acrylic interior grade plastic Emulsion paint of approved brand & shade over a coat of relevant Primer [water Based] over the interior surface of newly plastered concrete or masonry wall, RCC members such as columns; beams & other concrete surfaces, including providing & applying one coat putty for entire surface, preparation of surfaces by sand papering, cleaning the surface, surface shall be neat; clean & dry before application of Putty; Primer & Acrylic Distemper, providing, fixing & removing necessary staging / platform wherever required cleaning / mopping / washing the work area and disposing the debris / waste up to a lead of 2 to 3 kms. outside the periphery of the work premises etc. complete all as per specification and as directed by the Engineer-In-Charge at all lifts & locations.	SqM	80	150	-	-	12,000.00
							Rupees One Hundreds Fifty Only
17	Providing & fixing on the wall surfaces UPVC 4kgs. Pressure pipes of 6" dia. With specials (such as Tees; bends; junction with or without door, flanges and all other required fittings etc.0 od Ashirvad/Astral/finolex / Supreme make, for rain water down commner pipes including providing 7 fixing necessary clamps (GI clamps of 25 mm. wide x 4 mm thick) of length (as per site requirement), hard wood packing pieces, PVC solvents, screws / nails, cement & sand etc., providing, fixing & removing stging / platforms / scaffolding, collecting & disposing the generated waste, disposal of construction waste up to lead of 3000 to 4000 meters from the work area, etc. complete all as per standard technical specification, manufacturers standard technical specification, drawing (if any) and as directed by Engineer-In-Charge at all locations and at all lifts and height.	RM	50	500	-	-	25,000.00
							Rupees Five Hundreds Only
18	Providing and laying 52 mm. thick Hardonite Trimix flooring with cement concrete [PCC] 1:2:4 using 20 mm. & down size stone aggregates [40 mm thick PCC + 12 mm thick Hardonite topping] including mixing, transporting, laying, spreading, compaction, laying in bays [of suitable size as directed by the Engineer-In-Charge] to proper line; slope or level etc. using 4 mm. thick plane glass dividing strips [exposed top surface of glass shall be finished smooth & top edges shall be rounded smoothly] for flooring, steps, landings & ramps etc., ramming, finishing smooth, preparation of base & curing properly, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification, as per manufacturer's technical specification and as directed by Engineer-In-Charge at all locations and at all lift & height.	SqM	312	2000	-	-	6,24,000.00
							Rupees Two Thousand Only



Co		Name of Work: Construction of CS Drum storage at WMCF at Kaiga Generating Station 1&2, Kaiga Site, Kaiga.			Agency Name : RAVI S HALAGATTI		
		WO / SOQR Number : 102115					
Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
				Rate in Words			
19	Dismantling / breaking / removing by Manual or Mechanical means, PCC items including providing, fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification and as directed by Engineer-In-Charge at all locations and at all lift & height.	CuM	10	700	-	-	7,000.00
				Rupees Seven Hundreds Only			
20	Supplying and fixing Rolling Shutters of approved make, made of required size M.S. Laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with mechanically operated push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part and M.S. top cover of required thickness for rolling shutters. 80 X 1.25 mm M.S. laths with 1.25 mm thick top cover, including preparation of base, providing & applying One Coat of Red Oxide Primer & Two Coats of 1st quality Synthetic Enamel Paint of approved shade / colour [Primer & Paint shall of Asian Paints / Berger Paints / Dulux Paints], providing, fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification, as per manufacturer's technical specification and as directed by Engineer-In-Charge at all locations and at all lift & height. Note: Clear door opening measurement will be paid.	SqM	25	5000	-	-	1,25,000.00
				Rupees Five Thousand Only			

Note: All Item Rates are considered to be in Indian Rupees unless otherwise explicitly specified and in which case shall be always converted appropriately to arrive at the amount in Indian Rupees.

Work Order Total	Rs. 48,61,340.00
Overall Rebate (%)	0
Work Order Value After Overall Rebate in Figure	Rs. 48,61,340.00
Work Order Value After Overall Rebate in Words	Rupees Forty Eight Lakh Sixty One Thousand Three Hundreds Forty Only

Signature Not Verified

Digitally signed by BASANAGOUDA SHIVAGOUDA NAGANURI
Date: 2024.08.26 16:52:41 IST
Location: eProcurement System for Central PSUs

Amudhuru
21-8-2024
[ACCEPTED]

21/08/2024
H. S. S. S.

20/08/24