



न्यूक्लियर पावर कॉर्पोरेशन ऑफ इंडिया लिमिटेड

Nuclear Power Corporation of India Limited

(भारत सरकार का उद्यम Government of India Enterprise)

कैगा स्थल KAIGA SITE

CENTRALISED TENDER CELL केंद्रीय नीविदा प्रकोष्ठ

Corporate Identification No. U40104MH1987GOI149458

Phone: +91 8382 264002, Fax: +91 8382 264025, sdileep@npcil.co.in Website: www.npcil.nic.in

Head, CTC, NPCIL, Kaiga Site, Kaiga-581 400, Tq: Karwar, Dist: Uttara Kannada, State: Karnataka



Ref: NPCIL/KGS/CTC/CPPP-035/197154_1/WO/2024/1009

Date: 30-09-2024

To:

M/s Murugan Kannappa
Laxmi Nagar, Mallapur,
Uttara Kannada, Karnataka.
Pin- 581400.

Kind Atten: Shri K. Murugan
Cell No.: 9448806909
E-mail ID: gopikaiga@gmail.com

Work Order No.	:	102119
S.L. Code	:	K0085102119
Account Code	:	74200
Charge Code	:	6153
MSME	:	NA

WORK ORDER NO.: 2024_NPCIL_197154_1/WO

Name of work: "Miscellaneous Civil Maintenance and Repair works at
KGS Unit-1&2, Kaiga."

Ref: 1) Tender No.: NPCIL/KGS/CTC/C&SM-1&2/CPPP/2024/035
2) Last date of submission of tender is 26.06.2024
3) MOM for negotiation: NPCIL/KGS/CTC/CPPP/2024/035/MOM/356A, dated: 23.08.2024

Dear Sir

1) BID ACCEPTANCE:

1.1 This is to inform you that, the bid submitted by you and subsequently modified vide Ref. 3 above has been accepted for and on behalf of NPCIL, for the items of work shown in the enclosed schedule of quantities and rates for a total value of ₹. **1,01,19,835/-** (Rupees One Crore, One Lakh, Nineteen thousand Eight hundred thirty-five only) inclusive of all applicable taxes and including 18% GST.

2) QUANTITIES & RATES

2.1 You may note that the rates are for complete items of work including supply of all materials (unless otherwise specified), consumables, all temporary arrangements, all labours, all prevailing duties, taxes including GST.

2.2 AHR Items: Nil & ALR Item: Nil

Overall rebate of 3% (After Negotiation)

(MOM No.: NPCIL/KGS/CTC/CPPP/2024/035/MOM/356A, dated: 23.08.2024)

2.3 Payment to the manpower deployed for this work shall be made as specified in the tender.

RP
28/09

3) CONTRACT PRICE ADJUSTMENT:

Escalation of payment shall be applicable as per **Sl. No.: 21** of Schedule – A.

4) EXECUTION OF WORK:

The work shall be carried out strictly in accordance with the terms, conditions, specifications and drawings stipulated in the tender and also in best work man like manner. You shall employ and maintain qualified engineers / supervisors in the job at all times. You shall also bring to the site and employ such machinery and equipment and other materials as are necessary for the satisfactory completion of this work.

5) CONTRACT PERIOD:

5.1 Schedule completion Period:

The work shall be completed in all respect within **365 Calendar Days** (including monsoon period) from the date of commencement. The date of commencement of work will be reckoned within **Seven (07) days** from the **date of issue** of **Work Order**. The time shall be essence of the contract and the work shall be completed as per approved program of work.

5.2 Defect Liability Period:

The Defect Liability Period is 12 months - **Sl. No.: 18** of Schedule - A.

6) AUTHORISED OFFICIALS:


6.1 You are requested to inform the name of the authorized representative who will deal with all matter relating to the contract and the Power of Attorney in his favour duly executed on stamped paper of an appropriate value shall be furnished.

6.2 During the execution of the contract and until completion certificate is issued you will be fully liable to compensate all concerned for any loss, damage or destruction of work, structure, property etc. including third party risk arising due to causes attributable to you which will be decided by the engineer-in-charge whose decision in this regard will be final.

7) INSURANCE:

You are required to take out following insurance policies applicable to this contract at your cost immediately after receipt of this work order from the date of commencement of work to the **end** of the **Defect Liability Period** for the whole contract value inclusive of GST.

- a) **CAR policy for the whole contract value** – Applicable as per Schedule A
- b) **The Insurance amount should cover THIRD PARTY LIABILITY to 10% of Contract value subjected to maximum of Rs. 50.00 Lakhs.** – Applicable as per Schedule A
- c) **Employees State Insurances for contract workers.** – Applicable as per Schedule A
- d) **Wherever ESI Act not covers the contract worker based on monthly wage / salary, contractor shall obtain the employees / Workmen compensation for such workers.**


22/09/24

You may note that all insurance policies taken under 7 (a), (b) & (d) are to be in Joint names of Corporation and the contractor and specific to work by mentioning the name of work and Work Order Number in the policies and all Policies in Original should be submitted to the engineer-in-charge before the date of commencement of work. Copy of ESI registration certificate shall be submitted to **engineer-in-charge of work**, before commencement of the work.

8) TAXES & DUTIES:

For tax related compliance (including TDS) refer Supplement/ Amendment to GCC (Additional document pg no.:291/346).

9) ENGINEER-IN-CHARGE:

Shri P.F. Pandit, OIC, C&SM-1&2, will be the **Engineer-in-charge** of this work. You may make necessary arrangements for commencing the work immediately in consultation with Engineer-in-Charge.

10) SECURITY DEPOSIT:

Security Deposit shall be @ **10 %** of the contract value will be ₹. **10,11,984/-** (including GST), (Rupees Ten Lakhs, Eleven thousand Nine hundred and eighty-four only)

10.1 Performance Guarantee: (This clause revised on 09.12.2022)

As per **Clause No.: 4.2.3** of **GCC** you shall submit a performance guarantee for ₹. **5, 05,992/-** (50% of Security Deposit) to the Corporation within 30 days after issue of work order. It should cover the contract period plus Defects Liability period. In case, the Bank Guarantee need to be submitted as per the format given in tender document.

10.2 Retention Money:

As per **Clause No.: 4.2.5** of **GCC**, the remaining amount (50% of Security Deposit) of Security Deposit of ₹. **5, 05,992/-** will be deducted as a Retention money from the RA bill / final bill at the rate of 6% of each bill amount. Security Deposit amount will not bear any interest.

10.3 Refund of Security Deposit:

Refund of Security deposit will be regularized as per **General Condition of Contract**.

11) APPLICABLE LAWS & ACTS:

11.1 You shall comply with various provisions of the contract labour (Regulations & Abolition) Act 1970 and rules framed thereafter from time to time. In case, the Contract Labour Act does not apply to your organization you should intimate the Engineer-in-Charge of this work accordingly before commencing the work. Further you shall also comply with the provisions of other laws such as Workmen's Compensation Act 1923, Minimum Wages Act 1948, E.P.F. Act, ESI Act, Gratuity Act and other labor laws as applicable to your organization. In case, NPCIL is required to incur any expenses as principal employer under the provisions of the various laws, NPC shall be entitled to recover the same from you / your bills.

Handwritten signature
28/09/24

11.2 You have to give request for the issue of Principal Employer's Certificate for obtaining labour license based on the maximum number of workmen you proposed to employ for this work. You may please note that within 14 days from the date of issue of this work order, you will have to apply for a labour license to the Asstt. Labour Commissioner, of the area, for the maximum number of workers you had indicated to engage on the work.

11.3 The contractor shall make the payment to all its labours on or before 7th of succeeding month and as per special condition of contract.

11.4 Labour License (if applicable),

12) PAYMENT TERMS:

12.1 The progressive monthly payment for the work completed and accepted by Engineer-in-charge shall be made through Running Account bills once in a month on submission of measurement / bill by the contractor. Submission of bills on monthly basis shall be ensured by the contractor.

12.2 Payment of bills will be processed on submission of GST invoice duly supported with Annexure-8 (Declaration form for GST).

12.3 In addition to above, first Running Account bill will be processed only on submission of Intimation from Tender Section regarding Work order acceptance & agreement signed by the contractor, Insurance Policies, copy of PAN, GST Registration Certificate, cancelled cheque for bank account details etc., to the Engineer-in-charge.

13) PENALTY & LIQUIDATED DAMAGES CLAUSE:

Penalties imposed by Engineer-in-charge for non-compliance or violation of certain conditions of contract, Liquidated Damages for delay in execution and any other penalty in the nature of fine imposed during execution of work will be recovered along with applicable GST there on from bills of the contractor before release of payment.

14) SECURITY, SAFETY & HOUSEKEEPING:

You may have to comply all Security, Safety rules & regulations, Environmental measure as defined in the Contract.

You shall submit the Police Verification Certificate [PVC] for you, your staff and labour; as a pre-condition to issue of RFID cards / Gate Passes [if applicable].

15) TRANSPORT & ACCOMMODATION:

Contractor shall make his own arrangement for Accommodation & Transportation of manpower deployed for this work.


28/12/09

16) **AGREEMENT:**

A formal agreement incorporating all the terms and conditions agreed between NPCIL and M/s Murugan Kannappa, will be executed within the period from the date of issue of this work order. Till a **formal agreement** is executed the original tender together with letters under reference and this work order shall form the binding contract between NPCIL and M/s Murugan Kannappa.

Kindly acknowledge receipt of this Work Order.

Thanking you,

Yours faithfully
For and on behalf of NPCIL


28/09/24.

अनुरक्षण अधीक्षक, (केजीएस # 1 व 2)
Maintenance Superintendent, (KGS # 1&2)


28/09/24


28/09/24
Head, CR

ge
all
lift:

Name of Work: Miscellaneous Civil Maintenance and Repair works at KGS Unit-1&2, Kaiga. WO / SOQR Number : 102119		Agency Name : M/s Murugan Kannappa					
Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
Rate in Words							
6	Providing and laying reputed make [make as selected by engineer-in-charge] high yield strength deformed Reinforcement Bars of all diameters conforming to grade D-500 of IS:1786 [latest edition] including preparation of base, cutting, bending, transporting, placing in position & providing & tying using binding wire of suitable gauge [soft annealed binding wire] for all insitu concrete works and all other miscellaneous RCC works, providing & placing spacer bars, cover blocks [cover blocks shall be cast in same grade of concrete & cured properly], providing, fixing removing staging / platform, collecting and disposing the generated waste upto a lead of 3000 meters from the place of work & cleaning the work area etc., complete all as per standard & manufacturers technical specification and as directed by the engineer-in-charge at all locations and at all lifts & heights.	MT	7.3	114000	-	-	8,32,200.00
		Rupees One Lakh Fourteen Thousand Only					
7	Providing, placing and removing formwork for all in-situ concrete works including providing, fixing & removing centering, shuttering, supports, brackets, clips, preparation of surface etc, providing, fixing removing staging / platform, collecting and disposing the generated waste upto a lead of 3000 meters from the place of work & cleaning the work area etc., complete all as per standard technical specification and as directed by the engineer-in-charge at all locations and at all lifts & heights. Note: The measurement shall be made for the form work in contact with concrete surface.	SqM	300	436	-	-	1,30,800.00
		Rupees Four Hundredrs Thirty Six Only					
8	Providing & Constructing Masonry with approved C. C. Solid Blocks of size 400 X 200 X 200 mm / 300 X 200 X 200 mm, having crushing strength not less than 45 Kgs/cm2 and conforming to the BIS 2185 part-I of the latest edition, in CM 1:5 for foundations, trenches, walls, drains, plinths and all other miscellaneous masonry works etc. including simultaneous flush pointing, curing, preparation of base by close hacking / chipping the concrete / plastered surfaces, racking out the adjoining masonry joints & cleaning, providing; fixing & removing necessary staging / platform / ladder, collecting & disposing the generated waste, up to a lead of 3000 to 4000 mtrs. from the place of work & cleaning the work area, etc. complete all as per standard technical specification, drawing [if any] and as directed by engineer-in-charge at all locations & lifts / heights.	CuM	65	8000	-	-	5,20,000.00
		Rupees Eight Thousand Only					
9	Providing & Constructing Burnt Brick Masonry, of 230 mm thick, in CM 1:5 using well Burnt Bricks of standard size & shape for up to plinth level & Super Structure, plinth and all other Miscellaneous Masonry Works including simultaneous flush pointing, curing, preparation of base by close hacking / chipping the concrete / plastered surfaces, racking out the adjoining masonry joints & cleaning, providing; fixing & removing necessary staging / platform, collecting & disposing the general waste up to a lead of 3 Kms. From the place of work & cleaning the work area, etc. complete all as per standard technical specification, drawing [if any] and as directed by engineer-in-charge at all locations & lifts / heights.	CuM	17	8800	-	-	1,49,600.00
		Rupees Eight Thousand Eight Hundredrs Only					
10	Providing and laying Cement Plaster, 15 mm thick for internal surfaces of walls and columns in CM 1:5, rubbed perfectly so as to obtain smooth and even finish including preparation of base by closed hacking / chipping the concrete / plastered surfaces; racking out the adjoining masonry joints and cleaning, curing, providing; fixing removing staging / platform, collecting and disposing the generated waste upto a lead of 3000 meters from the place of work & cleaning the work area etc., complete all as per standard technical specification and as directed by the engineer-in-charge at all locations and at all lifts/heights.	SqM	310	500	-	-	1,55,000.00
		Rupees Five Hundredrs Only					

28.9/24

Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
Rate in Words							
11	Providing, fabricating and erecting Mild Steel Structural items of various thickness & sizes such as channels, angles, I sections, MS pipes, GI Pipes; flats, plates, MS & Reinf. rods, and other approved sections etc. & transporting to the work place, including loading, unloading, cutting, fabricating the MS gates, MS grills, ladders, hand rails, angle frames, panels, struts, tubular space frames, columns, beams, purloins, rafters, fencing posts, EP Plates, EP Flats & all other required miscellaneous structural steel works and fixing / erecting the same in position as directed. Including providing & fixing wherever required suitable anchor Fasteners, of approved quality, providing, fixing and removing necessary scaffolding, staging, platform wherever required, surface preparation, providing & painting One coat of approved Primer and two coats synthetic enamel paint of approved make, shade / colour. disposing the debris up to a lead of 2 to 3 km out side the periphery of the work premises etc., complete all as per specification, and as directed by the Engineer -in-charge at all lifts / heights & at all locations.	MT	14	126000	-	-	17,64,000.00
Rupees One Lakh Twenty Six Thousand Only							
12	Providing and laying 40 mm. thick Indian Patent Stone Flooring with cement concrete 1:2:4 using 10 / 12 mm. & down size, clean, crushed, well graded, cubical shape, sharp edged aggregates of hard, durable & approved quality stones / rubbles including machine mixing, transporting, laying, spreading, compaction, laying in bays to proper line; slope or level etc. using 6 mm. thick plane glass dividing strips for flooring, steps, landings & ramps including smooth finish, providing, fixing & removing necessary staging / platform, collecting & stacking the generated waste / dead debris up to a lead of 100 meters from the place of work etc. complete all as per specifications and as directed by engineer-in-charge at all locations & all lifts / heights.	SqM	585	600	-	-	3,51,000.00
Rupees Six Hundreds Only							
13	Providing, fixing / placing in position Rotary Press; Heavy Duty; Anti skid; 5Star; Short Blasted Paver Blocks of 65 mm thick [of standard size & colour as selected by EIC] of standard make & of superior 1st quality. Paver blocks shall be manufactured as per IS 15658-2006, including 50 mm. thick River Sand / M sand bedding below paver block including preparation of base by proper dressing / leveling and ramming [using Plate Vibrator to have uniform surface and to get the required line & level / gradient, camber] the base with proper watering, the gaps shall be filled with fine sand, ramming top surface of pavers using Plate Vibrator to have uniform surface and to get the required line & level / gradient, camber, collecting & disposing the generated waste, up to a lead of 2 to 3Kmts. from the place of work & cleaning the work area, etc. complete all as per standard technical specification, drawing, manufacturers technical specification and as directed by engineer-in-charge at all locations & lifts.	SqM	300	1100	-	-	3,30,000.00
Rupees One Thousand One Hundreds Only							
14	Providing and Mixing of Wet maccadam using supplied/stacked material with mechanical mixture as per specification, laying, spreading and compacting graded stone aggregate (size range 40 mm to 0.075 mm) including premixing the material with water at OMC for all leads & lifts, laying in uniform layers with manual/mechanical in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne or with suitable vibratory method to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. Note: Net quantity of measurement will be considered	CuM	65	3200	-	-	2,08,000.00
Rupees Three Thousand Two Hundreds Only							
15	Providing and fixing Powder Coated [of approved shade / colour] Aluminium frames and shutters for Windows & Ventilators, partitions & other miscellaneous works with extruded built up standard tubular and other sections of approved make conforming to IS:733 and IS:1285, fixed with rawl plugs and screws, clips, including cleat angle, aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, preparation of base, providing; fixing & removing necessary staging / platform, collecting & disposing the generated waste, up to a lead of 500 mtrs. from the place of work & cleaning the work area, etc. complete all as per standard technical specification, drawing, manufacturers technical specification, as per site requirement and as directed by engineer-in-charge at all locations & lifts / heights. Note: Glazing shall be paid separately under relevant item.	Kg	1000	700	-	-	7,00,000.00
Rupees Seven Hundreds Only							

28/09/24

Co		Name of Work: Miscellaneous Civil Maintenance and Repair works at KGS Unit-1&2, Kaiga. WO / SOQR Number : 102119				Agency Name : M/s Murugan Kannappa			
Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹		
				Rate in Words					
16	Providing and fixing 4 mm thick [minimum] Clear Glass for Windows, Door & Ventilator Shutters and Partitions etc. with nylon clear beading, Glass shall be of approved make and free from all defects including preparation of base, providing; fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification, as per manufacturer's technical specification and as directed by engineer-in-charge at all locations and at all lift & height.	SqM	14	980	-	-	13,720.00		
			Rupees Nine Hundreds Eighty Only						
17	Providing and laying/fixing Suspended False ceiling using Gyp Boards(of approved first quality & of approved make such as of India Gypsum) with GI Grid Work made using Perimeter channels [MF 6A], Ceiling Sections [MF5 : placing at 457 mm. (Maximum) C/C], Intermediate channels [MF7: placing @ 1220 mm. (Maximum) C/C], Ceiling angles 25 x 25 mm. Size, placing @ 1220 mm. (Maximum) C/C], Screws, soffit cleefits, nuts & bolts, connecting clips, Gyp board Dry wall screws, Jointing compound, Tape and all other required miscellaneous materials & consumable [of approved first quality & of approved make, such as of India Gypsum] etc., [all materials shall be conforming to the relevant BIS specification of the latest edition]. Providing & applying One coat of Interior grade primer [Of approved quality & make] and Two coats of plastic emulsion paint of approved shade /colour [of approved quality & make], providing; fixing & removing necessary staging/platform wherever as and when directed/required, collecting & stacking the generated waste / dead debris up to a lead of 100 meters from the place of work etc. complete all as per specifications and as directed by engineer-in-charge at all locations & all lifts / heights.	SqM	50	1300	-	-	65,000.00		
			Rupees One Thousand Three Hundreds Only						
18	Providing, transporting and Filling brick bat minimum size of 50 to 75mm to soak pit, including disposing the balance material & waste upto 2 Km all as per direction of Engineer-In-Charge etc.	CuM	4	3000	-	-	12,000.00		
			Rupees Three Thousand Only						
19	Providing and laying / fixing CPVC Pipes (SDR 11) with its all required plain & brass threaded fittings (Such as collars, elbows, tees, unions, coupling, reducers, enlargers, bends, nipples and all other fittings required for completing the job, as per code of practice for water supply to the buildings [BIS 2065 of the latest edition] of Ashirvad / Finolex / Supreme make including concealing in the wall (Making groove of 75 mm deep in wall with suitable width and finishing same with PCC 1:2: 4 - Using 6 mm downsize aggregate & plastering in cm 1:5) with suitable GI clamps, jointing the pipes & fittings using CPVC solvent, cost of all material like white or red lead, clamps, cement, sand, tools & tackles, testing the pipe with clean water (As per specification) and ensuring smooth functioning, providing , fixing & removing necessary scaffolding / staging / platform, cleaning the work area, collecting & disposing the construction waste up to a lead of 2 to 3 kms. from the place of work etc. complete all as per specification, as per manufacturer's technical specification and as directed by engineer-in-charge at all locations and at all lift & height.						-		
19.1	20 mm dia	RM	20	650	-	-	13,000.00		
			Rupees Six Hundreds Fifty Only						
19.2	25 mm dia	RM	50	560	-	-	28,000.00		
			Rupees Five Hundreds Sixty Only						
19.3	32 mm dia	RM	100	750	-	-	75,000.00		
			Rupees Seven Hundreds Fifty Only						

[Signature]
2/2/19

Co		Name of Work: Miscellaneous Civil Maintenance and Repair works at KGS Unit-1&2, Kaiga. WO / SOQR Number : 102119			Agency Name : M/s Murugan Kannappa		
Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
				Rate in Words			
20	Providing and fixing NP2 Class Precast RCC Septic Tank of size 2.50 meter long & 1.20 meter dia. Including necessary excavation [Size of pit shall be 3.50 meter (L) X 2.2 meter (W) X 1.30 meter (D)] of pit [for placing RCC Septic Tank] in Hard soil; loading; carriage; unloading; lowering [without damaging the RCC Septic Tank] in the pit; aligning [to true line & level / slope etc.]; finishing; ensuring smooth functioning & back filling the sides [as directed] etc.; cleaning the work area & disposing the debris / unwanted materials as directed up to a lead of 500 meters outside the periphery of the work premises etc., complete all as per specification, as per manufacturer's specification and as directed by the Engineer-in-charge at all locations and at all lifts.	Nos	1	40000	-	-	40,000.00
				Rupees Forty Thousand Only			
21	Providing & laying / fixing SWR, Type A, PVC Pipes of 6" dia (160mm) with- for laying below ground with its all required fittings [such as collars, elbows,tees, unions, coupling, reducers, enlargers, bends nipples and all other fittings required for completing th job, as per code of practice for water supply to the buildings -BIS 2065 of the latest edition) for flow of water & waste with water from kitchen, bath, wash basin,urinals & iolets, SWR PVC pipes & fittings shall be of superior 1st quality, of Truflor/ Ashirwad / Astral make and conforming to relevant BIS specification of latest edition including jointing the pipes & fittings using CPVC solvent and ensuring smooth functioning , preparation of base, providing; fixing & removing necessary staging/ platform, collecting & disposing the generated waste up to a lead of 3000 meters from the place of work & cleaning the work area, etc complete all as per standard & manufacturer's technical specification and as directed by the engineer-in-charge at all locations and at all lifts/heights.	RM	60	1100	-	-	66,000.00
				Rupees One Thousand One Hundreds Only			
22	Filling the selected & good quality soil brought from 2 to 3 Kms filling in below plinth level to the required gradient, watering properly and compacting the each layer by using portable hand compactor, collecting & disposing the generated waste-up to a lead of 2 to 3Kms from the place of work & cleaning the work area, etc. complete all as per standard & manufacturers technical specification, drawing (if any) and as directed by Engineer-in- charge at all location and at all lift/height	Cum	170	500	-	-	85,000.00
				Rupees Five Hundreds Only			
23	Providing & laying 300mm dia NP 2 Class RCC Hume Pipes , levelling, aligning to the true line / level / as directed, jointing the Pipes in CM 1:2 with jute; curing the joints properly , preparation of base [before laying pipes, Pipes shall be free from the craks & damage , cleaning the work area & disposing the debris / unwanted materials up to a lead of 100 meters outside the periphery of the work premises etc. complete all as per specifications, as per manufacturers specification and as directed by the engineer-in-charge at all locations & at all lifts.	RM	90	2000	-	-	1,80,000.00
				Rupees Two Thousand Only			
24	Providing & filling Chemical Grout for embedding reinforcement steel using Fischer chemical FIS EM 390S or equivalent material at all locations as per direction of EIC	ml	3000	8	-	-	24,000.00
				Rupees Eight Only			
25	Providing, supplying & erecting Readymade portable toilet/ Urinals made out of FRP, built type modular, of Size 4 feet length, 4 feet width & 8 feet height including fixing necessary urinals/W/C, Aluminium door fittings such as three heavy duty hinges, one aldrops, two minimum 5 inches handles, two tower bolts etc....all as per direction of EIC	Nos	3	63000	-	-	1,89,000.00
				Rupees Sixty Three Thousand Only			
26	Providing, supplying & erecting Readymade portable security cabin made out of FRP, built type modular, of Size 4 feet length, 4 feet width & 8 feet height including fixing necessary urinals/W/C, Aluminium door fittings such as three heavy duty hinges, one aldrops, two minimum 5 inches handles, two tower bolts etc....all as per direction of EIC	Nos	1	158000	-	-	1,58,000.00
				Rupees One Lakh Fifty Eight Thousand Only			

28/09/24

Co		Name of Work: Miscellaneous Civil Maintenance and Repair works at KGS Unit-1&2, Kaiga. WO / SOQR Number : 102119		Agency Name : M/s Murugan Kannappa			
Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹
Rate in Words							
27	Providing and fixing 2 mm thick, PVC flooring of Tusker brand from M/S Krishna Vynils or Royal House brand conforming to relevant BIS specification of latest edition, of approved shades and pattern with necessary adhesive of approved quality, providing; fixing & removing necessary staging / platform / ladder, collecting & disposing the generated waste up to a lead of 2 to 3 kms. from the place of work & cleaning the work area, etc. complete all as per standard & manufacturers technical specification, drawing [if any] and as directed by engineer-in-charge at all locations and at all lift / height.	SqM	150	850	-	-	1,27,500.00
		Rupees Eight Hundreds Fifty Only					
28	Dismantling / breaking / removing of PCC/ BB Masonry by Manual or Mechanical means including collecting & stacking neatly; all serviceable materials [such as stone aggregates - if any] in Civil sectional store, preparation of base, providing; fixing & removing necessary staging / platform / ladder, collecting & disposing the generated waste up to a lead of 2 to 3 kms. from the place of work & cleaning the work area, etc. complete all as per standard technical specification, drawing [if any] and as directed by engineer-in-charge at all locations and at all lift / height.	Cum	18	1000	-	-	18,000.00
		Rupees One Thousand Only					
29	Providing & Constructing R. R. Masonry using Stone Boulders, Stone chips, through / bond Stones [as per standard technical specification, through / bond Stones shall be used in RR masonry work], in CM 1:6 for retaining wall , foundation, repair, modification, alteration & rectification & plinth and other miscellaneous RR masonry works including simultaneous flush pointing, preparation of base by close hacking / chipping the concrete / plastered surfaces, racking out masonry joints & cleaning, providing; fixing & removing necessary staging / platform / ladder, curing, collecting & disposing the generated waste & construction waste etc. up to a lead of 2000 to 3000 meters from the place of work etc. complete all as per standard technical specifications and as directed by engineer-in-charge at all locations & all lifts.	Cum	35	8000	-	-	2,80,000.00
		Rupees Eight Thousand Only					
30	Removing / dismantling / detaching the rusted MS Steel members of structures (s), by cutting, grinding and using other tools including [using miscellaneous things], depositing the same in Civil Sectional Store, providing, fixing, removing necessary staging / platform / ladder, collecting & disposing the generated waste up to a lead of 2 to 3 kms. from the place of work & cleaning the work area, etc. complete all as per standard & manufacturers technical specification, drawing [if any] and as directed by engineer-in-charge at all locations and at all lift / height.	MT	2	10000	-	-	20,000.00
		Rupees Ten Thousand Only					
31	Providing and laying 230mm thick Rough Dry Stone Pitching for side slope of drains, road embankment sides / other back filled area using hard; durable & approved quality stones / rubbles including preparation of base by leveling; dressing to the required slope & hand ramming using hand rammer with proper watering, providing, filling & packing small stones & chips in the gaps properly, providing & laying pointing in CM 1:4, curing, collecting & disposing the generated waste & construction waste etc. up to a lead of 2000 to 3000 meters from the place of work etc. complete all as per standard technical specifications and as directed by engineer-in-charge at all locations & all lifts.	SqM	35	1000	-	-	35,000.00
		Rupees One Thousand Only					
32	Providing and Filling good quality river sand/ M-Sand free from debris around UPVC pipe to the required thickness, line & level as per direction of Engineer-In-Charge etc.	CuM	60	3200	-	-	1,92,000.00
		Rupees Three Thousand Two Hundreds Only					
33	Providing and fixing in position best quality Bib cock of Jaquar code: PRS-CHR-043 or equivalent makee including all necessary fixtures etc., complete as directed by Engineer-in-charge. Note: For Type ,Size,Shape and Pattern Jaquar code: PRS-CHR-043 is to be referred.	Each	15	3000	-	-	45,000.00
		Rupees Three Thousand Only					
34	Providing and fixing in position best quality Pillar cock of Jaquar code: PRS-CHR-031 or equivalent makee including all necessary fixtures etc., complete as directed by Engineer-in-charge. Note: For Type ,Size,Shape and Pattern Jaquar code: PRS-CHR-031 is to be referred.	Nos	10	3000	-	-	30,000.00
		Rupees Three Thousand Only					

28/09/24

Co		Name of Work: Miscellaneous Civil Maintenance and Repair works at KGS Unit-1&2, Kaiga. WO / SOQR Number : 102119				Agency Name : M/s Murugan Kannappa			
Item No	Description	Unit	Quantity	Rate in ₹	Rebate in %	Rebated Rate	Amount in ₹		
Rate in Words									
35	Engaging JCB for removal & disposal of road side collapsed soil / earth; stone boulders; wooden logs; dried trees & other unwanted materials / things which are making obstruction for free movement of men & vehicles etc., cleaning of existing drains for free flow of rain water, formation of new drains for free flow of rain water and other miscellaneous works etc, including hire charges of JCB; operator wages; JCB maintenance charges; cost of diesel & lubricants and tool & tackles etc, collecting & disposing the generated waste up to a lead of 2 to 3 kms. from the place of work & cleaning the work area, etc. complete all as per standard technical specification, drawing [if any] and as directed by engineer-in-charge at all locations and at all lift / height.	Hour	100	1300	-	-	1,30,000.00		
			Rupees One Thousand Three Hundreds Only						
36	Providing, Transporting and Stacking of good quality forest top soil/earth or loamy soil or garden earth (soil/earth should be free from roots, leaves, dust, dirt, stones, stone pebbles & other unwanted matters) including breaking of clods, loading, carriage, unloading, stacking at places wherever & as directed, complete all as directed by Engineer-in-Charge. Note: 1)Borrow pits shall be arranged by the contractor at his/their own cost & risk. 2) Measurement will be based on the truck/tractor volume supplied.	CuM	250	460	-	-	1,15,000.00		
			Rupees Four Hundreds Sixty Only						
37	Providing & installation at all floors, height,levels & locations of Aluminium Composite panel (ACP) Cladding over aluminium tube frame structure including fixing of sheets and filling of joints with structural silicon to acquire a smooth ripple free finish without any undulations. The composite panel sheet shall be a double layer aluminium panel consisting of a anti-toxic polythene layer core compressed between the aluminium layers. One side of the panel shall be a fluorocarbon paint finish in silver colour (as approved) with resistance to fading on exposure in exterior conditions & with a protective film on top to be removed after total completion of cladding. the sheet shall be 3mm thick of total flatness with no distortion or deflection. the sheets shall be corrosion resistant and not be affected by varying temperature variations and should resist thermal expansion. The sheets shall be fixed over aluminium framing system of tubing of size 1" X 1.5" evenly spaced at maximum 2'c/c to provide complete support to the sheets. The sheets shall be fixed to the framing system with double sided tape and duly anchored with maximum no. of screws all groves and finished edges.	SqM	35	5000	-	-	1,75,000.00		
			Rupees Five Thousand Only						
38	Providing and fixing 20 micron thick Sun Control Film of GARWARE or equivalent make, of approved quality, of approved colour/shade & confirming the relevant BIS specification of latest edition including cutting to the required size & shape, fixing the same to the glass panel, also including providing & applying adhesive of approved quality & make, surface preparation properly by cleaning & washing the surface (base) with clean water for removal of oil, grease, dead mortar & other unwanted matters/materials, surface(base) shall be fully neat, clean & dry before fixing sun control film, providing, fixing & removing necessary staging/platform, wherever as & when directed/ required additional lead & lift for carriage of construction/work materials upto the work spots(s)/place(s), cleaning the work area & disposing the debris/unwanted materials upto a lead of 1500 mtrs. outside the periphery of work premises etc. complete all as per specification, as per manufacturer's technical specification and as directed by Engineer-in-Charge at all locations and at all lifts/at all heights.	SqM	110	750	-	-	82,500.00		
			Rupees Seven Hundreds Fifty Only						
39	Providing painting of wall posters/sceneries over canvas 4' width X 3' depth using enamel/Acrylic paint as per drawing approved by EIC including making canvas frame from using canvas and 20X12mm thick soft wooden , enamel/acrylic paint etc complete. Design & drawing shall be approved by EIC before taking up final paints.	Each	4	38000	-	-	1,52,000.00		
			Rupees Thirty Eight Thousand Only						

Note: All Item Rates are considered to be in Indian Rupees unless otherwise explicitly specified and in which case shall be always converted appropriately to arrive at the amount in Indian Rupees.

 28/07/24

Work Order Total	Rs. 1,04,32,820.00
Overall Rebate (%)	3
Work Order Value After Overall Rebate in Figure	Rs. 1,01,19,835.00
Work Order Value After Overall Rebate in Words	Rupees One Crore One Lakh Nineteen Thousand Eight Hundreds Thirty Five Only

28/09/24
[MS, KGS-142]

28/09/24
Head cr

28/09/24

Signature Not Verified

Digitally signed by BASANAGOUDA SHIVAGOUDA NAGAMURI
Date: 2024.10.04 11:20:39 IST
Location: eProcurement System for Central PSUs