

न्यूक्लियर पावर कॉर्पोरेशन ऑफ इंडिया लिमिटेड Nuclear Power Corporation of India Ltd.

(भारत सरकार का उद्यम A Government of India Enterprise)

कुडनकुलम न्यूक्लियर पावर प्रोजेक्ट Kudankulam Nuclear Power Project


कुडनकुलम पोस्ट, राधापुरम तालुक, तिरुनेलवेली जिला, तमिलनाडु 627106-

Kudankulam P.O., Radhapuram Taluk, Tirunelveli District, Tamil Nadu – 627 106

वी.पी. विल्सन, मुख्य अभियंता (ईएंडयूएस) V P WILSON, Chief Engineer (E&US)

☎ 04637- 282553/249801

ई-मेल E-mail: vpwilson@npcil.co.in



सं .No. एनपीसीआईएल NPCIL/केकेएनपीपी KKNPP/C&MM-WG/2025/एस S/47

January 17<sup>th</sup>, 2025

To

M/s. S.A.V. Constructions,  
885, Radhapuram Main Road,  
Vadakkan kulam,  
Thirunelveli District 627116.  
Tamil Nadu.  
Phone: 04637-232333  
Mobile: 9443130652  
E-mail: sav\_constructions@yahoo.co.in;

|                |   |        |
|----------------|---|--------|
| Work Order No. | : | 300484 |
| Subledger Code | : | S10057 |
| Account Code   | : | 78203  |
| Charge Code    | : | 6185   |

Dear Sirs,

Subject : "WORK ORDER" – reg.

Name of work : Construction of toilet facilities for the schools of Government High School Koliyankulam, Government ITI Radhapuram, Arul Primary school, Kaduthula, Hindu Middle school Kudankulam & Sri Mutharamman Middle school Sivasubaramaniapuram at Radhapuram Taluk, Tirunelveli District

- Ref. 1. E-Tender No. : NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2024/132
2. Our letter No. : NPCIL/KKNPP/ C&MM-WG /2024/S/1112, dated: 12.11.2024 (Asking Rate Clarification reg.)
3. Your submission : Nil, dated: 18.11.2024 ( Submission of Rate Clarification letter reg .)



Please refer to your above cited tender in response to e-TENDER NOTICE No:

**NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2024/132** for the above work, Part-I and Part-II were opened on 14.10.2024 and 29.10.2024 respectively.

1. **BID ACCEPTANCE:**

This is to inform you that the tender submitted by you and modified in subsequent letters referred above has been accepted for and on behalf of Nuclear Power Corporation of India Limited, for the items of work shown in the schedule of quantities and rates covered by the tender for a total value of ₹ **1,04,32,105.00 (Rupees One Crore Four lakhs Thirty Two Thousand One hundred and Five only)** inclusive of all applicable taxes, BOCW Cess including Goods and Services Tax (GST).

2. **RATES:**

The rates quoted by the contractor as given in Annexure- 'I' (Schedule of Quantities and rates) are for complete items of work including supply of all materials (unless otherwise specified), consumables, all temporary arrangements, all labours, all taxes (including GST) cess, duties, levies, BOCW cess applicable from time to time and incidental charges as per terms, conditions and specifications mentioned in the tender document will remain firm until the entire period of contract.

Further during execution of the contract due to variation in quantities, if tender structure changes you have agreed to give suitable discount to remain in L1 position.

3. **EXECUTION OF WORK:**

The work shall be carried out strictly in accordance with the terms and conditions and specifications, drawings stipulated in the tender and also in best workmanlike manner. You shall employ and maintain qualified engineers/supervisors in the job at all times. You shall also bring to the site and employ such machinery and equipments and other materials as are necessary for the satisfactory completion of this work.

4. **CONTRACT PERIOD:**

The work shall be completed in all respects within **10 Months (including monsoon period)** from the date of commencement including Sunday, Holidays and rainy season/days, if any. The date of commencement will be reckoned within 14 days from the date of work order. The time shall be essence of the contract and the work shall be completed as per approved programme of work.



**5. CONTRACT PRICE ADJUSTMENT:**

Contract Price Adjustment is not applicable as per clause No.11.3.3 of Schedule :A of General Conditions of Contract.

**6. AUTHORISED OFFICIALS:**

You are requested to submit the name of the authorized Representative who will deal with all matters relating to the contract with the power of Attorney in his favour, duly executed on stamped paper of an appropriate value shall be furnished to Engineer-in-charge.

**7. LIABILITY FOR DAMAGE AND INSURANCE:** (As per clause No.2, Part-I of Special Instructions in Section-III of tender)

You shall provide the following insurance policies in the joint names of the Corporation and the Contractor with insurance cover from the date of commencement of work to the end of the Defects Liability Period. You will be fully responsible for any loss, damage or destruction of NPCIL plant & machineries, property, persons etc.,. Policies submitted should bear the Work Order (WO) number except Group Insurance for which WO number is not mandatory. You shall submit the copies of Insurance policies along with the original policy document to the Engineer-in-charge before the commencement of work.

**7.1 Contractor's All Risk(CAR) Policy**

You shall take Contractor's All Risk(CAR) Policy for the whole contract value (including GST) including Insurance for Third Party Liability for 10% of the work order value including applicable GST i.e, ₹ 10,43,211.00

**7.2 Employees Compensation Policy:**

You shall take the Employees Compensation Policy for employees who are engaged in this work.

**7.3 Group Insurance Policy:**

In case the employees engaged on this work are already covered under the Group Insurance policy of the Contractor, same shall be acceptable in lieu of employee compensation policy. In such case the proof of employment shall be submitted.

**8. TAXES**

8.1 Income tax and statutory levy etc. if any, on this contract, as notified by Central/State Govt. from time to time shall be recovered from your running bills as well as final bill for this work in the prescribed manner. You are requested to submit copy of your GST No. & Permanent Account Number to Engineer-in-charge.



8.2 For GST related compliance (including TDS) refer Special Conditions of Contract (SCC) is attached in Section-IV of tender and clause no 11 of Part-2 of Section-I / NIT.

**9. ENGINEER-IN-CHARGE:**

**Shri. G. Madasamy Scientific Officer-F(Civil)** will be the Engineer-in-charge for this work. You may make necessary arrangements for commencing the work immediately in consultation with Engineer-in-charge.

**10. SECURITY DEPOSIT:**

You may please note that security deposit will be ₹ 10,43,211.00. (@ 10% of the contract value). Initially you will have to submit a performance guarantee for ₹ 5,21,606.00 (50% of security deposit) within 30 days after issue of work order. The remaining amount of security deposit of ₹ 5,21,605.00 will be recovered from the RA bill/ final bill at the rate of 6% of each bill amount. Security deposit amount will not bear any interest. Refer clause No.2, page-3 of Section – II for full details of Security deposit and its release. Defect liability period is **12 months** from the certified date of completion of the contract as per Schedule: A Clause No.9.1.1 of General Conditions of Contract. Failure of furnishing the performance guarantee within 30 days as stated above shall constitute sufficient grounds for cancellation of the award of work.

**11. APPLICABLE LAWS & ACTS:**

You shall comply with various provisions of Contract Labour (Regulation & Abolition) Act 1970, and Rules framed there under from time to time. In case the Contract Labour Act does not apply to your organization the Contractor should intimate the Engineer-in-charge of this work accordingly before commencing the work. Further you shall also comply with the provisions of other laws such as Workmen's Compensation Act 1923, Minimum Wages Act 1948, E.P.F. Act, Bonus Act, Gratuity Act, BOCW cess Act and other Labour Laws as applicable to your organisation. In case NPCIL is required to incur any expenses as Principal Employer under the provisions of the various laws, NPCIL shall be entitled to recover the same from you from your bills.

**12. LABOUR LICENSE :**

If labour license is required to be obtained for the work as per the existing labour laws then the Principal Employer's Certificate required for obtaining Labour License for specified number of workmen proposed to be employed for the work and shall be issued on the request of the Contractor. A request for issue of Principal Employer's Certificate (Form – III) shall be submitted to the Engineer in charge of the work immediately after receipt of work



order. You shall ensure the submission of labour license application within 07 days of issue of Form-III.

**13. PAYMENT TERMS:**

- 13.1 In respect of all items in the schedule of quantities and rates of Work order, the payments shall be made on submission of bills for the work along with the joint measurements, through monthly RA bills, as per General Conditions of Contract of tender & against submission of Tax invoice as applicable to you.
- 13.2 The first running account bill will be paid only after submission of the documents as mentioned in Clause No.15 (A) and 15 (B) of Special instructions in Section-III (Part-I) of tender.
- 13.3 Final bill will be paid only after submission of the documents as mentioned in clause No.15 (C) and 15 (D) of special instructions in Section-III (Part-I) of tender.

**14. PENALTIES:**


Penalties imposed by Engineer-in-charge for non-compliance of work will be recovered from bills of the contractor before release of payment as per clause No.19 of Section-III (Part-I) of tender.

15. All other terms and conditions not specifically brought out in this work order shall be governed as per Special Conditions of Contract, special instructions and General Conditions of Contract.

**16. AGREEMENT:**

You shall enter into contract and shall execute and sign the Contract agreement in accordance with the Articles of Agreement. You shall bring appropriate value Bond paper/ Stamp paper (top page)(as per applicable stamp duty Act at work location) at your own cost in the joint name of NPCIL and the contractor, as mentioned in clause No.10, Part-I of Section-III of tender.

You are requested to attend the office for signing the agreement within 45 days from the date of issue of Work order. Till then a formal agreement document is executed, the original tender together with letters under reference and this Work order shall form the binding contract between us.






**17. ACCEPTANCE OF WORK ORDER:**

Please acknowledge by a letter, the receipt of this work order and the acceptance of the terms and conditions indicated in this contract immediately on issue of work order. Also as a token of acceptance, the Contractor is requested to sign the copy of this work order and send it along with the acceptance letter, to Engineer In-charge (C&MM-Works Group), C-Block, Ground Floor, Kudankulam Nuclear Power Project, Kudankulam P.O, Radhapuram Taluk, Tirunelveli District, Tamil Nadu and a copy to Engineer In-charge of this work.

Thanking you,

Yours faithfully,



वी.पी. विल्सन (V.P.Wilson)

मुख्य अभियंता (ईएंडयूस) Chief Engineer (E&US)

For and on behalf of  
Nuclear Power Corporation of India Ltd

Encl: Schedule of Quantities and Rates – Annexure –'I'





## Print Date: 07-Jan-2025

5.5.5





Name of Work: Construction of toilet facilities for the schools of Government High School Koliyankulam, Government ITI Radhapuram, Arul Primary school, Kaduthula Hindu Middle school Kudankulam & Sri Mutharamman Middle school Sivasubaramaniapuram at Radhapuram Taluk, Tirunelveli District  
WO / SOQR Number : 300484 Tender No.: NPCIL/KNPP/AD/CSR ACTIVITIES/PT/2024/132 Agency Name : M/s.SAV Constructions, Vadakkankulam

| Item No | Item Description                                                                                                                                                                                                                                                                                                                                                                                                            | Unit                                             | Quantity | Rate in ₹ | Rebate in % | Amount in ₹  |
|---------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------|----------|-----------|-------------|--------------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                             | Rate in Words                                    |          |           |             |              |
| 9       | Providing and laying M20/M25 Design mix concrete with cement content up to 350kg/Cum using 20mm and down graded stone aggregates including Mixing, Ramming, Compaction, leveling, curing, placing at all lifts, including scaffolding and Finishing smooth all exposed faces complete as per specification.                                                                                                                 | CuM                                              | 131      | 4500      | 0.00        | 589,500.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                             | Rupees Four Thousand Five Hundreds Only          |          |           |             |              |
| 10      | Providing, placing in position and removing Form work for all insitu concrete works including scaffolding etc., complete at all elevations as per drawing and specification (measurement for form work shall be the area of forms in contact with concrete surfaces)                                                                                                                                                        | SqM                                              | 1052     | 250       | 0.00        | 263,000.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                             | Rupees Two Hundreds Fifty Only                   |          |           |             |              |
| 11      | Providing cutting, bending placing and tying mild steel, high yield steel reinforcement in RCC works including providing spacer blocks in CM 1:2, binding wires etc. complete at all elevations as per drawings and specifications including dewatering wherever necessary etc complete as per drawings and specifications                                                                                                  | MT                                               | 13       | 73500     | 0.00        | 955,500.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                             | Rupees Seventy Three Thousand Five Hundreds Only |          |           |             |              |
| 12      | Providing and constructing brick masonry in CM 1:6, using country bricks, including scaffolding, curing and racking out joints etc complete as per specifications and drawings. In superstructure above plinth at all elevations.                                                                                                                                                                                           | CuM                                              | 241      | 6500      | 0.00        | 1,566,500.00 |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                             | Rupees Six Thousand Five Hundreds Only           |          |           |             |              |
| 13      | Providing cement plaster for the internal faces of brickwork / concrete at all elevations in cement mortar 1:5, 12mm thick using River sand finished smooth with a floating coat of neat cement including scaffolding, finishing, curing, forming grooves wherever necessary all complete as per drawings and specifications                                                                                                | SqM                                              | 1073     | 260       | 0.00        | 278,980.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                             | Rupees Two Hundreds Sixty Only                   |          |           |             |              |
| 14      | Providing cement plaster for the ceiling with 6 mm thick in cement mortar 1:3 using River sand at all elevations including hacking and preparing the surface, scaffolding, finishing, curing etc all complete as per drawings and specifications                                                                                                                                                                            | SqM                                              | 413      | 250       | 0.00        | 103,250.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                             | Rupees Two Hundreds Fifty Only                   |          |           |             |              |
| 15      | Plastering of external faces of brick work/concrete at all elevations in cement mortar 1:4, 20 mm thick using River sand including scaffolding, curing, forming grooves, plaster bands, border, keystone etc wherever required all as per drawings and specifications                                                                                                                                                       | SqM                                              | 1449     | 300       | 0.00        | 434,700.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                             | Rupees Three Hundreds Only                       |          |           |             |              |
| 16      | Plastering the Top of roof slab in Tile pattern design plaster 20mm thick with CM 1:3, 12 mm thick base coat and 8 mm thick for tile pattern design as instructed and the cost inclusive of scaffolding, curing all as per drawings and specifications                                                                                                                                                                      | SqM                                              | 164      | 600       | 0.00        | 98,400.00    |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                             | Rupees Six Hundreds Only                         |          |           |             |              |
| 17      | Providing and applying Acrylic Emulsion paint of Asian paints (Premium Emulsion)/Lewis Berger (Rangoli) /ICI Dulux (Super smooth)/Matex gold of NIPPON make of approved shade in two or more coats over a coat of primer including preparation of surface with required coats of putty using Birla/ JK make, sand papering etc., to get good finish at all elevations etc all as per as per drawings and specifications     | SqM                                              | 1525     | 150       | 0.00        | 228,750.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                             | Rupees One Hundreds Fifty Only                   |          |           |             |              |
| 18      | Providing and applying Exterior Emulsion Paint of Apex of Asian paints/Weather cote of Lewis Berger /Weather shield of ICI Dulux/Sumo Xtra of NIPPON make & shade in two or more coats to give an even shade over a coat of primer as per manufacturer's instructions to the external plastered surfaces including preparation of surfaces, scaffolding etc. at all elevations, complete as per drawings and specifications | SqM                                              | 1435     | 125       | 0.00        | 179,375.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                             | Rupees One Hundreds Twenty Five Only             |          |           |             |              |





Name of Work: Construction of toilet facilities for the schools of Government High School Koliyankulam, Government ITI Radhapuram, Arul Primary school, Kaduthula, Hindu Middle school Kudankulam & Sri Mutharamman Middle school Sivasubaramaniapuram at Radhapuram Taluk, Tirunelveli District  
WO / SOQR Number : 300484 Tender No.:NPCIL/KNPP/AD/CSR ACTIVITIES/PT/2024/132 Agency Name : M/s.SAV Constructions, Vadakkankulam

| Item No | Item Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Unit                                   | Quantity | Rate in ₹ | Rebate in % | Amount in ₹ |
|---------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------|----------|-----------|-------------|-------------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Rate in Words                          |          |           |             |             |
| 19      | Providing and applying two coats of First Quality synthetic enamel paint of Asian paints/ Lewis Berger/ ICI Dulux/NIPPON/NEROLAC make of approved colour over a coat of primer on new wood / steel work, suitably prepared for receiving the paint by surface scraping, rubbing applying filler etc., including cost of filler primer, paint etc all complete as per drawings and specifications                                                                                                                                                                                                                                                                      | SqM                                    | 27       | 125       | 0.00        | 3,375.00    |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Rupees One Hundreds Twenty Five Only   |          |           |             |             |
| 20      | Providing, Fixing and testing PVC rain water pipes of 110 mm dia as per IS-13592 of Type A of "Prince/Jain/ Kitec/Finolex/Supreme" make with necessary fittings and fixtures, such as bottom shoe, PVC grating, GI clamps, screws/nails, wooden packing pieces at minimum 1 m spacing, cost inclusive of Fixing the shoes in brick masonry in CM 1:6 and plastering the same with CM 1:4 etc complete all as per drawings and specifications                                                                                                                                                                                                                          | RM                                     | 36       | 325       | 0.00        | 11,700.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Rupees Three Hundreds Twenty Five Only |          |           |             |             |
| 21      | Supplying, manufacturing and Fixing frames and architraves for windows, ventilators, cupboards etc., with approved quality Malaysian Vengai wood of required sizes fixed in masonry/concrete with three numbers of MS holdfasts of size 40mm width x 5mm thick & 300 mm long on each side of the frame or providing fischer screws of required length for column portions wherever required all as directed, for the various sizes of structural openings including making necessary rebate/stopper for Fixing shutters as per drawings and specifications                                                                                                            | CuM                                    | 0.87     | 110000    | 0.00        | 95,700.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Rupees One Lakh Ten Thousand Only      |          |           |             |             |
| 22      | Providing, fabricating and erection of Structural steel members made out of M.S. angles, flats, plates, pipes, channels, tubes, rods etc conforming to relevant IS etc., including cost of welding, welding rods, drilling holes, bolts/nuts wherever required and providing and applying two or more coats of approved quality synthetic enamel paint over a coat of zinc chromate yellow primer etc., as per drawings and specifications                                                                                                                                                                                                                            | MT                                     | 3        | 90000     | 0.00        | 270,000.00  |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Rupees Ninety Thousand Only            |          |           |             |             |
| 23      | Providing and laying 20mm thick (+-2mm) polished Natural granite slab of approved colour for name board including writing by engraving, painting etc. as per required etc., with all exposed surfaces buffed, set over a base of cement mortar 1:4, 20 mm thick neatly pointed with white cement/black oxide and colouring pigments to match the shade of the stone as per the requirement, curing, rubbing, polishing, etc complete as per specifications and as per drawings and specifications                                                                                                                                                                     | SqM                                    | 14       | 10000     | 0.00        | 140,000.00  |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Rupees Ten Thousand Only               |          |           |             |             |
| 24      | Providing and Fixing 20mm thick Exterior grade designer tiles of approved colour and design over 20mm thick base cement mortar 1:4 laid and pointed with white cement slurry mixed with pigments to match with the shade of the tile including rubbing, curing, in Staircases (both tread & riser), Walkway areas, Entrances etc., as per drawings and specifications                                                                                                                                                                                                                                                                                                 | SqM                                    | 182      | 850       | 0.00        | 154,700.00  |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Rupees Eight Hundreds Fifty Only       |          |           |             |             |
| 25      | Providing and making RCC roof mother slab/sunken slab water proof by injection grout with the approved compound of SIKABASF/ROFF/FOSROC/ Dr.Fixit/ Bostic India make as per the manufacturers procedure/ specification by providing one water proofing membrane system by brush application as water proofing barrier for both slab and inner face of parapet/side wall including water testing by ponding for minimum 7 days and providing joint guarantee for water tightness for 10 years (This item may be got executed by specialized water proofing agents duly approved by NPCIL and 10 years joint guarantee for water proofing is required to be submitted). | SqM                                    | 384      | 475       | 0.00        | 182,400.00  |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Rupees Four Hundreds Seventy Five Only |          |           |             |             |
| 26      | Supply and laying one course of pressed cement tiles 20 mm thick of 250mmX250mm size as per IS:1237 of latest version, laid over the roof slab over a base of 20mm thick CM 1:4 and joints pointed neatly in cement mortar 1:3 mixed with water proofing admixture of approved make etc complete all as per drawings and specifications                                                                                                                                                                                                                                                                                                                               | SqM                                    | 184      | 800       | 0.00        | 147,200.00  |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Rupees Eight Hundreds Only             |          |           |             |             |



**Name of Work:** Construction of toilet facilities for the schools of Government High School Koliyankulam, Government ITI Radhapuram, Arul Primary school, Kaduthula Hindu Middle school Kudankulam & Sri Mutharamman Middle school Sivasubaramaniapuram at Radhapuram Taluk, Tirunelveli District  
**WO / SOQR Number :** 300484 **Tender No.:** NPCIL/KNPP/AD/CSR ACTIVITIES/PT/2024/132 **Agency Name :** M/s.SAV Constructions, Vadakkankulam

| Item No | Item Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Unit          | Quantity | Rate in ₹                      | Rebate in % | Amount in ₹ |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|----------|--------------------------------|-------------|-------------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Rate in Words |          |                                |             |             |
| 27      | Providing and Fixing Terracotta jally of 75mm thick of approved size and pattern including chasing the masonry/concrete if required and Fixing with CM 1:3 true to line and plumb & making good the surfaces, curing etc. at all elevations, complete all as per drawings and specifications                                                                                                                                                                                                                                                                                         | SqM           | 23       | 650                            | 0.00        | 14,950.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |               |          | Rupees Six Hundreds Fifty Only |             |             |
| 28      | Providing drip moulds of CM 1:4, 25mm thick on edges of sunshades including finishing, curing, scaffolding etc complete as per the standard specifications.                                                                                                                                                                                                                                                                                                                                                                                                                          | SqM           | 164      | 100                            | 0.00        | 16,400.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |               |          | Rupees One Hundreds Only       |             |             |
| 29      | Providing and Fixing in position ceramic glazed wall tiles minimum basic price of tiles shall be Rs.50/- Sq.ft without GST (thickness to be specified by the manufactures) of premium quality conforming to IS 15622 of JOHNSON/SOMANY/REGENCY/ASIAN/NITCO/BELL/KAJARIA make laid on 20mm thick Cement Mortar 1:3 (1 cement : 3Coarse sand ) and jointing with grey cement slurry @3.3 kg/Sqm including pointing the joint with white cement mixed with colour pigment of matching shade complete at all floors, all as per specification and as directed by the Engineer in charge. | SqM           | 716      | 800                            | 0.00        | 572,800.00  |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |               |          | Rupees Eight Hundreds Only     |             |             |
| 30      | Providing and Fixing in position vitrified wall tiles by using tiles adhesive of premium quality confirming to IS -15622 of JOHNSON/SOMANY/REGENCY/ASIAN/NITCO/BELL/KAJARIA make in all colour and shades in White, ivory, Gray , Fume red and Brown laid on already plastered surface including pointing the joint with spacer Epoxy joint filling and matching colour pigment etc. at all floors complete all as per directed by Engineer in – charge.                                                                                                                             | SqM           | 192      | 900                            | 0.00        | 172,800.00  |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |               |          | Rupees Nine Hundreds Only      |             |             |
| 31      | Providing and Fixing in position Anti-Skid ceramic floor tiles of approved sizes (thickness to be specified by the manufacturer) of premium quality confirming to IS-15622 of JOHNSON/ SOMANY/ REGENCY/ASIAN/NITCO/BELL/KAJARIA make, in all colours and shades laid on 20mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse Sand) including pointing the joint with white cement and matching colour pigment etc at all floors complete all as per drawings and specifications                                                                                                         | SqM           | 209      | 800                            | 0.00        | 167,200.00  |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |               |          | Rupees Eight Hundreds Only     |             |             |
| 32      | Providing, laying/Fixing in position approved PVC pipes Jain/ Finolex/Kitec/Supreme/Prince make IS - 4985 of latest version with required specials and Fixing arrangements for water Supply works as per standard specifications and providing and Fixing approved nails quality clamps and screws for Fixing as per drawings and specifications. (Excavation if required will be paid under relevant item)                                                                                                                                                                          |               |          |                                | 0.00        |             |
| 32.1    | PVC PIPES – 25mm dia-10kg/cm2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |               |          |                                | 0.00        |             |
| 32.1.1  | Supply                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | RM            | 273      | 30                             | 0.00        | 8,190.00    |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |               |          | Rupees Thirty Only             |             |             |
| 32.1.2  | Fixing                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | RM            | 273      | 30                             | 0.00        | 8,190.00    |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |               |          | Rupees Thirty Only             |             |             |
| 32.2    | PVC PIPES – 32mm dia-10kg/cm2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |               |          |                                | 0.00        |             |

*[Signature]*

*[Signature]*





Name of Work: Construction of toilet facilities for the schools of Government High School Koliyankulam, Government ITI Radhapuram, Arul Primary school, Kaduthula  
Hindu Middle school Kudankulam & Sri Mutharaman Middle school Sivasubaramaniapuram at Radhapuram Taluk, Tirunelveli District  
WO / SOQR Number : 300484 Tender No.:NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2024/132 Agency Name : M/s.SAV Constructions, Vadakkankulam

| Item No | Item Description                                                                                                                                                                                                                                                                                                                                                                                                           | Unit                           | Quantity | Rate in ₹ | Rebate in % | Amount in ₹ |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------|----------|-----------|-------------|-------------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                            | Rate in Words                  |          |           |             |             |
| 32.2.1  | Supply                                                                                                                                                                                                                                                                                                                                                                                                                     | RM                             | 545      | 45        | 0.00        | 24,525.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                            | Rupees Forty Five Only         |          |           |             |             |
| 32.2.2  | Fixing                                                                                                                                                                                                                                                                                                                                                                                                                     | RM                             | 545      | 30        | 0.00        | 16,350.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                            | Rupees Thirty Only             |          |           |             |             |
| 32.3    | PVC PIPES -- 40mm dia-10kg/cm2                                                                                                                                                                                                                                                                                                                                                                                             |                                |          |           | 0.00        |             |
| 32.3.1  | Supply                                                                                                                                                                                                                                                                                                                                                                                                                     | RM                             | 136      | 70        | 0.00        | 9,520.00    |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                            | Rupees Seventy Only            |          |           |             |             |
| 32.3.2  | Fixing                                                                                                                                                                                                                                                                                                                                                                                                                     | RM                             | 136      | 30        | 0.00        | 4,080.00    |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                            | Rupees Thirty Only             |          |           |             |             |
| 33      | Providing and Fixing in position at all elevations PVC pipes of "Prince/Jain/ Kitec/Finolex" make of Type-B conforming to IS 13592 of latest version and specials such as bends, junctions with or without doors, cowls, etc., for soil, waste, vent or anti-syphonage pipes & for under floors etc with necessary clamps and wooden packing pieces at minimum 1 m spacing etc complete as per drawings and specifications |                                |          |           | 0.00        |             |
| 33.1    | 75 mm                                                                                                                                                                                                                                                                                                                                                                                                                      |                                |          |           | 0.00        |             |
| 33.1.1  | Supply                                                                                                                                                                                                                                                                                                                                                                                                                     | RM                             | 137      | 150       | 0.00        | 20,550.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                            | Rupees One Hundreds Fifty Only |          |           |             |             |
| 33.1.2  | Fixing                                                                                                                                                                                                                                                                                                                                                                                                                     | RM                             | 137      | 75        | 0.00        | 10,275.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                            | Rupees Seventy Five Only       |          |           |             |             |
| 33.2    | 110 mm                                                                                                                                                                                                                                                                                                                                                                                                                     |                                |          |           | 0.00        |             |
| 33.2.1  | Supply                                                                                                                                                                                                                                                                                                                                                                                                                     | RM                             | 218      | 250       | 0.00        | 54,500.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                            | Rupees Two Hundreds Fifty Only |          |           |             |             |
| 33.2.2  | Fixing                                                                                                                                                                                                                                                                                                                                                                                                                     | RM                             | 218      | 100       | 0.00        | 21,800.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                            | Rupees One Hundreds Only       |          |           |             |             |
| 33.3    | 160 mm                                                                                                                                                                                                                                                                                                                                                                                                                     |                                |          |           | 0.00        |             |

G. V. Manoj





Name of Work: Construction of toilet facilities for the schools of Government High School Koliyankulam, Government ITI Radhapuram, Arul Primary school, Kaduthula Hindu Middle school Kudankulam & Sri Mutharamman Middle school Sivasubaramaniapuram at Radhapuram Taluk, Tirunelveli District  
WO / SOQR Number : 300484 Tender No.:NPCIL/KKNPP/AD/CSR ACTIVITIES/PT/2024/132 Agency Name : M/s.SAV Constructions, Vadakkankulam

| Item No                               | Item Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Unit | Quantity | Rate in ₹ | Rebate in % | Amount in ₹ |
|---------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|-----------|-------------|-------------|
| Rate in Words                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |          |           |             |             |
| 33.3.1                                | Supply                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | RM   | 82       | 500       | 0.00        | 41,000.00   |
| Rupees Five Hundreds Only             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |          |           |             |             |
| 33.3.2                                | Fixing                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | RM   | 82       | 125       | 0.00        | 10,250.00   |
| Rupees One Hundreds Twenty Five Only  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |          |           |             |             |
| 34                                    | Providing and Fixing in position approved vitreous chinaware orissa pattern Water Closet 580 mm x 440 mm Hindware/Cera/Nycer/ Parryware/Prayag/Johnson/Somany make with "S" or "P" trap with all jointing materials including excavation, making hole in masonry, reconstructing the same, encasing the pan and trap with brick jelly concrete 1:2:4 and finishing the same etc., complete as per drawings and specifications                                                                                                                         |      |          |           | 0.00        |             |
| 34.1                                  | Supply                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | No.  | 23       | 2000      | 0.00        | 46,000.00   |
| Rupees Two Thousand Only              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |          |           |             |             |
| 34.2                                  | Fixing                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | No.  | 23       | 1000      | 0.00        | 23,000.00   |
| Rupees One Thousand Only              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |          |           |             |             |
| 35                                    | Providing and Fixing PVC flushing cistern of 10 liters capacity Hindware/Cera/ Nycer/ Parryware/ Prayag/Johnson/Somany make with all syphonic fittings, including assembling the cistern components and flush pipe, testing etc., Complete all as per drawings and specifications                                                                                                                                                                                                                                                                     |      |          |           | 0.00        |             |
| 35.1                                  | Supply                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | No.  | 23       | 1100      | 0.00        | 25,300.00   |
| Rupees One Thousand One Hundreds Only |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |          |           |             |             |
| 35.2                                  | Fixing                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | No.  | 23       | 250       | 0.00        | 5,750.00    |
| Rupees Two Hundreds Fifty Only        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |          |           |             |             |
| 36                                    | Providing and Fixing in position approved European type water closet of Hindware/Cera/ Nycer/Parryware/Prayag/Johnson/Somany make comprising of a) Wash down EWC in white glazed vitreous chinaware with integral "P" of "S" trap with or without vent and jointing the trap with soil pipe in CM 1:1 b) Hindware/Cera/ Nycer/Parryware make PVC 10 liters capacity low level flushing cistern with all syphonic fittings. c) White solid plastic seat cover with CP pillar hinges and rubber buffers etc complete as per drawings and specifications |      |          |           | 0.00        |             |
| 36.1                                  | Supply                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | No.  | 14       | 3000      | 0.00        | 42,000.00   |
| Rupees Three Thousand Only            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |          |           |             |             |

Handwritten signature

Handwritten signature





9. m



Name of Work: Construction of toilet facilities for the schools of Government High School Koliyankulam, Government ITI Radhapuram, Arul Primary school, Kaduthula

Hindu Middle school Kudankulam & Sri Mutharaman Middle school Sivasubaramaniapuram at Radhapuram Taluk, Tirunelveli District

WO / SOQR Number : 300484

Tender No.:NPCIL/KKNP/AD/CSR ACTIVITIES/PT/2024/132

Agency Name : M/s.SAV Constructions, Vadakkankulam

| Item No | Item Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Unit          | Quantity | Rate in ₹                             | Rebate in % | Amount in ₹ |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|----------|---------------------------------------|-------------|-------------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Rate in Words |          |                                       |             |             |
| 41      | Providing and Fixing best quality PVC 150 x 150 mm size square mouth Gully trap and 100 mm P type outlet, "Supreme/Prince/Star/Finolex" make as per relevant IS and constructing brick masonry chamber 300 mm x 300 mm internal size in 110 mm thick fly ash brick masonry in CM 1:5 using fly ash bricks as per IS:12894, class designation : 5 from the approved manufacturer by NPCIL, with necessary excavation with bed of 100 mm thick cement concrete 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate of nominal size) for foundation and around the trap and plastering with CM 1:3 (1 cement : 3 fine sand) 15 mm thick on internal and external surfaces on top and up to 150 mm below ground level, finished smooth, curing providing and Fixing double seal CI cover and frame of weight not less than 7.0 kgs (as per relevant IS), at top etc complete as per drawings and specifications. (Earth work excavation will be paid under relevant item.) | No.           | 14       | 3000                                  | 0.00        | 42,000.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |               |          | Rupees Three Thousand Only            |             |             |
| 42      | Construction of inspection chambers of internal clear dimension 450 x450 up to a maximum depth of 600mm in 230 mm thick fly ash brick masonry in CM 1:6 using fly ash bricks as per IS:12894, class designation : 5 from the approved manufacturer by NPCIL, over a bed of 150mm thick 1:4:8 cement concrete foundation, plastering with CM 1:4, 20mm thick on inside, outside and all exposed surface finished with floating coat of neat cement, PCC 1: 2:4 for benching and channel finished with neat cement. Top covered with 100mm thick RCC 1:2:4 grade slab with required steel reinforcements, including providing & Fixing double seal C.I. manhole cover & frame of 450x 450mm weight not less than 38 kg (as per relevant IS), embedding the C.I. frame in RCC cover slab etc complete as per drawings and specifications. (Earth work excavation and steel reinforcement will be paid under relevant item)                                                       | No.           | 12       | 8000                                  | 0.00        | 96,000.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |               |          | Rupees Eight Thousand Only            |             |             |
| 43      | Providing and Fixing single/multi PVC Nahani trap of self cleaning design with 75 mm dia outlet, "Supreme/Prince/Star/Finolex/Jain/Kitec" make as per relevant IS, Stainless steel Grating and including necessary cement concrete 1:2:4 for embedding and making good the floor, connecting the trap to the waste pipe, forming circular hole up to floor level and rendering smooth etc. Complete as per drawings and specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | No.           | 19       | 175                                   | 0.00        | 3,325.00    |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |               |          | Rupees One Hundreds Seventy Five Only |             |             |
| 44      | Providing and Fixing heavy quality 15 mm dia, CP brass screw down short bodied bib tap with CP brass flanges as per relevant IS, "ADSON/CERA/PARRYWARE" make as per drawings and specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |               |          | 0.00                                  |             |             |
| 44.1    | Supply                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | No.           | 38       | 800                                   | 0.00        | 30,400.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |               |          | Rupees Eight Hundreds Only            |             |             |
| 44.2    | Fixing                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | No.           | 38       | 10                                    | 0.00        | 380.00      |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |               |          | Rupees Ten Only                       |             |             |
| 45      | Providing and Fixing heavy quality 15mm dia CP brass angle cock as per relevant IS, "ADSON/CERA/PARRYWARE" make as per drawings and specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |               |          | 0.00                                  |             |             |
| 45.1    | Supply                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | No.           | 38       | 700                                   | 0.00        | 26,600.00   |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |               |          | Rupees Seven Hundreds Only            |             |             |

Chk.

9.11.2024





4.5

Chick-





| Item No | Item Description                                                                                                                                                                                                                                                                            | Unit | Quantity                              | Rate in ₹     | Rebate in % | Amount in ₹ |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---------------------------------------|---------------|-------------|-------------|
|         |                                                                                                                                                                                                                                                                                             |      |                                       | Rate in Words |             |             |
| 51.2    | Boring/drilling borehole of 6" dia, by suitable method including hire & running charges of all equipments, tools, plants, machineries and manpower required for the job, all complete as per direction of Engineer -in-charge, from 91 meter to 120 meter depth below ground level.         | RM   | 90                                    | 275           | 0.00        | 24,750.00   |
|         |                                                                                                                                                                                                                                                                                             |      | Rupees Two Hundreds Seventy Five Only |               |             |             |
| 51.3    | Boring/drilling borehole of 6" dia, by suitable method including hire & running charges of all equipments, tools, plants, machineries and manpower required for the job, all complete as per direction of Engineer -in-charge, from 121 meter to 150 meter depth below ground level.        | RM   | 90                                    | 300           | 0.00        | 27,000.00   |
|         |                                                                                                                                                                                                                                                                                             |      | Rupees Three Hundreds Only            |               |             |             |
| 51.4    | Boring/drilling borehole of 6" dia, by suitable method including hire & running charges of all equipments, tools, plants, machineries and manpower required for the job, all complete as per direction of Engineer -in-charge, from 151 meter to 180 meter depth below ground level.        | RM   | 90                                    | 300           | 0.00        | 27,000.00   |
|         |                                                                                                                                                                                                                                                                                             |      | Rupees Three Hundreds Only            |               |             |             |
| 51.5    | Supplying, assembling, lowering and fixing in vertical position in borehole 7" dia PVC casing pipe of including hire & labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer-in-charge.                                                    | RM   | 90                                    | 1200          | 0.00        | 108,000.00  |
|         |                                                                                                                                                                                                                                                                                             |      | Rupees One Thousand Two Hundreds Only |               |             |             |
| 51.6    | supplying Bore well materials like 1.5 HP Texmo make submersible pump 32mm dia out let pipe , panel board,2.5mm cable,nylon rope 16mm dia,GI adopter,GI bend,GI clamp,GI elbo,end caps,insulation tape,mrf tape etc for the successful commissioning of pump in the bore well etc complete. | NO.  | 3                                     | 38000         | 0.00        | 114,000.00  |
|         |                                                                                                                                                                                                                                                                                             |      | Rupees Thirty Eight Thousand Only     |               |             |             |
| 51.7    | Providing and fixing open well submersible 1 HP Pump KSB make. with starter and cable 1.5 SqMM ,Tufflon tap, and etc complete.                                                                                                                                                              | NO.  | 2                                     | 10000         | 0.00        | 20,000.00   |
|         |                                                                                                                                                                                                                                                                                             |      | Rupees Ten Thousand Only              |               |             |             |
| 51.8    | Labour charges for fixing upto 90M                                                                                                                                                                                                                                                          | RM   | 270                                   | 30            | 0.00        | 8,100.00    |
|         |                                                                                                                                                                                                                                                                                             |      | Rupees Thirty Only                    |               |             |             |
| 51.9    | Labour charges for fixing 90M to 150M(in addition to 49.6.1 above)                                                                                                                                                                                                                          | RM   | 180                                   | 25            | 0.00        | 4,500.00    |
|         |                                                                                                                                                                                                                                                                                             |      | Rupees Twenty Five Only               |               |             |             |
| 51.10   | Labour charges 150m to 305 m                                                                                                                                                                                                                                                                | RM   | 90                                    | 35            | 0.00        | 3,150.00    |
|         |                                                                                                                                                                                                                                                                                             |      | Rupees Thirty Five Only               |               |             |             |
| 51.11   | Supplying UPvc bore well out let threaded pipe of 32mm dia CRI/FINOLEX/PRINCE or as per revelant IS make for bore wells.                                                                                                                                                                    | RM   | 525                                   | 200           | 0.00        | 105,000.00  |
|         |                                                                                                                                                                                                                                                                                             |      | Rupees Two Hundreds Only              |               |             |             |

**Schedule : CSR Activities:B(ELECT**

Schedule : CSR Activities:B(ELECT

Chalk

5.  $\frac{1}{2}$





Abul

5. Wavy





g. b. t.

Chh



Note.: All Item Rates are considered to be in Indian Rupees unless otherwise explicitly specified and in which case shall be always converted appropriately to arrive at the amount in Indian Rupees.

|                                                    |                                                                       |
|----------------------------------------------------|-----------------------------------------------------------------------|
| Work Order Total                                   | ₹10432105                                                             |
| Overall Rebate (%)                                 | 0                                                                     |
| Work Order Value After Overall Rebate (in Figure ) | ₹10432105                                                             |
| Final Work Order Value (in Figure)                 | ₹10432105                                                             |
| Final Work Order Value (in words)                  | Rupees One Crore Four Lakh Thirty Two Thousand One Hundreds Five Only |

*Chakr.*

*G.V.*  
17/01/2025



Cc: **Distribution:** (Through E-mail)

- |     |                        |                                                                                                                                                                   |
|-----|------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1.  | Site Director          | - For kind information                                                                                                                                            |
| 2.  | Station Director (1&2) | - -do-                                                                                                                                                            |
| 3.  | CE (E&US)              | - With Schedule of Quantities & Rates                                                                                                                             |
| 4.  | Chairman, CSR          | - With Schedule of Quantities & Rates                                                                                                                             |
| 5.  | Head(C&MM)             | With Schedule of Quantities & Rates                                                                                                                               |
| 6.  | Head(C&MM-Works Group) | With Schedule of Quantities & Rates                                                                                                                               |
| 7.  | AGM(F&A)               | - With Schedule of Quantities & Rates, Approval for Award of work, copy of vetted work order, Rate Clarification Letter, CST, Admin approval & Technical Sanction |
| 8.  | Engineer-in-charge     | - With Schedule of Quantities & Rates, Approval for Award of work, CST & Rate Clarification Letter                                                                |
| 9.  | Head (HR)              | -                                                                                                                                                                 |
| 10. | Head ( IS&F -1&2)      | - with Schedule-A                                                                                                                                                 |
| 11. | Commandant, CISF       | -                                                                                                                                                                 |
| 12. | Tender File            | -                                                                                                                                                                 |
| 13. | Work order File        | -                                                                                                                                                                 |