

न्यूक्लियर पावर कॉर्पोरेशन ऑफ इंडिया लिमिटेड Nuclear Power Corporation of India Ltd.

(भारत सरकार का उद्यम A Government of India Enterprise)

कुडनकुलम न्यूक्लियर पावर प्रोजेक्ट Kudankulam Nuclear Power Project


कुडनकुलम पोस्ट, राधापुरम तालुक, तिरुनेलवेली जिला, तमिलनाडु-627106

Kudankulam P.O., Radhapuram Taluk, Tirunelveli District, Tamil Nadu – 627 106

V.P WILSON, Chief Engineer (E&US)

☎ 04637- 282553/249801

ई-मेल E-mail: vpwilson@npcil.co.in



सं. No. एनपीसीआईएल NPCIL/केकेएनपीपी KKNPP/C&MM-WG/2025/एस S/525

June , 11th , 2025

To

A.Sankaralingam,
35A, Sacred Heart School Street,
Panagudi-627 109,
Radhapuram Taluk,
Thirunelveli District 627116.
Tamil Nadu.
Mobile: 9443110062 & 95003 95180

Work Order No.	:	201049
Subledger Code	:	S10184
Account Code	:	14390
Charge Code	:	6185

Dear Sirs,

Subject : "WORK ORDER" – reg.

Name of work : Providing covered structural steel fabricated shed for open air stage behind Saralswaram at Anuvijay Township.

Ref. 1. E-Tender No. : NPCIL/KKNPP/CONST/CIVIL-INFRA/PT/2024/138

2. Our ref No. : Through CPP Portal dated 23.11.2024.
(Bid Auto Extension up to 28.11.2024 Corrigendum reg.)

3. Our ref No. : Through CPP Portal dated 25.02.2025
(Shortfall documents submission confirmation reg.)

4. Your letter : dated 21.04.2025
(Acceptance of Bid validity period extension up to 31.05.2025 reg.)

5. Your letter : dated 09.06.2025 (Acceptance of Bid validity period extension up to 30.06.2025 reg.)

Please refer to your above cited tender in response to e-TENDER NOTICE No:

NPCIL/KKNPP/CONST/CIVIL-INFRA/PT/2024/138 for the above work, Part-I and Part-II were opened on 02.12.2024 and 14.03.2025 respectively.

1. **BID ACCEPTANCE:**

This is to inform you that the tender submitted by you and modified in subsequent letters referred above has been accepted for and on behalf of Nuclear Power Corporation of India Limited, for the items of work shown in the schedule of quantities and rates covered by the tender for a total value of **₹ 34,48,337.00 (Rupees Thirty Four lakhs Forty Eight Thousand Three hundred and Thirty Seven only)** Inclusive of all applicable taxes, BOCW Cess including Goods and Services Tax (GST).

2. **RATES:**

The rates quoted by the contractor as given in Annexure- 'I' (Schedule of Quantities and rates) are for complete items of work including supply of all materials (unless otherwise specified), consumables, all temporary arrangements, all labours, all taxes (including GST) levies, BOCW Cess applicable from time to time and incidental charges as per terms, conditions and specifications mentioned in the tender document will remain firm until the entire period of contract.

3. **EXECUTION OF WORK:**


The work shall be carried out strictly in accordance with the terms and conditions and specifications, drawings stipulated in the tender and also in best workmanlike manner. You shall employ and maintain qualified engineers/supervisors in the job at all times. You shall also bring to the site and employ such machinery and equipments and other materials as are necessary for the satisfactory completion of this work.

4. **CONTRACT PERIOD:**

The work shall be completed in all respects within **08 Months (including monsoon period)** from the date of commencement including Sunday, Holidays and rainy season/days, if any. The date of commencement will be reckoned within 14 days from the date of work order. The time shall be essence of the contract and the work shall be completed as per approved programme of work.

5. **CONTRACT PRICE ADJUSTMENT:**

Contract Price Adjustment is not applicable as per clause No.11.3.3 of Schedule: A of General Conditions of Contract.



6. AUTHORISED OFFICIALS:

You are requested to submit the name of the authorized Representative who will deal with all matters relating to the contract with the power of Attorney in his favour, duly executed on stamped paper of an appropriate value shall be furnished to Engineer-in-charge.

7. LIABILITY FOR DAMAGE AND INSURANCE: (As per clause No.2, Part-I of Special Instructions in Section-III of tender)

You shall provide the following insurance policies in the joint names of the Corporation and the Contractor, insurance cover from the date of commencement of work to the end of the Defects Liability Period. You will be fully responsible for any loss, damage or destruction of NPCIL plant & machineries, property, persons etc., Policies submitted, should bear the Work Order (WO) number except Group Insurance for which WO number is not mandatory. You have to submit the copies of Insurance policies along with the original policy document to the Engineer-in-charge before the commencement of work.

7.1 Contractor's All Risk (CAR) Policy

You shall take Contractor's All Risk (CAR) Policy for the whole contract value i.e, ₹ 34,48,337.00 (including GST). The Insurance amount shall also cover third Party Liability for 10% of the work order value i.e, ₹ 3,44,834.00

7.2 Employees Compensation Policy:

You shall take the Employees Compensation Policy for employees who are engaged in this work.

7.3 Group Insurance Policy:

In case the employees engaged on this work are already covered under the Group Insurance policy of the Contractor, same shall be acceptable in lieu of employee compensation policy. In such case the proof of employment shall be submitted.

8. TAXES

8.1 Income tax and statutory levy etc. if any, on this contract, as notified by Central/State Govt. from time to time shall be recovered from your running bills as well as final bill for this work in the prescribed manner. You are requested to submit copy of your GST No. & Permanent Account Number to Engineer-in-charge.

8.2 For GST related compliance (including TDS) refer Special Conditions of Contract (SCC) is attached in Section-IV of tender and clause no 11 of Section-I / NIT.

9. ENGINEER-IN-CHARGE:

Smt.Maloth Rajitha, Technical Officer/D(Civil) will be the Engineer-in-charge for this work. You may make necessary arrangements for commencing the work immediately in consultation with Engineer-in-charge.

10. SECURITY DEPOSIT:

You may please note that security deposit will be ₹ 3,44,834.00 (@ 10% of the contract value). Initially you will have to submit a performance guarantee for ₹ 1,72,417.00 (50% of security deposit) within 30 days after issue of work order. The remaining amount of security deposit of ₹ 1,72,417.00 will be recovered from the RA bill/ final bill at the rate of 6% of each bill amount. Security deposit amount will not bear any interest. Refer clause No.2, page-3 & 4 of Section – II for full details of Security deposit and its release. Defect liability period is **12 months** from the certified date of completion of the contract as per Schedule: A Clause No.9.1.1 of General Conditions of Contract. Failure of furnishing the performance guarantee within 30 days as stated above shall constitute sufficient grounds for cancellation of the award of work.

11. APPLICABLE LAWS & ACTS:

You shall comply with various provisions of Contract Labour (Regulation & Abolition) Act 1970, and Rules framed there under from time to time. In case the Contract Labour Act does not apply to your organization the Contractor should intimate the Engineer-in-charge of this work accordingly before commencing the work. Further you shall also comply with the provisions of other laws such as Workmen's Compensation Act 1923, Minimum Wages Act 1948, E.P.F. Act, Bonus Act, BOCW Cess Act, Gratuity Act and other Labour Laws as applicable to your organization. In case NPCIL is required to incur any expenses as Principal Employer under the provisions of the various laws, NPCIL shall be entitled to recover the same from you from your bills.

12. LABOUR LICENSE :

If labour license is required to be obtained for the work as per the existing labour laws then the Principal Employer's Certificate required for obtaining Labour License for specified number of workmen proposed to be employed for the work and shall be issued on the request of the Contractor. A request for issue of Principal Employer's Certificate (Form – III) shall be submitted to the Engineer in charge of the work immediately after receipt of work order. You shall ensure the submission of labour license application within 07 days of issue of Form-III.

13. PAYMENT TERMS:

- 13.1 In respect of all items in the schedule of quantities and rates of Work order, the payments shall be made on submission of bills for the work along with the joint measurements, through monthly RA bills, as per General Conditions of Contract of tender & against submission of Tax invoice as applicable to you.
- 13.2 The first running account bill will be paid only after submission of the documents as mentioned in Clause No.15 (A) and 15 (B) of Special instructions in Section-III (Part-I) of tender.
- 13.3 Final bill will be paid only after submission of the documents as mentioned in clause No.15 (C) and 15 (D) of special instructions in Section-III (Part-I) of tender.

14. PENALTIES:

Penalties imposed by Engineer-in-charge for non-compliance of work will be recovered from bills of the contractor before release of payment as per clause No.19 of Section-III (Part-I) of tender.

15. All other terms and conditions not specifically brought out in this work order shall be governed as per Special Conditions of Contract, special instructions and General Conditions of Contract.

16. AGREEMENT:

You shall enter into contract and shall execute and sign the Contract agreement in accordance with the Articles of Agreement. You shall bring appropriate value Bond paper/ Stamp paper (top page)(as per applicable stamp duty Act at work location) at your own cost in the joint name of NPCIL and the contractor, as mentioned in clause No.10, Part-I of Section-III of tender.

You are requested to attend the office for signing the agreement within 30 days from the date of issue of Work order. Till then a formal agreement document is executed, the original tender together with letters under reference and this Work order shall form the binding contract between us.



17. ACCEPTANCE OF WORK ORDER:

Please acknowledge by a letter, the receipt of this work order and the acceptance of the terms and conditions indicated in this contract immediately on issue of work order. Also as a token of acceptance, the Contractor is requested to sign the copy of this work order and send it along with the acceptance letter, to Engineer In-charge (C&MM-Works Group), C-Block,

Ground Floor, Kudankulam Nuclear Power Project, Kudankulam P.O, Radhapuram Taluk, Tirunelveli District, Tamil Nadu and a copy to Engineer In-charge of this work.

Thanking you,

Yours faithfully,




(V.P.Wilson)

Chief Engineer (E&US)

For and on behalf of

Nuclear Power Corporation of India Ltd

Encl: Schedule of Quantities and Rates – 'I'



NUCLEAR POWER CORPORATION OF INDIA LIMITED
(A Government of India Enterprise)
Kudankulam Nuclear Power Project
Schedule Of Quantities And Rates

Name of Work: Providing covered structural steel fabricated shed for open air stage behind Saralswaram at Anuvijay Township. WO / SOQR Number : 201049 Tender No.:NPCIL/KKNPP/CONST/CIVIL-INFRA/PT/2024/138 Agency Name : A.Sankaralingam, Panagudi						
Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
Rate in Words						
Schedule : Civil-Infra:ASchA						
1	Earth work excavation by mechanical means(hydraulic excavator)/manual means for foundation, trenches etc., in all types of soils below ground level including shoring, strutting, bailing / pumping of water, leveling, ramming the bottom of excavation, refilling with selected excavated materials in the sides of the foundation in layers, consolidating and disposing off the surplus earth at places as directed within a lead of 50 m all as per drawings and specifications. - up to 1.5m ht	Cu. Meter	220	140	0.00	30,800.00
			Rupees One Hundreds Forty Only			
2	Providing and laying plain cement concrete 1:3:6, using 40 mm and down graded stone aggregate at all height including mechanical mixing, leveling, compaction, vibrating, finishing smooth the exposed surfaces of concrete, curing etc complete as per drawings and standard specifications.	Cu. Meter	12	5500	0.00	66,000.00
			Rupees Five Thousand Five Hundreds Only			
3	Providing and laying M20/M25 Design mix concrete with cement content up to 350kg/Cum using 20mm and down graded stone aggregates including Mixing, Ramming, Compaction, leveling, curing, placing at all lifts, including scaffolding and Finishing smooth all exposed faces complete as per specification.	Cu. Meter	50	6800	0.00	340,000.00
			Rupees Six Thousand Eight Hundreds Only			
4	Providing cutting ,bending placing and tying mild steel, high yield steel reinforcement in RCC works including providing spacer blocks in CM 1:2, binding wires etc.complete at all elevations as per drawings and specifications including dewatering wherever necessary etc complete as per drawings and specifications	MT	6	90000	0.00	540,000.00
			Rupees Ninety Thousand Only			
5	Providing, fabricating and erection of Structural steel members made out of M.S. angles, flats, plates, pipes, channels, tubes, rods etc conforming to relevant IS etc., including cost of welding, welding rods, drilling holes, bolts/nuts wherever required and providing and applying two or more coats of approved quality synthetic enamel paint over a coat of zinc chromate yellow primer etc., as per drawings and specifications	MT	13	110000	0.00	1,430,000.00
			Rupees One Lakh Ten Thousand Only			
6	Providing and Fixing roofing at all elevations using Zinc-Aluminium alloy coated profile sheet of 0.45 mm thickness of TATA "Durashine" make or equivalent of approved colour including all shapes, over laps, side cladding, ridges, eaves board, gutters etc., including Supplying and Fixing of necessary 6mm dia J or L GI hooks, bolts, nuts, screws, bitumen washers, sealing of joints etc., complete all as per manufacturer's recommendations including scaffolding as per drawings and specifications. (Note: Payment shall be made only to the superficial area. No over laps, corrugations /profile shall be measured)	Sq. Meter	300	720	0.00	216,000.00
			Rupees Seven Hundreds Twenty Only			




Name of Work: Providing covered structural steel fabricated shed for open air stage behind Saralswaram at Anuvijay Township.
WO / SOQR Number : 201049 **Tender No.:** NPCIL/KKNPP/CONST/CIVIL-INFRA/PT/2024/138
Agency Name : A.Sankaralingam, Panagudi

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
		Rate in Words				
7	Providing and constructing brick masonry in CM 1:6, using country bricks, including scaffolding, curing and racking out joints etc complete as per specifications and drawings.				0.00	
7.1	In superstructure above plinth at all elevations.	Cu. Meter	13	6400	0.00	83,200.00
		Rupees Six Thousand Four Hundreds Only				
8	Plastering of external faces of brick work/concrete at all elevations in cement mortar 1:4, 20 mm thick including scaffolding, curing, forming grooves, plaster bands, border, keystone etc wherever required all as per drawings and specifications	Sq. Meter	100	410	0.00	41,000.00
		Rupees Four Hundreds Ten Only				
9	Providing and applying exterior emulsion paint of ACE of ASIAN/ Promise of ICI DULUX/Wall masta of LEWIS BERGER/ Atom 2 in 1 of NIPPON make & shade in two or more coat over a coat of approved primer to give an even shade as per manufacturer's instruction to the external plastered surfaces including preparation of surfaces, scaffolding etc. at all elevations, complete as per drawings and specifications	Sq. Meter	100	210	0.00	21,000.00
		Rupees Two Hundreds Ten Only				
10	Providing, placing in position and removing Form work for all insitu concrete works including scaffolding etc., complete at all elevations as per drawing and specification (measurement for form work shall be the area of forms in contact with concrete surfaces)	Sq. Meter	230	500	0.00	115,000.00
		Rupees Five Hundreds Only				
11	Providing and laying 230mm thick dry stone pitching using 230mm thick random rubble stones including preparation of bed in proper slope and spreading locally available earth over pitching to fill up the gaps as binding material etc., complete	Sq. Meter	150	500	0.00	75,000.00
		Rupees Five Hundreds Only				
Schedule : Civil-Infra:BSchB						
1	PDB : Providing and erection of 6 way three phase double door distribution board with complete interconnection Copper busbar, Neutral bar, Earth bar, top and bottom removable gland plates with knockout, and with the following 40A 4P Isolator-1 No.32A 4P RCCB (30 mA) - 1 no, 25A 2P RCCB(30mA) -1No. 32A TP MCB-1No.25A SP MCB-1 No and 20A/16A/6A SP MCB - 6 Nos (Make: Legrand/havells/GM) Scope includes construction of pedestal cubicle and Providing of necessary electrical components, hardwares for fixing the panel etc. to complete the work in all aspect.	SET	1	20855	0.00	20,855.00
		Rupees Twenty Thousand Eight Hundreds Fifty Five Only				

Name of Work: Providing covered structural steel fabricated shed for open air stage behind Saralswaram at Anuvijay Township.
WO / SOQR Number : 201049 **Tender No.:** NPCIL/KKNPP/CONST/CIVIL-INFRA/PT/2024/138
Agency Name : A.Sankaralingam, Panagudi

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
				Rate in Words		
2	Primary wiring:- For lighting, ceiling fan, and bulkhead fitting points, supply and wiring for point with two + one (earth-green) runs of 1.5sq.mm (22/0.3) 1100V grade FRLS insulated single core multi strand Copper conductor wire (Make:RR cables/polycab/KEI/Havells/Glosters) (without joint) drawn into the existing PVC conduit (inclusive of Providing and laying of PVC conduits while concreting), complete with angle / batten lamp holder or ceiling rose, 5 Amps modular type. Switch including pulling the wire from existing switch box to lighting point through the conduit and connecting at both ends. (Providing of the box, grid plate and the cover plate are not covered under this item.). All items such as 1.5sq.mm (22/0.3) Copper FRLS insulated wire, 6 Amps switch, 3 Plate ceiling rose, hylam sheet for JB's, necessary electrical components for wiring works (wherever applicable) shall be provided by the contractor as per the requirement. (Approximate length 13Mtr)	Nos	15	2406	0.00	36,090.00
		Rupees Two Thousand Four Hundreds Six Only				
3	Secondary wiring:- For lighting, 6A sockets supply and wiring for point with two + one (earth-green) runs of 1.5sq.mm (22/0.3) 1100V grade FRLS insulated single core multi strand Copper conductor wire (Make:RR cables/polycab/KEI/Havells/Glosters) (without joint) drawn into the existing PVC conduit (inclusive of Providing and laying of PVC conduits while concreting), complete with angle / batten lamp holder or ceiling rose, 5 Amps modular type. Switch box to lighting point through the conduit and connecting at both ends.(supply of the box ,grid plate and the cover plate are not covered under this item Providing of the box, grid plate and the cover plate are not covered under this item.). All items such as 1.5sq.mm (22/0.3) Copper FRLS insulated wire, 6 Amps switch, 3 Plate ceiling rose, hylam sheet for JB's, necessary electrical components for wiring works (wherever applicable) shall be provided by the contractor as per the site requirement. (Approximate length 10.5Mtr)	Nos	10	2149	0.00	21,490.00
		Rupees Two Thousand One Hundreds Forty Nine Only				
4	Supply, installation and wiring of 3R x 4sqmm Cu for FRLS insulated each core multistrand with 1100V Copper wire, drawn into the existing PVC conduit (inclusive of supplying and laying of PVC conduits while concreting) from MCB DB to various switch boards as circuit mains and switch board to switch board looping. The termination shall be done by using crimping type Copper lugs of Dowells make, suitable modular type switch box supply by contractor scope.(Refer Section-V)	Rm	100	947	0.00	94,700.00
		Rupees Nine Hundreds Forty Seven Only				
5	Providing and installation of 200W(20000 lumens) High bay light fittings (Make:Havells/Crompton/Philips/GM)	Nos	15	9875	0.00	148,125.00
		Rupees Nine Thousand Eight Hundreds Seventy Five Only				
6	Providing and installation of 600mm(24") ultra high speed metal body with metal blade(3 blades) heavy duty wall mounted fan(make: Almonard/Orient/Crompton)	Nos	6	13599	0.00	81,594.00
		Rupees Thirteen Thousand Five Hundreds Ninety Nine Only				
7	Providing and installation of Earthing with copper earth plate 600mm X 3mm thick including accessories and providing masonry enclosure with cover plate having locking arrangement and water pipe of 2.7 meter long with charcoal/coak and salt etc. as required	Nos	1	16690	0.00	16,690.00
		Rupees Sixteen Thousand Six Hundreds Ninety Only				






Name of Work: Providing covered structural steel fabricated shed for open air stage behind Saralswaram at Anuvijay Township.
 WO / SOQR Number : 201049 Tender No.:NPCIL/KNPP/CONST/CIVIL-INFRA/PT/2024/138
 Agency Name : A.Sankaralingam, Panagudi

Item No	Item Description	Unit	Quantity	Rate in ₹	Rebate in %	Amount in ₹
				Rate in Words		
8	Providing and Laying of 25mm x 5mm copper strip at 0.50 meter below ground level as strip earth electrode, including connection termination with nut, bolt, spring, washer etc. as required. (jointing shall be done by overlapping with 2 sets of brass nut bolt & spring washer spaced at 50mm.)	RM	15	998	0.00	14,970.00
			Rupees Nine Hundreds Ninety Eight Only			
9	POWER CABLE: Providing of power cable 1100 V, 4C x 16 sq.mm stranded compacted circular aluminum conductor, XLPE insulated, cores laid up, extruded PVC inner sheath, galvanized steel flat strip armoured and overall extruded PVC sheathed cable conforming to IS 7098(part1)/1988. (Make: RR cables/KEI/Havells/Glosters)	RM	50	466	0.00	23,300.00
			Rupees Four Hundreds Sixty Six Only			
10	Laying of PVC Insulated and PVC Sheathed /XLPE power cable of 1.1 KV grade of following size (upto 35 Sq mm) direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required	RM	50	578	0.00	28,900.00
			Rupees Five Hundreds Seventy Eight Only			
11	6 MODULE: Providing & installation of concealed in wall mounting 6 Modular switch board with covered plate comprising. (Switches are covered in the Point wiring) (Make: Legrand Mylinc/ MK India /Havells/Schneider/GM) all as directed by Engineer.	Nos	4	695	0.00	2,780.00
			Rupees Six Hundreds Ninety Five Only			
12	12 MODULE: Providing & installation of concealed in wall mounting 12 Modular switch board with covered plate comprising. (Switches are covered in the Point wiring) (Make: Legrand Mylinc/ MK India /havells/Schneider/GM) all as directed by Engineer.	Nos	1	843	0.00	843.00
			Rupees Eight Hundreds Forty Three Only			

Note:: All Item Rates are considered to be in Indian Rupees unless otherwise explicitly specified and in which case shall be always converted appropriately to arrive at the amount in Indian Rupees.

Work Order Total	₹3448337
Overall Rebate (%)	0
Work Order Value After Overall Rebate (in Figure)	₹3448337
Final Work Order Value (in Figure)	₹3448337
Final Work Order Value (in words)	Rupees Thirty Four Lakh Forty Eight Thousand Three Hundreds Thirty Seven Only


11/06/25

