



CAUVERY ASSET – KARAIKAL

Office of the I/C CIVIL, Neravy Complex, Karaikal- 609604

No.ONG/KKL/CA/ES/GM(C)/T(VC1CC24023)/2024-25/NOA/GASE

Date: 02.12.2024

To,

G.A.SIVANI ENTERPRISES,
No.33, Periyar Nagar,
Karaikal - 609 602.
Mob: 99657 17273 & 63819 30663

NOTIFICATION OF AWARD (NOA)

NAME OF WORK: "Revamping and facelift of compound wall at ONGC Neravy Office complex, Karaikal (Civil and electrical works)".

Dear Sir,

Your tender for the above mentioned work has been accepted on behalf of the ONGC at your quoted offer of **Rs.49,66,684.89 (Rupees Forty nine lakhs sixty six thousand six hundred eighty four and paise eighty nine only)** which is (-) 8.35% below the estimated cost of Rs.54,19,187.00.

You are requested to submit the Performance Guarantee in the form of NEFT/RTGS/Electronic fund transfer/ Electronic Bank Guarantee or SFMS Bank Guarantee for the sum of **Rs.4,96,669.00 (Rupees Four lakhs ninety six thousand six hundred sixty nine only)** in the prescribed proforma vide Appendix- 1 of bid document from any Nationalized / Scheduled Bank which is valid up to 30.06.2026.

You may kindly confirm within 03 days of issue of the NOA that SD/PBG shall be submitted within 15 days from the date of NOA and also execute an agreement on non-judicial stamped paper worth Rs. 100/- (Rupees One Hundred only) as per standard Performa, which shall be signed within 15 days from receipt of an acceptable SD or PBG.

You are requested to obtain a PF Code number from the respective PF Commissioner (if not yet obtained, so far) and to submit proof of the same before submitting your bill.

You are requested to start the work immediately. However, the time Limit of **03 (Three) months** shall be reckoned from the 7th day of this NOA or the handing over of the site, whichever is later.

Note: 1. The Nomenclatures, quantities, units and rates of the items provided in the original tender shall be considered for all purposes, in case of any dispute on account of Typographical error etc.


2. You are requested to contact I/c Civil who shall remain in charge for the above work and shall arrange to hand over the work to you. All further correspondence in respect of this work should be addressed to him.

N.o.o.

Copy to:-

1. CGM – HES
2. CGM - HR
3. GM (C) I/C – Civil for kind information pls.
4. GM (F&A), Neravy -----do----- (PR. No. 2090060240)
5. GM(C) - With a request:
To inform LEO through Form – VI-B for commencement & completion of the work.
To ensure the submission of proof of EPF Code by the Agency before processing his bill
6. Agreement Copy
7. Tender Cell.
8. File.

Encl: Schedule-B



GM (C)
For and on behalf of ONGC
K. Ganesh
GM (Civil)

Schedule-B

A : CIVIL PART

Sl. No	Description of item	Qty.	Unit	Rate (Excl. GST)	Amount
1	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and sapling of girth upto 30 cm measured at a height of 1m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	612.00	Sqm.	17.97	10,997.64
2	Boring, Providing and installing cast in situ single under reamed piles of specified diameter and length below pile cap cement concrete 1:1.5:3 (1 cement:1.5 coarse sand: 3 graded stone aggregate 20mm) using 400kg cement/cum to carry a safe work load not less than specified,excluding the cost of steel reinforcement but including the cost of boring with bentonite solution and the length of the pile to be embedded in pile cap etc. all complete.(length of pile for payment shall be measured up to the bottom of pile cap):300mm dia piles.	384.00	Meter	1,312.99	5,04,188.16
3	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	252.00	Cum.	265.81	66,984.12
4	Supplying and filling in plinth with sand under floors, including watering,ramming consolidating and dressing complete.	6.00	Cum.	2,168.74	13,012.44
5	Providing and laying in position cement concrete of specified grade excluding thecost of centering and shuttering - All work up to plinth level: 1:4:8 (1 cement : 4 coarse sand(Zone III) derived from natural source : 8 graded stone aggregate 40 mm nominal size derived from natural source)	6.00	Cum.	6,956.32	41,737.92
6	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:1.5:3 (1 cement : 1.5 coarse sand (Zone III) derived from natural source : 3 graded stone aggregate 20 mm nominal size derived from natural source)	42.00	Cum.	9,237.40	3,87,970.80

2/12/24
K. Ganesh
GM (Civil)

Sl. No	Description of item	Qty.	Unit	Rate (Excl. GST)	Amount
7.	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	1.00	Cum.	11,082.89	11,082.89
8	Coursed rubble masonry with hard stone (second sort) in superstructure above plinth level and upto floor five level. Masonry work (second sort), in cement mortar 1:6 (1 cement: 6 coarse sand)	69.00	Cum.	10,342.68	7,13,644.92
9	Brick Work with Country Bricks (compressive strength not less than 35 Kg/cm ²) in foundation and plinth in Cement Mortar 1 :4 (1 Cement : 4 Coarse sand).	6.00	Cum.	5,478.92	32,873.52
10	Brick Work with Country Bricks (compressive strength not less than 35 Kg/cm ²) in Superstructure above plinth level upto Floor five level in Cement Mortar 1 :4 (1 Cement : 4 Coarse sand). (including curing complete):	48.00	Cum	6,770.23	3,24,971.04
11	12 mm Cement Plaster of mix 1 : 4 (1 Cement : 4 coarse sand).	682.00	Sqm	354.40	2,41,700.80
12	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level- Thermo-Mechanically Treated bars of grade Fe-500D or more.	3797.00	Kg	110.13	4,18,163.61
13	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	2875.00	Kg	176.26	5,06,747.50
14	Centering and shuttering including strutting, propping etc. and removal of form work for: Lintels, beams, plinth beams, girders, bressumers and cantilevers	306.00	Sqm.	752.00	2,30,112.00
15	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.9 lit/10 sqm)	682.00	Sqm.	164.00	1,11,848.00
16	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	108.00	Cum.	2,103.85	2,27,215.80


 K. Ganesh
 GM (Civil)

Sl. No	Description of item	Qty.	Unit	Rate (Excl. GST)	Amount
17.	Felling trees of the girth (measured at a height of 1 m above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material. Beyond 30 cm girth upto and including 60 cm girth	3.00	Each	543.63	1,630.89
18	18 mm thick moulded cement mortar band in two coats under layer 12 mm thick with cement mortar 1:5 (1 cement : 5 coarse sand) top layer 6 mm thick with cement mortar 1:4 (1 cement : 4 fine sand).	9720.00	cm per metre	21.90	2,12,868.00
19	Dismantling barbed wire or flexible wire rope in fencing including making rolls and stacking within 50 metres lead.	266.00	Kg	37.58	9,996.28
20	Dismantling steel work in single sections including dismembering and stacking within 50 metres lead in: Channels, angles, tees and flats	616.00	Kg	2.35	1,447.60
21	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	108.00	cum	269.54	29,110.32

Total (Civil)	Rs.	40,98,304.25
Add GST @ 18.00%	Rs.	7,37,694.77
Total (Civil) incl GST	Rs.	48,35,999.02

B : ELECTRICAL PART

Sl. No.	Description of Item	Unit	Qty	Rate incl. GST	Amount
22	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/ RCCB/ Isolator) 6 way (4 + 18), Double door	Each	1.00	5,288.43	5,288.43
23	Supplying and fixing of 40 amps rating, four pole, (three phase and neutral), 415 volts, residual current circuit breaker (RCCB), having a sensitivity current upto 30 milliamperes in the existing MCB DB complete with connections, testing and commissioning etc. as required.	Each	1.00	3,389.48	3,389.48
24	Supplying and fixing of 40 amps rating, four pole, 415 volts, isolator in the existing MCB DB complete with	Each	1.00	1,031.56	1,031.56


 K. Ganesh
 GM (Civil)

Sl. No.	Description of Item	Unit	Qty	Rate incl. GST	Amount
	connections, testing and commissioning etc. as required.				
25	Supplying and fixing of Single pole , 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.	Each	18.00	272.10	4,897.82
26	Supplying and fixing of 6 way (2+2+6), Double door, horizontal type Single pole and neutral, sheet steel, MCB distribution board, 240 volts, with 1 no. 32A DP MCB & 1 no. 25A, DP, 30 mA RCCB as combined Incomer and 6 nos 5-32A SP MCBs as outgoing on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required.	No.	4.00	6,771.34	27,085.36
27	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	Mtr	225.00	292.66	65,848.71
28	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required 2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire	Mtr	425.00	247.85	1,05,334.84
29	Supplying and fixing of 25 mm size of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.	Mtr	50.00	153.83	7,691.60
30	Supply, erection, Testing and commissioning of 6 Nos X I W LED down light recess mount light or equivalent with all accessories like low loss high frequency electronic drives and fixing the same in the wall/ceiling with screws, hardwares as required	No.	120.00	2,006.00	2,40,720.00
31	CORALPT25W,LED75PSYMTOPC (CORAL(OPAL)-IP65) or similar model, post-top, aesthetically designed with symmetrical light distribution, spun aluminium landscape luminaire with high power LEDs as light source. Make : Philips/Bajaj/Havells	No.	4.00	4,618.52	18,474.08


 K. Ganesh
 GM (Civil)

Sl. No.	Description of Item	Unit	Qty	Rate incl. GST	Amount
32	Supply, Installation, testing and commssioning of 30 Watt LED flood Light, die cast aluminium fittings having with operating voltage 160 to 270 volt, AC 50 HZ, IP-65 rating, efficiency not less than 100 lumen/watt with suitable drives, the fittings should have good thermal management system & LED must be mounted on heat sink conductive aluminium bars with suitable large surface area by means of fins to dissipate the heat to ambient air. Makes of LED Cree/Nichia/Edison/Oshram/Philips (Specification attached)	No.	4.00	3,666.12	14,664.47
33	Supplying, testing and connecting of 1.1 Kv, LT UG armoured Aluminium conductor XLPE insulated cable following size Make: ICC/CCI/UNISTAR/INCAB/ Fort-GLOSTER/ NICCO / HAVELLS/Poly-Cab or equivalent ISI approved make as required. 4 X 16 sq.mm	Mtr	170.00	264.32	44,934.40
34	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 4 X 16 sq. mm (28mm)	No	6.00	328.47	1,970.83
35	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required. Upto 35 sq. mm	Mtr	150.00	229.10	34,365.04
36	Laying and fixing of one number PVC insulated and PVC sheathed/ XLPE power cable of 1.1 KV grade of following size on wall surface as required (clamped with 1mm thick saddle). i) Upto 35 sq. mm	Mtr	10.00	57.97	579.74
37	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL pipe as required. Upto 35 Sq. mm	Mtr	10.00	38.98	389.79
38	Earthing with 50mm G.I pipe B Clause 3 mtr long complete fabrication as per the IE rule with charcoal and salt connecting from earth pipe to MCB DB with 8swg G.I wire including brick masonry work construction of earth chamber 2 feet x2 feet x2 feet including plastering etc and on the top of the chamber RCC slab should be covered.	No.	1.00	4,653.67	4,653.67

21/12/24
K. Ganesh
GM (Civil)

Sl. No.	Description of Item	Unit	Qty	Rate incl. GST	Amount
39	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing as required	Mtr	25.00	74.69	1,867.24
Total (Electrical) Incl GST @ 18.00%				Rs.	5,83,187.06
Total (Civil + Electrical)				Rs.	54,19,187.00
Estimated cost (Civil + Electrical), Say				Rs.	54,19,187.00
Deduct Quoted offer @ (-) 8.35% below				Rs.	-4,52,502.11
Awarded value				Rs.	49,66,684.89

(Rupees Forty nine lakhs sixty six thousand six hundred eighty four and paise eighty nine only)

21/12/24
K. Ganesh
GM (Civil)