



संख्या: भा.वि.प्रा./बागडोगरा/सहा.महाप्रबंधक(अभि.-वि.)/सी.डब्ल्यू.-05/2024-25/243

No. : AAI/BD/AGM(E-E)/CW-05/2024-25/243

दिनांक: 12-02-2025

Date: 12-02-2025

सेवा मे,
मेसर्स. यंगमैन ट्रेडर्स,
पी-27/1, राष्ट्रगुरु एवेन्यु,
दम दम, कोलकाता,
कोलकाता - 700028
ई-मेल: boseranjan@hotmail.com

To,
M/s. Youngmen Traders,
P-27/1, Rastragure Avenue,
Dum Dum, Kolkata,
Kolkata-700028
E-Mail: boseranjan@hotmail.com

विषय/**Subject:** बागडोगरा हवाई अड्डे के सबस्टेशन पर मौजूदा पैनल में मामूली संशोधन के साथ आउटडोर प्रकार के फीडर पिलर का प्रतिस्थापन। (उपशीर्ष-I: विद्युत आपूर्ति का विस्तारीकरण)/**Replacement of Outdoor type Feeder Pillars along with minor modification of existing panel at substation of Bagdogra Airport. (SH-I : Augmentation of Power Supply.)**
संदर्भ / **Ref : 1)** ई-टेंडर आई.डी. क्रमांक/E-Tender ID No.: 2025_AAI_223070_1

महोदय / Sir(s),

- उपर्युक्त कार्य हेतु आपकी निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आपके द्वारा बताए गए मद मूल्यों पर आपकी उद्धृत राशि कुल रु. 25,04,680.00 (जी.एस.टी. छोड़कर), पर स्वीकृत की जाती है, जो कि टेंडर की न्यायोचित राशि रु. 39,23,079.00 से 36.16 % नीचे है।
Your tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs. 25,04,680.00 (Rupees Twenty Five Lakhs Four Thousand Six Hundred and Eighty only) excluding GST, which is 36.16% (Thirty six point one six percent) below the Justified Cost of Rs. 39,23,079.00 (excluding GST).
- सहायक महाप्रबंधक (अभि.-विद्युत)-II, भा.वि.प्रा., बागडोगरा हवाईअड्डा, बागडोगरा-734421, इस कार्य के लिए प्रभारी इंजीनियर होंगे। आपसे निवेदन है कि, आपकी ओर से आप अथवा आपके द्वारा अधीकृत प्रतिनिधि नियुक्त करें जो कि करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 10.03.2025 तक सहायक महाप्रबंधक (अभि.-विद्युत)-II, भा.वि.प्रा., बागडोगरा हवाईअड्डा के कार्यालय में करार पर हस्ताक्षर करने एवं उसको पूरा करने हेतु उपस्थित हों। ठेके का करारनामा रु. 100/- (रुपया एक सौ मात्र) के नॉन ज्युडिशियल स्टाम्प पेपर पर निष्पादित किया जाएगा तथा स्टाम्प पेपर का खर्च आपके द्वारा वहन किया जाएगा।
Assistant General Manager (Engg. -Elect.)-II, AAI, Bagdogra Airport, Bagdogra-734421 shall be the Engineer-in - Charge of the work. You are requested to attend the office of Assistant General Manager (Engg. -Elect.)-II, AAI, Bagdogra Airport, Bagdogra - 734421 by 10.03.2025 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.
- आपके निविदा से साथ प्राप्त बयाना राशि रु. 78,462/- को संविदा दस्तावेज के पृष्ठ 16 | GCC पर दी गई क्लॉज जी.सी.सी. 1(ए) के अनुसार सुरक्षा जमा के हिस्से के रूप में परिवर्तित कर दिया गया है। कृपया इस पत्र के जारी करने से 10 दिन में सुरक्षा जमा के लिए रु. 1,72,006/- जमा करवा दें, ऐसा नहीं करने पर संविदा दस्तावेज के पृष्ठ 16 | GCC पर दी गई क्लॉज जी.सी.सी. 1(ए) के अनुसार आपके रनिंग बिल से काट ली जाएगी।
The earnest money amount of Rs. 78,462/- (Rupees Seventy Eight Thousand Four Hundred and Sixty Two only) received along with your tender has been converted as part of security deposit as per GCC clause 1(A) on page 16 | GCC of the contract document. Please deposit Rs. 1,72,006/- (Rupees One Lakhs Seventy Two Thousand and Six only) towards Security Deposit within 10 days from issue of this letter, failing which, the same will be deducted from your running bills as per GCC clause 1(A) on page 16 | GCC of the contract document.
- आपसे निवेदन है कि आप केंद्रीय और राज्य सरकारों 1970 के अधिनियम श्रम अनुबंध नियम तथा 1971 के केंद्रीय नियम (नियमन तथा उन्मूलन) एवं केन्द्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और नियमों के प्रावधानों का अनुपालन अवश्य करें।
You are requested to comply with the provision of Contract Labour (Regulation & Abolition) Act 1970 and Contract Labour (Regulation & Abolition) Central Rules 1971 and minimum wages act and rules thereof Central and State Governments.

5. कृपया ध्यान दें कि कार्य को पूरा करने के लिए अनुमानित समय 04(चार) महीने होगा और इसकी गणना इस पत्र के जारी होने के 10वें दिन के बाद से की जाएगी।
Please note that the time allowed for carrying out the work shall be 04 (Four) months and same shall be reckoned from the 10th day after issue of this letter.
6. आपको निर्देश दिया जाता है कि आप तुरंत प्रबंधक (अभि.-विद्युत)-I, अ.वि.पा., बागडोगरा हवाई अड्डा, बागडोगरा-734420 से मिले वह आपको साईट सौंपने की व्यवस्था करेंगे।
You are directed to contact with the Manager (Engg. -Elect.)-I, AAI, Bagdogra Airport, Bagdogra-734420 who will arrange to hand over the site to you.
7. इस ठेके के संबंध में आगे का कोई भी पत्राचार इंजीनियर-इन-चार्ज को किया जाएगा।
Any further correspondence in connection with the contract should normally be addressed to the Engineering-in-Charge.
8. कृपया पावती भेजे और स्वीकृति प्रतिलिपि के तौर पर संलग्नित पत्र की हस्ताक्षरित प्रति इस कार्यालय को अवश्य भेजे।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
9. यदि अंग्रेजी और हिन्दी पाठ में कोई असंगति पायी जाती है तो अंग्रेजी पाठ को प्राथमिकता दी जायेगी।
If there is any discrepancy between English and Hindi, then meaning derived in English will be given precedence.

संलग्न/Encl: i) कार्य की अनुसूची (कुल 01 पेज) / Schedule of work (Total 01 page)

भवदीय/Yours faithfully,

(सुभ्र शान्त घोष /Subhra Santa Ghosh)
सहायक महान् प्रबंधक (अभि.-विद्युत)-II, ए.ए.आई., बागडोगरा विमानतल
AGM (Engg. -Elect.)-II, AAI, Bagdogra Airport,
अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण के लिए व उनकी तरफ से
For and on behalf of the Chairman, Airports Authority of India

AIRPORTS AUTHORITY OF INDIA
ENGINEERING ELECTRICAL WING
BAGDOGRA AIRPORT

SCHEDULE OF QUANTITY

Name of Work: Replacement of Outdoor type Feeder Pillars along with minor modification of existing panel at substation of Bagdogra Airport. (SI-I : Augmentation of Power Supply.)

E-Tender ID No.: 2025_AA1_223070_1

SLNo	Description of Item	Quantity	Units	Rate (Rs.) Excl. GST	Amount (Rs.) Excl. GST
1	Modification of existing panel by SITC of following rating MCCBs in blank compartments suitable to operate at 415V+/-10%, 3 Phase, 4 wire 50 Hz AC supply system, including required modification by supply & fixing of suitable rating Aluminium bus-bar (for fixing the MCCBs with terminal extension spreader link and extension of outgoing bus-bar for cable termination at back side of panel), including control wiring with 2.5 sqmm PVC insulated copper conductor cable (FRLS) and minor fabrication works as per specifications. All compartments shall be provided with (a) ON,OFF,TRIP indicator LED lamp including necessary control wiring with 2 A MCB protection (b) Multifunction meter with RS-485 port Class-I, LED display (Parameters: V, A, F, PF, kW, kVA, kVAR, kWh, kVAh, kVARh, Neutral Current) (c) Suitable rating (630/5A & 125/5A) cast resin CT of class-0.5 accuracy including connections etc. complete as per site requirement.				
1.1	(a) 630 Amps MCCB (Ics=100% Icu) with extended rotary handle, 4 pole, 35 kA with adjustable setting, microprocessor release with O/C & S/C protection.	3.00	Job	₹ 65,000.00	₹ 1,95,000.00
1.2	(b) 125 Amps MCCB (Ics=100% Icu) with extended rotary handle, 4 pole, 35 kA with adjustable setting, thermal magnetic release with O/C & S/C protection.	2.00	Job	₹ 40,000.00	₹ 80,000.00
2	Supply of following sizes XLPE insulated and PVC Sheathed, Aluminium Conductor (armoured) industrial cable of 1.1 KV grade conforming to IS 7098 (Part 1),1988 with up to date amendments. (The outer sheath shall be FRLS) (a) 4c x 16 Sq.mm	1200.00	Mtr.	₹ 125.00	₹ 1,50,000.00
2.1	(b) 3.5c x 70 Sq.mm	1000.00	Mtr.	₹ 365.00	₹ 3,65,000.00
2.2	(c) 3.5c x 240 Sq.mm	1300.00	Mtr.	₹ 1,100.00	₹ 14,30,000.00
3	Supply of surface/recessed mounted 2' x 2' (minimum 36W) LED type downlighter suitable to operate on 1Ø, 50 Hz, AC supply complete with all types of accessories and driver ready to be installed at site as per technical specifications attached.	50.00	Each	₹ 1,700.00	₹ 85,000.00
4	Laying of one number PVC insulated and PVC sheathed/XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required. (a) Above 185 sq. mm and upto 400 sq. mm	600.00	Mtr.	₹ 95.00	₹ 57,000.00
5	Laying of one number PVC insulated and PVC sheathed/XLPE power cable of 1.1 KV grade of following size in the existing RCC/GI/HUME pipe as required. (a) Above 185 sq. mm and upto 400 sq. mm	36.00	Mtr.	₹ 105.00	₹ 3,780.00
6	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on cable tray as required. (a) Above 185 sq. mm and upto 400 sq. mm (clamped with 40x3mm MS flat clamp)	260.00	Mtr.	₹ 150.00	₹ 39,000.00
7	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. (a) Above 185 sq. mm and upto 400 sq. mm (clamped with 40x3mm MS flat clamp)	100.00	Mtr.	₹ 150.00	₹ 15,000.00
8	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. (a) 3.5c x 240 Sq.mm	30.00	Each	₹ 1,300.00	₹ 39,000.00
9	Installation, testing and commissioning of pre-wired, LED downlighter / flood light of all types, complete with all accessories etc. directly on ceiling/ wall, including connection with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	20.00	Each	₹ 225.00	₹ 4,500.00
10	Providing, laying (parallel run at minimum 700mm deep) & fixing of 04 Nos. of 80mm dia GI Pipe (medium class) with fitting by excavation/demolition of existing concrete floor foundation/base (minimum 700mm depth & min 650 mm width; including getting out the excavated material and disposal of same within a lead of 50 Mtr) and providing & laying in position cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20mm nominal size) for filling-up & making new base including form work etc. as required.	9.00	Mtr.	₹ 4,600.00	₹ 41,400.00
Total					₹ 25,04,680.00
Say (Excluding GST)					₹ 25,04,680.00

(Total Amount: Rupees Twenty Five Lakhs Four Thousand Six Hundred and Eighty only)

* Note: GST will be paid on production of actual Tax Invoice as per prevailing rates Govt. Of India

Signature Not Verified

Digitally signed by DEBDEEP DUTTA
Date: 2025.10.09 20:19:02 IST
Location: eProcurement System for Central PSUs

Asstt. Gen. Manager (Engg-Elect)-II
Bagdogra Airport
Bagdogra 734421