



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

सोलापुर एयरपोर्ट, सोलापुर

SOLAPUR AIRPORT, SOLAPUR

संदर्भ सं.: भाविप्रा/सोलापुर/स.म.प्र.(अभि-सि)/W-02/Fire-Fighting/2024-25/104(1-10) दिनांक: 24.02.2025

Ref. No: AAI/SOLAPUR/AGM (E-C)/W-02/Fire-Fighting/2024-25/

Date: 24.02.2025

(कार्य आदेश / Work Order)

सेवा में,

मेसर्स योगेश बिल्डर्स

1308, डेल्फिया, आकृति हबटाउन

गार्डेनीया, मीरा रोड पूर्व,

महाराष्ट्र - 401107

To,

M/s. Yogesh Builders

1308, Delphiya, Ackruti Hubtown

Hardeniaya, Meera Road East,

Maharashtra - 401107

कार्य का नाम:- "Provision of internal and external Firefighting system at Solapur Airport. SH:- Construction of underground water tank, pump room, fire hydrants and other associated civil and electrical works at Solapur Airport."

संदर्भ / Ref.: - 1. दिनांक 24/01/2025 को ई-निविदा संख्या 2025_AAI_223178_1 की खोली गई वित्तीय बोली।

1. Financial bid of E-tender ID 2025_AAI_223178_1 opened on 24/01/2025.

महोदय / Dear Sir,

- उपर्युक्त कार्य के हेतु आपकी ई-निविदा, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से, आपके द्वारा उद्धृत मद दर पर कुल राशि रु. 1,01,80,000/- (रु. एक करोड़ एक लाख अस्सी हजार मात्र) (जीएसटी को छोड़कर) पर स्वीकृत की जाती है, जो कि निविदा में रखी गई अनुमानित लागत रु. 140.21 लाख से 27.39% नीचे है।

Your E-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airport Authority of India at the item rates quoted by you totaling to Rs. 1,01,80,000/- (Rs. One Crore One Lakh Eighty Thousand, only) (Excluding GST) which is 27.39% below the estimated cost put to tender of Rs. 140.21 Lakh.

- सहायक महाप्रबंधक (अभि-सिविल), भाविप्रा, सोलापुर एयरपोर्ट, सोलापुर - 413224 कार्य के प्रभारी अभियंता होंगे आपसे निवेदन है कि दिनांक 06/03/2025 तक सहायक महाप्रबंधक (अभि-सिविल), भाविप्रा, सोलापुर एयरपोर्ट, सोलापुर - 413224 के कार्यालय में उपस्थित हों तथा ठेके के करारनामे को पूरा करें। ठेके का करारनामा 300/- (रुपये तीन सौ मात्र) के नॉन-ज्युडिशियल स्टैम्प पेपर पर निष्पादित किया जायेगा, तथा स्टैम्प पेपर का खर्चा आपके द्वारा वहन किया जायेगा।

Asst. General Manager (Engg-Civil), AAI, Solapur Airport, Solapur - 413224 shall be Engineer-In-Charge of the work. You are requested to attend the office of Asst. General Manager (Engg-Civil), AAI, Solapur Airport, Solapur - 413224 by date 06/03/2025 to sign

(1)

अंजली
24/02/2025



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

सोलापुर एयरपोर्ट, सोलापुर

SOLAPUR AIRPORT, SOLAPUR

and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 300/- (Rupees Three Hundred Only) and the cost of the stamp paper shall be borne by you.

3. आपके निविदा के साथ प्राप्त अग्रिम धरोहर राशि रु. 2, 80,500/- (रुपए दो लाख अस्सी हजार पाँच सौ मात्र) निविदा दस्तावेज़ के पृष्ठ GCC-16 पर दी गई शर्त 1 (A) के अनुसार प्रतिभूति जमा के रूप में प्रयुक्त तथा संपरिवर्तित किया जाएगा। सी.पी.पी. पोर्टल पर AOC होने पर उक्त राशि आपको पुनः देय हो जाएगी। कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर पूर्ण जमानत राशि रु. 10,18,000/- (रुपये दस लाख अठरा हजार मात्र) जमा करना है, असफल होने पर पृष्ठ संख्या GCC 16 पर दी गई शर्त 1 (A) के अनुसार आपके चालू बिल से काट लिया जायेगा एवं AOC अग्रिम धरोहर राशि के मूल्य की जमानत राशि संग्रहीत होने पर ही किया जायेगा।

The earnest money amount of Rs. 2,80,500/- (Rupees Two Lakh Eighty Thousand Five Hundred only) received along with your tender will be treated and converted as part of Security Deposit as per condition of clause no. 1(A) on page GCC-16 of the contract document. The same shall be returned to you after doing AOC on CPP Portal. Please deposit amount of Rs. 10,18,000 /- (Rupees Ten Lakh Eighteen Thousand only) towards security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from your running bill as per clause 1(A) on page GCC-16 of the contract document and AOC shall be done after accumulation of Security Deposit amount equal to EMD amount.

4. आपसे अनुरोध है कि ठेका श्रम (विनियमन और उन्मूलन) अधिनियम 1970 के प्रावधान का पालन करें और ठेका श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार का विनियमन और सेवा की शर्त) अधिनियम 1996, भवन एवं अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 जैसा कि निविदा के जीसीसी के पृष्ठ संख्या 49 पर खंड 19 में और केंद्र और राज्य सरकार के नियम में निर्दिष्ट है।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) ACT 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other Construction Workers Welfare Cess Act 1996 as specified in Clause 19 at page no. 49 of GCC of tender and rules of Central and State Government.

5. आपको यह भी निर्देश दिया जाता है कि आप तुरंत प्रबंधक (अभी-सिविल), भाविप्रा, सोलापुर एयरपोर्ट, सोलापुर पर संपर्क करें वह आपको साइट सौंपने की व्यवस्था करेंगे।

You are also directed to contact Manager (Engg.Civil), Solapur Airport immediately, who will arrange to hand over the site to you.

6. कृपया ध्यान दें कि कार्य पूरा करने के लिए 02 (दो) महिना है जो की इस पत्र जारी होने के 10वें दिन से गिना जाएगा।



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

सोलापुर एयरपोर्ट, सोलापुर

SOLAPUR AIRPORT, SOLAPUR

Please note that the time allowed for carrying out the work shall be **60 (Sixty) Days** and same shall be reckoned from the 10th day after issue of this letter.

7. अनुबंध के संबंध में आगे कोई भी पत्राचार सामान्य रूप से प्रभारी अभियंता को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-Charge.

8. कृपया रसीद की पावती दें और इसके साथ संलग्न इस पत्र की डुप्लीकेट प्रति हस्ताक्षर करने के बाद अधोहस्ताक्षरी को स्वीकृति के प्रतीक के रूप में लौटाएं।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

9. संदर्भ के तहत यह पत्र करारनामे का हिस्सा होगा।

This letter under reference shall form part of Agreement.

10. हिंदी और अंग्रेजी संस्करण के बीच किसी भी विसंगति के मामले में, अंग्रेजी संस्करण मान्य होगा।

In case of any discrepancies between Hindi and English version, English version will prevail.

धन्यवाद /Thanking You,

भवदीय / Yours faithfully,

अंजनी
24/02/2025

(अंजनी कुमारी)

(Anjane Kumari)

सहायक महाप्रबंधक (अभि.-सिविल)

Asst. General Manager (Engg.-Civil)

सोलापुर हवाईअड्डा, सोलापुर

Solapur Airport, Solapur

कृते तथा ओर से अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण

For and on behalf of the Chairman, Airports Authority of India.

संलग्न :

1. वित्तीय बोली / Financial Bid (Pg. 01 to 11)

करारनामा प्रति / Agreement Copy.



भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

सोलापुर एयरपोर्ट, सोलापुर

SOLAPUR AIRPORT, SOLAPUR

प्रतिलिपि :

1. अतिरिक्त आयुक्त आयकर, 15, होतगी रोड, साईनाथ नगर, सोलापुर, महाराष्ट्र - 413003
2. प्रादेशिक श्रम आयुक्त (केन्द्रीय), 1 कौल बिल्डिंग, गुरुनानक नगर, शंकर सेठ रोड, पुणे - 411042
3. क्षेत्रीय भविष्य निधि आयुक्त, सुरवासे टावर, 165-ए, रेल्वे लाइन, सोलापुर - 413001

आंतरिक :

1. क्षेत्रीय कार्यपालक निदेशक, पश्चिमी क्षेत्र, भा.वि.प्रा, रीजनल हेड क्वार्टर्स, मुंबई-400 099
2. महा प्रबंधक (अभियांत्रिकी), पश्चिमी क्षेत्र, भाविप्रा, रीजनल हेड क्वार्टर्स, मुंबई-400 099
3. महाप्रबंधक (सतर्कता), पश्चिमी क्षेत्र, भा.वि.प्रा, रीजनल हेड क्वार्टर्स, मुंबई-400 099
4. महाप्रबंधक (वित्त एवं लेखा), पश्चिमी क्षेत्र, भाविप्रा, रीजनल हेड क्वार्टर्स, मुंबई-400 099
5. विमानपतन निदेशक, सोलापुर एयरपोर्ट, सोलापुर
6. प्रबंधक (अभियांत्रिकी-सिविल), सोलापुर एयरपोर्ट, सोलापुर
7. कार्य की फाइल ।

अंजनी
24/02/2024

(अंजनी कुमारी)

(Anjane Kumari)

सहायक महाप्रबंधक (अभि.-सिविल)

Asst. General Manager (Engg.-Civil)

सोलापुर हवाईअड्डा, सोलापुर

Solapur Airport, Solapur

कृते तथा ओर से अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण

For and on behalf of the Chairman,

Airports Authority of India.

Item Rate BoQ

Validate

Print

Help

Tender Inviting Authority: Asst. General Manager (Engg - Civil), Airports Authority of India, Solapur Airport, Solapur - 413224

Name of Work: Provision of internal and external Firefighting system at Solapur Airport. SH:- Construction of underground water tank, pumproom, fire hydrants and other associated civil and electrical works at Solapur Airport.

Contract No: AAI/SOLAPUR/ENGG-CIVIL/Fire Fighting/2024-25 (Tender ID: 2025_AAI_223178_1)

Name of the Bidder/ Bidding Firm / Company :

YOGESH BUILDERS

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	BASIC RATE In Figures To be entered by the Bidder Rs. P	NUMBER #	TOTAL AMOUNT Without Taxes	TEXT #	TOTAL AMOUNT In Words
Sl. No.	Item Description	Quantity	Units	NUMBER #	TEXT #	NUMBER #	TOTAL AMOUNT Without Taxes	TEXT #	TOTAL AMOUNT In Words
1	2	4	5	13		53		55	
1.01	SCHEDULE OF QUANTITY (CIVIL) Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	1370.00	Cum				123300.00		INR One Lakh Twenty Three Thousand Three Hundred & Paise Zero Only
1.02	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. a) Ordinary rock	1370.00	Cum				150700.00		INR One Lakh Fifty Thousand Seven Hundred & Paise Zero Only
1.03	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	139.70	Cum				349250.00		INR Three Lakh Forty Nine Thousand Two Hundred Fifty & Paise Zero Only
1.04	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	20.00	Cum				4000.00		INR Four Thousand & Paise Zero Only
1.05	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	32.35	Cum				177925.00		INR One Lakh Seventy Seven Thousand Nine Hundred Twenty Five & Paise Zero Only
1.06	Brick work with common burnt clay FPS (non modular) bricks of class designation 3.5 superstructure above plinth level upto floor V level all shapes and size in : Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)	29.40	Cum				161700.00		INR One Lakh Sixty One Thousand Seven Hundred & Paise Zero Only
1.07	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete.	63.00	Sqm				50400.00		INR Fifty Thousand Four Hundred & Paise Zero Only
1.08	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	500.00	Kg				41000.00		INR Forty One Thousand & Paise Zero Only

21/12/25

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	TEXT #
1	2	4	5	13	53	55	
1.09	Centering and shuttering including strutting, propping etc. and removal of form for Lintels, beams, plinth beams, girders, bressumers and cantilevers	50.00	Sqm	600.00	30000.00	INR Thirty Thousand & Paise Zero Only	
1.10	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand/zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	10.00	Cum	6000.00	60000.00	INR Sixty Thousand & Paise Zero Only	
1.11	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth.	21.00	Sqm	625.00	13125.00	INR Thirteen Thousand One Hundred Twenty Five & Paise Zero Only	
1.12	12mm Cement Plaster of mix: 1 : 6 (1 Cement : 6 Coarse Sand)	110.00	Sqm	300.00	33000.00	INR Thirty Three Thousand & Paise Zero Only	
1.13	18mm cement plaster in two coats under 12mm thick cement plaster 1:5 (1 Cement : 5 coarse sand) finished with a top layer 6mm thick cement plaster 1:6 (1 Cement : 6 Fine sand)	110.00	Sqm	400.00	44000.00	INR Forty Four Thousand & Paise Zero Only	
1.14	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 50 mm nominal dia Pipes	200.00	Meter	390.00	78000.00	INR Seventy Eight Thousand & Paise Zero Only	
1.15	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 65 mm nominal dia Pipes	200.00	Meter	775.00	155000.00	INR One Lakh Fifty Five Thousand & Paise Zero Only	
1.16	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 100 mm nominal dia Pipes	200.00	Meter	950.00	190000.00	INR One Lakh Ninety Thousand & Paise Zero Only	
1.17	Distemping with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, to achieve even shade and colour. New work (two or more coat) over and including waer thinable priming coat with cement primer having VOC content less than 50 gram/ litre.	188.00	Sqm	80.00	15040.00	INR Fifteen Thousand Forty & Paise Zero Only	
1.18	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	120.00	Sqm	120.00	14400.00	INR Fourteen Thousand Four Hundred & Paise Zero Only	

5/12/2025

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	BASIC RATE In Figures To be entered by the Bidder Rs. P	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words				
1	2	4	5	53	55				
1.19	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	50.00	Sqm	7500.00	INR Seven Thousand Five Hundred & Paise Zero Only				
1.20	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (1 Cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 40 mm nominal size derived from natural sources)	100.00	Cum	500000.00	INR Five Lakh & Paise Zero Only				
1.21	Providing and fixing pressed steel door frames conforming to IS: 4351, manufactured from commercial mild steel sheet of 1.60 mm thickness, including hinges, jamb, lock jamb, bead and if required angle threshold of mild steel angle of section 50x25 mm, or base ties of 1.60 mm, pressed mild steel welded or rigidly fixed together by mechanical means, including M.S. pressed butt hinges 2.5 mm thick with mortar guards, lock strike-plate and shock absorbers as specified and applying a coat of approved steel primer after pre-treatment of the surface as directed by Engineer-in-charge: Profile C Fixing with adjustable lugs with split end tail to each jamb	30.00	Meter	12000.00	INR Twelve Thousand & Paise Zero Only				
1.22	Providing and fixing factory made ISI marked steel glazed doors, windows and ventilators, side /top /centre hung, with beading and all members such as F7D,F4B, K11 B and K12 B etc. complete of standard rolled steel sections, joints mitred and flash butt welded and sash bars tenoned and riveted, including providing and fixing of hinges, pivots, including priming coat of approved steel primer, but excluding the cost of other fittings, complete all as per approved design, (sectional weight of only steel members shall be measured for payment). Fixing with 15x3 mm lugs 10 cm long embedded in cement concrete block 15x10x10 cm of C.C. 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	400.00	Kg	64000.00	INR Sixty Four Thousand & Paise Zero Only				
1.23	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	540.00	Kg	59400.00	INR Fifty Nine Thousand Four Hundred & Paise Zero Only				
1.24	Providing and fixing precast galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	120.00	Sqm	84000.00	INR Eighty Four Thousand & Paise Zero Only				
1.25	Supplying and filling in plinth with sand under floors, Underground Tank including watering, ramming, consolidating and dressing complete.	846.30	Cum	346983.00	INR Three Lakh Forty Six Thousand Nine Hundred Eighty Three & Paise Zero Only				

अनुमोदित
नमो डिप्टी

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	TEXT #
1	2 Supply, installation and commissioning of a 50,000-liter capacity Fiberglass Reinforced Plastic (FRP) underground water storage tank of approved make and size should be 12.80 meter in length and 2.40 meter in diameter. The tank should be Rustproof and leak-proof, Hygienic and suitable for potable water, Lightweight and easy to install, Durable and economical and should be made of 100% virgin material, Impermeable to roots of trees, etc. Specifications and materials include following components: 1. FRP Tank: A FRP tank of approved make with a capacity of 50,000 liters. 2. Concrete Base: Precast beam base for the tank for holding in a position. 3. Securing Elements: Tie belts and anchor fasteners to secure the tank in place. 4. Installation: Lowering the tank in a pit, installing on the foundation, and securing with tie belts and anchor fasteners. 5. The cost of excavation, backfilling, PCC, brickwork, sand filling will be paid extra in a relevant item. The rate is inclusive of transportation, loading, unloading, lowering and fixing in position etc complete as per direction and satisfaction of Engineer In-Charge.	4	5	13	53	55	
1.26		2.00	Each	1500000.00	3000000.00	INR Thirty Lakh & Paise Zero Only	
2	SCHEDULE OF QUANTITY (ELECTRICAL) Supplying, installation, testing and commissioning of Electric driven Main Fire Pump suitable for automatic operation and consisting of following, complete in all respects, as required : (a) Horizontal type, multistage, centrifugal, split casing pump of cast iron body & bronze impeller with stainless steel shaft, mechanical seal conforming to IS 1520. (b) Suitable HP Squirrel cage induction motor, TEFC, synchronous speed 1500 RPM, suitable for operation on 415 volts, 3 phase 50 Hz, AC supply with IP 55 protection for enclosure, horizontal foot mounted type with Class-'F' insulation, conforming to IS-325. (c) M.S. fabricated Common base plate, coupling, coupling guard, foundation bolts etc. as required. (d) Suitable cement concrete foundation duly plastered with anti vibration pads Note: *The head of the pump is selected in a manner so as to give a minimum 3.5kgf/cm2 pressure at the highest/farthest point. 2280 lpm at 80 m Head						
2.01		1.00	Set	2500000.00	2500000.00	INR Two Lakh Fifty Thousand & Paise Zero Only	
2.02	Supplying, installation, testing and commissioning of diesel engine driven main fire pump suitable for automatic operation and consisting of following, complete in all respects, as per specifications : Horizontal type (Diesel Driven Pump), multistage, centrifugal pump of cast of iron body and bronze impeller with stainless steel shaft, mechanical seal conforming to IS 1520. Suitable HP, 1500 RPM water cooled with radiator, diesel engine conforming to relevant IS standard complete with auto starting mechanism, 12 /24 volts electric starting equipment, diesel tank as per OEM standard with suitable M.S. stand, exhaust pipe extended upto 10 m outside pump house duly insulated with 50 mm thick glass wool with 1.0 mm thick aluminium sheet cladding, residential silencer, instruments and protection as per standard specification, stop solenoid for auto stop in the event of fault with audio indications, painted with post office red colour including battery, battery stand, AVM pads etc. as required. M.S fabricated, common base plate, coupling, coupling guard, foundation bolts etc. as required. Suitable cement concrete foundation duly plastered and with anti vibration pads. Note: *The head of the pump is selected in a manner so as to give a minimum 3.5kgf/cm2 pressure at the highest / farthest point. 2280 lpm at 80 m Head						
		1.00	Set	5000000.00	5000000.00	INR Five Lakh & Paise Zero Only	

5/10/2023

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	
1	2 Supplying, installation, testing and commissioning of electric driven pressurisation pump suitable for automatic operation and consisting of following, complete in all respects, as required : (Jockey Pump) Horizontal type, multistage, centrifugal pump of cast iron body and bronze impeller with stainless steel shaft, mechanical seal conforming to IS : 1520. Suitable HP squirrel cage induction motor TEFC type suitable for operation on 415 volts, 3 phase 50 Hz AC supply with IP 55 class of protection for enclosure, horizontal foot mounted type with Class-F insulation, conforming to IS : 325. M.S. fabricated Common base plate, coupling, foundation bolts etc. as required. Suitable cement concrete foundation duly plastered and with anti vibration pads. 180 lpm at 80 m Head	4	5	13	53	55	
2.03		1.00	Set	110000.00	110000.00	INR One Lakh Ten Thousand & Paise Zero Only	
2.04	Fabrication, supply, Installation testing & commissioning of Electrical control panel of cubical construction, floor mounted type, fabricated out of 2mm thick CRCA sheet, compartmentalised with hinged lockable doors, dust and vermin proof, powder coated of approved shade after 7 tank treatment process, cable alley, interconnection with suitable size copper conductor cable/solid copper strip, having switchgears and accessories, mountings and internal wiring, earth terminals, numbering etc. complete in all respect, suitable for main fire pump, pressurisation pump & diesel pump set complete as per CPWD specification with following in coming and Outgoings, suitable for operation on 415V, 3 phase, 50Hz Ac Supply with enclosure protection class IP 42 as required : INCOMING 250A, microprocessor based Over Load, Short circuit and Earth Fault Releases, 50kA 4 Pole MCCB, Ics=100% Icu rating Digital Voltmeter 0-500V with selector switch Digital Ammeter (0-250 A) with selector switch & CTsec. LED type RYB phase indicating lamps, ON, OFF, trip indicating lamps. Set of Copper/Aluminium Bus Bar 300A	1.00	Set	230000.00	230000.00	INR Two Lakh Thirty Thousand & Paise Zero Only	
2.05	Outgoing (Note : All outgoing feeders for pumps should have digital Ammeter with selector switches, and LED type ON, OFF, trip indicating lamps) a) Main Fire Pump 125 A, microprocessor based Over Load, Short circuit and Earth Fault Releases, 50kA TPN MCCB, Ics=100% Icu, with fully automatic soft starter suitable for 60 HP pump with overload protection, current sensing type single phase preventer complete with all accessories and internal wiring required for automatic operation, selector switch for local/remote, auto/manual/OFF operation. b) Jockey Pump 63 A, microprocessor based Over Load, Short circuit and Earth Fault Releases, 50kA TPN MCCB, Ics=100% Icu, with suitable HP fully automatic soft starter with overload protection, current sensing type single phase preventer complete with all accessories and internal wiring required for automatic operation, selector switch for local/remote, auto/manual/OFF operation c) DIESEL ENGINE CONTROL Control for diesel engine comprising - Automatic/Manual selector switch & 3 attempts starting device, timers and relays as required, push buttons, start/stop in manual mode Indicating lamp for high/ Low Lub. Oil pressure, High Water Temp and Engine on indication Battery charger suitable for 12V/24 V DC with boost and trickle selector switch, 0-30 V DC volt meter, and 0-20 A DC Ammeter All standard relays and accessories for automatic operation of diesel engine System Controller Designing, Supply, Installation, Testing and commissioning of system controller to control operation of main electric fire pump, diesel pump, Pressurization pump, Terrace pump in sequence as per specification consisting of relays, timers. Sensors, annunciation window for fault indication, complete as per specification d) 4P, 63 Amps MCB - 04 No.						

5/12/25
Hitesh

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	TEXT #
1	2	4	5	13	53	55	
2.06	Providing laying, testing & commissioning of 'C' class heavy duty MS Pipe conforming to IS 1239/3589 i/c fittings like elbows, tees, flanges, tapers, nuts bolts, gaskets etc. in ground including welding, excavation & providing cement concrete blocks as supports, anticorrosive treatment with coaltar/asphalt tape as per IS 10221, refilling the trench etc. of following sizes complete as required. 150 mm. Dia	140.00	Meter	2600.00	364000.00	INR Three Lakh Sixty Four Thousand & Paise Zero Only	
2.07	Providing, laying, testing & commissioning of 'C' class heavy duty MS pipe conforming to IS 3589/IS 1239 including Welding, fittings like elbows, tees, flanges, tapers, nuts bolts, gaskets etc. and fixing the pipe on the wall/ceiling with suitable clamp/support frame/MS angle and painting with two or more coats of synthetic enamel paint of required shade complete as required : 65 mm dia	40.00	Meter	1300.00	52000.00	INR Fifty Two Thousand & Paise Zero Only	
2.08	Providing, laying, testing & commissioning of 'C' class heavy duty MS pipe conforming to IS 3589/IS 1239 including Welding, fittings like elbows, tees, flanges, tapers, nuts bolts, gaskets etc. and fixing the pipe on the wall/ceiling with suitable clamp/support frame/MS angle and painting with two or more coats of synthetic enamel paint of required shade complete as required : 80 mm dia	50.00	Meter	1200.00	60000.00	INR Sixty Thousand & Paise Zero Only	
2.09	Providing, laying, testing & commissioning of 'C' class heavy duty MS pipe conforming to IS 3589/IS 1239 including Welding, fittings like elbows, tees, flanges, tapers, nuts bolts, gaskets etc. and fixing the pipe on the wall/ceiling with suitable clamp/support frame/MS angle and painting with two or more coats of synthetic enamel paint of required shade complete as required : 150 mm dia	500.00	Meter	2500.00	1250000.00	INR Twelve Lakh Fifty Thousand & Paise Zero Only	
2.1	Providing, laying, testing & commissioning of 'C' class heavy duty MS pipe conforming to IS 3589/IS 1239 including Welding, fittings like elbows, tees, flanges, tapers, nuts bolts, gaskets etc. and fixing the pipe on the wall/ceiling with suitable clamp/support frame/MS angle and painting with two or more coats of synthetic enamel paint of required shade complete as required : 200 mm dia	15.00	Meter	3800.00	57000.00	INR Fifty Seven Thousand & Paise Zero Only	
2.11	Supplying and fixing single headed Gunmetal internal hydrant valve with instantaneous Gunmetal coupling of 63 mm dia with cast iron wheel ISI marked conforming to IS 5290 (Type -A) with blank Gunmetal/Stainless Steel cap and chain as required :	6.00	Set	6500.00	39000.00	INR Thirty Nine Thousand & Paise Zero Only	
2.12	Providing & fixing non-percolating rubber reinforced lined (RRL) fire hose pipe (as per IS : 636) of 63 mm dia and 15 meter length. The hose shall be rated for burst pressure of 35.7 Kg/sqcm. Hose shall be complete with ISI marked gunmetal male & female coupling (IS:903) bound & riveted to hose pipe with copper rivets & 1.5 mm copper wire as required as per specifications. (Location : Internal fire hydrant)	12.00	Set	5200.00	62400.00	INR Sixty Two Thousand Four Hundred & Paise Zero Only	
2.13	Supplying and fixing first-aid Hose Reel with MS construction spray painted in post office red, conforming to IS 884 with upto date amendments complete with the following as required. 30m x 20 mm nominal internal dia water hose thermoplastic (Textile reinforced) type -2 as per IS: 12585 20 mm nominal internal dia gun metal globe valve & nozzle. Drum and brackets for fixing the equipment's on wall. Connections from riser with 25 mm dia stop gun metal valve & M.S. Pipe and socket.	6.00	Set	8000.00	48000.00	INR Forty Eight Thousand & Paise Zero Only	
2.14	Supplying and fixing of hose cabinet of size 0.9 x 0.6 x 0.5 mtr made out of SS sheet 2mm thick with 6 mm thick glazed glass doors i/c necessary locking arrangement suitable to accommodate Internal/external hydrant with butterfly valve, 2 no's 15mtr. long hose pipe, 1 no. branch pipe, mounted on wall OR raised brick platform & duly painted with post office red externally and white internally with synthetic enamel paint complete in all respect, for internal/external hydrant, as required. (Location : Internal/external fire hydrant)	16.00	Each	4200.00	67200.00	INR Sixty Seven Thousand Two Hundred & Paise Zero Only	

Signature

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	BASIC RATE In Figures To be entered by the Bidder Rs. P	NUMBER #	TEXT #	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
Sl. No.	Item Description	Quantity	Units						
1	2	4	5		13	53			55
2.15	Supplying & fixing 63 mm dia gun metal short branch pipe with 20 mm nominal internal diameter size nozzle conforming to IS 903 suitable for instantaneous connection to interconnect hose pipe coupling as required :	16.00	Each		3300.00	52800.00			INR Fifty Two Thousand Eight Hundred & Paise Zero Only
2.16	Supplying and fixing Single headed Gunmetal external yard hydrant valve with 1 No. 63 mm dia instantaneous FM Gunmetal coupling and cast iron wheel, ISI marked, conforming to IS 5290 (type A) with blank Gunmetal/Stainless Steel cap and chain as required :	10.00	Set		6500.00	65000.00			INR Sixty Five Thousand & Paise Zero Only
2.17	Providing & fixing controlled percolation fire hose pipe (as per IS:8423) of 63 mm dia and 15 meter length rated for burst pressure of 35.7 Kg/sqcm. The hose shall be tested for flame resistance test in accordance to IS:8423. Hose shall be complete with ISI marked GM male & female coupling (IS:903) bound & riveted to hose pipe with copper rivets & 1.5 mm copper wire as required as per specifications. (Location : External fire hydrant).	20.00	Set		5200.00	104000.00			INR One Lakh Four Thousand & Paise Zero Only
2.18	Supplying, fixing, testing & commissioning of CI double flanged sluice valve of rating PN 1.6 with non rising spindle, bronze/gun metal seat, ISI marked complete with nuts, bolts, washers, gaskets and conforming to IS 14846 of following sizes as required : 80 mm dia	2.00	Each		9500.00	19000.00			INR Nineteen Thousand & Paise Zero Only
2.19	Supplying, fixing, testing & commissioning of CI double flanged sluice valve of rating PN 1.6 with non rising spindle, bronze/gun metal seat, ISI marked complete with nuts, bolts, washers, gaskets and conforming to IS 14846 of following sizes as required : 150 mm dia	4.00	Each		19000.00	76000.00			INR Seventy Six Thousand & Paise Zero Only
2.2	Supplying, fixing, testing & commissioning of CI double flanged sluice valve of rating PN 1.6 with non rising spindle, bronze/gun metal seat, ISI marked complete with nuts, bolts, washers, gaskets and conforming to IS 14846 of following sizes as required : 200 mm dia	6.00	Each		37500.00	225000.00			INR Two Lakh Twenty Five Thousand & Paise Zero Only
2.21	Supplying, fixing, testing and commissioning of CI butterfly valve of PN 1.6 rating with bronze/gunmetal seat duly ISI marked complete with nuts, bolts, washers, gaskets conforming to IS 13095 of following sizes as required : 65 mm dia	10.00	Each		3500.00	35000.00			INR Thirty Five Thousand & Paise Zero Only
2.22	Supplying, fixing, testing and commissioning of CI butterfly valve of PN 1.6 rating with bronze/gunmetal seat duly ISI marked complete with nuts, bolts, washers, gaskets conforming to IS 13095 of following sizes as required : 80 mm dia	10.00	Each		4200.00	42000.00			INR Forty Two Thousand & Paise Zero Only
2.23	Providing, installation, testing and commissioning of CI dual plate non-return valve of following sizes conforming to IS: 5312 complete with rubber gasket, GI bolts, nuts, washers etc. conforming to IS 5312 of following sizes as required : 65 mm dia	4.00	Each		5500.00	22000.00			INR Twenty Two Thousand & Paise Zero Only
2.24	Providing, installation, testing and commissioning of CI dual plate non-return valve of following sizes conforming to IS: 5312 complete with rubber gasket, GI bolts, nuts, washers etc. conforming to IS 5312 of following sizes as required : 80 mm dia	1.00	Each		6000.00	6000.00			INR Six Thousand & Paise Zero Only
2.25	Providing, installation, testing and commissioning of CI dual plate non-return valve of following sizes conforming to IS: 5312 complete with rubber gasket, GI bolts, nuts, washers etc. conforming to IS 5312 of following sizes as required : 150 mm dia	2.00	Each		9500.00	19000.00			INR Nineteen Thousand & Paise Zero Only
2.26	Providing, installation, testing & commissioning of PN 16 CI Y-Type strainer fabricated out of 1.6 mm thick stainless steel sheet with 3 mm dia holes with stainless steel flange. 200 mm dia	2.00	Each		30000.00	60000.00			INR Sixty Thousand & Paise Zero Only

31521
29/12/25

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	TEXT #		
1	2	4	5	13	53	55			
2.27	Providing & fixing double flanged flexicon rubber expansion joint (suitable for system test pressure) of standard length as per specs including rubber gaskets, flanges, nuts, bolts and washers complete as required as per specifications. 80 mm dia	2.00	Each	6000.00	12000.00	INR Twelve Thousand & Paise Zero Only			
2.28	Providing & fixing double flanged flexicon rubber expansion joint (suitable for system test pressure) of standard length as per specs including rubber gaskets, flanges, nuts, bolts and washers complete as required as per specifications. 150 mm dia	2.00	Each	7800.00	15600.00	INR Fifteen Thousand Six Hundred & Paise Zero Only			
2.29	Providing & fixing double flanged flexicon rubber expansion joint (suitable for system test pressure) of standard length as per specs including rubber gaskets, flanges, nuts, bolts and washers complete as required as per specifications. 200 mm dia	2.00	Each	11000.00	22000.00	INR Twenty Two Thousand & Paise Zero Only			
2.3	Supplying and fixing orifice plate made out of 6 mm thick stainless steel (Grade 304) with orifice of required size to be fitted between flange & landing valve of external and internal hydrants to reduce pressure at the outlet to the level of 3.5 kg/cm2 complete as required.	10.00	Each	1100.00	11000.00	INR Eleven Thousand & Paise Zero Only			
2.31	Providing and Fixing of pressure switches with isolation ball valve suitable for working pressure of 250 PSI for Main/Jockey/diesel pump complete with all required accessories required for operation. Model Danfoss KPI 35 or its equivalent)	3.00	Each	5200.00	15600.00	INR Fifteen Thousand Six Hundred & Paise Zero Only			
2.32	Supplying and fixing of fire brigade connection of cast iron body with gun metal male instantaneous inlet couplings complete with cap and chain as reqd. for suitable dia MS pipe connection conforming to IS 904 as required : 4 way - 150 mm dia M.S. Pipe	3.00	Set	12500.00	37500.00	INR Thirty Seven Thousand Five Hundred & Paise Zero Only			
2.33	Providing & fixing MS cabinet to enclose fire brigade connection and draw out connection fabricated from MS sheet 2mm thick with 2mm thick MS sheet frame with full front glass door and locking arrangement duly painted with one coat of primer and two or more coats of synthetic enamel paint of approved make and shade and suitably mounted on a raised masonry platform as required as per specifications. (Approx. 0.6m x 0.6m x 0.45m) (Location : Fire brigade connection)	3.00	Set	3200.00	9600.00	INR Nine Thousand Six Hundred & Paise Zero Only			
2.34	Supplying and fixing air vessel made of 250 mm dia, 8 mm thick MS sheet, 1200 mm in height with air release valve on top and flanged connection to riser, drain arrangement with 25 mm dia gun metal wheel valve with required accessories, pressure gauge and painting with synthetic enamel paint of approved shade as required.	1.00	Set	20000.00	20000.00	INR Twenty Thousand & Paise Zero Only			
2.35	Providing & fixing dial type (100 mm) pressure gauge with isolation ball valve suitable for working pressure of 250 PSI, short pieces, nipples, elbows, stainless steel 'U' tube & ball valve, etc. as required as per specifications	4.00	Each	2100.00	8400.00	INR Eight Thousand Four Hundred & Paise Zero Only			
2.36	Supply of following size of XLPE insulated & PVC sheathed, armoured, aluminium conductor under ground cable of 1.1KV grade as per IS 7098:1988 Part-I with upto date amendments complete as required. 4Cx16 Sq.mm	80.00	Meter	150.00	12000.00	INR Twelve Thousand & Paise Zero Only			
2.37	Supply of following size DWVC HDPE pipe, ISI marked along with all accessories like socket, couplers etc. conforming to IS 16205 Part 24 complete as required. 63 mm dia (OD-63 mm & ID-51 mm nominal)	250.00	Meter	85.00	21250.00	INR Twenty One Thousand Two Hundred Fifty & Paise Zero Only			
2.38	Supplying and laying of following size DWVC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. 63 mm dia (OD-63 mm & ID-51 mm nominal)	250.00	Meter	150.00	37500.00	INR Thirty Seven Thousand Five Hundred & Paise Zero Only			

21/02/25

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	
1	2	4	5	13	53	55	
2.39	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL/DWC-HDPE pipe as required. Above 95 sq. mm and upto 185 sq. mm	280.00	Meter	68.00	19040.00	INR Nineteen Thousand Forty & Paise Zero Only	
2.4	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on cable tray as required. Upto 35 sq. mm (clamped with 1mm thick saddle)	70.00	Meter	40.00	2800.00	INR Two Thousand Eight Hundred & Paise Zero Only	
2.41	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on cable tray as required. Above 35 sq. mm and upto 95 sq. mm (clamped with 25x3mm MS flat clamp)	10.00	Meter	80.00	800.00	INR Eight Hundred & Paise Zero Only	
2.42	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. upto 35 sqmm (clamped with 1mm MS flat clamp)	10.00	Meter	50.00	500.00	INR Five Hundred & Paise Zero Only	
2.43	Supplying and installing following size of perforated Hot Dipped Galvanised Iron cable tray (Galvanisation thickness not less than 50 microns) with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.I. suspenders including G.I. bolts & nuts, etc. as required. 150 mm width X 50 mm depth X 1.6 mm thickness	30.00	Meter	650.00	19500.00	INR Nineteen Thousand Five Hundred & Paise Zero Only	
2.44	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 3.5C X 70 sq. mm (38mm)	2.00	Each	500.00	1000.00	INR One Thousand & Paise Zero Only	
2.45	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 4X 16 sq. mm (28mm)	8.00	Each	450.00	3600.00	INR Three Thousand Six Hundred & Paise Zero Only	
2.46	Earthing with G.I. earth plate 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	8.00	Set	6000.00	48000.00	INR Forty Eight Thousand & Paise Zero Only	
2.47	Providing and fixing 25 mm X 5 mm G.I. strip on surface or in recess for connections etc. as required	50.00	Meter	220.00	11000.00	INR Eleven Thousand & Paise Zero Only	
2.48	Providing and fixing 25 mm X 5 mm G.I. strip in 40 mm dia G.I. pipe from earth electrode including connection with G.I. nut, bolt, spring, washer excavation and re-filling etc. as required.	24.00	Meter	600.00	14400.00	INR Fourteen Thousand Four Hundred & Paise Zero Only	
2.49	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ recessed conduit/ submain wiring/ cable as required.	20.00	Meter	45.00	900.00	INR Nine Hundred & Paise Zero Only	
2.5	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator). 6 way (8 + 18), Double door	1.00	Each	7500.00	7500.00	INR Seven Thousand Five Hundred & Paise Zero Only	
2.51	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 8 way , Double door	1.00	Each	3300.00	3300.00	INR Three Thousand Three Hundred & Paise Zero Only	
2.52	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole (6 amps-12 no) MCB	12.00	Each	450.00	5400.00	INR Five Thousand Four Hundred & Paise Zero Only	

25/10/25

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs., P	TOTAL AMOUNT In Words
1	2	4	5	13	55
2.53	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 KA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Double pole (32amp)	1.00	Each	1200.00	INR One Thousand Two Hundred & Paise Zero Only
2.54	Supplying and fixing 4 pole, 63 A MCB rating, 240/415 V, 10 KA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.	1.00	Each	3800.00	INR Three Thousand Eight Hundred & Paise Zero Only
2.55	Supplying and fixing 4 pole, 63 A RCCB with 100 mA sensitivity, 240/415 V, 10 KA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.	1.00	Each	6500.00	INR Six Thousand Five Hundred & Paise Zero Only
2.56	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C	12.00	Point	1900.00	INR Twenty Two Thousand Eight Hundred & Paise Zero Only
2.57	Wiring for group controlled (looped) light point/fan point/exhaust fan point/ call bell point (without independent switch etc.) with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit, and earthing the point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C	15.00	Point	1100.00	INR Sixteen Thousand Five Hundred & Paise Zero Only
2.58	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required. 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	40.00	Meter	350.00	INR Fourteen Thousand & Paise Zero Only
2.59	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required. 2 X 4 sq. mm + 1 X 4 sq. mm earth wire	30.00	Meter	450.00	INR Thirteen Thousand Five Hundred & Paise Zero Only
2.6	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing of 2 No. 6 pin 5/6 & 15/16 A modular socket outlet and 2 no. 15/16 A modular switch, connections etc. as required.	8.00	Each	1550.00	INR Twelve Thousand Four Hundred & Paise Zero Only
2.61	Supply of 4 feet, 20 W, 6500K, extruded polycarbonate LED batten suitable to operate on single phase 240V supply	12.00	Each	200.00	INR Two Thousand Four Hundred & Paise Zero Only
2.62	Supply of 10 W, 6500K, IP 65, extruded polycarbonate bulk head light fitting suitable to operate on single phase 240V supply	10.00	Each	1100.00	INR Eleven Thousand & Paise Zero Only
2.63	Installation, testing and commissioning of pre-wired, fluorescent fitting / compact fluorescent fitting of all types, complete with all accessories and tubelamp etc. directly on ceiling/ wall, including connections with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	22.00	Each	190.00	INR Four Thousand One Hundred Eighty & Paise Zero Only
2.64	Supply of 450 mm Sweep heavy duty exhaust fan, totally enclosed, highly efficient heavy duty motor with pressure die cast aluminium rotor mounted on ball bearings, IP 55, 1400 r/min, conforming to IS: 2312 - 1967 suitable for operation on 230 / 240V 50 Hz single phase AC supply complete etc. as required.	4.00	Each	7500.00	INR Thirty Thousand & Paise Zero Only
2.65	Installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required. Upto 450 mm sweep	4.00	Each	190.00	INR Seven Hundred Sixty & Paise Zero Only

Accepted
26/10/2025

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	
1	2	4	5	13	53	55	
2.66	Supply and fixing of 450 mm Sweep, 1440 r/min pedestal fan suitable for operation on 230 / 240V 50 Hz single phase AC supply complete etc. as required.	2.00	Each	9000.00	18000.00	INR Eighteen Thousand & Paise Zero Only	
2.67	SITC of 2 KVA Online UPS with SMF batteries, 30 minutes of battery backup with each UPS.	1.00	Job	58647.00	58647.00	INR Fifty Eight Thousand Six Hundred Forty Seven & Paise Zero Only	
2.68	Excavation of the cable trenches in hard rock/bitumen road/concrete pavement/paver block not exceeding 1.5 metres in width, and lift upto 1.5 metres, including getting out the excavated soil and disposal of excavated soil as directed within a lead of 50 metres.	100.00	Cum	240.00	24000.00	INR Twenty Four Thousand & Paise Zero Only	
Total in Figures					10180000.00	INR One Crore One Lakh Eighty Thousand & Paise Zero Only	
Quoted Rate in Words		INR One Crore One Lakh Eighty Thousand & Paise Zero Only					

Signature
24/02/25