



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
प्रयागराज हवाई अड्डा, प्रयागराज
PRAYAGRAJ AIRPORT, PRAYAGRAJ

पत्रांक सं. : ए. ए. आई/ पीआरजे/का. सं. – 40/1448-56

दिनांक : 05.02.2025

सेवा में,
मेसर्स सिंह ट्रेडर्स,
3/38, 21 विक्रमादित्य मार्ग,
क्रिश्चियन कॉलोनी, हज़रतगंज,
लखनऊ, उत्तर प्रदेश - 226021

To,
M/s Singh Traders,
3/38, 21 Vikramaditya Marg,
christian colony, Hazratganj,
Lucknow, Uttar Pradesh - 226021

विषय : प्रयागराज हवाई अड्डे पर अतिरिक्त अत्यावश्यक सिविल कार्य प्रकृति का कार्य।

Subject: Additional Urgent Nature of Civil work at Prayagraj Airport.

संदर्भ : 1. आपकी ई-निविदा आई. डी. – 2025_AAI_223271_1 जो दिनांक 22.01.2025 को खोली गई।

Ref: 1 Your E-tender ID - 2025_AAI_223271_1 opened on dated: 22.01.2025.

महोदय,

Sir (s),

- उपरोक्त कार्य की ई-निविदा आप के द्वारा भरी गयी **रुपया 13,38,158.00 (रुपया तेरह लाख अड़तीस हजार एक सौ अठ्ठावन मात्र)** की मदद पर, जो की उक्त कार्य की अनुमानित लागत **रुपया 15.52 लाख (जीएसटी छोड़कर)** से **13.78% (तेरह दशमलव सात आठ प्रतिशत)** कम है, को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृति दी जाती है।

Your E-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs. 13,38,158.00 (Rupees Thirteen Lakhs Thirty Eight Thousand One Hundred Fifty Eight Only)** which is **13.78% below (Thirteen Point Seven Eight Percent)** the estimated cost put to tender of **Rs. 15.52 Lakhs (excluding GST)**.

- सहायक महाप्रबंधक (अभि.-सिविल), ए. ए. आई, प्रयागराज हवाई अड्डा, प्रयागराज – 211012 इस कार्य के कार्य प्रभारी अभियंता होंगे। आपसे अनुरोध है कि दिनांक **20.02.2025** तक सहायक महाप्रबंधक (अभि.-सिविल), ए. ए. आई, प्रयागराज हवाई अड्डा, प्रयागराज – 211012 के कार्यालय में उपस्थित होकर करारनामा हस्ताक्षरित कर पूर्ण करें। अनुबंध 100/- रूपए के गैर न्यायिक स्टाम्प पेपर पर संपादित किया जाएगा, स्टाम्प पेपर की कीमत आपके द्वारा वहन की जाएगी।

AGM (Engg.-Civil), AAI, Prayagraj Airport, Prayagraj – 211012 shall be the Engineer-in-Charge of the work. You are requested to attend the office of Asstt. General Manager (Engg.-Civil), AAI, Prayagraj Airport, Prayagraj – 211012 by **20.02.2025** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only) and the cost of stamp paper shall be borne by you.

Contd.



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
प्रयागराज हवाई अड्डा, प्रयागराज
PRAYAGRAJ AIRPORT, PRAYAGRAJ

- 3) कृपया प्रतिभूति जमा राशि **रुपया 1,33,815.00** (रुपया एक लाख तैंतीस हजार आठ सौ पन्द्रह मात्र) इस पत्र के निर्गत होने की दिनांक से 10 दिनों के भीतर जमा करने का कष्ट करें अन्यथा उक्त धनराशि की कटौती संविदा प्रपत्र मे संदर्भित शर्त के अनुसार चालू लेखा बिलों से की जाएगी।

Please deposit **Rs. 1,33,815.00 (Rupees One Lakhs Thirty Three Thousand Eight Hundred Fifteen Only)** towards security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from the running Account Bills as per condition of the contract document.

- 4) आपसे अनुरोध है कि संविदा श्रमिक प्रावधान (विनियम एवं उन्मूलन) 1970 श्रमिक प्रावधान (विनियम एवं उन्मूलन) – केन्द्रीय नियम 1971, बालक श्रम (प्रतिषेध और विनियमन) अधिनियम 1986, भवन और अन्य सन्निर्माण कर्मकार (नियोजन तथा सेवा-शर्त विनियमन) अधिनियम 1996, भवन और अन्य सन्निर्माण कर्मकार (नियोजन तथा सेवा-शर्त विनियमन) अधिनियम 1996 जैसा कि निविदा शर्त संख्या 19 जीसीसी पृष्ठ सं. 106 से 113 में निर्दिष्ट है तथा केन्द्र और राज्य सरकार के नियमों का पालन करना सुनिश्चित करें।

You are requested to comply with provision of contract Labour (Regulation and Abolition) Act 1970 and contract Labour (Regulation and Abolition) Central rules 1971, Child labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers welfare Cess Act 1996 as specified in tender document clause 19 on GCC page no. 106 to 113 and rules of central and State Government.

- 5) आपको निर्देशित किया जाता है कि तुरन्त प्रभाव से सहायक प्रबंधक (अभि०-सिविल), ए०. ए०. आई, प्रयागराज हवाई अड्डा, प्रयागराज – 211012 को संपर्क करें जो कि आपको कार्यस्थल सौंपने की व्यवस्था करेंगे।

You are also directed to contact Asst. Manager (Engg- Civil), AAI, Prayagraj Airport, Prayagraj – 211012, immediately who will arrange to hand over the site to you.

- 6) कृपया ध्यान दें कि कार्य करने की निर्धारित अवधि 90 दिन है, जो कि इस पत्र के निर्गत होने की तिथि के 10 दिन से मानी जाएगी।

Please note that time allowed for carrying out the work shall be **90 Days** and same shall be reckoned from the 10th day after issue of this letter.

- 7) संविदा के संदर्भ में सामान्यतः कोई भी पत्राचार कार्य प्रभारी अभियन्ता को सम्बोधित करते हुए किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-in charge.

- 8) कृपया प्राप्ति की पावती भेजें एवं पत्र कि अनुलिपि जो कि संलग्न है को हस्ताक्षरित कर अधोहस्ताक्षरी को स्वीकृत चिन्ह के रूप में वापस करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

संलग्नक : बीओक्यू (कुल 06 प्रष्ठ)

भवदीय,
Yours sincerely,

(अमर सिंह /Amar Singh)

सहायक महाप्रबंधक (अभि०-सिविल)

Asstt. General Manager (Engg.-Civil)

भारतीय विमानपत्तन प्राधिकरण

AIRPORTS AUTHORITY OF INDIA

प्रयागराज हवाई अड्डा, प्रयागराज

Prayagraj Airport, Prayagraj

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: AGM (Engg.-Civil)

Name of Work: Additional Urgent Nature of Civil work at Prayagraj Airport.


Contract No: 2025_AAI_223271_1

Name of the Bidder/	M/s Singh Traders					
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMB	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	2.00	Cum	7200.00	14400.00	INR Fourteen Thousand Four Hundred Only
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 cement : 4 fine sand : 8 graded stone aggregate 40 mm nominal size)	51.84	Cum	4000.00	207360.00	INR Two Lakh Seven Thousand Three Hundred & Sixty Only
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	1.00	Cum	7800.00	7800.00	INR Seven Thousand Eight Hundred Only
4	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	1.00	Cum	8000.00	8000.00	INR Eight Thousand Only
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	50.00	Kg	78.00	3900.00	INR Three Thousand Nine Hundred Only
6	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	4.00	Cum	6800.00	27200.00	INR Twenty Seven Thousand Two Hundred Only




AGM (E-C)


Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	4.00	Cum	7200.00	28800.00	INR Twenty Eight Thousand Eight Hundred Only
8	Providing and fixing 12 mm thick panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick. Marine plywood conforming to IS: 710	5.00	Sqm	2400.00	12000.00	INR Twelve Thousand Only
9	Providing & Fixing decorative high pressure laminated sheet of plain / wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality. 1.0 mm thick	5.00	Sqm	900.00	4500.00	INR Four Thousand Five Hundred Only
10	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	60.00	Kg	95.00	5700.00	INR Five Thousand Seven Hundred Only
11	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	30.00	Kg	105.00	3150.00	INR Three Thousand One Hundred & Fifty Only
12	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	50.00	Kg	550.00	27500.00	INR Twenty Seven Thousand Five Hundred Only
13	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	20.00	Sqm	270.00	5400.00	INR Five Thousand Four Hundred Only
14	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand)	20.00	Sqm	290.00	5800.00	INR Five Thousand Eight Hundred Only
15	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	50.00	Sqm	70.00	3500.00	INR Three Thousand Five Hundred Only
16	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	100.00	Sqm	90.00	9000.00	INR Nine Thousand Only


AGM(E-C)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
17	Painting runway/taxi track/apron marking with adequate nos of coats to give uniform finish with road marking paint of superior make as approved by the Engineer-in-charge, i/c cleaning the surface of all dirt, scales, oil, grease and other foreign material etc. and lining out complete. Old work (One or more coats)	100.00	Sqm	60.00	6000.00	INR Six Thousand Only
18	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	501.60	Sqm	730.00	366168.00	INR Three Lakh Sixty Six Thousand One Hundred & Sixty Eight Only
19	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured to calculate volume for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	2.48	Cum	8500.00	21080.00	INR Twenty One Thousand & Eighty Only
20	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately): For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	20.00	Kg	450.00	9000.00	INR Nine Thousand Only
21	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)	20.00	Sqm	750.00	15000.00	INR Fifteen Thousand Only
22	Providing tractor with attached harrow/disc harrow/excavator or hydraulic trolley of approx. size 125 to 150 cubic feet including driver and fuel for the purpose of transportation of stone boulders, roots of bushes and trees and likewise un-useful material from the various locations of all areas of Airport and dumping the same in the isolated safe location identified by Engineer-in-Charge within or outside of Airport premises all lifts and lead.	5.00	Day	5000.00	25000.00	INR Twenty Five Thousand Only


AOM (E-C)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
23	Providing and operating the J.C.B. for leveling, cutting etc., at the operational / non operational area including transportation to and from the site of operation fuel charges, driver charges and any other incidental expenses on this account all etc. as directed by the Engineer-in-charge. (The payment will be based on the number of hours worked at the site.)	10.00	Hour	1000.00	10000.00	INR Ten Thousand Only
24	Supplying labour for day to day maintenance jobs including required T & P complete as per direction of EIC. (Prevailing Minimum wages= (A) + CP on (A) @ 7.5%= (B) +Labour cess on (A+B) @ 1% = (C) Skilled Labour Note:- Contractor is bound to pay minimum wage or more to labour.	30.00	Day	750.00	22500.00	INR Twenty Two Thousand Five Hundred Only
25	Supplying labour for day to day maintenance jobs including required T & P complete as per direction of EIC. (Prevailing Minimum wages= (A) + CP on (A) @ 7.5%= (B) +Labour cess on (A+B) @ 1% = (C) Unskilled Labour Note:- Contractor is bound to pay minimum wage or more to labour.	10.00	Day	700.00	7000.00	INR Seven Thousand Only
26	Providing and fixing acrylic sheet of white or any other colour as per requirement and satisfaction of E.I.C. a) 4mm thick	5.00	Sqm	1100.00	5500.00	INR Five Thousand Five Hundred Only
27	Providing and fixing acrylic sheet of white or any other colour as per requirement and satisfaction of E.I.C. b) 2 mm thick	5.00	Sqm	650.00	3250.00	INR Three Thousand Two Hundred & Fifty Only
28	Providing and pasting vinyl digital print signages at all locations including all T&P, labour etc for cleaning the surface, pasting signages all complete as per direction of EIC. On 3mm Sunboard Base	5.00	Sqm	800.00	4000.00	INR Four Thousand Only
29	Providing and pasting vinyl digital print signages at all locations including all T&P, labour etc for cleaning the surface, pasting signages all complete as per direction of EIC. On 3mmAcrylic Base	5.00	Sqm	1000.00	5000.00	INR Five Thousand Only
30	Providing and pasting vinyl digital print signages at all locations including all T&P, labour etc for cleaning the surface, pasting signages all complete as per direction of EIC. On 3mm ACP base	5.00	Sqm	1700.00	8500.00	INR Eight Thousand Five Hundred Only
31	Providing, supplying and fixing High Intensity Retroreflective sheet of approved make on 3mm ACP Sheet. (Cost of ACP Sheet shall be paid extra) as per direction and satisfaction of Engineer-in-Charge. Printing matter	5.00	Sqm	950.00	4750.00	INR Four Thousand Seven Hundred & Fifty Only
32	Providing, supplying and fixing High Intensity Retroreflective sheet of approved make on 3mm ACP Sheet. (Cost of ACP Sheet shall be paid extra) as per direction and satisfaction of Engineer-in-Charge. Cutting matter	5.00	Sqm	1200.00	6000.00	INR Six Thousand Only


AGM(E-C)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
33	Fabricating and Providing required furniture like table almirah shutters, Stool or any other such items using plywood fevicol, nails, tape i/c all kind of manpower as per drawing & design given by the EIC or his representative using individual or comibantion of ply wood as follows:- 12 mm ply wood	10.00	Sqm	1250.00	12500.00	INR Twelve Thousand Five Hundred Only
34	Fabricating and Providing required furniture like table almirah shutters, Stool or any other such items using plywood fevicol, nails, tape i/c all kind of manpower as per drawing & design given by the EIC or his representative using individual or comibantion of ply wood as follows:- 18 mm ply wood	5.00	Sqm	1650.00	8250.00	INR Eight Thousand Two Hundred & Fifty Only
35	Providing and fixing beveled mirror edge 8 mm thick of approved make in required shape and size without plastic moulded frame, i/c fixing with studs and making necessary holes, as per direction and satisfaction of E.I.C.	6.00	Sqm	1500.00	9000.00	INR Nine Thousand Only
36	P/F (Aluminium Composite Panel) Sheet any colour on existing frame as per requirement all complete in all respect as per direction and satisfaction of Engineer-in-Charge. 4mm thick ACP (FR grade) of Aludecor ALAS color AD09	5.00	Sqm	2000.00	10000.00	INR Ten Thousand Only
37	P/F (Aluminium Composite Panel) Sheet any colour on existing frame as per requirement all complete in all respect as per direction and satisfaction of Engineer-in-Charge. 3mm thick ACP	5.00	Sqm	1600.00	8000.00	INR Eight Thousand Only
38	Providing and fixing Urinal Sensor compatible for Urinal cera make 320X300X525 mm (S4010102) or equivalent complete as per direction and satisfaction of engineer-in-charge.	15.00	Each	13000.00	195000.00	INR One Lakh Ninety Five Thousand Only
39	Cleaning of existing expansion joints and providing & filling with polysulphide joint sealing compound (confirming to grade BS:5212, Part-I, 1990) of Dr. Fixit or equivalent including painting the sides of slab with approved primer and filling the groove 20mm width x 25mm deep including inserting the backer rod of Supreme or equivalent of appropriate dia of approved make to receive the specified sealing compound, providing and applying bond breaking tape on top edges of joint to prevent accidental spillage of sealant on top surface and to give a neat finish to the sealant has been applied and tooled, all complete as per specification and direction of Engineer-in-Charge	50.00	Mtr	300.00	15000.00	INR Fifteen Thousand Only
40	Cleaning of existing Dummy/Contraction joints and providing & filling with polysulphide joint sealing compound (confirming to grade BS:5212, Part-I, 1990) of Dr. Fixit or equivalent including painting the sides of slab with approved primer and filling the groove 10mm width x 15mm deep including inserting the backer rod of Supreme or equivalent of appropriate dia of approved make to receive the specified sealing compound, providing and applying bond breaking tape on top edges of joint to prevent accidental spillage of sealant on top surface and to give a neat finish to the sealant has been applied and tooled, all complete as per specification and direction of Engineer-in-Charge	300.00	Mtr	150.00	45000.00	INR Forty Five Thousand Only


AGM(E-c)

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
41	Supplying of packed Elastomeric concrete compound (Flex - O - Patch of Choksey chemicals/ Delpatch of D.S Brown or equivalent) at site. The one pack of 10 kg Elastomeric concrete shall consist of 3 kg hardner 1.5 Kg base & 5.5 Kg of sand & fibre powder.	100.00	Kg	650.00	65000.00	INR Sixty Five Thousand Only
42	Repairing of damaged portion of rigid pavement with Elastomeric concrete compound(Flex - O - Patch of Choksey chemicals/ Delpatch of D.S Brown or equivalent) after marking, cutting, chipping the pavement up to required size by using mechanical chippers, side locking on the vertical face, cleaning the prepared area by sand blasting with medium grit sand, masking and pouring the compound, finishing & texturing complete, including applying primer as per manufacturer specifications and the direction of Engineer-In-charge with required machines & tools. Note: The rate quoted shall be exclusive of cost of material.	100.00	Kg	130.00	13000.00	INR Thirteen Thousand Only
43	Edge repair of Dummy/Construction/Expansion joints of different sizes varying from 5mm to 25mm by epoxy of Doctor Fikit grout as per the satisfaction of Engineer-In-Charge.	50.00	Mtr.	120.00	6000.00	INR Six Thousand Only
44	Repair of cracks in concrete by preparing the necessary V-joint, priming the surface, filling with necessary grouting compound of Dr. Fikit or equivalent as per the satisfaction of Engineer-In-Charge. Joints of 10mm wide.	150.00	RMT	75.00	11250.00	INR Eleven Thousand Two Hundred & Fifty Only
45	Repair of cracks in concrete by preparing the necessary V-joint, priming the surface, filling with necessary grouting compound of Dr. Fikit or equivalent as per the satisfaction of Engineer-In-Charge. Joint of 25mm wide.	30.00	RMT	180.00	5400.00	INR Five Thousand Four Hundred Only
46	Supplying of Fiberglass rectangular Planter of size 2 feet to site as per per dirction of Engineer-in-Charge	15.00	Each	1300.00	19500.00	INR Nineteen Thousand Five Hundred Only
47	Supplying of fiberglass Planter of size 16 inch square to site as per per dirction of Engineer-in-Charge	15.00	Each	1500.00	22500.00	INR Twenty Two Thousand Five Hundred Only
Total in Figures					1338158.00	INR Thirteen Lakh Thirty Eight Thousand One Hundred & Fifty Eight Only
Quoted Rate in Words		INR Thirteen Lakh Thirty Eight Thousand One Hundred & Fifty Eight Only				



Signature Not Verified

Digitally signed by SANJEEV KUMAR SINGH
Date: 2025.12.16 16:27:04 IST
Location: eProcurement System for Central PSUs

