भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

(पंजीकृत डाक)

संदर्भः भाविप्रा/रापु/स.म.प्र.(अभि-सि)/कर्ब स्टोन/2025/353-65 दिनांकः-01.04.2025

सेवा में,
मैसर्स एस. के. कंस्ट्रक्शन,.
ग्राम - बरेमा, पोस्ट - रामेश्वर,
वाराणसी, उत्तर प्रदेश - 221405

To,
M/s S.K. Construction,
Vill-Barema, Post-Rameshwar,
Varanasi, Uttar Pradesh - 221405

विषयः स्वामी विवेकानन्द हवाई अड्डा, रायपुर में हवाई अड्डे के सिटीसाइड पर सड़क के किनारे कर्ब स्टोन और फुटपाथ का प्रावधान ।
निविदा क्रमांक : 2025_AAI_223755_1

Sub: Provision of Kerb Stone and Footpath along road on Cityside of Airport at S.V. Airport, Raipur.
Tender ID: - 2025_AAI_223755_1

संदर्भः आपकी ई–निविदा जो दिनांक 21.02.2025 को खोली गयी।
Ref: Your E-tender opened on 21.02.2025

महोदय/Sir,

1. अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से उपरोक्त कार्य के लिए आपकी निविदा स्वीकार की जाती है आपके द्वारा उद्धरित राशि रू. 54,48,250.00 (रूपये चौवन लाख अड़तालीस हज़ार दो सौ पचास मात्र) जो कि अनुमानित लागत रू. 86,74,000/- (जी.एस.टी. छोड़कर) से 37.19% कम है।

   Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to Rs. 54,48,250.00 (Rupees Fifty-Four Lakhs Forty-Eight Thousand Two Hundred Fifty only) (Excluding GST) which is 37.19% Below the estimated cost put to tender of Rs. 86,74,000/- (Excluding GST).

2. सहा. महाप्रबंधक (इंजीनियरिंग-सिविल), भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर इस कार्य के प्रभारी अभियंता होंगे । आपसे अनुरोध है, कि कृपया दिनांक 26.04.2025 तक स्वामी विवेकानंद हवाई अड्डा, रायपुर पर अधोहस्ताक्षरकर्ता के कार्यालय में उपस्थित रहकर संविदा करार तथा करार की कार्यवाही पूर्ण करने का कष्ट करें। यह संविदा करार 100/-. रूपये (सौ रूपये मात्र) के गैर–न्यायिक स्टैम्प पेपर पर निष्पादित किया जायेगा, जिसका खर्च आपके द्वारा वहन किया जायेगा।

   Asst. General Manager (Engg.-Civil), AAI, Swami Vivekananda Airport, Raipur shall be the Engineer-In-Charge of the work. You are requested to attend the office of the undersigned at Swami Vivekananda Airport, Raipur by 26.04.2025 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

3. संविदा करार के पेज नंबर जी.सी.सी–16 पर धारा नं. 1ए के अनुसार आपके निविदा के साथ प्राप्त धरोहर राशि रूपये 1,73,480-/ (रूपये एक लाख तिहत्तर हज़ार चार सौ अस्सी मात्र) जमानत जमा के एक हिस्से के रूप में जमा माना जायेगा । कृपया इस कार्यादेश के जारी होने के तिथि से 10 दिनो के भीतर जमानत जमा के शेष रूपये 3,71,345/- (रूपये तीन लाख इकहत्तर

Check AGM(E-C)

हज़ार तीन सौ पैंतालीस मात्र) इस कार्यालय में जमा कराये अन्यथा यह निविदा दस्तावेज के पेज नंबर जी.सी.सी–16 पर धारा नं. 1A के अनुसार काटा जायेगा।

The Earnest Money amount of Rs. 1,73,480/- (Rupees One Lakh Seventy-Three Thousand Four Hundred Eighty Only) received along with your tender. Please deposit Rs. 3,71,345/- (Rupees Three Lakhs Seventy-One Thousand Three Hundred Forty-Five Only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause no. 1A at Page GCC-16 of tender document.

4. आपसे अनुरोध है कि संविदा करार के पेज नंबर जी.सी.सी–52 पर धारा नं. 19 के अनुसार आप ठेका श्रमिक (विनिमय एवं उन्मूलन) अधिनियम 1970 के उपबंधो का अनुपालन करें, साथ ही ठेका श्रमिक (विनिमय एवं उन्मूलन) केन्द्रीय नियमावली 1971, बाल श्रम (निषेध एवं विनिमय) अधिनियम 1986, निर्माण श्रमिक (रोजगार और सेवा की हालत का विनिमय) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 तथा केन्द्र और राज्य सरकारों के अधिनियमों के प्रावधानों का पूर्णतः अनुपालन करेंगे।

   You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause no. 19 on Page no. 52 of GCC of tender and rules of Central and State Governments.

5. आपसे यह भी अनुरोध है कि आप कर्मचारी भविष्य निधि और विविध प्रावधान अधिनियम, 1952 और ई.एस.आई. अधिनियम, 1948 (सभी संशोधनों सहित) एवं उस के अतंर्गत बनाये गये सभी नियमो एवं प्रावधानों का पूर्णतः अनुपालन करेंगे तथा क्षेत्रीय पीएफ आयुक्त द्वारा आबंटित पीएफ खाता कोड संख्या एवं ई.एस.आई. कॉर्पोरेशन द्वारा आबंटित ई.एस.आई. रजिस्ट्रेशन नंबर भी इस कार्यालय में जमा करायेंगे तथा पीएफ खाता कोड और ई.एस.आई. पंजीकरण काम के वास्तविक समापन तक वैध रहें।

   You are also requested to comply with all the provision of the employees Provident Fund & Misc. Provision Act, 1952 and ESI Act, 1948 amended from time to time and rules framed there under and furnish the PF account code number allotted by Regional PF Commissioner and ESI Registration number allotted by ESI Corporation and continue to have valid PF account code and ESI registration number till actual completion of the work.

6. आपसे यह भी अनुरोध है कि आप अधोहस्ताक्षरी से अविलम्ब संपर्क करें जो आपको साईट हस्तांतरित करने का व्यवस्था करेंगे|

   You are also directed to contact Undersigned immediately who will arrange to hand over the site to you.

7. कृपया ध्यान दें कि काम करने के लिए अनुमति देने का समय 04 (चार) महीने होगा और इस पत्र के जारी होने के बाद दसवें दिन से माना जायेगा।

   Please note that the time allowed for carrying out the work shall be 04 (Four) Months and same shall be reckoned from the 10th day after issue of this letter.

8. आगे से इस अनुबंध के संबंध में किसी प्रकार के पत्राचार को प्रभारी अभियंता को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.

9. कृपया इस पत्र की प्राप्ति–सूचना और स्वीकृति के प्रतीक रूप में इस पत्र की दूसरी प्रति हस्ताक्षर करने के बाद अधोहस्ताक्षरकर्ता को वापस भेज दें।

Please acknowledge the receipt and return the duplicate copy of this letter after signing it to the undersigned as a token of acceptance.

Note: किसी भी विसंगति की स्थिति में अंग्रेजी संस्करण/पाठ मान्य होगा |

In case any discrepancy the English version/text shall prevail.

सधन्यवाद

संलग्नः 1) अनुसूची – अ
2) फॉर्म - III

भवदीय,

01/04/25
(विवेक चन्द्रवंशी)
सहा. महाप्रबंधक (अभि.सि.)
भा.वि.प्रा., एस.व्ही. हवाई अड्डा, रायपुर

<u>मूलप्रति में नही</u>

प्रतिलिपिः

1. क्षेत्रीय कार्यपालक निदेशक, पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता–52।
2. महाप्रबंधक (अभि), पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता–52।
3. महाप्रबंधक (वित्त), पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता–52।
4. उप. महाप्रबंधक (सर्तकता), पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता–52।
5. सहायक श्रम आयुक्त (सी), डी–6, आदर्श सोसाइटी, सेक्टर–1, अवंती विहार, रायपुर।
6. क्षेत्रीय भविष्य निधि आयुक्त, भविष्य निधि कार्यालय, ब्लॉक–डी, स्कीम नं.–32, इंदिरा गांधी व्यावसायिक परिषद, पंडरी, रायपुर (छ.ग.)–492004।

प्रतिलिपिः

1. विमानपत्तन निदेशक, भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
2. उप. महाप्रबंधक (वित्त), भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
3. उप. महाप्रबंधक (अभि–सि), भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
4. उप. महाप्रबंधक (अभि–वि), भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
5. सहा. महाप्रबंधक (सीएनएस/प्रचालन), भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
6. मुख्य सुरक्षा अधिकारी, भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
7. कार्यालय प्रति।

02/04/25
M/s S.K. Construction

01/04/25
(विवेक चन्द्रवंशी)
सहा. महाप्रबंधक (अभि.सि.)
भा.वि.प्रा., एस.व्ही. हवाई अड्डा, रायपुर

SCHEDULE 'A'

Bill of Quantities

Name of Work: Provision of Kerb Stone and Footpath along road on Cityside of Airport at S.V. Airport, Raipur.

Item No.	Description of Work	Units	Qty.	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. a) All kinds of soil.	Cum	780.00	70.00	54600.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a) 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	110.00	4420.00	486200.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a) 1:4:8 (1 cement : 4 coarse sand (zone-iii) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	Cum	270.00	4010.00	1082700.00
4	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. (i) Single socketed pipes. a) 110 mm diameter	Metre	180.00	165.00	29700.00
5	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : a) Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	Sqm	1760.00	80.00	140800.00
6	Providing and applying 2.5 mm thick road marking strips (retroreflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications.	Sqm	2650.00	325.00	861250.00
7	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5 mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured to calculate volume for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	Cum	320.00	5120.00	1638400.00
8	Providing and laying 60 mm thick faciory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	Sqm	2510.00	460.00	1154600.00
				Total	5448250.00

01/04/25
AGM(E-C).

FORM III

[Under rule 21(2) of the Contract Labour (Regulation and Abolition) Central Rules, 1971: and rule 7(3) of the Inter-State Migrant Workmen (Regulation of Employment and Conditions of Service) Central Rules, 1980]

From of Certificated by Principal Employer

Certified that:

1. I have engaged the applicant **M/s S.K. Construction** as a contractor in my establishment for the work **"Provision of Kerb Stone and Footpath along road on City side of Airport at S.V. Airport, Raipur."** to be carried out from 26.04.2025 to 25.08.2025.
2. I undertake to be bound by all the provisions of the Contract Labour (Regulation and Abolition) Act, 1970 (37 of 1970) and the Contract Labour (Regulation and Abolition) Central Rules, 1971 ~~/ the Inter-State Migrant Workmen (regulation of Employment and Conditions of Service) Act, 1979 (30 of 1979) and the Inter-State Migrant Workmen (Regulation of Employment and Conditions of Service) Central Rules, 1980~~ in so far as the Provisions are applicable to me in respect of the employment of contract labour~~/inter-state migrant workmen~~ by the applicant in my establishment.
3. The engagement of contract labour in the said work is not prohibited under sub section (1) of section 10 of the Contract Labour (Regulation and Abolition) Act, 1970 (37 of 1970) ~~or an award or a settlement~~.

Place: Raipur

Signature of Principal Employer

Date: 01.04.2025

01/04/25

(Vivek Chandrawanshi)
AGM (Engg-Civil)
AAI, S. V. Airport, Raipur

Signature Not Verified
Digitally signed by VIVEK CHANDRAWANSHI
Date: 2025.04.25 15:55:12 IST
Location: eProcurement System for Central PSUs