

Government eProcurement System

Created By: Ramnivas Kumavat

Created Date/Time: 14-Feb-2025 05:19 PM

Tender Title: Providing and fixing barricading inside operational area and around Interim Terminal Building at Rajkot International Airport Rajkot

Tender ID: 2025_AAI_225151_1

Tender Inviting Authority: Bid Manager / Asstt. General Manager (E C), AAI, CA Rajkot.

Name of Work : Providing and fixing barricading inside operational area and around Interim Terminal Building at Rajkot International Airport

Contract No : Tender ID: 2025_AAI_225151_1

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Estimated Rate	Unicon Engineering Co (GSTN- 24AAEFU0438A1ZU) BID ID -815578	Arpan Engineering Co (GSTN- 24AAZFA7613G1Z8) BID ID -815806	Parikh Kashyap Indulal (GSTN- 24ADFPB3401N1Z9) BID ID -815950	Bhimabhai A Ravaliya (GSTN- 24AFMPLZ717J1Z7) BID ID -816208	Umiya Construction (GSTN- 24AABFU5911F1Z1H) BID ID -816389					
					Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount		
1.00	Providing and erecting 2.00 metre high barricading, each panel of size 2.50mx2.00m made of 40x40x6mm angle iron or 50x50x3mm hollow MS tube posts/horizontal members/bracings covered with 1.63mm thick MS sheet. The sheet shall be fixed with 30x5mm MS flat by suitable welding/inletting. The panels shall be made so that gap of 50cm above the ground is available making overall height as 2.5m. MS channel ISLC 75 @ 5.70 kg/m. 50cm long shall be provided at the bottom having oval shaped holes of size 50x25mm at both ends with 50cm long MS angle 40x40x6mm bracing. Suitable arrangement shall be made to fix the barricading to avoid from overturning by providing 250mm long expansion fasteners at both ends. The work shall be executed as per direction of Engineer-in-Charge which includes writing and painting. Rate include painting, all incidentals, labour materials, equipments and works required to execute the job.	120.00	Metre		4518.00	542160.00	3750.00	450000.00	4100.00	492000.00	6200.00	744000.00	4250.00	510000.00
2.00	Providing and fixing ISI boiled water resistance plywood with necessary screws, nails and nuts wherever necessary etc. complete as per direction of Engineer-in-charge. (a) 18 mm thick ISI boiled water resistance plywood	21.00	Sqm		150.00	3150.00	4950.00	103950.00	2900.00	60900.00	1500.00	31500.00	1250.00	26250.00
3.00	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	777.00	Kg		108.00	83916.00	150.00	116550.00	140.00	108780.00	120.00	93240.00	120.00	93240.00
4.00	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m) having 50 nos rounds per 6 metre length upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R B T reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape (R B T) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	120.00	metre		400.00	48000.00	425.00	51000.00	510.00	61200.00	275.00	33000.00	380.00	45600.00

L1 Amount	L1 Vendor
450000.00	Arpan Engineering Co
3150.00	Unicon Engineering Co
83916.00	Unicon Engineering Co
33000.00	Bhimabhai A. Ravaliya

AMC(E-C)
17/02/25

AMC(E-C)
17/02/2025

5.00	Providing and fixing 19mm thick both side balancing lamination factory pressed BVP grade maine ply as per IS 710 of approved brand boxes, shelves, racks, almirah cupboard and drawer etc. including necessary nails, screws etc. complete as per direction of Engineer-in-charge	25.00	Sqm
6.00	Providing & Fixing decorative high pressure laminated sheet of plain / wood grain in glass / matt / suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS 2046 Type S, including cost of adhesive of approved quality a) 1.5 mm thick	35.00	Sqm

Total in Figures

Lowest Amount Quoted By: Unicon Engineering Co(696256.00)

190.00	4750.00	5750.00	143750.00	4500.00	112500.00	2300.00	57500.00	2450.00	61250.00
408.00	14280.00	1550.00	54250.00	1300.00	45500.00	900.00	31500.00	893.00	31255.00

696256.00

919500.00

880890.00

990740.00

787395.00

4750.00	Unicon Engineering Co
14280.00	Unicon Engineering Co

14/10/25
AGM(E-C)
14/10/25

17/10/2025
AGM(E-C)
17/10/2025

BOQ Summary Details

Tender Title: Providing and fixing barricading inside operational area and around Interim Terminal Building at Rajkot
International Airport Rajkot
Tender ID: 2025_AAI_225151_1

Sheet Name	Sl.No	Bidder Name	Amount	Bid Rank
BoQ1	1	Unicon Engineering Co (BID ID -815578)	696256.00	L1
	2	Umiya Construction (BID ID -816389)	767595.00	L2
	3	Parikh Kashyap Indulal (BID ID -815950)	880880.00	L3
	4	Arpan Engineering Co (BID ID -815806)	919500.00	L4
	5	Bhimabhai A Ravaliya (BID ID -816208)	990740.00	L5


AGM(E-C)
14/02/25


AGM(E-C)
17/02/2025

Signature Not Verified

Digitally signed by
RAMNIVAS KUMAWAT
Date: 2025.02.17 14:23:41
IST
Location: eProcurement