



भारतीय विमानपत्तन प्राधिकरण  
AIRPORTS AUTHORITY OF INDIA  
Dimapur Airport

स: एएआई/एनईआर/डीएमपी/डीजीएम (ई-सी/ पहुंच मार्ग/25-26/  
No.: AAI/NER/DMP/DGM(E-C)/ Approach Road/25-26/ 248

दिनांक: 28.04.2025  
Date: 28.04.2025

सेवा में,  
मैसर्स एस आर कंपनी,  
सरकार. ठेकेदार, भवन निर्माण सामग्री  
आपूर्तिकर्ता, पंजीकरण संख्या-  
एनपीडब्ल्यू/सीएसएस-1/1455  
पुराना बाजार-दीमापुर. नागालैंड.

To,  
M/s S R Company,  
Govt. Contractor, Building Materials  
Supplier, Regd No.-NPW/CASS-I/1455  
Purana Bazar-Dimapur. Nagaland.

कार्य का नाम: दीमापुर हवाई अड्डे पर आवासीय कॉलोनी में आरसीसी ओवरहेड टैंक को जोड़ने वाली एप्रोच रोड का निर्माण।

Name of Work: Construction of Approach road connecting RCC overhead tank in Residential colony at Dimapur airport.

निविदा आईडी/Tender ID : - 2025\_AAI\_225878\_1 dated: 25.02.2025

महोदय/Sir,

1. उपर्युक्त कार्य के लिए आपका ई-टेंडर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आपके द्वारा उद्धृत मद दर पर कुल 52,22,064.50 रुपये (बावन लाख बाईस हजार चौसठ और पचास पैसे मात्र) स्वीकार किया जाता है, जो कि टेंडर में रखी गई अनुमानित लागत 81,61,700 रुपये से 36.02% कम है।

Your E-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rate quoted by you totalling to Rs. 52,22,064.50 (Rupees Fifty Two Lakhs Twenty Two Thousand sixty four and fifty paise Only) which is 36.02% below the estimated cost put to tender of Rs. 81,61,700/-.

2. उप महाप्रबंधक (अभि.- सिविल), एएआई दीमापुर हवाई अड्डा, इस कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि अनुबंध करार को पूरा करने एवं हस्ताक्षर करने के लिए आप दिनांक 08.05.2025 तक उप महाप्रबंधक (अभि.- सिविल), एएआई, दीमापुर हवाई अड्डा के कार्यालय में उपस्थित हों। अनुबंध करार 100 (सौ रूपए) के गैर-न्यायिक स्टांप पेपर पर होगा एवं स्टांप पेपर का खर्च आपके द्वारा वहन किया जाएगा।

DGM General Manager (Engg.-Civil), AAI, Dimapur Airport shall be the Engineer-in-charge of the work. You are requested to attend the office of DGM (Engg.-Civil), AAI Dimapur Airport by 08.05.2025 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100 - (Rupees: One Hundred only) and the cost of the stamp paper shall be borne by you.

de

Received  
S.R. COMPANY  
Govt. Contractor, Building Material Supplier  
Regd. No. NPW/Class-1/1455  
Purana Bazar, Dimapur-797112, Nagaland

Signature



3. आपके टेंडर के साथ प्राप्त की गई बयाना राशि 2,44,851.00 (दो लाख चौवालीस हजार आठ सौ इक्यावन रुपये मात्र) को अनुबंध दस्तावेज के पृष्ठ 16 पर खंड संख्या 1ए की शर्त के अनुसार सुरक्षा जमा के एक भाग के रूप में माना जाएगा और परिवर्तित किया जाएगा। कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर सुरक्षा जमा के रूप में 2,77,356.00 (दो लाख सत्तर हजार तीन सौ छप्पन रुपये मात्र) जमा करें, अन्यथा जीसीसी के पृष्ठ 16 पर खंड संख्या 1ए की शर्त के अनुसार राशि काट ली जाएगी।

The Earnest money amount of Rs. 2,44,851.00 (Rupees Two Lakhs Forty Four Thousand Eight Hundred Fifty one only) received along with your Tender will be treated and converted as a part of Security Deposit as per condition of clause no. 1A on page – 16 of Contract Document. Please deposit Rs. 2,77,356.00 (Rupees Two Lakhs Seventy Seven Thousand Three Hundred Fifty Six Only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause no. 1A at page no. 16 of GCC.

4. निवेदन है कि आप श्रम अनुबंध (विनियम एवं उन्मूलन) अधिनियम 1970 एवं श्रम अनुबंध (विनियम एवं उन्मूलन) केन्द्रीय नियम 1971, बाल श्रम (विनियम एवं निषेध) अधिनियम 1986, निर्माण मजदूर (रोजगार विनियम एवं सेवा शर्त) अधिनियम 1996, भवन एवं अन्य निर्माण मजदूर कल्याण अधिनियम 1996 का पालन करेंगे, जोकि केन्द्र एवं राज्य सरकार के टेंडर के पृष्ठ संख्या 49 जीसीसी के अनुच्छेद 19 पर दर्शाए गए हैं।

You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and contract labour (Regulation and Abolition) Central rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause 19 on page no. 49 of GCC of tender and rules of Central and State Government.

5. आपको निर्देश दिए जाते हैं कि आप शीघ्रातिशीघ्र वरिष्ठ प्रबंधक (अभि.- सिविल), से सम्पर्क करें जोकि आपको साइट को सौंपने का प्रबंध करेंगे।


You are also directed to contact SM (Engg.-Civil)- immediately who will arrange to hand over the site.

6. कृपया ध्यान दें कि कार्य पूरा करने के लिए 03 (तीन) महीने का समय दिया जाएगा और इसकी गणना इस पत्र के जारी होने के 10वें दिन से या वास्तविक साइट पर कब्जा लेने के बाद, जो भी पहले हो, से माना जाएगा।

Please note that the time allowed for carrying out the work shall be 03(Three) months and same shall be reckoned from the 10th day after issue of this letter or actual site taken over whichever is earlier.

7. इस करार के संबंध में भविष्य में होने वाले सभी पत्राचार प्रभारी अभियंता को संबोधित किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.



8. कृपया इस पत्र की पावती भेजें एवं संलग्न प्रतिलिपि पर हस्ताक्षर करके स्वीकृति के प्रमाणस्वरूप अधोहस्ताक्षरी को वापिस भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

9. किसी भी विवाद की स्थिति में पाठ का अंग्रेजी रूप मान्य होगा।

If case of difference or ambiguity in Hindi and English version, the English version will prevail.

धन्यवाद,

Thanking you,

भवदीय/Yours faithfully,

उप महाप्रबंधक (अभि०-सिविल) / DGM (Engg. - Civil)  
अध्यक्ष, ए ए आई की ओर से तथा उनके लिए/For and on behalf of the Chairman, AAI

संलग्न:- मात्राओं की अनुसूची

Enclosed:- Schedule of Quantities

Validate

Print

Help

## Item Rate BoQ

Tender Inviting Authority: SM(E-C) AAI, Dimapur Airport.

Name of Work: "Construction of Approach road connecting RCC overhead tank in Residential colony at Dimapur airport."

Contract No: 2025\_AAI\_225878\_1

Name of the Bidder/ Bidding Firm / Company : S R COMPANY

## PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

| NUMBER # | TEXT #                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | NUMBER # | TEXT # | NUMBER #                                          | NUMBER #              |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|--------|---------------------------------------------------|-----------------------|
| Sl. No.  | Item Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Quantity | Units  | RATE In Figures To be entered by the Bidder Rs. P | TOTAL AMOUNT in Rs. P |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 4        | 5      | 7                                                 | 8                     |
| 1        | Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in charge. All kinds of soil                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 687.00   | Cum    | 100.00                                            | 68700.00              |
| 2        | Excavating,filling and supplying of earth from AAI premises the by mechanical transport upto a lead of 2km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 1020.00  | Cum    | 80.00                                             | 81600.00              |
| 3        | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : "1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 16.50    | Cum    | 6500.00                                           | 107269.50             |
| 4        | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 cement : 4coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 186.95   | Cum    | 6500.00                                           | 1215175.00            |
| 5        | Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in :cement mortar 1:4 (1 cement : 4 coarse sand).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 11.00    | Sqm    | 800.00                                            | 8800.00               |
| 6        | Steel work in built up tubular (round, square or rectangular hollow tubes etc.), including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 108.00   | Kg     | 160.00                                            | 17280.00              |
| 7        | Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two or more coats on new work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | 260.00   | sqm    | 100.00                                            | 26000.00              |
| 8        | Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earthwith lead upto 50 metres.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 4427.50  | Sqm    | 40.00                                             | 177100.00             |
| 9        | Providing and applying tack coat using hot straight run bitumen of grade VG - 10, including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications :<br>On bituminous surface @ 0.50 Kg / sqm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 810.00   | Sqm    | 30.00                                             | 24300.00              |
| 10       | Painting road surface marking with adequate nos of coats to give uniform finish with ready mixed road marking paint conforming to IS : 164, on bituminous surface in white/yellow shade, including cleaning the surface of all dirt, scales, oil, grease and foreign material etc. complete. Old work (One or more coats).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 430.00   | sqm    | 80.00                                             | 34400.00              |
| 11       | Providing and fixing Glow studs of size 100x20 mm made of heavy duty body shall be moulded ASA (Acrylic styrene Acryloretrite ) or HIP (High impact polystyrene) or ABS having electronically welded micro-prismatic lens with abrasion resistant coating as approved by Engineer in charge. The glow stud shall support a load of 13635 kg tested in accordance with ASTM D4280. The slope of retro- reflective surface shall be 35 (+/-5) degress to base .The reflective panels on both sides with at least 12 cm of reflective area up each side. Theluminance intensity should be as per the specification and shall be tested as described in ASTM I: 809 as recommended in BS: 873 part 4 : 1973. The studs shall be fixed to the Road surface using the adhesive conforming to IS, as per procedure recommended by the manufacturer complete and as per direction of Engineer-in-charge. | 715.00   | each   | 200.00                                            | 143000.00             |

|                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                                                                          |      |         |            |
|----------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------|------|---------|------------|
| 12                   | Providing and laying of Hot Mix Dense Asphaltic Concrete (DAC) using crushed stone aggregate of quality, size and grading as specified and 2% cement by weight of aggregates as filler of quality as specified and Viscosity Grade VG-30 Bitumen (supplied in packed drums) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-in-Charge for tendering purpose VG bitumen of grade (VG-30) content shall be taken as 135 kg/m3 of mix supplied in packed drums produced by Govt. Refineries and 2% cement by weight of aggregates as filler material.                                                                                                | 65.00                                                                    | cum  | 7500.00 | 487500.00  |
| 13                   | Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).                                                                                                                                                               | 65.00                                                                    | Cum  | 4300.00 | 279500.00  |
| 14                   | Supplying and laying locally available sand & gravel mix for construction of granular sub-base & filling including carriage of mixed material by tippers to work site, for all leads, loading & Unloading, spreading in uniform layers of specified thickness manually on prepared surface, complete                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 270.90                                                                   | Cum  | 600.00  | 162540.00  |
| 15                   | Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern. | 1873.00                                                                  | Sqm  | 1100.00 | 2060300.00 |
| 16                   | Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete. 450 mm dia RCC pipes.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 56.00                                                                    | mtr  | 600.00  | 33600.00   |
| 17                   | Providing and fixing Traffic Safety Convex Mirrors mounted simply and easily with the brackets made of Polycarbonate Convex mirrors round body with 130 degree of viewing angle. These Polycarbonate Convex mirrors need to be placed at strategic locations to avoid collision of vehicles to be installed as per direction of Engineer-in-charge. With all complete Pole, bracket mounting & fittings.                                                                                                                                                                                                                                                                                                                                              | 3.00                                                                     | each | 5000.00 | 15000.00   |
| 18                   | Providing and fixing ABS Plastic Speed Breaker of length 1mtr & 75mm height per each need to be placed at strategic locations to control the speed of vehicles & to be installed as per direction of Engineer-in-charge. With all complete Pole, bracket mounting & fittings.                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 70.00                                                                    | each | 4000.00 | 280000.00  |
| Total in Figures     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                                                                          |      |         | 5222064.50 |
| Quoted Rate in Words |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | INR Fifty Two Lakh Twenty Two Thousand & Sixty Four and Paise Fifty Only |      |         |            |

  
DGM(Engg-C)  
Airport Authority of India

Signature Not Verified

Digitally signed by IMPANOLUEN JAMIR  
Date: 2025.12.17 18:10:26 IST  
Location: eProcurement System for Central PSUs