



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
डिब्रूगढ़ हवाई अड्डा, डिब्रूगढ़
DIBRUGARH AIRPORT, DIBRUGARH

Ref: AAI/DIB/ENGG(E)/Grading/W.O.-02/2025-26/335

Date: 06.05.2025

To,
M/s Lalowari Electricals,
Milan Nagar, C.R Building
Dibrugarh, Assam - 786003

Name of Work: "Wall to Wall Grading at Dibrugarh Airport
SH: Execution of Electrical Works related to Wall to Wall Grading at
Dibrugarh Airport."

Ref: 1. Tender Id: 2025_AAI_226404_1

महोदय/Sir,

1. उल्लिखित कार्य हेतु आपकी ई निविदा के सम्बन्ध में, आपके द्वारा उद्धरित राशि कुल रु. **44,99,600 (रूपये चौवालीस लाख नित्यानबे हजार छः सौ मात्र (जी.एस.टी. के बिना))**, जो कि निविदा की औचित्तीय मूल्य राशि रु. 62,21,483/- मात्र से 27.68% कम है, को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है। जीएसटी चालान के उत्पादन पर वास्तविक के अनुसार अतिरिक्त जीएसटी राशि का भुगतान किया जाएगा।

Your E-tender for the above-mentioned work is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling **Rs.44,99,600/- (Rupees Forty-Four Lakhs Ninety-Nine Thousand and Six Hundred Only) (excluding GST)** which is 27.68% below the justified cost of Rs. 62,21,483/- only. Amount of GST will be paid extra as per actual on production of GST invoice.

2. प्रबंधक (इंजी.-विद्युत), डिब्रूगढ़ हवाईअड्डा, कार्य के लिए प्रभारी इंजीनियर होंगे। आपसे अनुरोध है कि आप अपना प्राधिकृत प्रतिनिधि जिसे कि आप की ओर से संविदा करार पर हस्ताक्षर करने की शक्ति दी गई है को प्रबंधक (इंजी.-विद्युत) के कार्यालय में करार पर हस्ताक्षर करने के लिए दिनांक **16.05.2025** तक तैनात करें। (संविदा करार सौ रुपये के नॉन ज्युडिशियल स्टाम्प पेपर पर निष्पादित किया जाएगा और स्टाम्प पेपर की लागत आपको ही वहन करनी होगी।)

Manager (Engg. -E), Dibrugarh Airport, shall be the Engineer-In-Charge of the work. You are requested to depute your accredited representative, empowered to sign the contract agreement on your behalf to attend the office of the **Manager (Engg-E)** by **16.05.2025** to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100.00 (Rupees One Hundred) only and the cost of the stamp paper shall be borne by you.

 06/5/2025

3. कृपया सुरक्षा जमा राशि रु **4,49,960.00** (चार लाख उन्तालीस हजार नौ सौ साठ रुपये मात्र) इस पत्र के जारी होने की तारीख से 10 (दस) दिनों के भीतर जमा करें। ऐसे न करने पर, संविदा के अनुसार यह राशि आपके रनिंग बिल में से काट दिया जाएगा। सुरक्षा जमा दोष दायित्व अवधि के संतोषजनक पूरा होने के बाद ही वापस किया जाएगा।

Please deposit **Rs. 4,49,960.00 (Rupees Four Lakhs Forty-Nine Thousand Nine Hundred and Sixty Only)** towards security deposit within 10 (Ten) days from the date of issue of this letter, failing which, the same will be deducted from your running bill as per contract agreement. The Security deposit shall be refunded only after satisfactory completion of defect liability period.

4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण कार्यकर्ताओं (रोजगार और सेवा की शर्त का विनियमन)) अधिनियम 1996, बिल्डिंग और अन्य निर्माण श्रमिक कल्याण सेस अधिनियम 1996 केंद्रीय और राज्य सरकार के नियमों का पालन करें।

You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and contract labour (Regulation and Abolition) Central rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act of Central and State Government.

5. आपको निर्देश दिए जाते हैं कि आप **सहा. प्रबंधक (अभि.- विद्युत), भा.वि.प्र., डिब्रूगढ़ हवाईअड्डा**, से तत्काल सम्पर्क करें जो कि आपको कार्यस्थल सुपर्द करने की व्यवस्था करेंगे। कृपया यह नोट कर लें कि काम करने का समय **06 महीना** है जिसे तारीख **16.05.2025** से गिना जाएगा।

You are directed to contact **Asst. Manager (Engg-E), AAI, Dibrugarh Airport**, immediately who will arrange to handover the site to you. Please note that the time allowed for carrying out the work is **06 MONTHS**, which shall be reckoned from **16.05.2025**

6. अनुबंध की दोष देयता अवधि पूरा होने की दर्ज तिथि से **12 (बारह) महीने**

Defects liability period of contract is **12 (Twelve) months** from the recorded date of completion.

7. संविदा के संबंध में आगे किया जाने वाला पत्राचार समान्यतः **प्रबंधक (इंजी.-विद्युत), भा.वि.प्र., डिब्रूगढ़ हवाईअड्डा, डिब्रूगढ़ -786012**, से किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the **Manager (Engg. -E), AAI, Dibrugarh Airport, Dibrugarh -786012**.

 06/5/2025


8. कृपया प्रतिग्रहण के टोकन के रूप में कार्य आदेश की प्राप्ति को स्वीकार करें ।

Please acknowledge the receipt of the Letter of Award as a token of acceptance.

9. यदि कहीं विसंगति पाई जाती है तो अंग्रेज़ी भाषा ही मान्य होगी ।

In case any discrepancy is found, then English version will be taken as correct.

भवदीय / Yours faithfully,



(के के सुरेशकुमार)

(K K Sureshkumar)

प्रबंधक (अभि.-विधुत)

Manager (Engg.- Elect.)

कृते तथा की ओर से अध्यक्ष, भा.वि.प्रा.

For and on behalf of Chairman, AAI

भा.वि.प्रा. डिब्रूगढ़ विमानपत्तन

AAI, Dibrugarh Airport

Item Rate BoQ

Tender Inviting Authority:

Name of Work: Wall to Wall Grading at Dibrugarh Airport S.H : Execution of Electrical Works related to Wall to Wall Grading at Dibrugarh Airport

Contract No: 2025_AAI_226404_1


Name of the Bidder/ Bidding Firm / Company		M/s Lalowari Electricals				
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Supply of following size of XLPE insulated & PVC sheathed, armoured, aluminium conductor under ground cable of 1.1KV grade as per IS 7098:1988 Part-I with upto date amendments complete as required. (Make: As per AAI list of approved makes)					
1.01	3.5C X 185 sqmm	1500.00	Mtr	800.00	1200000.00	INR Twelve Lakh & Paise Zero Only
1.02	3.5C X 120 sqmm	1000.00	Mtr	550.00	550000.00	INR Five Lakh Fifty Thousand & Paise Zero Only
1.03	3.5C X 50 sqmm	1000.00	Mtr	260.00	260000.00	INR Two Lakh Sixty Thousand & Paise Zero Only
1.04	4 C X 16 sqmm	1000.00	Mtr	150.00	150000.00	INR One Lakh Fifty Thousand & Paise Zero Only
2	Supply of 110 mm dia HDPE pipe, ISI marked along with all accessories like socket, couplers etc. conforming to IS 4984-1995, PN4 grade, PE63 etc.	2000.00	Mtr	270.00	540000.00	INR Five Lakh Forty Thousand & Paise Zero Only
3	Supply of 63 mm dia HDPE pipe, ISI marked along with all accessories like socket, couplers etc. conforming to IS 4984-1995, PN4 grade, PE63 etc.	1900.00	Mtr	110.00	209000.00	INR Two Lakh Nine Thousand & Paise Zero Only
4	Laying of HDPE/ DWC pipe of up to 63 mm dia size complete with fitting and cutting, jointing etc.direct in ground (80 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc. , complete as required.	1900.00	Mtr	110.00	209000.00	INR Two Lakh Nine Thousand & Paise Zero Only
5	Laying of HDPE/ DWC of pipe above 63mm and upto(including) 110mm dia size complete with fitting and cutting, jointing or including butt joint welding wherever required etc.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc. , complete as required.	2000.00	Mtr	100.00	200000.00	INR Two Lakh & Paise Zero Only
6	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL/DWC-HDPE pipe as required					
6.01	Upto 35 sqmm	1200.00	Mtr	40.00	48000.00	INR Forty Eight Thousand & Paise Zero Only
6.02	Above 35 sq. mm and upto 95 sq. mm	700.00	Mtr	60.00	42000.00	INR Forty Two Thousand & Paise Zero Only

Handwritten signature and date: 26/5/2025

6.03	Above 95 sq. mm and upto 185 sq. mm	2000.00	Mtr	70.00	140000.00	INR One Lakh Forty Thousand & Paise Zero Only
6.04	185 sq. mm and upto 400 sq. mm	200.00	Mtr	130.00	26000.00	INR Twenty Six Thousand & Paise Zero Only
7	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of size in the existing masonry open duct as required					
7.01	Upto 35 sqmm	100.00	mtr	30.00	3000.00	INR Three Thousand & Paise Zero Only
7.02	Above 35 sq. mm and upto 95 sq. mm	100.00	Mtr	30.00	3000.00	INR Three Thousand & Paise Zero Only
7.03	Above 95 sq.mm and upto 185 sqmm	50.00	Mtr	50.00	2500.00	INR Two Thousand Five Hundred & Paise Zero Only
8	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV/5KV grade of following size on cable tray/surface as required					
8.01	upto 35 sqmm	250.00	Mtr	50.00	12500.00	INR Twelve Thousand Five Hundred & Paise Zero Only
8.02	Above 35 sq. mm and upto 95 sq. mm (clamped with 25x3mm MS flat clamp)	50.00	Mtr	100.00	5000.00	INR Five Thousand & Paise Zero Only
8.03	Above 95 sq.mm and upto 185 sqmm	50.00	Mtr	100.00	5000.00	INR Five Thousand & Paise Zero Only
8.04	Above 185 sq.mm and upto 400 sqmm	50.00	Mtr	200.00	10000.00	INR Ten Thousand & Paise Zero Only
9	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.					
9.01	3.5 C X 50 sqmm	2.00	Each	2300.00	4600.00	INR Four Thousand Six Hundred & Paise Zero Only
9.02	3.5 C X 70 sqmm	2.00	Each	3200.00	6400.00	INR Six Thousand Four Hundred & Paise Zero Only
9.03	3.5 C X 95 sqmm	4.00	Each	3200.00	12800.00	INR Twelve Thousand Eight Hundred & Paise Zero Only
9.04	3.5 C X 120 sqmm	4.00	Each	4500.00	18000.00	INR Eighteen Thousand & Paise Zero Only
9.05	3.5 C X 185 sqmm	6.00	Each	4500.00	27000.00	INR Twenty Seven Thousand & Paise Zero Only
9.06	3.5 C X 240 sqmm	4.00	Each	4500.00	18000.00	INR Eighteen Thousand & Paise Zero Only
9.07	3.5 C X 300 sqmm	3.00	Each	5500.00	16500.00	INR Sixteen Thousand Five Hundred & Paise Zero Only
10	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.					
10.01	3.5C x 50 sq.mm (35mm)	10.00	Set	300.00	3000.00	INR Three Thousand & Paise Zero Only
10.02	3.5 x 70 sq. mm (38mm)	10.00	Set	400.00	4000.00	INR Four Thousand & Paise Zero Only
10.03	3.5 C X 95 sq.mm (45 mm)	10.00	Set	500.00	5000.00	INR Five Thousand & Paise Zero Only
10.04	3.5 x 120 sq.mm (45mm)	6.00	Set	500.00	3000.00	INR Three Thousand & Paise Zero Only
10.05	3.5 C x 185 sq. mm (57 mm)	10.00	Set	600.00	6000.00	INR Six Thousand & Paise Zero Only
10.06	3.5 x 240 sq.mm (62 mm)	8.00	Set	800.00	6400.00	INR Six Thousand Four Hundred & Paise Zero Only
10.07	3.5 x 300 sq.mm (70 mm)	8.00	Set	900.00	7200.00	INR Seven Thousand Two Hundred & Paise Zero Only

Handwritten signature and date:
 26/5/2023

10.08	4 x 10 sq. mm (25mm)	50.00	Set	200.00	10000.00	INR Ten Thousand & Paise Zero Only
10.09	4 C X 16 sqmm	50.00	Set	200.00	10000.00	INR Ten Thousand & Paise Zero Only
10.10	4 C X 25 sqmm (28 mm)	50.00	Set	200.00	10000.00	INR Ten Thousand & Paise Zero Only
11	Excavation of the cable trenches in hard rock not exceeding 1.5 meter in width, and lift upto 1.5 meter, including getting out the excavated soil and disposal of excavated soil as directed within a lead of 50 meter.	3.00	Cum	900.00	2700.00	INR Two Thousand Seven Hundred & Paise Zero Only
12	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required.	20.00	Set	3500.00	70000.00	INR Seventy Thousand & Paise Zero Only
13	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing CI Collar of height 300mm, 330mm dia made of 10mm thick cast iron moulding all round, (installation of collar/enclosure with cement concrete around collar) including 10mm thick MS cover plate fixing on collar with SS bolts, side entry hole on collar for earth strip/wire entry arrangement and watering pipe etc. with charcoal/ coke and salt as required.	30.00	Set	5000.00	150000.00	INR One Lakh Fifty Thousand & Paise Zero Only
14	Providing and fixing 25 mm X 5 mm G.I. strip on surface or in recess for connections etc. as required.	100.00	Mtr	150.00	15000.00	INR Fifteen Thousand & Paise Zero Only
15	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ recessed conduit/submain wiring/ cable as required	500.00	mitr	20.00	10000.00	INR Ten Thousand & Paise Zero Only
16	Providing and laying in position cement concrete of specified grade 1:2:4(1 Cement:2Coarse sand :4 graded stone aggregate 20mm nominal size) at all levels for damaged portion of wall/road/paver block portion etc., complete as required.	15.00	Cumtr	3500.00	52500.00	INR Fifty Two Thousand Five Hundred & Paise Zero Only
17	Constructing masonry Chamber 120x120x100 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 M sand) , with RCC top slab 1:2:4 mix (1 cement : 2 M sand : 4 graded stone aggregate 20 mm nominal size) , i/c necessary excavation, foundation concrete 1:5:10 (1 cement : 5 M sand : 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3M sand) 12 mm thick, finished with a floating coat of neat cement complete as per standard design :	15.00	Each	8500.00	127500.00	INR One Lakh Twenty Seven Thousand Five Hundred & Paise Zero Only
18	Supply and Fixing of Cable termination box of minimum size of 160 x 200 x 98 mm, including terminals for connecting LT cables including 6A SP MCB, fixing of box on wall/pole with suitable clamps etc., as required equivalent to hensei KM 9255	100.00	Each	1500.00	150000.00	INR One Lakh Fifty Thousand & Paise Zero Only
19	Supply and Laying of PVC insulated, PVC sheathed round flexible cable of size 3C X 2.5 sqmm cable, from junction box to light points including necessary connection, suitable glanding etc., as required.	400.00	Mtr	190.00	76000.00	INR Seventy Six Thousand & Paise Zero Only
20	Supply and fixing of CI collar compatible with existing installed CI box, round type, metal complainer of outside size 330mm dia, height 75-150 mm made of 10mm thick cast iron moulding all round, except the top and bottom side shall have 6 hole (without tapping) in line with tapped holes (6 nos) of existing transformer housing box top surface, The collar should have clear opening of 220 mm at the top & bottom surface, installing the collar on existing CI box by providing suitable cement concrete along with providing necessary M10 bolts, washer etc., 1 no. gasket etc. complete as required.	35.00	Each	1800.00	63000.00	INR Sixty Three Thousand & Paise Zero Only
Total in Figures					4499600.00	INR Forty Four Lakh Ninety Nine Thousand Six Hundred & Paise Zero Only
Quoted Rate in Words					INR Forty Four Lakh Ninety Nine Thousand Six Hundred & Paise Zero Only	


 प्रबंधक (अभियन्ता)
 Manager (Engg-Elect.)
 भारतीय विमानपत्तन प्राधिकरण
 Airports Authority of India
 गढ़ हवाई अड्डा, गढ़ब्रुगढ़ Airport.