

संदर्भ सं. भाविप्रा/बिओ/सहा.म.प्र.(अभि-वि)/एसी-दीव/डबल्यू-05/2025-26 / 8/
Ref. No.: AAI/BO/Jt.GM(E-E)/AC-DIU/W-05/2025-26

दि. 29.05.2025
Dt. 29.05.2025

By Speed Post / E-mail

सेवा में,
मेसर्स सुरभि एसोसिएशन
ई-17-बी, सुरेंद्र विहार
बागमुगालिया, होशंगाबाद रोड
भोपाल (म.प्र.) - 462043

To,
M/s Surbhi Association,
E-17- B, Surendra Vihar,
Bagmugaliya, Hoshangabad Road
Bhopal (M.P.) - 462043.

कार्य का नाम : दीव हवाई अड्डे पर विभिन्न स्थानों पर स्प्लिट प्रकार के एयर कंडीशनर तथा अन्य विद्युत उपकरणों का प्रावधान।

Name of work : Provision of Split type air conditioners at various place and other Electrical items at Diu
Airport

संदर्भ : सीपीपी पोर्टल निविदा संख्या 2025_AAI_227193_1 प्राप्त आपकी ई-निविदा (वित्तीय बिड) दिनांक
17.04.2025 को खोला गया।

महोदय,

1) कृपया उपरोक्त सीपीपी आई.डी.से संबंधित आपके टेंडर का अवलोकन करे।

Kindly refer your tender submission i.r.o above CPP I.D.

2) उपरोक्त कार्य हेतु आपकी ई-निविदा, अध्यक्ष, भा.वि.प्रा. की ओर से स्वीकृत की जाती है। आपके द्वारा बताये गए आइटम मूल्यों पर आपकी ई-निविदा राशि कुल रु 34,25,150.00 (रु चौंतीस लाख पच्चीस हजार एक सौ पचास मात्र) (जीएसटी रहित) है, जोकि ई-निविदा की उचित लागत रु 37,90,123.00 (जीएसटी रहित) से 9.63 % निचे है। एजेंसी द्वारा वैध टैक्स इनवॉइस प्रस्तुत करने पर जीएसटी अदा किया जायेगा। दीव के लिए एएआई जीएसटी क्रमांक GSTIN 26AAACA6412D1ZA है।

Your e-tender for the work mentioned above is hereby accepted on behalf of The Chairman, Airports Authority of India at the item rates quoted by you totalling to Rs. 34,25,150.00 (Rs. Thirty-four lakh twenty-five thousand one hundred fifty only.) (Excl GST), which is 9.63% below the estimated cost of Rs. 37,90,123.00 (Excl. GST). GST will be paid against valid tax invoice from the agency. For Diu UT, AAI GSTIN is 26AAACA6412D1ZA.

3) संयुक्त महाप्रबंधक (अभि.-वि.), भारतीय विमानपत्तन प्राधिकरण, वडोदरा हवाई अड्डा, वडोदरा - 390022 कार्य के प्रभारी अभियंता होंगे। आप से निवेदन है की आपकी ओर से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करे जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वहा दिनांक 15.06.2025 तक संयुक्त महाप्रबंधक (अभि.-वि.), भारतीय विमानपत्तन प्राधिकरण, वडोदरा हवाई अड्डा, वडोदरा - 390022 के कार्यालय में उपस्थित हो तथा करारनामे को पूरा करे। ठेके का करारनामा रु.300/- (रुपये तिन सो मात्र) के नोनज्युडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा स्टैम्प पेपर का खर्च आपके द्वारा उठाया जाएगा।

Cont.page:- 2/-

Jt.GM (Engg-E), Airports Authority of India Vadodara Airport, Vadodara – 390 022 shall be Engineer-in-Charge of the work. You are requested to depute your accredited representative, empowered to sign the contract agreement on your behalf to attend the office of the Jt.GM (Engg-E), Airports Authority of India Vadodara Airport, Vadodara – 390 022 by 15.06.2025 to sign and complete the agreement. The contract agreement shall be executed on a non - judicial stamp paper of value Rs. 300/- and the cost of the stamp paper shall be borne by you.

- 4) कृपया इस पत्र के जारी होने के 15 दिनों के भीतर निविदा की सामान्य शर्तों प्रष्ठ संख्या GCC के clause No.1 A के अनुसार सिक्यूरिटी डिपोजिट के लिए राशी रु 3,42,515/- (तीन लाख बयालीस हजार पांच सौ पंद्रह रुपये) केवल जमा कर दे, अन्यथा इतनी ही राशी आपके रनिंग बिलो से काट ली जाएगी ।

Please deposit Rs. 3,42,515.00 (Rupees Three Lakh Forty Two Thousand Five Hundred Fifteen Only) towards security deposit as per clause No.1A of GCC of tender document within 15 Days from the Date of issue of this letter, falling which the same will be deducted from your running bill.

- 5) आपसे निवेदन है कि आप केन्द्रीय और राज्य सरकारों 1970 के अधिनियम अनुबंध श्रम नियम (नियम तथा उन्मुलन), 1971 के केन्द्रीय नियम श्रम नियम (नियम तथा उन्मुलन) एवं केंद्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और नियमों के प्रावधानों का अनुपालन करें ।

You are requested to comply with the provision of contract labour (Regulation and abolition Act of 1970 and contract labour Regulation and abolition) Central rules 1971 and minimum wages Act & rules thereof central and state Governments.

- 6) आपको निर्देश दिया जाता है की आप तुरंत सहायक प्रबंधक (इंजी- विद्युत), दिव हवाई अड्डा से संपर्क करें जो आपको साईट सोपने की व्यवस्था करेंगे । कृपया नोट कर ले की काम करने का अनुमानित समय 06 महीने (छह महीने) है जोकि इस कार्य आदेश के जारी होने के दसवे दिन से गिना जाएगा ।

You are also directed to contact Asst. Manager (Engg-E) Diu Airport immediately who will arrange to hand over the site to you. Please note that the time allowed for carrying out the work is 06 Months (Six Months) which shall be reckoned from the 10th day of issue of this workorder.

- 7) ठेकेदार द्वारा किसी सुरक्षा विनियमों का उलंघन करते पाये जाने पर उसे ब्लैकलिस्टेड कर दिया जायेगा और अन्य कानूनी कार्यवाही की जायेगी ।

If contractor is found to violate any of security regulation, he shall be black listed and will be subjected to other legal proceedings.

- 8) इस ठेके के संबंध में आगे का कोई भी पत्राचार संयुक्त महाप्रबंधक (इंजी -विद्युत), भारतीय विमानपत्तन प्राधिकरण, वडोदरा हवाई अड्डा, वडोदरा - 390022 के पते पर किया जाए ।

Any further correspondences in connection with the contract should normally be addressed to the Jt.GM (Engg-Elect), Airports Authority of India Vadodara Airport, Vadodara – 390 022.

Cont.page:- 3/-

- 9) उपरोक्त कार्य के लिए त्रुटी दायित्व की अवधि 01 साल होगी जो कार्य के प्रमाणित समाप्ति के दिन से गिनी जाएगी।
The defects liability period for the above mentioned work shall be 01 year from the certified date of completion work.
- 10) उपरोक्त अंग्रेजी और हिंदी पाठ में मतभेद होने पर अंग्रेजी लिपि में लिखित पाठ्य मान्य होगा।
In case of discrepancy in Hindi and English text than English text will be taken as correct.
- 11) कृपया पावती बेजे।
Please acknowledge the receipts

संलग्नक: Schedule of Quantity

धन्यवाद / Thanking you,

भवदीय / Yours Faithfully,



(सचिन बी. खंगार)
(Sachin B. Khangar)
संयुक्त महाप्रबंधक (अभि.-विधुत)
Jt. General Manager (Engg-E)
कृते तथा ओर से अध्यक्ष
For and on behalf of chairman,
भारतीय विमानपत्तन प्राधिकरण, वडोदरा एयरपोर्ट.
Airports Authority of India, Vadodara Airport.

प्रतिलिपि/ Copy To - For Favour of Information

1. सहायक श्रम आयुक्त (केन्द्रीय), कोठी कम्पाउंड, राजकोट-360001।
The Assistant Labour Commissioner(Central), Kothi Compound, Rajkot-360001.
2. क्षेत्रीय भविष्य निधि आयुक्त, पंचायत नगर चौक, यूनिवर्सिटी रोड, राजकोट - 360005।
The Regional P.F Commissioner, Panchayat Nagar Chowk, University Road, Rajkot - 360005.

Cont.page:- 4/-

- 4 -

प्रतिलिपि/ Copy To : (NOO)

1. महाप्रबंधक (अभि), भारतीय विमानपत्तन प्राधिकरण, आरएचक्यू, पश्चिम क्षेत्र, इंटीग्रेटेड प्रशासनिक भवन, पारसी वाड़ा के सामने, सहार रोड, विले पार्ले(पूर्व), मुंबई - 400 099.
General Manager (Engg), Airports Authority of India, RHQ, Western Region, Integrated Administrative Building, Opp. Parsiwada, Sahar Road, Vile Parle (E), Mumbai - 400099.
2. संयुक्त महाप्रबंधक(सतकर्ता), भारतीय विमानपत्तन प्राधिकरण, आरएचक्यू, पश्चिम क्षेत्र, इंटीग्रेटेड प्रशासनिक भवन, पारसी वाड़ा के सामने, सहार रोड, विले पार्ले(पूर्व), मुंबई - 400 099.
Jt.Gen.Manager (Vigilance), Airports Authority of India, RHQ, Western Region, Integrated Administrative Building, Opp. Parsiwada, Sahar Road, Vile Parle (E), Mumbai - 400099..
3. संयुक्त महाप्रबंधक(वित्त), भारतीय विमानपत्तन प्राधिकरण, आरएचक्यू, पश्चिम क्षेत्र, इंटीग्रेटेड प्रशासनिक भवन, पारसी वाड़ा के सामने, सहार रोड, विले पार्ले(पूर्व), मुंबई - 400 099.
Jt.Gen.Manager (Fin), Airports Authority of India, RHQ, Western Region, Integrated Administrative Building, Opp. Parsiwada, Sahar Road, Vile Parle (E), Mumbai - 400099.

आंतरिक विवरण / INTERNAL: (By E-mail)

1. विमानपत्तन निदेशक, भाविप्रा, दीव एयरपोर्ट, दीव /Airport Director, Airports Authority of India, Diu Airport, Diu. - सूचनार्थ ।
2. सहायक प्रबंधक (अभि-विधुत)/AM (E-E), Airports Authority of India, Diu Airport, Diu- कार्य निष्पादन हेतु।
3. कार्य फाइल / Work File
4. करारनामा फाइल / Agreement File
5. हिन्दीगार्ड फाइल/ Hindi Guard File

सचिन खंगार
29/5/2025

(सचिन बी. खंगार)

(Sachin B. Khangar)

संयुक्त महाप्रबंधक (अभि-विधुत)

Jt. General Manager (Engg-E)

कृते तथा ओर से अध्यक्ष

For and on behalf of chairman,

भारतीय विमानपत्तन प्राधिकरण, वडोदरा एयरपोर्ट.
Airports Authority of India, Vadodara Airport.

SCHEDULED OF QUANTITY

Name of Work- Provision of Split type air conditioners at various place and other Electrical items at Diu Airport.

Item No.	Item Description	Unit	Qty.	Rate (w/o GST)	Amount (w/o GST)
1	Supply of 1.5 TR , single phase Split type Airconditioner, 5 star BEE rated having one no. non-ductable, wall mounting type indoor unit fitted with copper evaporator and one no. anti-rust coated outdoor unit fitted with copper condenser with sealed compressor, operating on eco-friendly refrigerant , suitable for operation on 230 V, 50 HZ AC power supply, capable of performing (a) Cooling (b) hydro blue coating Fins or hydro golden color coating Fins (c) suitable for operation near seashore environment (Heavily Corrosive) etc. including refrigerant piping, PVC drain pipe and standard power cable up to length of 3 meters, complete as per technical specification.	Each	25	37000.00	925000.00
2	Supply of 2 TR , Single phase Split type Airconditioner, 5 star BEE rated having one no. non-ductable, wall mounting type indoor unit fitted with copper evaporator and one no. anti-rust coated outdoor unit fitted with copper condenser with sealed compressor, operating on eco-friendly refrigerant , suitable for operation on 230 V, 50 HZ AC power supply, capable of performing (a) Cooling (b) hydro blue coating Fins or hydro golden color coating Fins (c) suitable for operation near seashore environment (Heavily Corrosive) etc. including refrigerant piping, PVC drain pipe and standard power cable up to length of 3 meters, complete as per technical specification.	Each	8	49000.00	392000.00
3	Installation, testing and commissioning of 1.5 TR/ 2 TR Split AC units including fixing the outdoor unit with duly painted MS angle iron Suitable stand and fixing of Indoor unit including wall cutting, hole cutting etc. and fixing of (i) insulated copper pipe - liquid line & suction line (ii) wiring between indoor and outdoor units (iii) drain piping (all up to the standard length of 3 mtrs), and first charge of eco - friendly refrigerant etc. complete as per technical specification and site condition.	Job	33	1500.00	49500.00
4	Supply and fixing of refrigerant copper piping - liquid line & suction line with insulation & other accessories in all respect for connection between Indoor and Outdoor unit, extra after standard length of 3 mtrs for 1.5 TR/2 TR, single phase AC units complete as per technical specification and site condition.	Mtr.	150	600.00	90000.00
5	SITC of auto change over timer for seriallax opration of main and stand by AC, suitable for single phase 230 volt, 50Hz AC supply,complete with standard accessories and as per site requirement.	Job	8	2500.00	20000.00

SCHEDULED OF QUANTITY

Name of Work- Provision of Split type air conditioners at various place and other Electrical items at Diu Airport.

Item No.	Item Description	Unit	Qty.	Rate (w/o GST)	Amount (w/o GST)
6	SITC of Low Impedance Digital Grounding System 240KA Three Phase four wire LIDGS 4th Generation equipment Grounding & bonding system with built in 100% Lightning and Surges, static charge, Noises, ESD, EPR and abnormal electrical characteristics eliminator which enter from power and other service lines and ensuring clear bonding potential (earth to Neutral voltage) less than 1.0V, a digital 3 Digit LCD Impulse real Date time Counter with threshold of IKA, self-health visual status indicator, built Zero leakage Current based solution. Lightning Impulse Current Discharge Capability up to 12 KA (10/350µsec) Surge Discharge Current Capability up to 40KA (8/20µsec) 7 Modes of Protection (LI-N, N-PE, LI PE) total surge handling capacity 240KA Short-circuit extinguishing and limiting capabilities up to 25KA Arms without tripping of Let-through-energy of less than 01 Joule in a Pre-wired pulverulent body painted metal enclosure to be connected in parallel to the power supply circuit, Conforming solution and Accessories Kit is CE NABL IEC 61643-11-2011. (Make - NEXPO / VASU / DEHN)	Job	1	205000.00	205000.00
7	SITC of Reverse Osmosis System Industrial Grade with a capacity of 250 LPH designed for Treatment of saline water in the TDS range of 500-2000ppm which are Completely assembled /Pre-piped/Pre-wired with Microprocessorbased control Pannel for ease of operation and inbuilt process Logic having provision for Auto start/stop based on Water level in the Tank with MCB for Plantoperation and Raw water pump integrated with Plant. Integrated pretreatment Module for removal of suspended solids along with pressure gauges, Robusthigh Pressure Pump, Inbuilt Protection to high Pressure Pump by Way of LowPressure Switch/high Pressure switch and Glycerine filled SS Pressure gauges for durability, On line Rota meter for measuring permeate flow and SS skid with plated hardware with provision of Blending cartridge to adjust Taste/TDS having Following. (a) Pressure Sand Filter (PSF) (b) Activated Carbon Filter Capacity (ACF) (c) Antiscalant Dosing System. (d) Antiscalant Dosing Tank Capacity Litres 50 (f) Micron cartridge Filter(PP) (g) High Pressure Pump (HPP) (h) RO Membrane 4''X40''-1nos (i) UV Filtration (k) Raw water pump	Job	1	295000.00	295000.00

SCHEDULED OF QUANTITY

Name of Work- Provision of Split type air conditioners at various place and other Electrical items at Diu Airport.

Item No.	Item Description	Unit	Qty.	Rate (w/o GST)	Amount (w/o GST)
8	SITC of RO Reverse osmosis system designed to deliver min 50 liters of purified water per hour through a 6 stage purification process. Its membrane should have a pore size of 0.0001 micron size which prevents the passage the of micro organisms and total dissolved salts making the water lighter, taste natural and safe to drink with automated Switching on/ off device for water level monitoring system.	Job	2	90000.00	180000.00
9	Supply of 300 mm dia, Size 12inch, 1400 RPM Exhaust fan (PVC Type) suitable for single phase 230 volt, 50Hz AC supply complete with motor, capacitor,having low noise level, louvers/shutters and all accessories as required complete of AAI approved make.	Each	10	1650.00	16500.00
10	Supply and providing rubbur insulating mat (Black) 1 meter wide and 2mm thick to with stand 3.3 kv dielectric strenth as per IS 5424-1696	Mtr.	100	850.00	85000.00
11	Supply and providing rubbur insulating mat (Blue) 1 meter wide and 2.5mm thick to with stand 15 kv dielectric strenth as per IS 5424-1696	Mtr.	60	1000.00	60000.00
12	Supply of Refrigerator of capacity 175 litre & above, single phase 230V, 50 Hz AC,having operating on eco-friendly refrigerant, system factory built complete with standard accessories, protections, etc. of AAI approved make.	Each	2	11000.00	22000.00
13	Supply of Refrigerator of capacity 45 litre & above, single phase 230V, 50 Hz AC,having operating on eco-friendly refrigerant, system factory built complete with standard accessories, protections, etc. of AAI approved make.	Each	7	8500.00	59500.00
14	Supply and fixing of Automatic Jet Hand dryer made out of stainless steel / High grade ABS, wall mounted type and operated on touch free infrared activation sensor range upto 15cm , Noise level 60 to 80 db suitable for operation of 230v,50Hz AC supply etc as required.	Job	10	18500.00	185000.00
15	Supply of 20A, TPN, 10KA, MCB, C SERIES switchgears suitable to operate on 220/440 volt 50 Hz AC supply etc. as required.	Each	10	1300.00	13000.00
16	Supply of portable emergency LED light with Inbuilt rechargeable battery having minimum 5 hrs. backup time,brightness control etc.as required.	Each	8	1500.00	12000.00
17	Supply of L&T Make 630A 4P 50kA MCCB for existing Panel with thermal based release, 415V AC, 50Hz with suitable CTs. (Ics=100% Icu=50KA)	Each	2	35000.00	70000.00
18	Supply of Single core,1.5Sqmm Wire FR-LSH PVC insulated copper condutor cable (unsheathed), 1100 volt conforming to IS 694 of approved make and different colour etc as required. (90 Mtr length of each Roll)	Mtr.	1000	17.25	17250.00

SCHEDULED OF QUANTITY

Name of Work- Provision of Split type air conditioners at various place and other Electrical items at Diu Airport.

Item No.	Item Description	Unit	Qty.	Rate (w/o GST)	Amount (w/o GST)
19	Supply of Single core,2.5Sqmm Wire FR-LSH PVC insulated copper conductor cable (unsheathed), 1100 volt conforming to IS 694 of approved make and different colour etc as required. (90 Mtr length of each Roll)	Mtr.	400	28.50	11400.00
20	Supply of Single core,4Sqmm Wire FR-LSH PVC insulated copper conductor cable (unsheathed), 1100 volt conforming to IS 694 of approved make and different colour etc as required. (90 Mtr length of each Roll)	Mtr.	800	44.00	35200.00
21	Supply of 3Cx1.5Sqmm PVC insulated and FR PVC round sheathed copper conductor (Flexible) industrial cable, 1100V conforming to IS:694, etc as required.	Mtr.	400	62.00	24800.00
22	Supply of 3Cx2.5Sqmm PVC insulated and FR PVC round sheathed copper conductor (Flexible) industrial cable, 1100V conforming to IS:694, etc as required.	Mtr.	400	100.00	40000.00
23	Supply of 3Cx4Sqmm PVC insulated and FR PVC round sheathed copper conductor (Flexible) industrial cable, 1100V conforming to IS:694, etc as required.	Mtr.	400	145.00	58000.00
24	Supply of 5Cx6Sqmm PVC insulated and FR PVC round sheathed copper conductor (Flexible) industrial cable, 1100V conforming to IS:694, etc as required.	Mtr.	1000	350.00	350000.00
25	Supply of 4 x 16 Sq.mm,1.1 kV grade, XLPE insulated and PVC sheathed aluminium conductor armoured Power cable conforming to IS:7098 (Part 1) with up to date amendments.	Mtr.	1000	135.00	135000.00
26	Supply of 12V, 180 AH maintenance free battery having quick recharge facility with leak resistant design, provision of magic eye ready to use condition suitable for direct installation at the site.(for Electric panel and Vehicle usage)	Each	4	18500.00	74000.00
TOTAL (A)					3425150.00

Rupees ThirtyFour Lakh TwentyFive Thousand One Hundred Fifty Only

Note :- The GST shall be paid extra as applicable on production of documentary evidence

(Sachin B. Khangar)
Jt. GM (E-E)
AAI, Vadodara Airport

Signature Not Verified
Digitally signed by RAVINDER SINGH MEHROK
Date: 2025.06.06 13:40:04 IST
Location: eProcurement System for Central PSUs