



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

भाविप्रा/वडोदरा/ई-सी/B-Wall&WatchTowerWorks/डब्ल्यू-279/2025-26/1204
AAI/Vadodara/E-C/B-Wall&WatchTowerWorks/W-279/2025-26/

दिनांक: 15/04/2025
Date: 15/04/2025

सेवा में,
मेसर्स शारदे इंफ्राकॉन प्राइवेट लिमिटेड,
ए-193, सनसिटी, जय अम्बे स्कूल के पास,
मांजलपुर, वडोदरा, गुजरात-390011

To,
M/s. Shardey Infracon Private Limited,
A-193, Suncity, Opp. Jay Ambe School,
Manjalpur, Vadodara, Gujarat-390011

कार्य का नाम: वडोदरा नागरिक हवाई अड्डे पर चरण-1 के तहत परिचालन सीमा दीवार का निर्माण (एफएस क्षेत्र और झुकी हुई सीमा दीवार)

उप-शीर्षक: एफएस क्षेत्र एवं झुकी हुई सीमा दीवार पर परिचालन सीमा दीवार और 5 प्रहरीदुर्गों (वॉच टावर) का निर्माण।

(निविदा आई. डी. - 2024_AAI_227846_1)

Name of Work: C/o operational boundary wall in stretches at C.A Vadodara (Phase-1) (AFS area and tilted portion of B/wall)

Sub-Head : Construction of Operational boundary wall at AFS area & Tilted portion and 5 no. watch towers.

(Tender ID - 2024_AAI_227846_1)

संदर्भ:- दिनांक 28/03/2025 को खोला गया आपका ई-टेंडर । (वित्तीय बोली)

Ref: Your e-tender opened on 28/03/2025 (Financial Bid)

महोदय/Sir,

- उपर्युक्त कार्य हेतु आपकी निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से, आपके द्वारा बताए गये मद दर मूल्यों पर निविदा की राशि कुल रु. 1,00,91,475.00 (रुपये एक करोड़ इक्यानवे हजार चार सौ पचहतर मात्र) (बगैर GST) स्वीकृत किया जाता है, जो कि निविदाकी अनुमानित लागत राशि रु. 135.94 Lakh (बगैर GST) से 25.77% कम है।
Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs. 1,00,91,475.00 (Excluding GST) (Rupees One Crore Ninety-One Thousand Four Hundred Seventy-Five only), which is 25.77% below the estimated cost put to tender of Rs. 135.94 Lakh (Excluding GST).
- सहायक महाप्रबंधक (अभि-सिविल), वडोदरा विमानक्षेत्र, वडोदरा कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप स्वयं या आपकी ओर से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करे जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 30.04.2025 तक सहायक महाप्रबंधक (अभि-सिविल), वडोदरा विमानक्षेत्र के कार्यालय में उपस्थित हो तथा करारनामे को पूरा करे। ठेके का करारनामा रु. 300/- (रु. तीन सौ मात्र) के नोन ज्यूडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा स्टैम्प पेपर का खर्च आपके द्वारा वहन किया जाएगा।
Assistant General Manager (Engg- Civil), Vadodara Airport, Vadodara shall be the Engineer-in-charge of the work. You are requested to attend or depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the office of the Assistant General Manager (Engg- Civil), Vadodara Airport by 30.04.2025 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 300/- (Rs. Three Hundred only) and the cost of the stamp paper shall be borne by you.

पवन नै. पारधी
15.04.2025

पवन नै. पारधी / PAWAN N. PARDHI
सहायक महाप्रबंधक (अभि-सिविल)
Asstt General Manager (E-C)
भा.वि.प्र. वडोदरा विमानक्षेत्र / AAI, VADODARA AIRPORT



3. इस पत्र के जारी होने की तारीख से 10 दिनों के भीतर सुरक्षा जमा राशि के लिए, **₹ 10,09,147.00 (रुपये दस लाख नौ हजार एक सौ सैंतालीस मात्र)** जमा करे जोकि अनुबंध मूल्य का 10% है। ऐसा न करने पर निविदा दस्तावेज़ के जीसीसी के खंड 1A पृष्ठ 16 के अनुसार यह राशि चालू खाता बिल से काट लिया जाएगा। आपके टेंडर के साथ प्राप्त ईएमडी राशि **₹. 4,07,820.00 (रुपये चार लाख सात हजार आठ सौ बीस मात्र)** ऑनलाइन वापस कर दी जाएगी जब एसडी राशि ईएमडी से अधिक होगी।
Please deposit **Rs. 10,09,147.00 (Rupees Ten Lakh Nine Thousand One Hundred Forty-Seven, Only) i.e. @10% of Contract value** towards security deposit within 10 days from the date of issue of this letter, failing which the same shall be deducted from the Running Account Bills as per the Tender document Clause 1A GCC Page 16. The earnest money amount of **Rs 4,07,820.00 (Rupees Four Lakh Seven Thousand Eight Hundred Twenty, Only)**, received along with your tender shall be refunded online once SD amount exceeds the EMD
4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) 1971 केंद्रीय नियमों के प्रावधान का पालन करे, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण कार्यकर्ता (रोजगार का विनियमन और सेवा की शर्त) अधिनियम 1996, बिल्डिंग और अन्य निर्माण कार्यकर्ता कल्याण सेस अधिनियम 1996 जैसा कि निविदा के जीसीसी के खंड 19 पृष्ठ 49 और केंद्रीय तथा राज्य सरकार के नियमों में निर्दिष्ट है।
You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and Contract labour (Regulation and Abolition) Central rules 1971 Child labour (Prohibition and Regulation) Act 1986, Construction workers (Regulation of Employment and Condition of service) Act 1996, Building and other construction workers welfare cess act 1996 as specified in clause 19 page 49 of GCC of tender & minimum wage act and rules of Central and state government.
5. आपको निर्देश दिया जाता है कि आप तुरंत **प्रबंधक(अभि-सिविल)**, वडोदरा विमानक्षेत्र से मिले वह आपको साइट सौंपने की व्यवस्था करेंगे। कृपया नोट कर ले कि काम करने का अनुमत समय **9 (नौ) महीना** जोकि बरसात के मौसम के 2 महीने सहित इस पत्र के जारी होने के दस दिन बाद से गिना जाएगा।
You are also directed to contact **Manager (Engg- Civil), AAI, Vadodara Airport** immediately who will arrange to hand over site to you. Please note that the time allowed for carrying out the work is **9 (Nine) Months i/c 2 month of Rainy season** which shall be reckoned from 10th days after the issuance of this letter.
6. इस ठेके के संबंध में आगे की कोई भी पत्राचार सहायक महाप्रबंधक (अभि-सिविल), वडोदरा विमानक्षेत्र, वडोदरा 390022 के पते पर किया जाए।
Any further correspondence in connection with the contract should normally be addressed to the Assistant General Manager (Engg- Civil) Vadodara Airport, Vadodara -390022.
7. उपरोक्त संदर्भित सभी पत्र इस ठेके का भाग होंगे।
All the letters referred above shall from part of contract.
8. उपर्युक्त कार्य के लिए त्रुटि दायित्व की अवधि **12 (बारह) महीने** होगी।
The defects liability period for the above-mentioned work is **12 (Twelve) months**.
9. यदि ठेकेदार सुरक्षा नियमों का भंग करेगा तो उनका कालि यादी में सम्मिलित किया जाएगा एवं उचित कानूनी कार्यवाही के लिए भी जिम्मेदार होगा।
If Contractor is found Violate any of Security Regulations, he shall be Black listed and will be subjected to other Legal Proceedings.

15.04.2025

पवन नै. पारधी

पवन नै. पारधी / PAWAN N. PARDHI
सहायक महाप्रबंधक (अभि-सि)
Asstt General Manager (E-C)
भा.वि.प्रा. वडोदरा विमानक्षेत्र /AAI, VADODARA AIRPORT



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

10. स्वीकृति के प्रतीक के रूप में अधिसूचना में हस्ताक्षर करने के बाद कृपया इस पावती को स्वीकार करें और इस पत्र की नकल प्रतिलिपि वापस करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

11. यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण को सही रूप में लिया जाएगा ,
In case any discrepancy is found then English version will be taken as correct.

भवदीय /Yours faithfully

पवन नै. पारधी
15.04.2025

सहायक महाप्रबंधक (अभि-सिविल),

वडोदरा हवाईअड्डा, वडोदरा

कृतेअध्यक्ष, भारतीय विमानपत्तन प्राधिकरण

Assistant General Manager (Engg.-Civil),

Vadodara Airport, Vadodara

For and on behalf of Chairman

Airports Authority of India

पवन नै. पारधी / PAWAN N. PARDHI

सहायक महाप्रबंधक (अभि-सि)

Asstt General Manager (E-C)

भा वि.प्रा. वडोदरा विमानक्षेत्र /AAI, VADODARA AIRPORT

11/11/11
11/11/11
11/11/11

11/11/11
11/11/11
11/11/11

Item Rate BoQ

Validate Print Help

Tender Inviting Authority: Assistant General Manager (Engg.-Civil)
Name of Work: C/o operational boundary wall in stretches at C.A Vadodara (Phase-I) (AFS area and tilted portion of Biwall)
Sub-Head : Construction of Operational boundary wall at AFS area & Tilted portion and 5 no. watch towers.
Contract No: 2025_AAL_227846_1

PRICE SCHEDULE						
Name of the Bidder/ Bidding Firm / Company		Shardey Infracon Private Limited				
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	
Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge. All kinds of soil.	1177.00	Cum	146.00	170665.00	INR One Lakh Seventy Thousand Six Hundred Sixty Five & Paise Zero Only
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	8.00	Cum	170.00	1360.00	INR One Thousand Three Hundred Sixty & Paise Zero Only
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 and for all lift.	801.00	Cum	90.00	72090.00	INR Seventy Two Thousand Ninety & Paise Zero Only
4	Extra for every additional lift of 1.5 m or part thereof in excavation / banking excavated or stacked materials. All kinds of soil	458.00	Cum	25.00	11450.00	INR Eleven Thousand Four Hundred Fifty & Paise Zero Only
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-II)) derived from natural sources : 6 graded stone aggregate 40 mm nominal size derived from natural sources)	46.00	Cum	5180.00	238280.00	INR Two Lakh Thirty Eight Thousand Two Hundred Eighty & Paise Zero Only
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III)) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	54.00	Cum	4997.00	269838.00	INR Two Lakh Sixty Nine Thousand Eight Hundred Thirty Eight & Paise Zero Only
7	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete	299.00	Sqm	250.00	74750.00	INR Seventy Four Thousand Seven Hundred Fifty & Paise Zero Only

पवन नै. पार्धी / PAWAN N. PARDHI
15.06.2025
सहायक महाप्रबंधक (अचि-रि)
Asstt General Manager (E-C)
भा.प्र. वडोदरा विमानक्षेत्र /AAI, VADODARA AIRPORT

Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder Rs. p	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
8	Centering and shuttering including strutting, propping etc. and removal of form for : Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	549.00	Sqm	417.00	228933.00	INR Two Lakh Twenty Eight Thousand Nine Hundred Thirty Three & Paise Zero Only
9	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Suspended floors, roofs, landings, balconies and access platform	144.00	Sqm	525.00	75600.00	INR Seventy Five Thousand Six Hundred & Paise Zero Only
10	Centering and shuttering including strutting, propping etc. and removal of form for : Lintels, beams, plinth beams, girders, bressumers and cantilevers	133.00	Sqm	417.00	55461.00	INR Fifty Five Thousand Four Hundred Sixty One & Paise Zero Only
11	Centering and shuttering including strutting, propping etc. and removal of form for : Edges of slabs and breaks in floors and walls. Under 20 cm wide	720.00	Mtr	160.00	115200.00	INR One Lakh Fifteen Thousand Two Hundred & Paise Zero Only
12	Centering and shuttering including strutting, propping etc. and removal of form for : Edges of slabs and breaks in floors and walls. Above 20 cm wide	46.00	Sqm	525.00	24150.00	INR Twenty Four Thousand One Hundred Fifty & Paise Zero Only
13	Centering and shuttering including strutting, propping etc. and removal of form for : Columns, Pillars, Piers, Abutments, Posts and Struts	346.00	Sqm	417.00	144282.00	INR One Lakh Forty Four Thousand Two Hundred Eighty Two & Paise Zero Only
14	Steel reinforcement for R.C.C. work including straightening, cutting bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	17175.00	Kg	80.38	1380526.50	INR Thirteen Lakh Eighty Thousand Five Hundred Twenty Six & Paise Fifty Only
15	Steel reinforcement for R.C.C. work including straightening, cutting bending, placing in position and binding all complete above plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more.	5600.00	Kg	82.38	461328.00	INR Four Lakh Sixty One Thousand Three Hundred Twenty Eight & Paise Zero Only
16	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced concrete work, using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength, including pumping of concrete to site of laying, curing, carriage for all leads, but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge, for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works upto plinth level Concrete of M25 grade with minimum cement content of 330 kg /cum	229.00	cum	6460.00	1479340.00	INR Fourteen Lakh Seventy Nine Thousand Three Hundred Forty & Paise Zero Only

पूरी पारखी
पवन नै. पार्थी / PAWAN N. PARDHI
15.04.2025
सहायक महाप्रबंधक (अभि-सि)
Asstt General Manager (E-C)
आ.प्र. बड़ोदा विमानक्षेत्र (AAI) VADODARA AIRPORT

Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT in Words
17	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced concrete work, using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength, including pumping of concrete to site of laying, curing, carriage for all leads, but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge, for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works above plinth level upto floor V level Concrete of M25 grade with minimum cement content of 330 kg /cum	56.00	cum	7217.00	404152.00	INR Four Lakh Four Thousand One Hundred Fifty Two & Paise Zero Only
18	Add for using extra cement in the items of design mix over and above the specified cement content therein.	100.00	Qlt	66.40	6640.00	INR Six Thousand Six Hundred Forty & Paise Zero Only
19	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	630.00	Kg	92.00	57960.00	INR Fifty Seven Thousand Nine Hundred Sixty & Paise Zero Only
20	Providing and fixing 1 mm thick M.S. sheet door with frame of 40 x 40 x 6 mm angle iron and 3 mm M.S. gusset plates at the junction and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. Using flats 30 x 6 mm for diagonal braces and central cross piece.	10.00	Sqm	2516.00	25160.00	INR Twenty Five Thousand One Hundred Sixty & Paise Zero Only
21	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	5137.00	Kg	92.00	472604.00	INR Four Lakh Seventy Two Thousand Six Hundred Four & Paise Zero Only
22	Providing and fixing hand rail by welding etc. to steel ladder railing, balcony railing & staircase railing including applying a priming coat of approved steel primer. M.S. tube (medium) 40 mm nominal bore	395.00	Kg	91.00	35945.00	INR Thirty Five Thousand Nine Hundred Forty Five & Paise Zero Only
23	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate.	144.00	Sqm	314.00	45216.00	INR Forty Five Thousand Two Hundred Sixteen & Paise Zero Only
24	Providing and applying fibre reinforced elastomeric liquid water proofing membrane with resilient acrylic polymers having Sun Reflectivity Index (SRI) of 105 on top of concrete roof in three coats @10.76 litre/ 10 sqm. One coat of self-priming of elastomeric waterproofing liquid (dilution with water in the ratio of 3:1) and two coats of undiluted elastomeric waterproofing liquid (dry film thickness of complete application/system not less than 500 microns). The operation shall be carried out after scraping and properly cleaning the surface to remove loose particles with wire brushes, complete in all respect as per the direction of Engineer-in-Charge	80.00	Sqm	376.00	30080.00	INR Thirty Thousand Eighty & Paise Zero Only

पं. पारधी
15.06.2025

पं. पारधी / PAWAN N. PARDHI
आसुतक महाप्रबन्धक (अभि-रि)
Asstt General Manager (E & C)
आ. वडोदा विमानक्षेत्र /AAI VADODARA AIRPORT

Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder Rs. p	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
25	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	917.00	Sqm	295.00	270515.00	INR Two Lakh Seventy Thousand Five Hundred Fifteen & Paise Zero Only
26	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement: 4 fine sand)	917.00	Sqm	323.00	296191.00	INR Two Lakh Ninety Six Thousand One Hundred Ninety One & Paise Zero Only
27	6 mm cement plaster of mix : 1:3 (1 cement: 3 fine sand)	698.00	Sqm	292.00	203816.00	INR Two Lakh Three Thousand Eight Hundred Sixteen & Paise Zero Only
28	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 liter/10 sqm).	2385.00	Sqm	161.00	383985.00	INR Three Lakh Eighty Three Thousand Nine Hundred Eighty Five & Paise Zero Only
29	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	184.00	Sqm	145.00	26680.00	INR Twenty Six Thousand Six Hundred Eighty & Paise Zero Only
30	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour Two coats	98.00	Sqm	161.50	15827.00	INR Fifteen Thousand Eight Hundred Twenty Seven & Paise Zero Only
31	Removing white or colour wash by scraping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	129.00	Sqm	134.00	17286.00	INR Seventeen Thousand Two Hundred Eighty Six & Paise Zero Only
32	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (One or more coat applied @ 0.90 ltr/10 sqm).	129.00	Sqm	150.00	19350.00	INR Nineteen Thousand Three Hundred Fifty & Paise Zero Only
33	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	210.00	Mtr	340.00	71400.00	INR Seventy One Thousand Four Hundred & Paise Zero Only
34	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	345.00	Sqm	705.00	243225.00	INR Two Lakh Forty Three Thousand Two Hundred Twenty Five & Paise Zero Only

पंवेपा रथी
15.04.2025
पवन नै. पारधी | PAWAN N. PARDHI
सहायक महाप्रबंधक (अभि-सि)
Asstt General Manager (E-C)
आ. वि. प्र. वाडोदा विमानक्षेत्र /AAI, VADODARA AIRPORT

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
35	Providing and erecting 2.00 metre high temporary barricading at site, each panel of size 2.50 m x 2.00 m made of 40x40x6 mm angle iron or 50x50x3 mm hollow MS tube posts/horizontal members/bracings covered with 1.63 mm thick MS sheet. The sheet shall be fixed with 30x5 mm MS flat by suitable welding/inverting. The panels shall be made so that gap of 50cm above the ground is available making overall height as 2.5 m. MS channel (SLC 75 @ 5.70 kg/m, 50 cm long shall be provided at the bottom having oval shaped holes of size 50x25 mm at both ends with 50 cm long MS angle 40x40x6 mm bracing. Suitable arrangement shall be made to fix the barricading to avoid from overturning by providing 250 mm long expansion fasteners at both ends. The work shall be executed as per drawing/direction of Engineer-in-Charge which includes writing and painting, arrangement for traffic diversion such as traffic signals during construction at site for day and night, glow lamps, reflective signs, marking, flags, caution tape as directed by the Engineer-in-Charge. The barricading provided shall be retained in position at site continuously including shifting of barricading from one location to another location as many times as required during the execution of the entire work till its completion. Rate include its maintenance for damages, painting, all incidentals, labour materials, equipments and works required to execute the job. The barricading shall not be removed without prior approval of Engineer-in-Charge. (Note :- One time payment shall be made for providing barricading from start of work till completion of work including shifting. The barricading provided shall remain to be the property of the contractor on completion of the work)	110.00	Mtr	2000.00	220000.00	INR Two Lakh Twenty Thousand & Paise Zero Only
36	Boring with hydraulic piling rigs with power units, providing and installing cast in situ single under reamed piles of specified diameter and length below pile cap in M-25 cement concrete, to carry a safe working load not less than specified, excluding the cost of steel reinforcement but including the cost of boring with bentonite solution and the length of the pile to be embedded in pile cap etc. all complete. (Length of pile for payment shall be measured upto to the bottom of pile cap) : 400 mm dia piles	221.00	Metre	1625.00	359125.00	INR Three Lakh Fifty Nine Thousand One Hundred Twenty Five & Paise Zero Only
37	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, milled and jointed mechanically wherever required including clear angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	69.00	Kg	417.00	28773.00	INR Twenty Eight Thousand Seven Hundred Seventy Three & Paise Zero Only

पब्लिक
 15.04.2025
 पवन नै. पार्थी / PAWAN N. PARDHI
 सहायक महाप्रबंधक (अभ-सि)
 Asstt General Manager (E-C)
 आ. वि. वडोदरा विमानक्षेत्र / AA, VADODARA AIRPORT

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
38	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitted and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately). For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	53.00	Kg	417.00	22101.00	INR Twenty Two Thousand One Hundred One & Paise Zero Only
39	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item) With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)	6.00	Sqm	58.25	349.50	INR Three Hundred Forty Nine & Paise Fifty Only
40	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	44.00	Cum	1200.00	52800.00	INR Fifty Two Thousand Eight Hundred & Paise Zero Only
41	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	34.00	Cum	2243.00	76262.00	INR Seventy Six Thousand Two Hundred Sixty Two & Paise Zero Only

पुनर्पाश्चि
15.04.2025

पवन नै. पारधी / PAWAN N. PARDHI
सहायक महाप्रबंधक (अभि-सि)
Asstt General Manager (E-C)
भा. वि. प्र. वडोदरा विमानक्षेत्र IAAI, VADODARA AIRPORT

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
42	Deduct for not using pumping for concrete in item no. 16 & 17 of design mix concrete as per direction of Engineer in Charge.	285.00	Cum	100.00	-28500.00	INR Minus Twenty Eight Thousand Five Hundred & Paise Zero Only
43	Rubble soling below plinth level using dry stone of nominal size 22.5 cm, laid in layers of maximum 22.5 cm in level including filling of voids using stone aggregate of size 53 mm to 22.4mm size, including supply of material and preparing surface complete.	101.00	Cum	4129.00	417029.00	INR Four Lakh Seventeen Thousand Twenty Nine & Paise Zero Only
44	Brick work with clay flyash F.P.S. (non modular) brick of class designation 5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	67.00	Cum	5250.00	351750.00	INR Three Lakh Fifty One Thousand Seven Hundred Fifty & Paise Zero Only
45	Brick work with clay flyash F.P.S. (non modular) brick of class designation 5 in superstructure above plinth level up to floor one level in: Cement mortar 1:6 (1 cement : 6 coarse sand)	85.00	Cum	5900.00	333500.00	INR Three Lakh Eighty Three Thousand Five Hundred & Paise Zero Only
46	Pointing/ Embossing AAI Logo Size 650 mm x 450mm with cement mortar 1:3 (1cement: 3fine sand) Projecting out by 12mm raised on cement plastered wall as per drawing and directions of Engineer-in-Charge.	10.00	Nos	900.00	9000.00	INR Nine Thousand & Paise Zero Only
47	Supplying and fixing of single FRP structure (Min Thickness 5mm) bio-toilet of inside dimension of 3ftx(Length) x 3ft (Width) x 6.5 ft (Height) with the inclusion of following: [A]-FRP Bio toilet with accessories [1] Western type toilet pan with hand flush system [2] Interconnecting plumbing PVC Piping & Sanitary Fitting with PVC ball Valve [3] PTMT Tap [B]-FRP Bio Digester tank : Size 1000mm (length) x 1000mm (width) x 500mm (Height), wall Thickness 5mm & Weight =27Kg Microbial solution: 200 Ltr Other Specifications: 1. Partition respectively inside the tank having 3mm thickness 2.PVC Matrix at each partition for bacteria culture 3.PVC Pipes and fitting at inlet and outlet 4. Tank with airtight Top cover FRP Specification: % of glass content-33.33%, % of resin content - 66.67%, Water absorption-0.30%, Tensile strength 115Mpa. Specific gravity -1.6, Izod impact strength-65KJ/sqm 160-180 liter PVC water storage tank Note: The quoted rate shall include all materials, labor, tools, and transportation required for installation. The item must be executed as per the approved specifications and site requirements.	14.00	Nos	55000.00	770000.00	INR Seven Lakh Seventy Thousand & Paise Zero Only
Total in Figures				10091475.00		
Quoted Rate in Words				INR One Crore Ninety One Thousand Four Hundred Seventy Five & Paise Zero Only		

युवा पार्श्व
15.04.2025

पवन नै. पार्श्वी / PAWAN N. PARDHI
सहायक महाप्रबंधक (अभि-सि)
Asstt General Manager (E-C)
सा. नि. प्र. बड़ोदा विमानक्षेत्र /AAI, VADODARA AIRPORT