



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

सं.:/Ref. No. AAI/HYD/ENGG (E)/CW-1/2025-26/3200

दिनांक /Date: 07.05.2025

स्पीड पोस्ट / ई-मेल BY SPEED POST/E-MAIL

सेवा में/To,

सर्वश्री स्टैंडर्ड एयर कंडिशनिंग & रेफ्रीजरिऑन इंजीनीर्स
M/s. Standard Air Conditioning & Refrigeration Engineers,
ग्राउंड, 1/9/670/65, आदिकमेट एसआरटी कॉलोनी
Ground, 1/9/670/65, Adikmet Srt Colony,
विद्यानगर, हैदराबाद - 500044
Vidyanagar, Hyderabad - 500044
ई-मेल / E-mail Id: standardacre@gmail.com

कार्य का नाम : बेगमपेट हवाई अड्डे, हैदराबाद में क्वार्टरों का विस्तार और नवीनीकरण। एसएच: एयर कंडीशनर और अन्य संबद्ध कार्यों की एसआईटीसी।

Name of Work : Extension and Renovation of Quarters at Begumpet Airport, Hyderabad.
SH: SITC of Air conditioners and other allied works.

संदर्भ / Ref. 1. बोली आमंत्रण सं. 2025_भाविप्रा_228076_1 दिनांक. 07.03.2025

Bid Invitation No. 2025_AAI_228076_1 Dt: 07.03.2025

2. आपकी ई-निविदा (आवरण-II वित्तीय बोली) खुलने की तिथि 08.04.2025

Your E-tender (Envelope-II -Financial bid) opened on 08.04.2025

महोदय / Dear Sir(s),

- यथोक्त कार्य के लिए आपकी निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आपके द्वारा उद्धृत मद दरों पर कुल रु. 18,35,072/- (अठारह लाख पैंतीस हजार बहत्तर रुपये मात्र) जीएसटी को छोड़कर जो रुपये की उचित लागत 18,61,626.00 से 1.43% कम है जीएसटी को छोड़कर।
Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rates quoted by you totaling to Rs. 18,35,072/- (Rupees Eighteen Lakhs Thirty Five Thousand and Seventy Two Only) excluding GST which is 1.43% below the Justified cost of Rs. 18,61,626.00 excluding GST.
- संयुक्त महाप्रबंधक (अभियांत्रिकी-विद्युत), भाविप्रा, हैदराबाद हवाई अड्डा, बेगमपेट, कार्य के लिए प्रभारी अभियंता होंगे। आप से अनुरोध है कि आप अनुबंध पर हस्ताक्षर करने और अनुबंध को पूरा करने के लिए दिनांक 16.05.2025 तक संयुक्त महाप्रबंधक(अभियांत्रिकी-विद्युत), भाविप्रा, हैदराबाद अंतरराष्ट्रीय हवाई अड्डा, बेगमपेट, कार्यालय में उपस्थित होने का कष्ट करें। अनुबंध करार 100/- रुपये (केवल एक सौ रुपये) के गैर-न्यायिक स्टाम्प पेपर पर निष्पादित किया जाएगा तथा स्टाम्प पेपर की लागत आपके द्वारा वहन की जाएगी।
The Jt. General Manager (Engg-E), AAI, Hyderabad International Airport, Begumpet, shall be the Engineer-in-Charge for the work. You are requested to attend the office of the Jt. General Manager (Engg-E), AAI, Begumpet Airport, Hyderabad - 500 016 by 16.05.2025 to sign and complete contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees One hundred only) and the cost of the stamp papers shall be borne by you.

3. अनुबंध खंड के संख्या 1 ए के खंड जीसीसी के अनुसार, कृपया 1,83,507.00 (रुपये केवल एक लाख तिरासी हजार पांच सौ सात) इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर सुरक्षा जमा के रूप में जमा करें। ऐसा न करने पर अनुबंध दस्तावेजों की शर्त के अनुसार आपके चालू बिल से काट लिया जाएगा। As per the clause of the contract Clause No.1A of GCC, Please Deposit Rs. 1,83,507.00 (Rupees One Lakh Eighty Three Thousand Five Hundred and Seven Only) towards Security Deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from your running bill as per condition of contract documents.
4. आपसे अनुरोध है कि संविदा श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और संविदा श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971 और न्यूनतम मजदूरी अधिनियम तथा केंद्र और राज्य सरकारों के नियमों के प्रावधानों का पालन करें। You are requested to comply with the provisions of Contract Labour (Regulation and Abolition) Act of 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 and minimum wages act and rules there of Central and State Governments.
5. आपको प्रबंधक (अभियांत्रिकी-विद्युत), भाविप्रा, हैदराबाद अंतरराष्ट्रीय हवाई अड्डा, बेगमपेट, से तुरंत संपर्क करने के लिए भी निर्देशित किया जाता है। जो आपको साइट सौंपने की व्यवस्था करेंगे। You are also directed to contact Manager (Engg-Elect), AAI, Hyderabad International Airport, Begumpet immediately who will arrange to hand over the site to you.
6. कृपया ध्यान दें कि कार्य करने के लिए अनुमत निर्धारित समय-सीमा **03 (तीन)** माह है और इसे कार्य आदेश जारी होने के 07 वें दिन से गिना जाएगा। Please note that the time allowed for carrying out the work shall be **03 (Three)** months and same shall be reckoned from 10th day after issue of work order.
7. अनुबंध के संबंध में पत्राचार सामान्य रूप से प्रभारी अभियंता को संबोधित किया जाना चाहिए। Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.
8. कृपया पावती दें और साथ में संलग्न इस पत्र की डुप्लीकेट प्रति हस्ताक्षर करने के बाद अधोहस्ताक्षरी को स्वीकृति के प्रतीक के रूप में लौटा दें। Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

सूचना: हिंदी अनुवाद में विसंगति होने के संदर्भ में अंग्रेजी पाठ को अधिकृत माना जाएगा।

Note: In case of discrepancy in Hindi translation the English version shall prevail.

अनुलग्नक/Encl: परिमाण-सूची Schedule of Quantities

भवदीय/Yours Faithfully,


सहायक महाप्रबंधक (अभि-वि) Asst. General Manager (Engg-E),
कृते अध्यक्ष / For & On Behalf of The Chairman,
भारतीय विमानपत्तन प्राधिकरण Airports Authority of India,
भाविप्रा, हैदराबाद अंतरराष्ट्रीय हवाई अड्डा AAI, Hyderabad International Airport
बेगमपेट / Begumpet - 500 016

Validate Print Help

Item Rate BoQ

Tender Inviting Authority: The Asst.General Manager(Engg-E), AAI, Begumpet Airport.

Name of Work : Extension and Renovation of Quarters at Begumpet Airport, Hyderabad. SH: SITC of Air conditioners and other allied works.

Contract No: 2025_AAI_228076_1

Name of the Bidder/ Bidding Firm / Company :		STANDARD AIR CONDITIONING & REFRIGERATION ENGINEERS				
<p style="text-align: center;">PRICE SCHEDULE</p> <p>NOTE: In the event of no rate has been quoted for any item(s) leaving space (or) amount blank, it will be presumed that the contractor has included the cost of this / these item(s) in other items and rate for such item(s) will be considered as zero.</p>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE Ex GST In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Ex GST in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Supply of air cooled factory assembled 5-star rated minimum 1.0 TR Split type Inverter AC having remote operation, minimum 5.00 ISEER rated, eco friendly refrigerant, copper condensor coil, Inverter Rotary compressor along with the supply of manufacturer standard length of copper refrigerant liquid, suction pipe and Copper conductor multi core cable etc. with all necessary standard protections, features as per OEM suitable for operation on high ambient temperatures of upto minimum 52°C, stabiliser free operation, operation on 230V+/-10%V, 50 Hz, 1-Phase AC Supply etc. complete as required.	36	Each	32400.00	1166400.00	INR Eleven Lakh Sixty Six Thousand Four Hundred Only
2	Installation, Testing and Commissioning of above minimum 1.0 TR AC system including supply and fixing of heavy gauge wall bracket/MS angle i/c minor civil work for ODU(if any) as per site requirement along with laying of standard length of copper refrigerant liquid, suction pipe and Copper conductor multi core cable as per manufacturer recommendation by drilling necessary hole/core cut on the concrete/brick wall (if required) i/c making good the damages if any etc. complete as required .	36	Each	1300.00	46800.00	INR Forty Six Thousand Eight Hundred Only
3	Supply and Laying of additional length of suitable size refrigerant Copper piping along with insulation and suitable size FR PVC insulated multicore Cu conductor cable as per manufacturer recommendation as required for connection between indoor and outdoor units of above AC's etc. complete as required.	50	Mtr	490.00	24500.00	INR Twenty Four Thousand Five Hundred Only

M. S. S. S.
Permit

4	Supply and Laying of additional length of suitable size hard PVC pipe for draining out the water etc. complete as required.	50	Mtr	90.00	4500.00	INR Four Thousand Five Hundred Only
5	Supplying and fixing 20 A, 415 V, SP MCB protected socket in sheet steel enclosure, on surface or in recess etc. complete with connections, testing and commissioning etc. as required.	12	Each	544.00	6528.00	INR Six Thousand Five Hundred & Twenty Eight Only
6	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed medium class PVC conduit alongwith 1 No 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	100	Meter	265.00	26500.00	INR Twenty Six Thousand Five Hundred Only
7	SITC of 5-Star rated minimum 10 Litre storage capacity wall mountable Water Heater system having auto cut off facility complete with all accessories and features as per manufacturer standard suitable for operation on 230V+/-10%V, 50 Hz, 1-Phase AC supply etc. complete as required.	18	Job	7200.00	129600.00	INR One Lakh Twenty Nine Thousand Six Hundred Only
8	SITC of Water Cooler with inbuilt RO based 7 stage water purification system with 80 Ltrs storage capacity and 50 LPH purification capacity having two faucets , gas as refrigerant and compressor complete with all accessories and standard manufacturer design suitable for operation on 230V+/-10%V, 50 Hz, 1-Phase AC supply etc. complete as required.	4	Job	96311.00	385244.00	INR Three Lakh Eighty Five Thousand Two Hundred & Forty Four Only
9	SITC of minimum 5W minimum 90 lumen/w table study lamp having surge protection of upto 2 KV, Over voltage protection, short circuit protection, capable for burning of upto 25000 hours etc. complete with standard length of wire suitable for operation on 230V+/-10%V, 50 Hz, 1-Phase AC supply etc. complete as required.	60	Each	750.00	45000.00	INR Forty Five Thousand Only
Total in Figures					1835072.00	INR Eighteen Lakh Thirty Five Thousand & Seventy Two Only
Quoted Rate in Words		INR Eighteen Lakh Thirty Five Thousand & Seventy Two Only				

Handwritten signature: 7/5/25
Asst. Gen. Manager (Engg - Elect)

Signature Not Verified

Digitally signed by BUSIREDDY SUDHAKAR REDDY
Date: 2025.06.28 11:28:04 IST
Location: eProcurement System for Central PSUs

