



Work-order

संख्या: भा.वि.प्रा./एनएसी/बैडमिंटन/24-25/WO-05

दिनांक: 13.05.2025

No. AAI/NAC/Badminton/24-25/WO-05

Date : 13.05.2025

सेवा मे,

M/s. Converge Construction

Plot No.1, New Gautam Nagar,
Mumbai - 400 043.

Email: convergeconstruction.kk@gmail.com

GSTN: 27CVPPK7045H2Z3

कार्य का नाम: न्यू एयरपोर्ट कॉलोनी, मुंबई में अस्थायी बैडमिंटन कोर्ट का प्रावधान।

Name of Work: Provision of Temporary Badminton court at New Airport Colony, Mumbai.

Tender Id : 2025_AAI_228205_1

बीड क्र./ Bid No: 829232

संदर्भ:- आपका दिनांक 02.04.2025 को खोला गया वित्तीय ई-निविदा।

Ref.: Your e-tender Finance bid Opened on dated 02.04.2025

महोदय/ Dear Sir (S),

- ऊपर उल्लेखित कार्य हेतु आपकी ई-निविदा, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है। आपके द्वारा बताए गए मद मूल्यों पर आपकी टेंडर राशि कुल रु. 50,92,396.44 (रुपये पचास लाख बरानवे हजार तीन सौ छियानवे रुपये एवं चौवालीस पैसा मात्र) (जीएसटी रहित) हैं, जो की टेंडर की अनुमानित लागत राशि रु. Rs. 92,29,000.00 (रुपये बानबे लाख उनतीस हजार मात्र) (जीएसटी रहित) से 44.82 प्रतिशत नीचे हैं। आपकी उद्धृत गणना से लाई रकम पर 18% फीसदी जी.एस.टी. (यानि 9 फीसदी CGST और 9 फीसदी SGST) राशि का वैध टैक्स चालान का जमा करने पर भुगतान किया जाएगा।
- Your e-tender for the work mentioned above is hereby accepted on the behalf of the Chairman, Airports Authority of India at your quoted rate amounting to Rs. 50,92,396.44 (Rupees fifty lakh ninety two thousand three hundred ninety six Rupees and forty four paisa only) (excluding GST). Your bid quote is 44.82% below the estimate cost put to tender of Rs. 92,29,000.00 (Rupees Ninety Two Lakh Twenty Nine Thousand only) (excluding GST) The GST at 18 per cent (i.e. 9 per cent CGST plus 9 per cent SGST) will be paid over and above the amount calculated on your quoted rate on submission to valid tax invoice.

अभि
13.05.25
AUM/12



Work-order

2. सहायक महा प्रबन्धक (अभि-सिविल), मुंबई कार्य के अभियंता-प्रभारी होंगे। आपसे निवेदन है कि आप आपकी और से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 23.05.2025 तक सहायक महा प्रबन्धक (अभि-सिविल), ए.ए.आई., सिविल मटेनेंस ऑफिस, एनएसी, मुंबई के कार्यालय में उपस्थित हो और करारनामे को पूरा करें। ठेके का करारनामा 100/- रुपये के गैर-न्यायिक स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा स्टैम्प पेपर की लागत आपके द्वारा ली जाएगी।

Asstt. Gen. Manager (Engg-Civil), Mumbai shall be Engineer-In-Charge of the work. You are requested to depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the O/o. Asstt. Gen. Manager (Engg-Civil), AAI, Civil Maintenance office, NAC, Mumbai by 23.05.2025 to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- and the cost of the stamp paper shall be borne by you.

2. कृपया इस पत्र जारी होने की तारीख से 15 दिनों के भीतर सुरक्षा जमा रु 2,32,370 (कुल दो लाख बत्तीस हजार तीन सौ सत्तर उनहत्तर रुपये मात्र) जमा करें, असफल होने पर ठेके के दस्तावेज के पृष्ठ सं. 16 पर दी गयी शर्त 1 (ए) के अनुसार आपके चालू बिल से कटौती की जाएगी।
3. Please deposit Rs. 2,32,370/- (Rupees Two Lakh Thirty Two Thousand Three Hundred Seventy Only) towards security deposit within 15 days from the date of issue of this letter, failing which the same will be deducted from your running bill as per condition 1 (A) on page 16 of the contract document.
4. आपसे निवेदन है कि आप केन्द्रीय एवं राज्य सरकारों के 1970 के अधिनियम अनुबंध श्रम नियम तथा 1971 के केन्द्रीय नियम (नियमन तथा उन्मूलन) एवं केंद्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और अन्य नियमों का अनुपालन किया जाए।
4. You are requested to comply with the provisions of contract labour (Regulation and abolition) Act of 1970 and contract labour (Regulation and abolition) Central rules 1971 and minimum wages Act & rules thereof Central and State Governments.

अभि
13.05.25
AUM(F-1)

Work-order

5. आपको निर्देश दिया जाता है कि आप तुरंत प्रबन्धक (अभि-सिविल), सिविल रखरखाव कार्यालय, न्यू एयरपोर्ट कॉलोनी से तुरंत संपर्क करें, वह आपको साइट सौंपने की व्यवस्था करेंगे और कार्य के निष्पादन और निगरानी के लिए अपेक्षित दिशा-निर्देश जारी करने के लिए अधिकृत हैं। कृपया ध्यान दें कि काम करने के लिए अनुमति देने का समय 06 (छह) महीने हैं जिनमें 02 (दो) महीने बारिश के लिए है जिसे इस पत्र जारी करने के बाद दसवे दिन या वास्तविक कार्य चालू करने पर, इनमें से जो भी पहले हो वह गिना जाएगा।
5. You are also directed to contact Manager (Engg-Civil), Civil Maintenance office, New Airport Colony immediately who will arrange to hand over the site to you and is authorised for issuing requisite directions for executing and monitoring the work. Please note that the time allowed for carrying out the work is **06 (Six) Months including 02 (Two) months considered for rains** which shall be reckoned from the 10th day after the date of issue of this letter or the day of actual start of work whichever is earlier.
6. अनुबंध दस्तावेज के पृष्ठ संख्या 47 और 48 पर खंड संख्या 17 में उल्लिखित दोष देयता अवधि बारह महीने है।
6. The defects liability period mentioned in clause No. 17 on page no.47 & 48 of the contract document is Twelve Months.
7. इस ठेके के सम्बंध में आगे कोई भी पत्राचार सहायक महा प्रबन्धक (अभि-सिविल), भारतीय विमानपत्तन प्राधिकरण, सिविल मेंटेनेंस कार्यालय, न्यू एयरपोर्ट कॉलोनी, विले पार्ले (पूर्व), मुम्बई-400 099 के पत्ते पर संदर्भ भा.वि.प्रा./एनएसी/बैडमिंटन/24-25/WO-05 से किया जाए।
7. Any further correspondence in connection with the contract should be addressed to the Asstt. Gen. Manager (Engg-Civil), WR, Airports Authority of India, Civil maintenance office, New Airport Colony, Vile-Parle (East), Mumbai-400 099 and the reference number for this work is AAI/NAC/Badminton/24-25/WO-05
8. कृपया इस पत्र की प्रतिलिपि स्वीकृति के एक टोकन के रूप में हस्ताक्षर कर अधोहस्ताक्षरी को वापिस करें।

अभि
13.05.24
AUM (EC)



Work-order

8. Please acknowledge the receipt and return the copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

धन्यवाद/ Thanking you,

संलग्न : शेड्यूल -अ / Schedule A -05 पृष्ठ
फॉर्म - V / Form - V

भवदीय / Yours faithfully,

13.05.2025

सहायक महा प्रबन्धक (अभि-सिविल)
Asstt. Gen. Manager (Engg-Civil)
कृते तथा ओर से, अध्यक्ष
For and on behalf of chairman,
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India



Work-order


फॉर्म - V / Form V

नियम 21(2) देखें / See Rule 21(2)

मुख्य नियोक्ता द्वारा प्रमाण पत्र / Form of Certificate by Principal Employer

प्रमाणित किया जाता है कि एएआई ने आवेदक मेसर्स कनवर्ज कन्स्ट्रक्शन को न्यू एयरपोर्ट कॉलोनी, मुंबई में अस्थायी बैडमिंटन कोर्ट का प्रावधान के लिए ठेकेदार के रूप में लगाया है। एएआई आवेदक को अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम विनियमन और उन्मूलन (केंद्रीय नियम 1971, बाल श्रम निषेध और विनियमन) (अधिनियम 1986 , निर्माण कार्यकर्ताओं) रोजगार और सेवा- की शर्तों का विनियमन (अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996), जहां तक इस प्रतिष्ठान में अनुबंध श्रम के रोजगार के संबंध में प्रावधान लागू होते हैं। आवेदक द्वारा के एएआई के सभी प्रावधानों से बंधेगा।

Certified that AAI have engaged the applicant M/s. Converge Constructions, Mumbai, as a contractor for the work of "Provision of Temporary Badminton court at New Airport Colony, Mumbai. AAI undertakes to be bound by all the provision of Contract labour (Regulation and Abolition) Act 1970 and contract labour (Regulation and Abolition) Central rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996, in so far as the provisions are applicable to them in respect of the employment of contract labour by the applicant in this establishment.


सहायक महा प्रबन्धक (अभि-सिविल)
Asstt. Gen. Manager (Engg-Civil)
भाविप्रा, एन ए सी मुंबई
AAI, NAC, Mumbai.

सेवामें / To,

M/S. CONVERGE CONSTRUCTION
PLOT NO.-01, NEW GAUTAM NAGAR,
GOVANDI, MUMBAI, Mumbai Suburban,
Maharashtra, 400043.

Email: convergeconstruction.kk@gmail.com

13.05.2025
 AM/17
 (Signature)

7	Steel work in built up tubular round square or rectangular hollow tubes etc., including cutting, hoisting, fitting in position and applying a priming coat of approved steel primer, including welding and bolting with special shaped washers etc. complete a) Electric resistance or induction butt welded tubes	17511.94 kg	INR	91.00	1593586.54 Only	INR Fifteen Lakh Ninety Three Thousand Five Hundred Eighty Six & Paise Fifty Four Only
8	Providing and fixing precast galvanised iron profile sheets (size, shape and pitch of consumption as approved by Engineer-in-Charge) of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness, with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-Charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/vertical or curved surfaces, excluding the cost of purllins, rafters and trusses and including cutting to size and shape wherever required.	1074.50 sqm	INR	357.00	394341.50	INR Three Lakh Ninety Four Thousand Three Hundred Forty One & Paise Fifty Only
9	Brick work with common burnt clay F.P.S. (non modular) bricks of class, designation 3.5 in foundation and plinth in: Cement mortar 1:4 (1 cement, 4 coarse sand)	29.44 cum	INR	4999.00	147770.56	INR One Lakh Forty Seven Thousand One Hundred Seventy & Paise Fifty Six Only
10	15 mm cement plaster on rough side of single or half brick wall of mix: 1:4 (1 cement, 4 coarse sand)	357.35 sqm	INR	249.00	88980.15	INR Eighty Eight Thousand Nine Hundred Eighty & Paise Fifteen Only
11	Providing and fixing 3 layer PP-R (Poly propylene Random copolymer) pipes conforming to IS:15801 UV stabilized & anti - microbial fusion welded, having thermal stability for hot & cold water supply, including all PP - R plain & brass threaded polypropylene random fittings, including trenching, refilling & testing of joints complete as per direction of Engineer-in-Charge. External work. PN-10 Pipe, 63 mm OD (SDR-11)	10.00 meter	INR	599.00	5990.00	INR Five Thousand Nine Hundred Ninety & Paise Zero Only
12	Providing and fixing 3 layer PP-R (Poly propylene Random copolymer) pipes conforming to IS: 15801 UV stabilized & anti - microbial fusion welded, having thermal stability for hot & cold water supply, including all PP - R plain & brass threaded polypropylene random fittings, including trenching, refilling & testing of joints complete as per direction of Engineer-in-Charge. External work. PN-10 Pipe, 110 mm OD (SDR-11)	40.00 meter	INR	550.00	22000.00	INR Twenty Two Thousand & Paise Zero Only
13	Constructing masonry Chamber 120x120x100 cm inside, in brick work in cement mortar 1:4 (1 cement, 4 coarse sand) for sluice valve, with C.I. surface box 100 mm top diameter and RCC top slab 1:1.5:3 mix (1 180 mm deep (inside) with chained lgd and stone aggregate 20 mm nominal cement, 1.5 coarse sand, 3 gravels, foundation concrete 1:5:10 (1 size), including necessary excavation stone aggregate 40 mm nominal size) cement, 5 fine sand : 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement: 3 coarse sand) 12 mm thick, finished with a floating coat of neat cement sand) complete as per standard design: 18.35.1 With common burnt clay F.P.S. (non modular) bricks of class designation 3.5	2.00 each	INR	9000.00	18000.00	INR Eighteen Thousand & Paise Zero Only
14	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. a) On steel work	515.50 Sqm	INR	110.00	56711.50	INR Fifty Six Thousand Seven Hundred Eleven & Paise Sixty Only
15	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 metres.	393.75 Sqm	INR	110.00	43312.50	INR Forty Three Thousand Three Hundred Twelve & Paise Fifty Only

13.05.2025
THW/EL
21/05

16	Providing and Fixing wooden sub-base floor complete i/c loading, unloading, transportation, assembly, fixings, etc. as per instruction of Engineering in Change having the following layers and specifications: 1) Layer - 1 Providing and Laying of 150 GSW plastic sheet over prepared concrete surface to prevent moisture to enter system. 2) Layer - 2 Providing and fixing EPDM Rubber Butlon with min rubber layer thickness 3mm and having plan dimension not less than 70mmx50mm and having uniform slots of height not less than 12mm with Dia 10mm and 4 mm deep spaced at 100mm apart in a staggered pattern. 3) Layer - 3 Providing and fixing treated pine wood runners (Wood to be treated anti-termite treatment and moisture resistance of dimension not less than 70mm x 45mm in required length joint with adhesive and metal clips / nails. Runners to be placed at a C/C distance of not less than 23 cm. (Note: Testing of wood will be carried out to ascertain type of wood, moisture content and other parameters). 4) Layer - 4 Providing and fixing teak wood of grade A in flooring having min thickness of 20mm, min width of 50mm, fixed over runners using SS screws having min length of 25mm. The space between the runners to be filled with teak wood of min 25mm x 25mm x 10mm. The final surface to be finished with machine sanding and polished with water based PU polish. The markings over the polished surface, if required, to be marked with Epoxy paint as required. (Note: Testing of wood will be carried out to ascertain type of wood, moisture content and other parameters). The supplier / manufacturer / assembler will give a warranty of min. 5 years on the guarantee bond for the above system against damages due to termite, moisture absorption, defects in wood used, defects due to workmanship, sinking of the system and failure of the system.	393.75	Sqm	INR	2600.00	1023750.00	INR Ten Lakh Twenty Three Thousand Seven Hundred Fifty & Paise Zero Only
17	Providing and Fixing 4.5 mm thick PVC vinyl flooring for badminton court over sub-base of wooden floor in required colors i/c installation by setting core, fixing the flooring with appropriate adhesive, painting court for markings, transportation, loading and unloading complete as per instruction of Engineering in Change.	393.75	Sqm	INR	1000.00	393750.00	INR Three Lakh Ninety Three Thousand Seven Hundred Fifty & Paise Zero Only
18	Providing and fixing Roof mounted ventilators having specifications as 1) throat / neck diameter 800mm, 2) natural wind driven ventilator; 3) manufactured from of Glass Filled Nylon integrated with Aluminium assembly made up of Glass Filled Nylon integrated with Aluminium tube; 4) 2 Nos. Ball bearing not exposed to exhaust air flow; 5) MS Plated shaft and having 42 Nos. of vanes; 6) mill finished; 7) manufactured in three-part construction; 8) The rotating head with Aluminium variable angle throat to be mounted on an Aluminium ring and to be able to counter the roof slope range 0-180 to enable vertical to-ground installation of the head; 9) ventilator assembly has to be mounted on a customized FRP base making the ventilator assembly weather-tight complete installation, assembly base, application of weather proof sealant, accessories, etc. as per instruction of Engineering in Change.	6.00	each	INR	3100.00	18600.00	INR Eighteen Thousand Six Hundred & Paise Zero Only
19	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed PVC conduit, with modular switch, modular plate, suitable PVC box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required.	18.00	Point	INR	1000.00	18000.00	INR Eighteen Thousand & Paise Zero Only
20	Wiring for group controlled (looped) light point/fan point/exhaust fan point/ call bell point (without independent switch etc.) with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ FRLS PVC insulated steel conduit, and earthing the point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc. as required.	15.00	Point	INR	700.00	10500.00	INR Ten Thousand Five Hundred & Paise Zero Only
21	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required.	250.00	Meter	INR	180.00	45000.00	INR Forty Five Thousand & Paise Zero Only
22	(a) 12 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire) Supplying and fixing suitable size PVC box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required.	8.00	Each	INR	700.00	5600.00	INR Five Thousand Six Hundred & Paise Zero Only

13.05.2025
 13.05.2025
 13.05.2025

23	Supplying and fixing suitable size PVC box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5A modular socket outlet and 5A modular switch, connections etc as required	5.00 Each	INR	600.00	3000.00	INR Three Thousand & Paise Zero Only
24	Supplying and fixing brass battery/angle holder (ring type) including connection etc as required	5.00 Each	INR	240.00	1200.00	INR One Thousand Two Hundred & Paise Zero Only
25	Wiring for light/ power plug with 2x4 sq. mm FRLS PVC insulated copper conductor single core cable in surface recessed PVC conduit along with 1 No 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required	140.00 Metre	INR	200.00	28000.00	INR Twenty Eight Thousand & Paise Zero Only
26	Supply of Flood light LED fitting with minimum output of 18500 lumens and minimum 110 Lumens/Watt for 230V Single Phase AC supply, 50Hz, PF>0.85, CRI>70, CCT - 5700K. Life of fitting not less than 50000 hrs complete as required. Luminaire should have high pressure die cast Aluminium/standard alloy housing with surge protection system > 4KV. Luminaire should have proper thermal management. Min IP protection should be IP65. It shall meet as per technical specification enclosed with tender complete in all respect as required as per direction and satisfaction of Engineer-in-charge	14.00 Each	INR	2500.00	35000.00	INR Thirty Five Thousand & Paise Zero Only
27	Fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with turned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/isolator) (12 way SPN DB, Double door to be provided by AAI)	2.00 Each	INR	400.00	800.00	INR Eight Hundred & Paise Zero Only
28	Fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc as required (Single pole MCB 6-32 Amp) (Single pole MCBs 6-32 Amp to be provided by AAI)	12.00 Each	INR	77.00	924.00	INR Nine Hundred Twenty Four & Paise Zero Only
29	Fixing following rating, 4 Pole, 415 V, Isolator in the existing MCB DB complete with connections, testing and commissioning etc as required. 63 A (4 Pole, 415 V, Isolator 63 Amp to be provided by AAI)	2.00 Each	INR	151.00	302.00	INR Three Hundred Two & Paise Zero Only
30	Supply of following size DWG HDPE pipe (SI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14330, Part II) etc complete as required. 63 mm dia (OD-63 mm & ID-51 mm nominal)	300.00 Metre	INR	40.00	12000.00	INR Twelve Thousand & Paise Zero Only
31	Laying of following size DWG HDPE pipe (SI marked along with all accessories like socket, bend, couplers etc. complete with fitting and leveling) etc directed in ground (75 cm below grading and leveling) cutting, joint excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. 63 mm dia (OD-63 mm & ID-51 mm nominal)	300.00 Metre	INR	60.00	18000.00	INR Eighteen Thousand & Paise Zero Only
32	Supplying and making and termination with brass compression gland and aluminum lugs for following size of PVC insulated and PVC sheathed / XLPE aluminum conductor cable of 1.1 KV grade as required	4.00 Set	INR	400.00	1600.00	INR One Thousand Six Hundred & Paise Zero Only
33	3.5 x 50 Sqmm (35 mm) Supply of XLPE/PVC insulated, PVC sheathed aluminum conductor armoured power cable of 11KV grade conforming to IS 7098 (Part I) 1988 with upto date amendments etc as required for the following sizes (Make As per approved list) 3.5 C x 50 Sqmm	110.00 Metre	INR	250.00	27500.00	INR Twenty Seven Thousand Five Hundred & Paise Zero Only
34	Laying of one number PVC insulated and PVC sheathed/XLPE power cable of 1.1 KV grade of following size in the existing RCC/HU/ME/Mini-HDPE/PVC pipe as required	150.00 Metre	INR	35.00	5250.00	INR Five Thousand Two Hundred Fifty & Paise Zero Only
35	Laying of one number PVC insulated and PVC sheathed/XLPE power cable of 1.1 KV grade of following size in the existing RCC/HU/ME/Mini-HDPE/PVC pipe as required	150.00 Metre	INR	55.00	8250.00	INR Eight Thousand Two Hundred Fifty & Paise Zero Only
36	Laying of one number PVC insulated and PVC sheathed/XLPE power cable of 1.1 KV grade of following size in the existing RCC/HU/ME/Mini-HDPE/PVC pipe as required a) Above 35 sq. mm and upto 95 sq. mm b) Above 95 sq. mm and upto 140 sq. mm Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with charcoal/coke and locking arrangement and watering pipe etc. With charcoal/coke and earthing as required	1.00 Set	INR	6000.00	6000.00	INR Six Thousand & Paise Zero Only

13.05.2025
AMV/ELM

37	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ recessed conduit/ submain wiring cable as required	300.00	Meter	INR	30.00	9000.00	INR Nine Thousand & Paise Zero Only
38	Installation, testing and commissioning of pre-wired Flood Light LED fitting with all accessories including nut, bolt, washer and hanging/fixing arrangements if required directly on existing in false ceiling / wall / surface including connection etc complete as per site requirement.	12.00	Each	INR	200.00	2400.00	INR Two Thousand Four Hundred & Paise Zero Only
39	Supply of 230 v. 50 Hz industrial heavy duty exhaust fan having 230 mm sweep and speed not less than 1400 rev/minute including installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required.	4.00	Each	INR	1600.00	7200.00	INR Seven Thousand Two Hundred & Paise Zero Only
40	Supplying and installation of plastic body exhaust fan (1/c louvers/shutters) of 150 mm sweep, 1300 rpm, operating on 230 V AC, 50 Hz power supply, in the existing opening using suitable size SS double nut & bolt with spring washer & plain washer, including making good the damage, connection, testing, commissioning etc. as required.	2.00	Each	INR	1500.00	3000.00	INR Three Thousand & Paise Zero Only
Total in Figures		INR Fifty Lakh Ninety Two Thousand Three Hundred Ninety Six & Paise Forty Four Only					
Quoted Rate in Words		INR Fifty Lakh Ninety Two Thousand Three Hundred Ninety Six & Paise Forty Four Only					

Signature Not Verified
Digitally signed by AMIT KARTIKESHWAR AVACHAR
Date: 2025.11.18 11:42:46 IST