



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

भाविप्रा/भोपाल/अभि.-सि./Misc. works/2024-25/177(1-9)

दिनांक:- 23/04/2025

सेवा में / To,

मेसर्स क्यूपिड इंटरप्राइजेस
26, अंबिकापुरी, बी.एस.एफ. वाटर टैंक के
सामने, एयरपोर्ट रोड, इन्दौर (म.प्र.) - 452005

M/s. CUPID ENTERPRISES
26, Ambikapuri, Opps. BSF Water tank
Airport Road, Indore (M.P.) - 452005

विषय :- राजा भोज विमानतल, भोपाल पर एयरलाइंस कार्यालयों, आरसीसी ड्रेन, प्री-कास्ट बाउंड्री वॉल और अन्य विविध सिविल कार्यों का निर्माण।

Subject:- "Construction of Airlines Offices, RCC Drain, Pre-Cast Boundary wall and other miscellaneous civil works at Raja Bhoj Airport, Bhopal."

संदर्भ:- आपकी निविदा संख्या 2025_AAI_228276_1 दिनांक 25/03/2025 को खोला गया।

Ref: Your E-tender No. 2025_AAI_228276_1, opened on dated 25/03/2025.

महोदय/Dear Sir (S),

1. अध्यक्ष भारतीय विमानपत्तन प्राधिकरण की ओर से उपरोक्त वर्णित कार्य को आपकी मद मूल्यों पर आधारित ई-निविदा कुल राशि रु. 1,24,48,172.00/- (रुपये एक करोड़ चौबीस लाख अउतालीस हजार एक सौ बहत्तर मात्र, बिना जी.एस.टी.) तथा रु. 1,46,88,843/- (रुपये एक करोड़ छियालीस लाख अठ्ठासी हजार आठ सौ तैंतालीस मात्र, जी.एस.टी. सहित) होगी, जोकि अनुमानित लागत रु. 2,01,47,000/- (रुपये दो करोड़ एक लाख सैंतालीस हजार मात्र) (बिना जी.एस.टी.) तथा रु. 2,37,73,460/- (रुपये दो करोड़ सैंतीस लाख तिहतर हजार चार सौ साठ मात्र)(जी.एस.टी. सहित) से (-) 38.21% (अउतीस दशमलव दो एक प्रतिशत) नीचे हैं, स्वीकृत की जाती हैं।

Your E-tender for the above-mentioned work is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rate quoted by you totaling to Rs. 1,24,48,172/- (Rupees one crore twenty-four lacs forty-eight thousand one hundred and seventy-two Only) (Without GST) and Rs 1,46,88,843/- (Rupees one crore forty-six lacs eighty-eight thousand eight hundred forty-three Only) (including GST @18%) which is (-) 38.21% (Thirty - Eight Point two one Percent) below the estimated cost put to the tender i.e. Rs. 2,01,47,000/- (Rupees two crore one lacs forty-seven thousand Only) (without GST) and Rs. 2,37,73,460/- (Rupees two crore thirty-seven lacs seventy-three thousand four hundred sixty Only) (including GST @18%).

2. उप महाप्रबंधक (अभि-सिविल) भाविप्रा राजा भोज एयरपोर्ट भोपाल इस कार्य के इंजीनियर प्रभारी होंगे। आपसे अनुरोध है कि आप उप महाप्रबंधक अभियांत्रिकी (सिविल) कार्यालय भाविप्रा राजा भोज एयरपोर्ट भोपाल में दिनांक 07/05/2025 तक उपस्थित होकर कारनामों पर हस्ताक्षर कर पूरा करें। यह कारनामा रु 500/- (पाँच सौ रुपये) मूल्य के गैर-न्यायिक स्टाम्प पेपर पर निष्पादित किया जायेगा और स्टाम्प पेपर की लागत आपके द्वारा वहन की जाएगी।

Dy. Gen. Mgr. (E – C), AAI, Raja Bhoj Airport, Bhopal, shall be the Engineer-in-Charge of the work and you are requested to attend the office of Dy. Gen. Mgr. Engg. (Civil), AAI Raja Bhoj Airport, Bhopal by **07/05/2025** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 500.00/- (Rupees Five Hundred only) and the cost of the stamp paper shall be borne by you.

3. आपकी निविदा के साथ प्राप्त धरोहर राशि रु. 6,04,419/- (रुपये छ लाख चार हजार चार सौ उन्नीस मात्र) CPP पोर्टल के माध्यम से मुक्त हो जाएगी इस पत्र के जारी होने की तारीख से 10 दिनों के भीतर सुरक्षा निधि राशि रु. 12,44,817/- (रुपये बारह लाख चौवालीस हजार आठ सौ सत्रह मात्र) जमा करें। असफल होने पर अनुबंध की पृष्ठ संख्या जी.सी.सी. - 16 पर क्लॉज संख्या 1 (अ) की शर्तों के अनुसार सुरक्षा निधि राशि को बिलों से काटा जायेगा।

The earnest money for an amount of Rs. 6,04,419/- (Rupees six lacs four thousand four hundred nineteen Only) received along with your tender will be refunded to you through CPP portal. Please deposit amount of Rs. 12,44,817/- (Rupees twelve lacs forty four thousand eight hundred and seventeen Only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted from your R/A bills as per condition of Clause no 1 (A) at page no GCC -16 of contract document.

4. आपसे निवेदन है कि आप विभिन्न लागू वैधानिक अधिनियमन जैसे कर्मचारी भविष्य निधि व विविध प्रावधान अधिनियम 1952, कर्मचारीराज्य बीमा(ESI) अधिनियम, 1948, ठेका श्रमिक (रोजगार व सेवा की शर्त) अधिनियम, 1979 न्यूनतम मजदुरी अधिनियम 1948, मजदुरी भूगतान अधिनियम, 1936, श्रमिक प्रतिपूर्ति अधिनियम, 1923 एवं अन्य संगत नियम व अधिनियम, अनुदेश इत्यादि जो समय समय पर जारी/प्रवर्तित किया जाते हैं उक्त वैधानिक अधिनियम व प्रावधानों का नियमित अनुपालन व इनके अंतर्गत सारी विधिक बाध्यताओं का पूर्ण प्रेक्षण आपका एकल दायित्व होगा।

You are requested to comply with the provisions under various applicable statutory enactments including the employees Provident Fund & Miscellaneous Provisions Act, 1952, the Employees State Insurance (ESI) Act, 1948, the Contract Labour (Regulation & Abolition) Act, 1970, the Inter-State Migrant workmen (Regulation of employment & conditions of Service) Act, 1979, the Minimum Wages Act, 1948, the Payment of Wages Act, 1936, the workmen's Compensation Act, 1923 and other relevant Act, Rules and Regulations, instructions etc. issued/enforced from time to time. It shall be your sole liability to abide with and fully observing the legal obligations under the aforesaid statutory acts and provisions.

5. आपको निर्देश दिया जाता है कि आप तुरंत वरिष्ठ प्रबंधक (अभि.-नागर) से संपर्क करें जो आपको कार्यस्थल को सौंपने की व्यवस्था करेंगे।

You are also directed to contact Sr.Mgr. (Engg. – Civil) immediately who will arrange to hand over the site to you.

7. कृपया ध्यान दें कि कार्य को पूरा करने के लिए अनुमानित समय 08 (आठ) महीने होगा और इसकी गणना इस पत्र के जारी होने के 10 वें दिन से की जायेगी।

Please note that the time allowed for carrying out the work shall be 08 (eight) months and same shall be reckoned from the 10th day after issue of this letter.

8. यह संदर्भित पत्र अनुबंध का एक हिस्सा होगा ।

This letter under reference shall form part of agreement.

9. इस अनुबंध के संबंध में आगे का कोई भी पत्राचार प्रभारी अभियंता के पते पर किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-Charge.

10. कृपया अपनी अभिस्वीकृती भेजे तथा सहमति के लिये डुप्लीकेट कापी, जोकि इस पत्र के साथ संलग्न है, हस्ताक्षर करके अधोहस्ताक्षरी को भेजे।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.


11. यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण को ही सही रूप में लिया जाएगा ।

In case any discrepancy is found then English version will be taken as correct.

भवदीय/Yours faithfully

संलग्नक/ Encl.

i) Schedule 'A' (BoQ)



उप महा प्रबंधक (अभि.-नागर)

Dy. Gen. Mgr. (Engg. - Civil)

राजा भोज विमानतल भोपाल,

Raja Bhoj Airport, Bhopal

अध्यक्ष - भा.वि.प्रा. की ओर से

(For and on behalf of the Chairman-AAI)

मूलप्रति से अतिरिक्त /N.O.O

1. क्षेत्रीय श्रम आयुक्त (केन्द्रीय),
निर्माण सदन, सी.जी.ओ. कॉम्प्लेक्स रूम नंबर 306,
तीसरा माला, अरेरा हिल्स, भोपाल-462016.
The Regional Labour Commissioner(Central),
Nirman Sadan. C.G.O. Complex, Room No. 306.
3rd floor, Arera hills Bhopal-462016.
2. क्षेत्रीय भविष्य निधि आयुक्त, मध्यप्रदेश,
भविष्य निधि भवन, 59-अरेरा हिल्स, भोपाल-462011
The Regional Provident Fund Commissioner (M.P.)
Bhavishy Nidhi Bhavan, 59-Arera Hills, Bhopal-462011

आंतरिक/INTERNAL

1. महाप्रबंधक (अभि.-नागर) पश्चिम क्षेत्र, भाविप्रा, मुम्बई जानकारी हेतु।
GM (Engg. – Civil), Western Region, AAI, Mumbai..... for information please.
2. विमानपत्तन निदेशक, भाविप्रा.राजा भोज विमानतल, भोपाल जानकारी हेतु।
The Airport Director, AAI, Raja Bhoj Airport, Bhopal..... for information please.
3. वरिष्ठ प्रबंधक(अभि.- नागर) भाविप्रा, राजा भोज विमानतल, भोपाल जानकारी हेतु।
Senior Mgr. (Engg. – Civil), AAI, Raja Bhoj Airport Bhopal..... for information please.
4. सहायक महाप्रबंधक – (वित्त) भाविप्रा. राजा भोज विमानतल. भोपाल.
Asstt.GM (Finance), AAI, Raja Bhoj Airport Bhopal.
5. सहायक महाप्रबंधक(अभि.- वि.) भाविप्रा, राजा भोज विमानतल, भोपाल जानकारी हेतु।
Asstt. Gen. Mgr. (Engg. – Elect.), AAI, Raja Bhoj Airport Bhopal..... for information please.
6. कार्यालय प्रतिलिपि/ For office copy

उप महा प्रबंधक (अभि.-नागर)
Dy. Gen. Mgr. (Engg. – Civil)
राजा भोज विमानतल भोपाल,
Raja Bhoj Airport, Bhopal

Tender Title: Construction of Airlines Offices, RCC Drain, Pre - Cast boundary wall and other miscellaneous civil works at Raja Bhoj Airport, Bhopal.
Tender ID: 2025_AAI_228276_1


Tender Inviting Authority: Sr. Mgr. (Engg. - Civil), Raja Bhoj Airport, Bhopal

Name of Work: Construction of Airlines Offices, RCC Drain, Pre - Cast boundary wall and other miscellaneous civil works at Raja Bhoj Airport, Bhopal.

Contract No: AAI/BHO/ENGG-C/MISCWORKS/24 - 25

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Cupid Enterprises (GSTN-23AAIFC2788B1ZP) BID ID - 832650	
				Rate	Amount
1.00	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth For lead upto 5 Km and lift upto 1.5 m, within Airport premises as directed by Engineer-in-charge. All kinds of soil	53.00	cum	110.00	5830.00
2.00	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth For lead upto 5 Km and lift upto 1.5 m, within Airport premises as directed by Engineer-in-charge. Ordinary rock	26.00	cum	90.00	2340.00
3.00	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms; lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	920.00	cum	110.00	101200.00
4.00	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. Ordinary rock	391.00	cum	200.00	78200.00
5.00	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. Hard rock	19.00	cum	250.00	4750.00
6.00	Filling available excavated earth (excluding rock) in trenches, plinth,sides of foundations etc. in layers not exceeding 20cm in depth,consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	682.00	cum	50.00	34100.00
7.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	30.00	cum	5800.00	174000.00
8.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	5.00	cum	4800.00	24000.00
9.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	74.00	cum	4000.00	296000.00
10.00	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns	850.00	sqm	150.00	127500.00
11.00	Centering and shuttering including strutting, propping etc. and removal of form work for : Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc.	1600.00	sqm	180.00	288000.00
12.00	Providing and laying damp-proof course 50mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20mm nominal size derived from natural sources).	70.00	sqm	205.00	14350.00
13.00	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size de rived from natural sources)	260.00	cum	5400.00	1404000.00



SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Cupid Enterprises (GSTN-23AAIFC2788B1ZP) BID ID - 832650	
14.00	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	120.00	cum	5800.00	696000.00
15.00	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	59.00	sqm	152.00	8968.00
16.00	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform	950.00	sqm	450.00	427500.00
17.00	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Lintels, beams, plinth beams, girders, bressumers and cantilevers	139.00	sqm	250.00	34750.00
18.00	Centering and shuttering including strutting, propping etc. and removal of form for Columns, Pillars, Piers, Abutments, Posts and Struts	144.00	sqm	200.00	28800.00
19.00	Centering and shuttering including strutting, propping etc. and removal of form for Edges of slabs and breaks in floors and walls Under 20 cm wide	51.00	metre	60.00	3060.00
20.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	35678.00	kg	61.00	2176358.00
21.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more	7366.00	kg	61.00	449326.00
22.00	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works upto plinth level Concrete of M25 grade with minimum cement content of 330 kg /cum	40.00	cum	5700.00	228000.00
23.00	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works above plinth level upto floor V level Concrete of M25 grade with minimum cement content of 330 kg /cum	80.00	cum	6000.00	480000.00
24.00	Add for using extra cement in the items of design mix over and above the specified cement content therein	75.00	quintal	500.00	37500.00
25.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 3.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	5.00	cum	5000.00	25000.00
26.00	Brick work with common burnt clay modular / flyash bricks of class designation 3.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	20.00	cum	4800.00	96000.00
27.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 3.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	9.00	cum	6000.00	54000.00
28.00	Half brick masonry with common burnt clay modular / flyash bricks of class designation 3.5 in foundations and plinth in : cement mortar 1:4 (1 cement : 4 coarse sand)	10.00	sqm	400.00	4000.00
29.00	Half brick masonry with common burnt clay modular / flyash bricks of class designation 3.5 in superstructure above plinth level up to floor V level. Cement mortar 1:4 (1 cement :4 coarse sand)	15.00	sqm	700.00	10500.00

[Handwritten Signature]

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Cupid Enterprises (GSTN-23AAIFC2788B12P) BID ID - 832650	
30.00	Brick work with clay modular / flyash brick of class designation 3.5 in superstructure above plinth level up to floor five level in :Cement mortar 1:4 (1 cement : 4 coarse sand)	30.00	cum	5800.00	174000.00
31.00	Coursed rubble masonry (second sort) with hard stone in foundation & plinth with : Cement mortar 1:6 (1 cement : 6 coarse sand)	30.00	cum	4800.00	144000.00
32.00	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete at all levels. Granite stone slab of colour black, Cherry/Ruby red Area of slab over 0.50 sqm	25.00	sqm	3300.00	82500.00
33.00	Providing and fixing 75 Cm high, 50 Cm deep and 18 mm thick stone slab table rubbed, edges rounded and polished, fixed in urinal partitions by cutting a chase of appropriate width with chase cutter and embedding the stone in the chase with epoxy grout or with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 6 mm nominal size) as per direction of Engineer-in-charge and finished smooth. Granite Stone of approved shade	2.00	sqm	3200.00	6400.00
34.00	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	80.00	sqm	900.00	72000.00
35.00	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	32.00	sqm	2200.00	70400.00
36.00	Providing and fixing bright finished brass 100 mm mortice latch with one dead bolt and a pair of lever handles of approved quality with necessary screws etc. complete.	13.00	each	400.00	5200.00
37.00	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : 300x16 mm	18.00	each	150.00	2700.00
38.00	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 250x10 mm	18.00	each	75.00	1350.00
39.00	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. Twin rubber stopper	5.00	each	50.00	250.00
40.00	Providing and fixing factory made P.V.C. door frame of size 50x47 mm with awall thickness of 5 mm, made out of extruded 5mm rigid PVC foam sheet, mitred at corners and joined with 2 Nos of 150 mm long brackets of 15x15 mm M.S. square tube, the vertical door frame profiles to be reinforced with 19x19 mm M.S. square tube of 19 gauge, EPDM rubber gasket weather seal to be provided through out the frame. The door frame to be fixed to the wall using M.S. screws of 65/100 mm size, complete as per manufacturer's specification and direction of Engineer- in-Charge.	10.00	meter	250.00	2500.00
41.00	Providing and fixing factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19 mm x 19 mm for styles and 15x15 mm for top & bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture. M.S. frame covered with 5 mm thick heat moulded PVC 'C' channel of size 30 mm thickness, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on both side forming styles and 5 mm thick, 95 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided both side of the panel. 10 mm (5 mm x 2) thick, 20 mm wide cross PVC sheet be provided as gap insert for top rail & bottom rail, paneling of 5 mm thick both side PVC sheet to be fitted in the M.S. frame welded/ sealed to the styles & rails with 7 mm (5 mm+2 mm) thick x 15 mm wide PVC sheet beading on inner side, and joined together with solvent cement adhesive. An additional 5 mm thick PVC strip of 20 mm width is to be stuck on the interior side of the 'C' Channel using PVC solvent adhesive etc. complete as per direction of Engineer-in-charge, manufacturer's specification & drawing. 30 mm thick plain PVC door shutters	5.00	sqm	2000.00	10000.00
42.00	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	3250.00	kg	90.00	292500.00

[Handwritten Signature]

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Cupid Enterprises (GSTN-23AAIFC2788B12P) BID ID - 832650	
43.00	Providing and fixing pressed steel door frames conforming to IS: 4351, manufactured from commercial mild steel sheet of 1.60 mm thickness, including hinges, jamb, lock jamb, bead and if required angle threshold of mild steel angle of section 50x25 mm, or base ties of 1.60 mm, pressed mild steel welded or rigidly fixed together by mechanical means, including M.S. pressed butt hinges 2.5 mm thick with mortar guards, lock strike-plate and shock absorbers as specified and applying a coat of approved steel primer after pre-treatment of the surface as directed by Engineer-in-charge: Profile B Fixing with carbon steel galvanised dash fastener of required dia and size (to be paid for separately)	60.00	meter	300.00	18000.00
44.00	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	5250.00	kg	100.00	525000.00
45.00	Providing and fixing mild steel round holding down bolts with nuts and washer plates complete.	135.00	kg	72.00	9720.00
46.00	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	1100.00	kg	110.00	121000.00
47.00	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	29.00	sqm	1500.00	43500.00
48.00	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	5.00	sqm	1300.00	6500.00
49.00	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	25.00	sqm	500.00	12500.00
50.00	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm	110.00	sqm	1000.00	110000.00
51.00	Providing and laying brick tiles over mummy roofs, grouted with cement mortar 1:3 (1 cement : 3 fine sand) mixed with 2% of integral water proofing compound by weight of cement, over 12 mm layer of cement mortar 1:3 (1 cement : 3 fine sand) and finished neat: With common burnt clay F.P.S. (non modular) brick tiles of class designation 10	45.00	sqm	300.00	13500.00
52.00	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 75 mm diameter	50.00	meter	120.00	6000.00
53.00	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 110 mm diameter	50.00	meter	130.00	6500.00
54.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Coupler 75 mm Dia	10.00	each	50.00	500.00
55.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Coupler 110 mm Dia	10.00	each	50.00	500.00
56.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Single Pushfit Coupler 75 mm Dia	10.00	each	50.00	500.00
57.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Single Pushfit Coupler 110 mm Dia	10.00	each	50.00	500.00
58.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Single tee with door 75x75x75 mm	10.00	each	100.00	1000.00

[Handwritten Signature]

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Cupid Enterprises (GSTN-23AAIFC2788B12P) BID ID - 832650	
59.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Single tee with door 110x110x110 mm	10.00	each	150.00	1500.00
60.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Single tee without door 75x75x75 mm	10.00	each	75.00	750.00
61.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Single tee without door 110x110x110 mm	10.00	each	100.00	1000.00
62.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. 75mm Bend 87.5°	10.00	each	50.00	500.00
63.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. 110mm Bend 87.5°	10.00	each	100.00	1000.00
64.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. 75mm Shoe (Plain)	10.00	each	50.00	500.00
65.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. 110mm Shoe (Plain)	10.00	each	75.00	750.00
66.00	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	485.00	sqm	450.00	218250.00
67.00	12 mm cement plaster of mix : 1:6 (1 cement: 6 Fine sand)	396.00	sqm	200.00	79200.00
68.00	15 mm cement plaster of mix : 1:6 (1 cement: 6 Fine sand)	396.00	sqm	250.00	99000.00
69.00	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	75.00	sqm	150.00	11250.00
70.00	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	867.00	sqm	100.00	86700.00
71.00	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.9 Ltr/10 sqm)	1596.00	sqm	75.00	119700.00
72.00	Finishing walls with ready mixed Premium acrylic emulsion paint (Company Depot Tinted) having VOC less than 50gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10sqm over and including priming coat of exterior primer applied @ 0.90 litre/10sqm)	116.00	sqm	75.00	8700.00
73.00	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	715.00	sqm	60.00	42900.00
74.00	Wall painting with acrylic emulsion paint, having VOC(Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two Coat	280.00	sqm	70.00	19600.00
75.00	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earthwith lead upto 50 metres.	1160.00	sqm	90.00	104400.00

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Cupid Enterprises (GSTN-23AAIFC2788B12P) BID ID - 832650	
76.00	Providing and laying design mix cement concrete of M-30 grade, in roads/ taxi tracks/ runways, using cement content as per design mix, using coarse sand and graded stone aggregate of 40 mm nominal size in appropriate proportions as per approved & specified design criteria, providing dowel bars with sleeve/ tie bars wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/ camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction/ expansion, construction & longitudinal joints (10 mm wide x 50 mm deep) by groove cutting machine, providing and filling joints with approved joint filler and sealants, complete all as per direction of Engineer-in-charge (Item of joint fillers, sealants, dowel bars with sleeve/ tie bars to be paid separately). Note:- Cement content considered in M-30 is @ 340 kg/cum. Excess/ less cement used as per design mix is payable/ recoverable separately. Cement concrete manufactured in automatic batching plant (RMC plant) i/c transportation to site in transit mixer	100.00	cum	6100.00	610000.00
77.00	Providing and fixing pre-moulded joint filler in expansion joints of RCC roads / CC pavements after making the joints dust free with high pressure air jet cleaners, all complete as per direction of the Engineer-in-Charge. (Pre-moulded joint fillers shall be made of bitumen hot sealing compound impregnated fibre board having impregnation more than 35%, conforming to IS:1838 for fibre board and IS: 1834 for hot sealing bitumen compound grade A.)	100.00	per cm depth per cm width per metre length	2.00	200.00
78.00	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	250.00	meter	180.00	45000.00
79.00	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	100.00	sqm	500.00	50000.00
80.00	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia 4 mm	460.00	sqm	600.00	276000.00
81.00	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30	135.00	cum	1200.00	162000.00
82.00	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paver/finisher in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	110.00	cum	1200.00	132000.00
83.00	Construction of dry lean cement concrete sub base over a prepared sub-grade with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per specifications, cement content not to be less than 150 Kg/cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, for all leads & lifts, laid with a mechanical paver, compacting with 8-10 tonne vibratory roller, finishing and curing etc. complete as per direction of Engineer-in-charge.	105.00	cum	3000.00	315000.00
84.00	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	2.00	each	2500.00	5000.00
85.00	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid	3.00	each	4500.00	13500.00

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Cupid Enterprises (GSTN-23AAIFC2788B1ZP) BID ID - 832650	
86.00	Providing and fixing white vitreous china flat back half stall urinal of size 580x380x350 mm with fittings, standard size C.P. brass flush pipe, spreaders with unions and clamps (all in C.P. brass) with waste fitting as per IS : 2556, C.I. trap with outlet grating and other couplings in C.P. brass, including painting of fittings and cutting and making good the walls and floors wherever required : Single half stall urinal	4.00	each	7000.00	28000.00
87.00	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 550x400 mm with a pair of 15 mm C.P. brass pillar taps	4.00	each	1500.00	6000.00
88.00	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required : Kitchen sink with drain board 510x1040 mm bowl depth 225 mm	1.00	each	3500.00	3500.00
89.00	Providing and fixing CP Brass 32mm size Bottle Trap of approved quality & make and as per the direction of Engineer-in-charge.	8.00	each	500.00	4000.00
90.00	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Flexible pipe 40 mm dia	8.00	each	60.00	480.00
91.00	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	4.00	each	1000.00	4000.00
92.00	Providing and fixing PTMT liquid soap container 109 mm wide, 125 mm high and 112 mm distance from wall of standard shape with bracket of the same materials with snap fittings of approved quality and colour, weighing not less than 105 gms.	4.00	each	80.00	320.00
93.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 15 mm nominal dia Pipes	50.00	meter	200.00	10000.00
94.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 20 mm nominal dia Pipes	50.00	rm	200.00	10000.00
95.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 50 mm nominal dia Pipes	50.00	rm	300.00	15000.00
96.00	Providing and fixing brass stop cock of approved quality : 15 mm nominal bore	2.00	each	200.00	400.00
97.00	Providing and fixing uplasticised PVC connection pipe with brass unions :45 cm length 15 mm nominal bore	20.00	each	50.00	1000.00
98.00	Providing and fixing rectangular high density polyethylene water storage loft tank with cover, conforming to ISI : 12701, colour of opaque white or as approved by Engineer-in-charge. The rate includes making necessary holes for inlet, outlet & over flow pipes. The base support i/c fittings & fixtures for tank shall be paid separately.	1000.00	ltr	8.00	8000.00
99.00	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 : 15 mm nominal bore	5.00	each	300.00	1500.00
100.00	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms. 15 mm nominal bore	5.00	each	400.00	2000.00
101.00	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15mm nominal bore	5.00	each	350.00	1750.00
102.00	Providing and fixing C.P. Brass extension nipple (size 15mmx50mm) of approved make and quality as per direction of Engineer-in-charge.	5.00	each	30.00	150.00
103.00	Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design :Inside size 90x80 cm and 45 cm deep including C.I. cover with frame (light duty) 455x610 mm internal dimensions, total weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) : With common Stone Dust (non modular) bricks of class designation 3.5	1.00	each	8000.00	8000.00

[Handwritten Signature]

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Cupid Enterprises (GSTN-23AAIFC2788B12P) BID ID - 832650	
104.00	Constructing soak pit 1.20x1.20x1.20 m filled with brickbats including S.W. drain pipe 100 mm diameter and 1.20 m long complete as per standard design.	1.00	each	1500.00	1500.00
105.00	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	115.00	kg	300.00	34500.00
106.00	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	200.00	kg	300.00	60000.00
107.00	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)	38.00	sqm	1000.00	38000.00
108.00	Providing and applying fibre reinforced elastomeric liquid water proofing membrane with resilient acrylic polymers having Sun Reflectivity Index (SRI) of 105 on top of concrete roof in three coats @10.76 litre/ 10 sqm. One coat of self-priming of elastomeric waterproofing liquid (dilution with water in the ratio of 3:1) and two coats of undiluted elastomeric waterproofing liquid (dry film thickness of complete application/system not less than 500 microns). The operation shall be carried out after scrapping and properly cleaning the surface to remove loose particles with wire brushes, complete in all respect as per the direction of Engineer-in-Charge.	245.00	sqm	320.00	78400.00
109.00	Providing and fixing false ceiling at all heights with integral densified calcium silicate reinforced with fibre and natural filler false ceiling tiles of Size 595x595mm of approved texture, design and patterns as per CPWD Specification 2019, to be laid in true horizontal level suspended on inter-locking metal T-Grid of hot dipped galvanised iron section of 0.33mmthick (galvanized @ 120 grams per sqm including both sides) comprising of main-T runners of size 24x38 mm of length 3000 mm, cross - T of size 24x32 mm of length 1200 mm and secondary intermediate cross-T of size 24x32 mm of length 600mm to formgrid module of size 600 x 600 mm, suspended from ceiling usinggalvanised mild steel items (galvanizing @ 80 grams per sqm) i.e. 12x50 mm long dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape level adjuster of size 76x25x25x1.6 mm fixed with grid and Z cleat of size 25x37x25x1.6mm thick with precut hole on both 25mm flange to pierce into 12x50mm or even bigger size dash fastener if require, fixed with Glavanised iron perimeter wall angle or size 24x24x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450mm center to center and 40 mm long dry wall S.S screws. The workshall be carried out as per specifications, drawing and as per directions of the Engineer-in- Charge. With 15 mm thick Tegular edged light weight calcium silicate false ceiling tiles	110.00	sqm	1800.00	198000.00
110.00	Manufacturing, Transportation and Fixing at site Precast RCC Boundary wall unit (minimum M-30 grade concrete) of height 8 feet above average ground in required length, fixed at site with centre to centre spacing between pillars maximum 2.10 meter or as per site condition. Excavation, Aligning and Fixing in position with specified cement concrete in foundation all complete as per direction and satisfaction of engineer-in-charge. The precast Boundary wall unit consist of RCC pillars of dimension 150mm x 150mm of length 10.5 feet (i/c 2 feet below ground) having reinforcement of minimum 7 nos wire of 4mm dia with required groove and precast RCC slabs of minimum thickness 50 mm having reinforcement of minimum 4 nos wire of 4mm dia in 1 feet high panel and having sufficient length and width to fit between column unit grooves.(cement concrete for fixing shall be paid in relevent item)	530.00	sqm	700.00	371000.00


SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Cupid Enterprises (GSTN-23AAIFC2788B1ZP) BID ID - 832650	
111.00	Providing and laying transparant (1st quality) polythene sheet (separation membrane) 400 microns thick on the base course with overlaps of not less than 100mm both way all complete as per directions of Engineer-in-charge. Only plan area shall be measured for payment.	1050.00	sqm	60.00	63000.00
112.00	Providing and laying in position for expansion joint, 25mm thick pre cut Synthetic joint filler board of approved make (HD 100 or equivalent of density 100 kg / cum +/- 10%) conforming to IS:1838 (part 3)-2011, 45 mm from top (to be removed at the time of filling of Silicon sealant), complete as per particular specifications and directions of Engineer-in-charge. (Note: Nothing extra shall be paid for the filler board from top upto the bottom of polyethylene backing rod.) (Note: Mode of measurement shall be length of joint multiplied by depth of filler board including precut portion.)	4.00	sqm	200.00	800.00
113.00	Providing and fixing of GI profile sheet Trim of size 55 mm X 55 mm in C shape of sheet thickness 2 mm thick fixed with self drilling / tapping Screw all complete as per the direction of Engineer-in-charge.	110.00	meter	300.00	33000.00
114.00	Supplying and filling moorum / Good earth obtained from approved quarry Up to plinth in building area as instructed and in layers not exceeding 20 cm (loose) in depth (or any thickness as approved by the Engineer-in-Charge) including breaking clods, watering, consolidating each layer complete including leveling, fine dressing to the required grade, camber and slope complete as directed by the Engineer-in-Charge with all leads and lifts. (The item includes cost of work, payment of necessary royalty, carriage of moorum / suitable earth upto work site for all leads and lifts involved from all sources acquired or arranged by the contractor. Payment shall be made for compacted quantity only.)	15.00	cum	345.00	5175.00
115.00	Providing and fixing G.I Wire mesh in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With Galvanised wire mesh of average width of aperture 1.4 mm and nominal dia of wire 0.63 mm)	11.00	sqm	295.00	3245.00

Total in Figures

12448172.00

Lowest Amount Quoted BY: Cupid Enterprises(12448172.00)



Signature Not Verified

Digitally signed by VIKAS SHRIVASTAVA
Date: 2025.07.15 16:14:25 IST
Location: eProcurement System for Central PSUs