



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
सूरत अंतरराष्ट्रीय हवाई अड्डा, सूरत-394550
SURAT INTERNATIONAL AIRPORT, SURAT-394550

सन्दर्भ संख्या : - भाविप्रा/सूरत/विद्युत/स.म.प्र(अभि-वि)/2025-26/W-01/1441-1450
Ref. No: - AAI/SURAT/Elect/AGM (E-E)/2025-26/W-01 | 1441 -1450

दिनांक :- 22/04/2025

Date :- 22/04/2025

(-मेल द्वारा / By Mail-)

(कार्य आदेश / Work Order)

सेवा में,

मेसर्स, ज्योना पावर,

"ज्योना हाउस", प्लॉट नंबर. 4/5/6,

माली नी वाडी, ए.के. रोड,

सूरत -395008

E-Mail ID: jyonapower@jyonagroup.com

To,

M/s. Jyona Power,

"Jyona House", Plot No. 4/5/6,

Mali ni Wadi, A. K. Road,

Surat-395008

E-Mail ID: jyonapower@jyonagroup.com

कार्य का नाम: सूरत अंतरराष्ट्रीय हवाई अड्डे पर नए डीवीओआर का निर्माण। एसएच: विद्युत कार्य।

Name of Work: Construction of New DVOR at Surat Int'l Airport. SH: Electrical Works.

संदर्भ / Reference 1 :- आपकी निविदा / Your tender for 2025_AAI_228598_1

(Financial bid opening on Dt: 07.04.2025)

1. उल्लेखित कार्य हेतु आपकी निविदा के संबंध में, आपके द्वारा उद्धृत कुल ₹ 1,26,87,027.00 (रुपए: एक करोड़ छब्बीस लाख सत्तासी हजार सत्ताईस मात्र जी.एस.टी. छोड़कर) जो की निविदा की उचित लागत राशि ₹ 1,85,39,685.00 से 31.57% कम है, को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है।

Your tender for the above-mentioned work is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to ₹ 1,26,87,027.00 (Rupees: One Crore Twenty-Six Lakh Eighty-Seven Thousand Twenty-Seven Only excluding GST). which is 31.57% below the Justified cost put to the tender ₹ 1,85,39,685.00

2. सहायक महाप्रबंधक (अभि-वि.) भाविप्रा, सूरत अंतरराष्ट्रीय हवाई अड्डा, सूरत - 394550, उपरोक्त कार्य के प्रभारी होंगे। आपसे निवेदन है कि आप के अधिकृत प्रतिनिधि, जिन्हें आपकी ओर से ठेका करार पर हस्ताक्षर करने का अधिकार हो, को दिनांक: 16/05/2025 तक सहायक महाप्रबंधक (अभि-वि.) के कार्यालय में भेजकर करार पर हस्ताक्षर करने तथा करार की कार्यवाही पूर्ण कराने का कष्ट करें। ठेका करार का निष्पादन तीन सौ रुपए मूल्य के गैर अदालती स्टैम्प पेपर (गुजरात) पर किया जाएगा तथा स्टैम्प पेपर का खर्च आपके द्वारा वहन किया जायेगा।

AGM (Engg-Elect.) AAI, Surat Int'l Airport, Surat - 394550, shall be the Engineer-in-charge of the work. You are requested to depute your accredited representative, empowered to sign the contract agreement on your behalf to attend the office of the AGM (Engg-Elect.), AAI, Surat Int'l Airport, Surat by the 16/05/2025 to sign and complete the agreement. The contract agreement shall be executed on a Non-Judicial Stamp Paper (Gujarat) of value ₹ 300/- and the cost of the same shall be borne by you.

|
Jyona
22/04/2025
AGM (E-E)

3. कृपया इस पत्र के जारी होने के 10 दिनों के अन्दर प्रतिभूति जमा के रूप में ₹ 12,68,703/- (रुपये: बारह लाख अड़सठ हजार सात सौ तीन मात्र), की राशि इस कार्यालय में जमा करा दें अन्यथा संविदा की सामान्य शर्तों के पृष्ठ संख्या 29 पर दी गई शर्त 1 (ए), के अनुसार उक्त राशि आपके चालू बिल से काट ली जाएगी।

Please deposit ₹ 12,68,703/- (Rupees: Twelve lakh Sixty-Eight Thousand Seven Hundred Three Only) towards security deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted from your running bills as per General Terms & Conditions Clause 1 (A) on page 29 of the contract document.

4. आपसे अनुरोध है कि आप ठेका श्रमिक (विनियम एवं अन्मूलन) अधिनियम 1970 के उपबन्धों का अनुपालन करें। साथ ही ठेका श्रमिक (विनियम एवं अन्मूलन) केन्द्रीय नियमावली 1971 एवं केन्द्रीय एवं राज्य सरकारों के न्यूनतम वेतन तथा उससे सम्बन्धित अन्य नियमों का पालन करें।

You are requested to comply with the provisions of contract labour (Regulation and Abolition) Act of 1970 and contract labour (Regulation and Abolition) Central Rules 1971 and Minimum Wages Act and Rules there of Central and State Governments.

5. आपको यह भी निर्देश दिया जाता है कि आप प्रबंधक (अभि.-वि.), भा.वि.प्रा, सूरत से अविलम्ब सम्पर्क करें जो आपको कार्यस्थल सौंपने की व्यवस्था करेंगे।

You are directed to contact Manager (Engg.-Elect.), AAI, Surat immediately who will arrange to hand over the site to you.

6. कृपया यह भी भली भांति नोट कर लें की निविदा के अनुसार कार्य निष्पादन हेतु अनुमत समय 06 (छह) माह है जो इस पत्र को जारी करने के दस दिन बाद से गिना जाएगा।

Please note that the time allowed for carrying out the work shall be 06 (Six) Months, and same shall be reckoned from 10th day after the date of issue of this letter.

7. इस ठेके से संबंधित किसी भी प्रकार के पत्र व्यवहार के लिए सहायक महाप्रबंधक (अभि.-वि.), भारतीय विमानपत्तन प्राधिकरण, सूरत अंतरराष्ट्रीय हवाई अड्डा, सूरत-394 550 को संबोधित करेंगे।

Any further correspondence in connection with the contract should normally be addressed to the AGM (Engg.-Elect.), Airports Authority of India, Surat Int'l Airport, Surat – 394 550.


8. संविदा दस्तावेज की अनुसूची "E" के पृष्ठ संख्या 144 के अनुसार दोष दायित्व अवधि एलईडी फिक्सचर को छोड़कर सभी वस्तुओं के लिए 12 महीने और एलईडी फिक्सचर के लिए 60 महीने काम पूरा होने की तारीख से।

The defect liability period is 12 Months for all Items except LED fixtures and 60 Months for LED Fixtures from the date of completion of work. as per condition on page 144 of schedule "E" of the contract document.

9. कृपया इस पत्र की प्राप्ति सुचना दें तथा इसके साथ अनुलग्न अनुप्रति पर हस्ताक्षर करके टोकन प्रतिग्रहण के रूप में अधोहस्ताक्षरी को वापस भेज दें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

धन्यवाद / Thanking you,

संलग्न: Item Rate BOQ. (Page.1 to10)


(एम एम अग्रवाल) / (M.M.Agrawal)

सहायक महाप्रबंधक (अभि.-वि.) / AGM (Engg.-Elect)

कृते तथा की ओर से अध्यक्ष, भा.वि.प्रा. / For and on behalf of Chairman, AAI

भा.वि.प्रा.,सूरत अंतरराष्ट्रीय हवाई अड्डा, सूरत / AAI, Surat Int'l Airport, Surat

विशेष ध्यान : अर्थ निर्णय के सम्बन्ध में कोई विवाद होने पर अंग्रेजी पाठ को ही प्राधिकृत माना जाएगा।

Note: In the event of any dispute regarding interpretation the English text will be treated as authentic.

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: AGM (E-E), AAI, Surat Airport, Surat

Name of Work : "Construction of New DVOR at Surat Int'l Airport. SH: Electrical Works."

Contract No: Tender ID 2025_AAI_228598_1

Name of the Bidder/ Bidding Firm / Company :	M/s. Jyona Power
--	------------------


PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)


NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE including all taxes, duties etc. but excluding GST. In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. (excluding GST)	TOTAL AMOUNT in Rs. (excluding GST) In Words
1	2	3	4	5	6	7	8
1	SH:- Internal Electrification, Light Fixtures.						
1.01	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLSH PVC insulated copper conductor single core cable in surface / recessed steel conduit i/c supply and laying of suitable size medium class steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLSH PVC insulated copper conductor single core cable etc as required. (a) Group B	Item 1	24	Point	768.00	18432.00	INR Eighteen Thousand Four Hundred & Thirty Two Only
1.02	Wiring for circuit/ submain wiring alongwith earth wire with the sizes of 2 x 2.5 Sq.mm + 1 x 2.5 Sq.mm Earth Wire FRLSH PVC insulated copper conductor, single core cable in surface/ recessed steel conduit i/c supply and laying of suitable size medium class steel conduit complete as required.	Item 2	120	Meter	168.00	20160.00	INR Twenty Thousand One Hundred & Sixty Only
1.03	Wiring for circuit/ submain wiring alongwith earth wire with the sizes of 2 x 4 Sq.mm + 1 x 4 Sq.mm Earth Wire FRLSH PVC insulated copper conductor, single core cable in surface/ recessed steel conduit i/c supply and laying of suitable size medium class steel conduit complete as required.	Item 3	220	Meter	194.00	42680.00	INR Forty Two Thousand Six Hundred & Eighty Only
1.04	Wiring for circuit/ submain wiring alongwith earth wire with the sizes of 2 x 6 Sq.mm + 1 x 6 Sq.mm Earth Wire FRLSH PVC insulated copper conductor, single core cable in surface/ recessed steel conduit i/c supply and laying of suitable size medium class steel conduit complete as required.	Item 4	50	Meter	267.00	13350.00	INR Thirteen Thousand Three Hundred & Fifty Only
1.05	Wiring for light/ power plug with 2X4 sq. mm FRLSH PVC insulated copper conductor single core cable in surface/ recessed steel conduit alongwith 1 No 4 sq. mm FRLSH PVC insulated copper conductor single core cable for loop earthing as required.	Item 5	250	Meter	197.00	49250.00	INR Forty Nine Thousand Two Hundred & Fifty Only
1.06	Supplying and fixing of 25 mm sizes of medium class steel conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.	Item 6	30	Meter	117.00	3510.00	INR Three Thousand Five Hundred & Ten Only
1.07	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required.	Item 7	20	Each	267.00	5340.00	INR Five Thousand Three Hundred & Forty Only

Agm
27/04/2025
Agm (E-E)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE including all taxes, duties etc. but excluding GST. In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. (excluding GST)	TOTAL AMOUNT in Rs. (excluding GST) In Words
1	2	3	4	5	6	7	8
1.08	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. (A). Telephone Socket Outlet	Item 8	3	Each	68.00	204.00	INR Two Hundred & Four Only
1.09	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. (A). 15/16 A Switch	Item 9	30	Each	72.00	2160.00	INR Two Thousand One Hundred & Sixty
1.1	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. (A). 6 pin 15/16 A socket outlet	Item 10	30	Each	90.00	2700.00	INR Two Thousand Seven Hundred
1.11	Supplying and fixing 12 Module (200 mm x 150 mm) size/ modules, GI box along with modular base & cover plate for modular switches in recess etc as required.	Item 11	2	Each	247.00	494.00	INR Four Hundred & Ninety Four
1.12	Supplying and fixing 3 Module (100 mm x 75 mm) size/ modules, GI box along with modular base & cover plate for modular switches in recess etc as required.	Item 12	6	Each	151.00	906.00	INR Nine Hundred & Six Only
1.13	Supplying and fixing 6 Module (200 mm x 75 mm) size/ modules, GI box along with modular base & cover plate for modular switches in recess etc as required.	Item 13	6	Each	185.00	1110.00	INR One Thousand One Hundred & Ten
1.14	Supplying and fixing of 6 way (4 +18), double door , metal, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing, blanking plates etc. as required. (But without MCB/RCCB/Isolator).	Item 14	2	Each	2217.00	4434.00	INR Four Thousand Four Hundred & Thirty Four Only
1.15	Supplying and fixing of 12 way (2+10), Double Door, Single pole and neutral (SPN), sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing , blanking plates etc. as required. (But without MCB/RCCB/Isolator)	Item 15	6	Each	1040.00	6240.00	INR Six Thousand Two Hundred & Forty Only
1.16	Supplying and fixing of 6 way (2+4), Double Door, Single pole and neutral (SPN), sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing , blanking plates etc. as required. (But without MCB/RCCB/Isolator)	Item 16	2	Each	988.00	1976.00	INR One Thousand Nine Hundred & Seventy Six Only
1.17	Supplying and fixing of 63A rating, 415 V, 10 kA, 4 Pole MCB suitable in the existing TPN MCB DB complete with connections, testing and commissioning etc. as required.	Item 17	2	Each	1135.00	2270.00	INR Two Thousand Two Hundred & Seventy
1.18	Supplying and fixing of 63A rating, 240/415 V, 10 kA, "C" curve, DP MCB In the existing MCB DB complete with connections, testing and commissioning etc. as required.	Item 18	6	Each	655.00	3930.00	INR Three Thousand Nine Hundred & Thirty
1.19	Supplying and fixing of 32 Amp rating, Two pole, (one phase and neutral), 415/240 volts, residual current breaker with overload protection (RCBO), having a sensitivity current 100 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required.	Item 19	5	Each	2265.00	11325.00	INR Eleven Thousand Three Hundred & Twenty Five
1.2	Supplying and fixing of 40 Amp rating, Two pole SPN, (one phase and neutral), 240 volts, residual current breaker with overload protection (RCBO), having a sensitivity current 100 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required.	Item 20	5	Each	2570.00	12850.00	INR Twelve Thousand Eight Hundred & Fifty
1.21	Supplying and fixing of 5 A to 32 A rating , 240/415 V, 10 kA, "C" curve, SP MCB suitable for inductive load in the existing MCB DB complete with connections, testing and commissioning etc. as required.	Item 21	82	Each	145.00	11890.00	INR Eleven Thousand Eight Hundred &九十


 22/04/2025
 AGM (E&B)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE including all taxes, duties etc. but excluding GST. In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. (excluding GST)	TOTAL AMOUNT in Rs. (excluding GST) In Words
1	2	3	4	5	6	7	8
1.22	Supply and Fixing of Modular type Socket having Residual Current Device (SRCD) with steel enclosure with 25 Amps DP MCB having Over current protection suitable for 1.5 TR Inverter AC complete as required.	Item 22	9	Each	1130.00	10170.00	INR Ten Thousand One Hundred & Seventy Only
1.23	Supply of Recessed mounting 2' x 2' LED panel Luminaire, 36W, IP 20, 6500K CRCA deep-drawn housing suitable for 600 mm X 600 mm modular ceiling complete as per technical specifications.	Item 23	10	Each	2035.00	20350.00	INR Twenty Thousand Three Hundred & Fifty Only
1.24	Supply of Recessed mounting 2' x 2' LED panel Luminaire, 36W, IP 20, 6500K CRCA deep-drawn housing suitable for 600 mm X 600 mm modular ceiling having battery back up complete as per technical specifications. (Make : eveready model :LEDPLB036I6-04BB or Equivalent).	Item 24	10	Each	2750.00	27500.00	INR Twenty Seven Thousand Five Hundred Only
1.25	Supply of 35 Watt LED type Road/ Street light with minimum protection level IP 66, pressure die cast housing with epoxy power coated prismatic poly carbonate cover with individual LED lenses and complete assembly with LED, driver and accessories pre-wired up to terminal block i/c suitable mounting accessories etc. as required.	Item 25	6	Each	2115.00	12690.00	INR Twelve Thousand Six Hundred & Ninety Only
1.26	Installation, testing and commissioning of pre-wired, LED fitting of all types, complete with all accessories etc. directly on/in ceiling/ wall, including connection with 1.5 Sq.mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	Item 26	19	Each	100.00	1900.00	INR One Thousand Nine Hundred Only
1.27	Fixing of LED street light fitting on pole / wall including supply and bending the 40mm medium class GI pipe upto 2.5 mtr length to the required shape, iron clamps with nuts, bolts and washer, painting the flat iron with primer and finish paint including connection with 1.5 Sq.mm PVC insulated copper conductor single core cable, testing and commissioning complete as required.	Item 27	6	Each	745.00	4470.00	INR Four Thousand Four Hundred & Seventy Only
1.28	Supply of 1200 mm sweep five star BLDC ceiling fan of rating from 26 watt to 32 watt and all standard accessories etc., complete as required.(Havells , Model no.FHCEO5SWHT48 or equivalent)	Item 28	4	Each	2500.00	10000.00	INR Ten Thousand Only
1.29	Installation, testing and commissioning of ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 Sq.mm FRLSH PVC Insulated, copper conductor, single core cable etc. as required.	Item 29	4	Each	105.00	420.00	INR Four Hundred & Twenty Only
1.3	Supply and fixing of 12 W fully Automatic Emergency LED Light having back up time of 3 hours complete with standard accessories all as required. Make: Prolite or AAI preferred make list.	Item 30	3	Each	2890.00	8670.00	INR Eight Thousand Six Hundred & Seventy Only
1.31	Supply and Installation of Astro digital time switch suitable for single phase 240V AC for lighting control based on sunrise/sunset timings by latitude/longitude settings. (Make: L&T ; Model : DHTQB01016 or Equivalent) (Time switch is to be installed near street light DB of DVOR building)	Item 31	1	Each	2075.00	2075.00	INR Two Thousand & Seventy Five Only
1.32	Supply & Fixing of 230 Volt , 50 Hz industrial heavy duty exhaust fan having 300 mm sweep, 1400 rev/minute including Installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required.	Item 32	2	Each	2465.00	4930.00	INR Four Thousand Nine Hundred & Thirty Only
1.33	Supply of LED type Aviation Obstruction light as per ICAO requirement.(bajaj model no BGJV 302 or equivalent)	Item 33	2	Each	2500.00	5000.00	INR Five Thousand Only


 22/04/2025
 AEM (EF)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE including all taxes, duties etc. but excluding GST. In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. (excluding GST)	TOTAL AMOUNT in Rs. (excluding GST) In Words
1	2	3	4	5	6	7	8
2	SH:II - SITC of Earthing , LA , SPD.						
2.01	SITC of Three Phase modular type Surge Protection Device (CLASS- B,1,Stage-1/primary) with minimum lightning impulse current (Iimp) of 100KA (10/350 micro seconds) neutral to earth, 50 KA (10/350 micro sec) line to neutral ,limiting voltage less than 1.5 KV,to be installed in parallel at the mains panel of power entry point including making connection of surge protection device in parallel to the busbar of the main electrical panel using 16 Sq mm single core PVC insulated flexible copper conductor cables, in IP55 grade powder coated metal enclosure with 63 Amp. service / bypass changeover switch, on the mains power entry point at the incomers including all accessories such as suitable rating , MCBs, making end terminations, fixing/mounting arrangement of SPD , modifications in the existing panels by cutting the section,wiring/cable connection modification if required as per the site requirement etc complete as required as per enclosed specification.	Item 34	1	Each	51000.00	51000.00	INR Fifty One Thousand Only
2.02	SITC of Single Phase modular type Surge Protection Device (CLASS- B,1,Stage-1/primary) with minimum lightning impulse current (Iimp) of 100KA (10/350 micro seconds) neutral to earth, 50 KA (10/350 micro sec) line to neutral ,limiting voltage less than 1.5 KV,to be installed in parallel at the mains panel of power entry point including making connection of surge protection device in parallel to the busbar of the main electrical panel using 16 Sq mm single core PVC insulated flexible copper conductor cables, in IP55 grade powder coated metal enclosure with 63 Amp. service / bypass changeover switch, on the mains power entry point at the incomers including all accessories such as suitable rating , MCBs, making end terminations, fixing/mounting arrangement of SPD , modifications in the existing panels by cutting the section,wiring/cable connection modification if required as per the site requirement etc complete as required as per enclosed specification.	Item 35	1	Each	37500.00	37500.00	INR Thirty Seven Thousand Five Hundred Only
2.03	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc.with charcoal/ coke and salt as required.	Item 36	3	Set	4500.00	13500.00	INR Thirteen Thousand Five Hundred Only
2.04	Providing and fixing 25 mm X 5 mm GI strip in 40 mm dia G.I. pipe from earth electrode including connection with GI nut, bolt, spring, washer excavation and re-filling etc. as required.	Item 37	30	Meter	315.00	9450.00	INR Nine Thousand Four Hundred Only
2.05	Providing and fixing 25 mm X 5 mm GI strip on surface or in recess for connections etc. as required.	Item 38	30	Meter	115.00	3450.00	INR Three Thousand Four Hundred Only
2.06	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	Item 39	4	Set	6000.00	24000.00	INR Twenty Four Thousand Only
2.07	Providing and fixing of lightning conductor finial, made of 25 mm dia 300 mm long, G.I. tube, having single prong at top, with 85 mm dia 6 mm thick G.I. base plate including holes etc. complete as required.	Item 40	2	Each	315.00	630.00	INR Six Hundred & Thirty Only
2.08	Supplying and fixing of Medium class G.I. pipe of 50 mm dia. (nominal) 02 metres length and to be grouted on concrete foundation with installation including base plate , nut bolts , washer etc complete as required on the roof.	Item 41	4	Each	1500.00	6000.00	INR Six Thousand Only
2.09	Providing and fixing G.I. tape 20 mm X 3 mm thick on parapet or surface of wall for lightning conductor complete as required. (For horizontal run)	Item 42	30	Meter	60.00	1800.00	INR One Thousand Eight Hundred Only
2.1	Providing and fixing G.I. tape 20 mm X 3 mm thick on parapet or surface of wall for lightning conductor complete as required. (For vertical run)	Item 43	30	Meter	95.00	2850.00	INR Two Thousand Eight Hundred & Fifty
2.11	Providing joints by using brazing technique on 25 mm X 3 mm copper strip on surface or in recess for connections to another copper earth strip for interconnection to all earth's of Lightening Arrestors, counterpoise , Equipment and Electrical power supply earthing etc. as required.	Item 44	200	Each	205.00	41000.00	INR Forty One Thousand Only

24/04/2025
A.M (E.E)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE including all taxes, duties etc. but excluding GST. In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. (excluding GST)	TOTAL AMOUNT in Rs. (excluding GST) In Words
1	2	3	4	5	6	7	8
2.12	Supply of Copper Plate of Size 600 mm x 600 mm x 3.15 mm thickness of purity not less than 90% complete as required	Item 45	17	Each	14000.00	238000.00	INR Two Lakh Thirty Eight Thousand
2.13	Supply of Copper strip of Size 25 mm x 5 mm thickness of purity not less than 90% complete as required.	Item 46	1000	Meter	1125.00	1125000.00	INR Eleven Lakh Twenty Thousand
2.14	Supply of Copper wire of atleast 4 mm dia. of purity not less than 90% complete as required	Item 47	400	Meter	145.00	58000.00	INR Fifty Eight Thousand
2.15	Supply of Copper rod of 1 inch dia and 5 feet length having 2 inch thread on one side and cone shape on other side of purity not less than 90% complete as required	Item 48	10	Each	8750.00	87500.00	INR Eighty Seven Thousand Five
2.16	Supply of 70 Sqmm HRFR PVC Insulated Copper conductor flexible cable suitable for 1.1 kv confirming to IS:694 of green color complete as required	Item 49	200	Meter	815.00	163000.00	INR One Lakh Sixty Three Thousand
2.17	Supply of 4 inch (100 mm) dia medium class GI pipewith suitable GI base plate to mount 4-inch GI pipe complete as required.	Item 50	12	Meter	1600.00	19200.00	INR Nineteen Thousand Two Hundred Only
2.18	Supply of 2 inch (50 mm) dia medium class GI pipe having minimum thickness 3 mm alongwith the required socket from 2 inch to 1 inch complete as required.	Item 51	36	Meter	1350.00	48600.00	INR Forty Eight Thousand Six Hundred Only
2.19	Supply of 40 mm dia dia perforated and 10 feet length GI pipe for earthing having minimum thickness of 3 mm complete as required.	Item 52	17	Each	975.00	16575.00	INR Sixteen Thousand Five Hundred & Seventy Five Only
2.2	Supply of UV resistant PVC pipe of 2 inch dia and 20 feet length complete as required	Item 53	50	Each	1875.00	93750.00	INR Ninety Three Thousand
2.21	Supply of Heavy duty PVC pipe (plastic corrugated hose) of 4 inch dia complete as required.	Item 54	20	Meter	250.00	5000.00	INR Five Thousand
2.22	Supply of Heavy duty PVC pipe (plastic corrugated hose) of 2 inch dia complete as required.	Item 55	90	Meter	97.00	8730.00	INR Eight Thousand
2.23	Supply of granular salt having approx size of 1-3 cm complete as required.	Item 56	4250	Kg	5.00	21250.00	INR Twenty One Thousand
2.24	Supply of granular Charcoal having approx size of 1-3 cm complete as required.	Item 57	4250	Kg	7.00	29750.00	INR Twenty Nine Thousand
2.25	Supply of 150mm width x 50 mm depth x 1.6 mm thickness hot dipped GI cable raceway (Galvanisation thickness shall not be less than 50 microns) alongwith L and T joint complete as required.	Item 58	15	Meter	485.00	7275.00	INR Seven Thousand Two Hundred & Seventy Five Only
2.26	Supply of 150mm width x 50 mm depth x 1.6 mm thickness hot dipped GI perforated cable tray (Galvanisation thickness shall not be less than 50 microns) with perforation not more than 17.5% alongwith L and T joint complete as required.	Item 59	15	Meter	405.00	6075.00	INR Six Thousand & Seventy Five Only
2.27	Supply of extension board having 4 x 5/15 amp with individual switch with 30 meter 3x1.5 sqmm PVC sheather copper conductor cable complete as required.	Item 60	2	Each	1750.00	3500.00	INR Three Thousand Five Hundred Only
2.28	Supply of 16 Amps 3-Pin Top complete as required.	Item 61	10	Each	115.00	1150.00	INR One Thousand One Hundred Only
2.29	Supply of 3x2.5 Sqmm Copper conductor flexible cable as per IS 694 complete as required.	Item 62	40	Meter	145.00	5800.00	INR Five Thousand Eight Hundred Only
2.3	Supply of 4x16 Sqmm Cu Flexible Cable as per IS 694 complete as required	Item 63	100	Meter	1135.00	113500.00	INR One Lakh Thirteen Thousand
3	SH: III - Supply and Laying of Cable, HDPE Pipe, LT panel						
3.01	Supply of 3.5CX 240 sq.mm size of XLPE Insulated, PVC sheathed, aluminium conductor, armoured, power cable of 1.1 KV grade conforming to IS 7098 (Part I), 1988 amended upto date complete as required.	Item 64	2600	Mtr	1600.00	4160000.00	INR Forty One Lakh Sixty Thousand
3.02	Supply of 110mm (OD-110mm, PN 8, PE 80) ISI marked HDPE pipe, conforming to IS 4984, along with all accessories like socket, bend, couplers as required including fitting, cutting, jointing etc., etc. complete in all respect as per direction of Engineer-in-Charge. required.	Item 65	2600	Mtr	440.00	1144000.00	INR Eleven Lakh Forty Four Thousand Only

Jul 20/04/2025
AQM (E/S)


NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE including all taxes, duties etc. but excluding GST. In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. (excluding GST)	TOTAL AMOUNT in Rs. (excluding GST) In Words
1	2	3	4	5	6	7	8
3.03	Laying of 110 mm (OD-110mm,PN 08,PE 80) ISI marked HDPE pipe, along with all accessories like socket, bend, couplers, suitable size PP rope as required including fitting, cutting, jointing with HDD trenchless method direct in ground (up to 3 mtrs below ground level) in all type of soil etc complete in all respect as per direction of Engineer-in-Charge. required.	Item 66	2500	Mtr	550.00	1375000.00	INR Thirteen Lakh Seventy Five Thousand Only
3.04	Laying of 110 mm (OD-110mm,PN 08,PE 80) ISI marked HDPE pipe, along with all accessories like socket, bend, couplers, suitable size PP rope as required including fitting, cutting, jointing direct in ground (up to 75cm below ground level) in all type of soil i/c excavation & re-filling the trench but excluding sand cushioning and protective covering etc complete in all respect as per direction of Engineer-in-Charge. required.	Item 67	100	Mtr	90.00	9000.00	INR Nine Thousand Only
3.05	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of Above 185 sq. mm and upto 400 sq. mm size in the existing RCC/ HUMER/ METAL/DWC-HDPE pipe as required	Item 68	2600	Mtr	70.00	182000.00	INR One Lakh Eighty Two Thousand
3.06	Supplying and making end termination with brass compression gland and aluminium/copper lugs for 3.5 X 240 sq. mm (62 mm) - Aluminium size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.	Item 69	6	Set	750.00	4500.00	INR Four Thousand Five Hundred Only
3.07	Design, Supply, Installation, Testing & Commissioning of Indoor Type, Floor Mounted compartmentalized cubical type panel board of 415 Volt (Nominal), fabricated out of 2 mm (14 SWG) thick CRCA Sheet, free standing and totally enclosed, IP42, Weather proof / dust proof / vermin proof with bottom / top cable entries and cable alleys. The panel board shall be suitable for operation on 3 Phase, 4 wire, 50 Hz AC Supply and with suitable size busbar, earth bar and following switchgear instrumentation and protection devices etc. complete with connections, interconnection, earthing, painting and marking as per site conditions etc complete as required as per the specifications. Supplier must take LT Panel Design Approval from EIC before the supply. (i) Incomer: 160A, MCCB, 4P, 35-37 KA (Icu= 100% Ics) with extended rotary handle and spreaders - 02 Nos. Multi function Meter (Shows Voltage, Current & Frequency) with 3 line LCD/LED Display of size 96 x 96 mm. - 02 Nos.,Indication Lamp R, Y & B (LED Type) -02 set, (ii) Buscoupler : 160A, MCCB, 4P, 35-37 KA (Icu= 100% Ics) with extended rotary handle and spreaders - 01 No. with ON, OFF indication lamp. Outgoing: 63A, MCCB, 4P, 25 KA (Icu= 100% Ics) with extended rotary handle - 08 Nos.,Indication Lamp R & G (LED type) - 08 Set, 200A Aluminium busbar, 3 Phase & Neutral,Electrically & Mechanically interlocked with Mechanical key lock (3 Lock +2 Key), Necessary CT & Control wiring arrangement , Power terminal and other accessories . The Bus bar chamber size shall be suitable for connection of 3.5x 240 Sqmm size Incoming cable.	Item 70	1	Job	200000.00	200000.00	INR Two Lakh Only


 22/04/2025
 Agm (EE)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE including all taxes, duties etc. but excluding GST. In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. (excluding GST)	TOTAL AMOUNT in Rs. (excluding GST) In Words
1	2	3	4	5	6	7	8
3.08	Design, Supply, Installation, Testing & Commissioning of Outdoor Type, Floor Mounted compartmentalized cubical type panel board of 415 Volt (Nominal), fabricated out of 2 mm thick CRCA Sheet, free standing and totally enclosed, IP66, Weather proof / dust proof / vermin proof with bottom / top cable entries and cable alleys. The panel board shall be suitable for operation on 3 Phase, 4 wire, 50 Hz AC Supply and with suitable size busbar, earth bar and following switchgear instrumentation and protection devices etc. complete with connections, interconnection, earthing, painting and marking as per site conditions etc complete as required as per the specifications. Supplier must take LT Panel Design Approval from EIC before the supply. (i) Incomer: 160A, MCCB, 4P, 35-37 KA (Icu= 100% Ics) with extended rotary handle and spreaders - 02 Nos. Multi function Meter (Shows Voltage, Current & Frequency) with 3 line LCD/LED Display of size 96 x 96 mm. - 02 Nos., Indication Lamp R, Y & B (LED Type) -02 set, (ii) Buscoupler : 160A, MCCB, 4P, 35-37 KA (Icu= 100% Ics) with extended rotary handle and spreaders - 01 No. with ON, OFF indication lamp. Outgoing: 63A, MCCB, 4P, 25 KA (Icu= 100% Ics) with extended rotary handle - 04 Nos., Indication Lamp R & G (LED type) - 04 Set, 200A Aluminium busbar, 3 Phase & Neutral, Electrically & Mechanically interlocked with Mechanical key lock (3 Lock +2 Key), Necessary CT & Control wiring arrangement , Power terminal and other accessories . The Bus bar chamber shall be suitable for connection of 3.5x 240 Sqmm size incoming cable.	Item 71	1	Job	175000.00	175000.00	INR One Lakh Seventy Five Thousand Only
3.09	Supply and fixing of 5KVA-02 (1+1) single phase 230V online UPS system alongwith 26 Ah± 10% Battery- (1+1) with 30 minute back up as per technical specifications complete as required.	Item 72	1	Job	250000.00	250000.00	INR Two Lakh Fifty Thousand Only
3.1	Supply and fixing of insulation mats for electric shock protection of 2 mm thickness x 1 m wide polysynthetic mats conforming to IS 15652 : 2006, Class - A up to 3.3 KV along with suitable adhesive etc complete as required.	Item 73	30	Mtr	1540.00	46200.00	INR Forty Six Thousand Two Hundred Only
3.11	Supply Installation Testing and commissioning of IP65 MI combinable type Bus Bars Junction Box with 250 amps Al. bus bars, should be made of high quality Polycarbonate PC-GFS (totally Insulated class II) (shock proof, rust free, corrosion free, acid and chemical resistant, fire retardant, having high impact, made of halogen and silica free recyclable material), UV resistant, having high grade gasket made of Polyurethane, should withstand glow wire test at 9600C, should be flame retardant, materials suitable for outdoor application and the enclosure should have pre-moulded knock out for cable entry on side walls and enclosure should have PC hinged option. For cable entry from bottom part a de-touchable type PC flange should be fitted with plain wall. The plain wall of flange can be drilled as per cable size. Lid screws should be made of polyamide spring loaded half turn type and to open a triangular key or tool will be required. Inside enclosure should have lot of self-threaded holes so that mounting plate/bus bars can be mounted easily. Degree of Protection : IP 65 _Busbar rating: 250A (RYBN: 30 X 06) MM CU Dimensions : 500 [L] x 1075 [H] x 630 [D] mm_ Given Cable Size : 3.5C X 240 Sq.mm Al. Cable (Loop In / Loop Out) Mounting Type : Outdoor / Floor Mounting (FRP Frangible Frame)	Item 74	6	Each	13750.00	82500.00	INR Eighty Two Thousand Five Hundred Only
3.12	Providing and fixing of 100 A Change over switch along with Metal Enclosure and required bus bar with DIN type 4 fuses suitable to terminate the 240 Sq.mm cable as incomer (02 nos) and 240 Sq.mm Cable as outgoing complete as required.	Item 75	1	Job	9000.00	9000.00	INR Nine Thousand Only

Agm
22/04/2025
Agm (EF)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE including all taxes, duties etc. but excluding GST. In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. (excluding GST)	TOTAL AMOUNT in Rs. (excluding GST) In Words
1	2	3	4	5	6	7	8
3.13	SITC of 100A, 3phase, 415VAC, four pole, solenoid based Automatic Transfer Switch (changeover time range 0.1 - 6 seconds programmable) with Microprocessor based Programmable controller for monitoring and storing electrical parameters of power supply, and optically isolated RS 485 Interface including dismantling of existing ATS from the existing housing, fixing of new ATS in existing housing including modification in the housing if required, laying and connection of power cables, supply and laying of Modbus serial communication cables for interconnection between ATS controller and gateway, connection of CT, suitable for existing air conditioning, lighting & UPS load etc. complete as per the site requirement.	Item 76	1	Job	98500.00	98500.00	INR Ninety Eight Thousand Five Hundred Only
3.14	SITC of 3 phase Multi functional meter for measuring Line Voltage, Phase Voltage, Line Current, Frequency, Watts, power factor, VA, Watt hour with RS 485 serial Interface and optically isolated, 50A Clip on CT's, including all other works such as fixing of Multi functional meters in distribution panel by cutting face plate of distribution panel, laying and connection of power cables, supply and laying of Modbus serial communication cables for interconnection between Multifunctional Meters and gateway, connection of CT, wiring etc. complete as per the site requirement.	Item 77	4	Job	6000.00	24000.00	INR Twenty Four Thousand Only
3.15	SITC of Temperature monitor with RS 485 serial Interface and optically isolated including all other works such as fixing of Temperature sensors in remote room, laying and connection of power cables, supply and laying of Modbus serial communication cables for interconnection between Temperature Sensor monitor and gateway, connection of sensor, wiring etc. complete as per the site requirement.	Item 78	1	Job	7500.00	7500.00	INR Seven Thousand Five Hundred Only
3.16	SITC of gateway for the serial interface of existing RS 485 to GPRS with included LTE 4G sim having one year internet plan subscription for cloud based remote monitoring with inbuilt 16GB memory for data backup including wall mounted enclosure/housing for housing the same gateway and all other activities such as fixing of gateway in provided wall mounted enclosure/housing, laying and connection of power cables, connection of communication cables, wiring etc. complete as per the site requirement.	Item 79	1	Job	105000.00	105000.00	INR One Lakh Five Thousand Only
3.17	SITC of Line Interactive UPS with Load Capacity of minimum 600VA and having Input voltage range 140-300VAC, 50 Hz, 230VAC Output voltage, inbuilt battery of capacity 12V 17AH for supplying power backup to Multi Functional Meters and Gateway.	Item 80	1	Job	5500.00	5500.00	INR Five Thousand Five Hundred Only
3.18	Interfacing of item no. 76 to item no. 80 including providing and commissioning of totally hiring based and Cloud based Energy Monitoring Software with Programming, required Licencing, facility of data logging, remote monitoring, event notification system (Max. 5 minutes delay interval between two successive readings), Auto SMS, Email Alert Feature for any abnormal deviation of pre-set electrical parameters range of the power supply at the site etc. with five year subscription of cloud based energy management system, site support etc. complete as required.	Item 81	1	Job	5000.00	5000.00	INR Five Thousand Only
3.19	Supplying and laying 6 SWG G.I. wire at 0.50 metre below ground level for conductor earth electrode, including connection/ termination with GI thimble etc. as required.	Item 82	2600	Meter	20.00	52000.00	INR Fifty Two Thousand Only
4	SH: IV - SITC of Air Conditioning System						
4.01	Supply of 5 Star rating fully inverter split type Air conditioner of 1.5 TR (Minimum ISEER 4.5) capacity with adjustable mode different cooling capacities for different cooling needs, fitted with rotary/scroll compressor of min 05 years warranty, having copper condenser coil, operating for Refrigerant R32/other eco friendly green gas and indoor unit suitable for wall mounting operation with cordless LCD/LED Remote, Auto restart operation, connecting copper refrigerant pipes (with suitable nitrile insulation including charging of suitable refrigerant gas, 4C x 4 Sq.mm copper cable, drain pipe) up to 3Mtr. and suitable for operating on 230V ±10%, 50Hz, Single Phase, AC, control wiring, thermostat, washable synthetic air filter etc. complete as capable of performing Cooling, Dehumidifying, Air Circulating, Filtering functions, stabilizer free operation etc. meeting the technical specifications and make as per the list of approved make. Note:- The AC units shall be rust proof coating in cooling coil and condensor.	Item 83	9	Each	40000.00	360000.00	INR Three Lakh Sixty Thousand Only


 21/04/2025
 Anil (E)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE including all taxes, duties etc. but excluding GST. In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. (excluding GST)	TOTAL AMOUNT in Rs. (excluding GST) In Words
1	2	3	4	5	6	7	8
4.02	Installation, Testing and Commissioning of split type Air conditioner of upto and including 1.5TR capacity and fixing of refrigerant copper piping of suitable size for both suction and discharge along with suitable nitrile / thermal insulation and Electrical Cable (4C x 4 Sq.mm) of size having suitable size of copper conductor for connection from indoor to outdoor unit including charging of suitable refrigerant gas, providing mounting stand for out door unit and all suitable necessary accessories complete as per site requirement.	Item 84	9	Each	2525.00	22725.00	INR Twenty Two Thousand Seven Hundred & Twenty Five Only
4.03	Supply & Fixing of Extra Refrigerant copper piping for 1.5 TR A.C of suitable size for both suction and discharge along with suitable thermal insulation and Electrical Cable of suitable size copper conductor for connection from indoor to outdoor unit and suitable necessary accessories for connection complete as required. (One length of suction piping , one length of discharge piping and one length of copper wire shall be measured one meter for this item)	Item 85	50	Mtr	910.00	45500.00	INR Forty Five Thousand Five Hundred Only
4.04	Supply and fixing of 75mm dia medium class PVC pipe for covering refrigerant copper piping for both suction , discharge and Electrical Cable with suitable necessary accessories for pipe connection complete as required.	Item 86	50	Mtr	152.00	7600.00	INR Seven Thousand Six Hundred Only
4.05	Supply and fixing of hard UPVC drain pipe of 25 mm dia connection from indoor to outside of wall including bends, suitable insulation , U straps , clamps and necessary accessories for connection etc. complete as required.	Item 87	50	Mtr	157.00	7850.00	INR Seven Thousand Eight Hundred & Fifty Only
4.06	Supply and fixing of 5KVA, 15Amp / 130V-300V working voltage Digital electronics voltage stabilizer of wall mounting type with Instant Start and Intelligent time delay provisions suitable for 1.5 TR Split AC units. (Make : V-guard Model : VGB500 Digital/ Make: Everest Model: EWD 500 or its Equivalent from AAI approved make list)	Item 88	9	Each	2500.00	22500.00	INR Twenty Two Thousand Five Hundred Only
4.07	Supply & fixing of of Timer with 2 hr/4 hr / 8 hr duration and having digital temp. controller & sensor suitable for AC power supply 240 V, 50 Hz. etc. complete as required. (Make: Smart Electronics Model: TIM 2T or equivalent)	Item 89	4	Each	2500.00	10000.00	INR Ten Thousand Only
5	SH: V-SITC of Fire Alarm & Fire Suppression System						
5.01	Supplying & laying of 2x1.5 sqmm fire survival armoured cable, 600/1000V rated with annealed copper conductor having glass mica fire barrier tape covered by an extruded layer of Cross Linkable Ethylene Propylene Rubber (EPR) insulation and LSZH inner bedding, steel wire armouring & LSZH outer sheath complete as required.	Item 90	100	Meter	105.00	10500.00	INR Ten Thousand Five Hundred Only
5.02	Supplying, installation, testing & commissioning of IP based Addressable fire alarm panel, LCD display, suitable for 01 loop, complying relevant national fire alarm code for local fire alarm system with mimic diagram for all area / zone covered, complete with all connections. The panel shall have input of 240 volts AC power supply, inbuilt automatic battery charger, 24volts, 2X12volts, 7Ah sealed lead acid maintenance free batteries sufficient for 24 hours normal power backup & working, interconnections. The panel shall be UL / EN / FM listed and along with GSM auto dialer facility (20 Nos min.) etc. as required.	Item 91	1	Each	227250.00	227250.00	INR Two Lakh Twenty Seven Thousand Two Hundred & Fifty Only
5.03	Supply, Installation, Testing & commissioning of UL / EN listed (latest version) addressable Smoke detector base and with unique optical sensing chamber, visible LED, fully coated circuit board, superior RF / Transient protection suitable for 2 wires loop connection, complete with plug into common separate base & housing constructed of LEXAN (or polycarbonate) complete with connections etc. as required and to be installed below / above false ceiling roof and concealed space and as per enclosed specifications ,complete as required. (Cost of plug in common base shall deemed to be included in cost of detectors).	Item 92	10	Each	3333.00	33330.00	INR Thirty Three Thousand Three Hundred & Thirty Only

24/04/2025
AGM (EE)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE including all taxes, duties etc. but excluding GST. In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. (excluding GST)	TOTAL AMOUNT in Rs. (excluding GST) In Words
1	2	3	4	5	6	7	8
5.04	Supply, Installation, Testing & commissioning of UL / EN listed (latest version) Addressable Manual call station (Resetable pull / push type) suitable for semi flush mounting, IP 54 for Indoor use & IP 65 for outdoor use with inbuilt fault isolator / Isolator module with double gang outlet box, equipment for key operated test-reset lock. Manual pull station shall be connected with two wire to SLC loop of Fire Control Panel. Cover shall be made out of LEXAN (or poly carbonate equivalent) with clear operating instruction and the word Fire appearing on the front complete with connections etc. as required and as per enclosed specifications.	Item 93	2	Each	4545.00	9090.00	INR Nine Thousand & Ninety Only
5.05	Supply, installation, testing and commissioning of UL / EN listed (latest version) Hooter-cum- strobe with inbuilt fault isolator / isolator module with adjustable sound level in the range of min. 90 db to Max. 120 db at 1M distance complete with termination etc. as required and as per enclosed specification.	Item 94	1	Each	2121.00	2121.00	INR Two Thousand One Hundred & Twenty One Only
5.06	SITC of 4.5 kg Co2 type fire extinguisher wall mounting accessories etc complete as required.	Item 95	4	Each	3939.00	15756.00	INR Fifteen Thousand Seven Hundred & Fifty Six Only
5.07	SITC of 4.5 kg ABC type fire extinguisher wall mounting accessories etc complete as required.	Item 96	2	Each	2121.00	4242.00	INR Four Thousand Two Hundred & Forty Two Only
5.08	SITC of 2.8 kg Aerosole based automatic fire extinguishers along with complete system required to operate in case of fire complete as required.	Item 97	6	Each	103020.00	618120.00	INR Six Lakh Eighteen Thousand One Hundred & Twenty Only
5.09	SITC of 2 Zone Gas release panel complete with battery back up complete as required.	Item 98	3	Each	15150.00	45450.00	INR Forty Five Thousand Four Hundred & Fifty Only
5.1	SITC of conventional multi criteria type smoke detector complete as required.	Item 99	14	Each	1515.00	21210.00	INR Twenty One Thousand Two Hundred & Ten Only
5.11	SITC of Monitor Module complete as required.	Item 100	3	Each	3333.00	9999.00	INR Nine Thousand Nine Hundred & Ninety Nine Only
5.12	Supply and fixing of Aerosol fire Extinguishing Generator - 8 Gram	Item 101	16	Each	4848.00	77568.00	INR Seven Lakh Seven Thousand Five Hundred & Sixty Eight Only
5.13	Supply and fixing of Aerosol fire Extinguishing Generator - 20 Gram	Item 102	7	Each	12120.00	84840.00	INR Eighty Four Thousand Eight Hundred & Forty Only
6	SH: VI-SITC of DG Sets						
6.01	SITC of 4 wheel Trolley mounted (with jack arrangement) outdoor Mobile DG Set along with canopy of 25 KVA capacity complying the CPCB standards complete as required.	Item 103	1	Each	525000.00	525000.00	INR Five Lakh Twenty Five Thousand Only
6.02	Dismantling, Shifting, installation, testing and commissioning of existing 35 kVA DG Set of Mahindra make from Existing DVOR to New Location of DVOR at approx distance of 2 km by loading/ unloading by truck in operationla area complete as required.	Item 104	1	Job	25455.00	25455.00	INR Twenty Five Thousand Four Hundred & Fifty Five Only
Total in Figures						12687027.00	INR One Crore Twenty Six Lakh Eighty Seven Thousand & Twenty Seven Only
Quoted Rate in Words						INR One Crore Twenty Six Lakh Eighty Seven Thousand & Twenty Seven Only	

Signature Not Verified

Digitally signed by MADAN MOHAN AGRAWAL

Date: 2025.06.20 19:04:05 IST

Location: eProcurement System for Central PSU

Madan
27/06/2025

Agm (EG)

म.म.अग्रवाल/M.M.AGRAWAL

असि. जन. प्रबन्धक (अग्नि-वि)/Asstt. Gen. Manager(Engg.-Elect)

भारतीय विमानपत्तन प्राधिकरण/Airports Authority of India

विमानतल, सूरत/Surat Airport, Surat-394 550