



सन्दर्भ स: भा.वि.प्रा./ग्वा./उ.म.प्र.(अभि.-सि.)/परिधि सीमा/2025-26/क-1/26

दिनांक: 02.06.2025

सेवा में,

मेसर्स सृष्टि इन्फ्राइंजीनियरिंग प्रा. लिमिटेड,
1 ए, चन्द्र नगर, रेलवे ब्रिज के नीचे
गोपालपुरा बाईपास, जयपुर,
राजस्थान -302018
मो.- 9414051776, 9983315275
ई-मेल- shristiinfracengineering@gmail.com

To,

M/s Shristi Infraengineering Pvt. Ltd.,
1A, Chandra Nagar, Under Railway Bridge
Gopalpura Bypass, Jaipur,
Rajasthan-302018
Mob. - 9414051776, 9983315275
Email: shristiinfracengineering@gmail.com

विषय : ग्वालियर हवाई अड्डे पर बाहरी परिधीय नाले के साथ परिधि सीमा दीवार का निर्माण ।
(निविदा आईडी: 2025_AAI_228721_1)

Subject: Construction of Perimeter Boundary wall along external Peripheral nallah at Gwalior Airport. (Tender Id: 2025_AAI_228721_1)

संदर्भ: 1. आपकी वित्तीय बोली दिनांक 02.05.2025 को सीपीपी पोर्टल के माध्यम से खोली गई ।
Ref: 1. Your financial bid opened on dated 02.05.2025 through CPP Portal.

महोदय/Dear Sir(s),

1. उपर्युक्त निर्दिष्ट कार्य हेतु आपकी ई-निविदा को आपके द्वारा उद्धृत मद दरों पर कुल राशि रुपये 2,25,71,771.00 (रुपये दो करोड़ पच्चीस लाख इकहत्तर हजार सात सौ इकहत्तर मात्र) (जीएसटी रहित), जो कि निविदा की अनुमानित लागत रुपये 3,29,53,263.00 (तीन करोड़ उनतीस लाख तिरपन हजार दो सौ तिरसठ रुपये मात्र) (जीएसटी रहित) से 31.50 % कम है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से एतद द्वारा स्वीकार किया जाता है ।

Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totalling to Rs. 2,25,71,771.00 (Rupees Two Crore Twenty Five Lakhs Seventy One Thousands Seven Hundred Seventy One only) (excluding GST) which is 31.50% below the estimated cost put to tender of Rs. 3,29,53,263.00 (Rupees Three Crore Twenty Nine Lakhs Fifty Three Thousand Two Hundred Sixty Three only) (excluding GST).

2. उप महाप्रबंधक (अभि.-सिविल), भा.वि.प्रा., आर.वी.एस.टी. एअरपोर्ट, ग्वालियर कार्य के प्रभारी अभियंता होंगे । आपसे अनुरोध है कि आप उप महाप्रबंधक (अभि.-सिविल), आर.वी.एस.टी. एअरपोर्ट, ग्वालियर के कार्यालय में 11.06.2025 तक उपस्थित होकर अनुबंध समझौते पर हस्ताक्षर करें और उसे पूरा करें । अनुबंध समझौते को रुपये 100 (रुपये एक सौ मात्र) मूल्य के एक गैर-न्यायिक स्टाम्प पेपर पर निष्पादन किया जायेगा और स्टाम्प पेपर की लागत आपके द्वारा वहन की जाएगी ।

Deputy General Manager (Engg -C), A.A.I., R.V.S.T. Airport, Gwalior shall be the Engineer-in-charge of the work. You are requested to attend the office of Deputy General Manager (Engg-C), A.A.I. R.V.S.T. Airport, Gwalior, by 11.06.2025 to sign



and complete the Contract Agreement. The contract Agreement shall be executed on a non-judicial Stamp paper of value of Rs. 100/- (Rupees One Hundred Only) and the cost of the stamp paper shall be borne by you.

3. आपकी ई-निविदा के साथ प्राप्त रुपये 9,88,598.00 (रुपये नौ लाख अठासी हजार पांच सौ अठ्ठानवे मात्र) की बयाना राशि को निविदा दस्तावेज के पृष्ठ क्रमांक - 68 पर खंड संख्या- 1 (ए) के अनुसार सुरक्षा जमा के हिस्से के रूप में माना जायेगा और परिवर्तित किया जाएगा। इसके बाद अनुबंध की शर्त के अनुसार प्रत्येक रनिंग बिल से सुरक्षा जमा राशि वसूल की जाएगी। कृपया इस पत्र के जारी होने की तारीख से 10 दिनों के भीतर सुरक्षा जमा के रूप में रुपये 22,57,177.00 (रुपये बाईस लाख सत्तावन हजार एक सौ सतहत्तर मात्र) जमा करें। ऐसा न करने पर निविदा दस्तावेज के पृष्ठ क्रमांक - 68 पर खंड संख्या- 1 (ए) की शर्त के अनुसार इस राशि की कटौती की जाएगी।

The Earnest money amount of Rs. 9,88,598. 00 (Rupees Nine Lakhs Eighty-Eight Thousands Five Hundred Ninety Eight Only) received along with your tender will be treated and converted as part of Security deposit as per Clause no.-1 (A) on page no. 68 of tender document. Please deposit Rs. 22,57,177.00 (Rupees Twenty-Two Lakhs Fifty-Seven Thousands One Hundred Seventy Seven only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of clause no.- 1 (A) at page no. 68 of tender document.

4. आपसे अनुरोध है कि आप निविदा के जीसीसी के पृष्ठ संख्या 98-105 पर खंड 19 में निर्दिष्ट, ठेका श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और ठेका श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (प्रतिषेध और विनियमन) अधिनियम 1986, भवन और अन्य निर्माण श्रमिक (रोजगार और सेवा की शर्तों का विनियमन) अधिनियम, 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम, 1996, न्यूनतम मजदूरी अधिनियम 1948, कर्मचारी भविष्य निधि अधिनियम 1952 और ईएसआई अधिनियम 1948 के प्रावधानों और केंद्र और राज्य सरकार के नियमों का पालन करें।

You are requested to comply with the provision of contract labour (Regulation and Abolition) Act of 1970 and contract labour (Regulation and Abolition) Central Rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Building and Other Construction Workers (Regulation of Employment and Conditions of Service) Act, 1996, Building and Other Construction Workers' Welfare Cess Act, 1996, Minimum wages Act 1948, Employee provident fund Act 1952 and ESI Act 1948 as specified in clause 19 on page no 98-105 of GCC of Tender and rule of Central and State Government.

5. आपको वरिष्ठ प्रबंधक (अभि.-सिविल) भा.वि.प्रा., आर.वी.एस.टी. हवाई अड्डा, ग्वालियर से तुरंत संपर्क करने के लिए भी निर्देशित किया जाता है जो सम्बंधित कार्यस्थल को आपको सौंपने की व्यवस्था करेंगे।



You are also directed to contact Senior Manager (Engg.-Civil), A.A.I., R.V.S.T. Airport, Gwalior immediately who will arrange to hand over the site to you.

6. कृपया ध्यान दें कि कार्य करने के लिए अनुमानित अवधि 06 माह (45 दिन की बारिश सहित) होगा और इसे इस पत्र के जारी होने की दिनांक से दसवे दिन से संगणित किया जायेगा।

Please note that the time allowed for carrying out the work shall be 06 months (including 45 days rains) and same shall be reckoned from the tenth day from the date of issue of this letter.

7. कृपया पत्र प्राप्ति की रसीद को स्वीकार करें और स्वीकृति के प्रतीक के रूप में अधोहस्ताक्षरी को हस्ताक्षर करने के बाद इसके साथ संलग्न इस पत्र की डुप्लिकेट प्रति वापस कर दें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

8. इस कायदेशि की संख्या भा.वि.प्रा./ग्वा./उ.म.प्र.(अभि.-सि.)/परिधि सीमा/2025-26/क.१/२६ आवंटित की जाती है, जो आपके द्वारा इस कार्य आदेश के संबंध में भविष्य के सभी पत्राचार के लिए उद्धृत की जाएगी।

This work order is allotted the number भा.वि.प्रा./ग्वा./उ.म.प्र.(अभि.-सि.)/परिधि सीमा/2025-26/क.१/२६ which shall be quoted by you for all future correspondence in connection with this work order.

9. यह कायदेशि के साथ सभी शुद्धिपत्र, ई-निविदा प्रक्रिया के दौरान उठाए गए प्रश्न, स्पष्टीकरण आदि यदि कोई हों एवं उनके उत्तर, भी अनुबंध समझौते का हिस्सा होंगे

This work order along with all corrigendum, queries, clarifications etc., if any, raised during e-tendering process and replies thereof shall also form part of the contract agreement.

10. अनुबंध के संबंध में भविष्य में कोई भी अन्य पत्राचार सामान्यतः प्रभारी अभियंता, ग्वालियर हवाई अड्डे को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer In-Charge, Gwalior Airport.

11. कृपया पावती की सूचना दें तथा स्वीकृति के प्रतीक के रूप में इस पत्र की संलग्न दूसरी प्रति पर विधिवत हस्ताक्षर करने के उपरांत अधोहस्ताक्षरी को वापस भेजें।

Please acknowledge the receipt and return the enclosed duplicate copy of this letter after duly signing it, to the undersigned as a token of acceptance.



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

12. यदि हिन्दी अथवा अंग्रेजी संस्करण के बीच कोई विसंगति पाई जाती है, तो अंग्रेजी संस्करण ही मान्य होगा।

In case of any discrepancy found between Hindi or English version, then English version will prevail.

भवदीय/Your's faithfully,

(Handwritten signature)
26/5

(आभाष कुमार गोस्वामी)
(Abhash Kumar Goswami)
उप महाप्रबंधक (अभि.-सिविल),
Deputy General Manager (Engg-C)
रा.वि.सि.टी.विमानपत्तन, ग्वालियर,
R.V.S.T. AIRPORT. GWALIOR
अध्यक्ष., भा.वि.प्रा.के लिए उनके तरफ से,
For and on behalf of the Chairman, A.A.I.

Encl: 1. Schedule of Quantities -'A' (Pg no. 01 to 04)

Validate Print Help

Item Rate BoQ

Tender Inviting Authority: Senior Manager (Engg-Civil), AAI, Gwalior Airport

Name of Work: Construction of Perimeter Boundary wall along external peripheral nallah at Gwalior Airport.

Contract No: 2025_AAI_228721_1

Name of the Bidder/ Bidding Firm / Company : SHRISTI INFRAENGINEERING PVT.LTD.

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	3790.00	cum	100.00	379000.00	INR Three Lakh Seventy Nine Thousand Only
2	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. Ordinary rock	350.00	cum	500.00	175000.00	INR One Lakh Seventy Five Thousand Only
3	Supplying, filling, spreading gravels of size range 5 mm to 10 mm in required thickness including ramming, compacting and dressing complete., for all leads & lifts. all complete as per direction of Engineer-in-charge.	1060.00	cum	400.00	424000.00	INR Four Lakh Twenty Four Thousand Only
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources).	178.00	cum	3500.00	623000.00	INR Six Lakh Twenty Three Thousand Only

308
21/6/24
mye (RT)

Sm (F-2)
02/09/25

For
26
3-01-24-2024

5	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works upto plinth level Concrete of M25 grade with minimum cement content of 330 kg /cum.	850.00	cum	5000.00	4250000.00	INR Forty Two Lakh Fifty Thousand Only
6	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 and for all lift.	1730.00	Cum	120.00	207600.00	INR Two Lakh Seven Thousand Six Hundred Only
7	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works above plinth level upto floor V level Concrete of M25 grade with minimum cement content of 330 kg /cum	80.00	cum	5200.00	416000.00	INR Four Lakh Sixteen Thousand Only
8	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete.	1485.00	sqm	150.00	222750.00	INR Two Lakh Twenty Two Thousand Seven Hundred & Fifty Only
9	Centering and shuttering including strutting, propping etc. and removal of form for : Lintels, beams, plinth beams, girders, bressumers and cantilevers.	1490.00	sqm	175.00	260750.00	INR Two Lakh Sixty Thousand Seven Hundred & Fifty Only
10	Centering and shuttering including strutting, propping etc. and removal of form for : Columns, Pillars, Piers, Abutments, Posts and Struts.	1470.00	sqm	200.00	294000.00	INR Two Lakh Ninety Four Thousand Only
11	Centering and shuttering including strutting, propping etc. and removal of form work for : retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc.	260.00	sqm	500.00	130000.00	INR One Lakh Thirty Thousand Only
12	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	102000.00	kg	69.90	7129800.00	INR Seventy One Lakh Twenty Nine Thousand Eight Hundred Only

216/25
MPL/BSG

Sm(GC)
02/06/25

246
12.07.2025

13	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500 D or more.	9600.00	kg	69.96	671616.00	INR Six Lakh Seventy One Thousand Six Hundred & Sixteen Only
14	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand).	260.00	cum	5600.00	1456000.00	INR Fourteen Lakh Fifty Six Thousand Only
15	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand).	221.00	cum	5600.00	1237600.00	INR Twelve Lakh Thirty Seven Thousand Six Hundred Only
16	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand).	1550.00	sqm	150.00	232500.00	INR Two Lakh Thirty Two Thousand Five Hundred Only
17	12 mm cement plaster of mix : 1:6 (1 cement: 6 Coarse sand).	2060.00	sqm	170.00	350200.00	INR Three Lakh Fifty Thousand Two Hundred Only
18	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 coarse sand)	2060.00	sqm	200.00	412000.00	INR Four Lakh Twelve Thousand Only
19	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm)	5670.00	sqm	115.00	652050.00	INR Six Lakh Fifty Two Thousand & Fifty Only
20	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	1030.00	Mtr	280.00	288400.00	INR Two Lakh Eighty Eight Thousand Four Hundred Only
21	Cutting holes of required size in brick masonry wall for fixing and providing 110 mm dia PVC pipe in inclined direction and making good the same etc. complete as per direction of Engineer-in-charge.	1750.00	each	115.00	201250.00	INR Two Lakh One Thousand Two Hundred & Fifty Only
22	Lettering with Synthetic enamel paint of approved brand and manufacture.	14000.00	per letter per cm height	4.00	56000.00	INR Fifty Six Thousand Only
23	Designing, Providing, fixing of 30 mm Thick GFRG Screen (panel with design) with acrylic Paint Cladding:GFRG is a form of concrete that uses fine sand, cement, polymer (usually an acrylic polymer), water, other admixtures and alkali-resistant (AR) glass fibers. The nominal thickness would be 20mm with additional stiffeners at the perimeter or any embedded studs for ease in installation.TiO2 shall be added in the mix for better performance. Materials used for making the GRC unit shall be generally comply with relevant standards or be approved by the Engineer-in-Charge. Note:- Thickness of GFRG sheet is including of thickness of embossing.	450.00	Sqm	4000.00	1800000.00	INR Eighteen Lakh Only

30/06/25
mgk/18-4

30/06/25
mgk/18-4

30/06/25
mgk/18-4

24	Providing and fixing machine moulded aluminium covering of approved pattern & design, made out of machine cut aluminium sheet and machine holed for receiving dash fastener, over expansion joints on vertical surfaces/ceiling floors, the fixing on plate in one row on one side of joint only shall be done with stainless steel dash fasteners of 8 mm dia and 75 mm long bolt including providing aluminium washers 2 mm thick & 15 mm dia , at a staggered pitch of 200 mm centre to centre including drilling holes in the receiving surface and providing expandable plastic sleeves in holes etc. complete as per direction of Engineer-in-charge. a) Powder coated aluminium sheet 2.5 mm thick (minimum thickness of powder coating 50 micron)	175.00	kg	400.00	70000.00	INR Seventy Thousand Only
25	Providing and applying of swellable type water stop tape, 19 mm x 25 mm thick in linear metre (expansive nature) for construction joints treatment of RCC structure such as raft slab, retaining walls, water storage tank and at the junctions of raft slab with the retaining walls etc.. After cleaning the surface, one coat of required primer for swellable water stop tape shall be applied throughout the length of the joint @3.78 litre per 240 running metre. Over the primed surface swellable type water stop tape shall be placed. The work shall be carried out all complete as per specification and the direction of the Engineer-In-Charge. The product performance shall carry guarantee for 10 years against any leakage.	320.00	Mtr	340.00	108800.00	INR One Lakh Eight Thousand Eight Hundred Only
26	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	3620.00	kg	100.00	362000.00	INR Three Lakh Sixty Two Thousand Only
27	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge Nominal concrete 1:3:6 or richer mix (including equivalent design mix)	100.00	Cum	745.00	74500.00	INR Seventy Four Thousand Five Hundred Only
28	Dismantling barbed wire or flexible wire rope in fencing including making rolls and stacking within 50 metres lead.	680.00	kg	5.00	3400.00	INR Three Thousand Four Hundred Only
29	Dismantling steel work in single sections including dismembering and stacking within 50 metres lead in: Channels, angles, tees and flats.	2555.00	kg	1.00	2555.00	INR Two Thousand Five Hundred & Fifty Five Only
30	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	21.00	Cum	1000.00	21000.00	INR Twenty One Thousand Only
31	Providing Engineering Consultancy services for steel structure for RCC foundation work, Column , Beams, Slab Etc. and testing for load bearing capacity with all relevant calculation sheet and design vetted by I.I.T/NIT/Govt Engg collage, Providing detailed construction drawing i/c visiting charges etc. required during execution etc. as specified in tender document and any other details related to consultancy work which are essential for successful execution of works etc completes as per direction and satisfaction of EIC.	1.00	Job	60000.00	60000.00	INR Sixty Thousand Only
Total in Figures					22571771.00	INR Two Crore Twenty Five Lakh Seventy One Thousand Seven Hundred & Seventy One Only
Quoted Rate in Words		Signature Not Verified				

Digitally signed by AJAY KUMAR GUPTA
Date: 2025.06.05 16:09:55 IST
Location: eProcurement System for Central PSUs

26/6/25

26/6/25
02/06/25

26/6/25
3.81.5 PM/25