



भाविप्रा/औ'बाद/अभि.-वि/कैप/25-26/डब्लू-03/ 296
AAI/AU/Engg-E/CAP/25-26/W-03/

दिनांक: 30.07.2025
Date: 30.07.2025

सेवा में,
मेसर्स रिवाइंडर टेक्नो इलेक्ट्रिकल्स,
D-38, आचार्य निकेतन, मयूर विहार,
फेज-1, ईस्ट दिल्ली,
दिल्ली - 110091

To,
M/s Rewinder Techno Electricals,
D-38, Acharya Niketan, Mayur Vihar,
Phase-1, East Delhi,
Delhi - 110091

(PAN No. AAFFR7457K)
GST No. 07AAFFR7457K1ZO

कार्य का नाम : औरंगाबाद हवाईअड्डे पर रनवे टर्नपेड लाइट्स और अन्य संबंधित कार्य का प्रावधान।
Provision of Runway Turn Pad Lights and other associated work at Aurangabad Airport.

संदर्भ : 1) निविदा आई. डी संख्या : 2025_AAI_233481_1
2) आपकी ई - निविदा जो दिनांक 19.05.2025 को खोली.

महोदय,/ Dear Sir (S),

- उल्लिखित कार्य हेतु आपकी ई - निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की और से आपके द्वारा बताए गये मद मूल्यों पर रु. 99,31,950.00 (रु. निन्यानवे लाख इकतीस हजार नौ सौ पचास मात्र) (जी एस टी अतिरिक्त) के लिए स्वीकृत की जाती है जो कि अनुमानित लागत राशि रु 1,22,08,921.00 से 18.66 % कम है।

Your e-tender for the work mentioned above is hereby accepted on behalf of the chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs. 99,31,950.00** (Rupees Ninety Nine Lakh Thirty One Thousand Nine Hundred and Fifty Only) (Excluding GST) which is **18.66%** below the justification cost put to tender of **Rs. 1,22,08,921.00**.

- वरि. प्रबंधक (अभियांत्रिकी- विद्युत), भाविप्रा, औरंगाबाद हवाईअड्डा, महाराष्ट्र कार्य के प्रभारी अभियंता होंगे, आपसे निवेदन है कि, आप दिनांक 18.08.2025 तक वरि. प्रबंधक (अभियांत्रिकी- विद्युत), भाविप्रा, औरंगाबाद हवाईअड्डा, औरंगाबाद, के कार्यालय में उपस्थित हों तथा करारनामे को पुरा करें. ठेके के करार नामा रुपये 100/- के नोनजुडिशियल स्टैम्प पर निष्पादित किया जायेगा तथा पेपर का खर्चा आपके द्वारा उठाया जायेगा।

Senior Manager (E-E), AAI, Aurangabad Airport, Maharashtra, shall be the Engineer -In -Charge of the work. You are requested to attend the office of Senior Manager (E-E), AAI, Aurangabad Airport by **18.08.2025** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees one Hundred Only) and the cost of the stamp paper shall be borne by you.

विमानक्षेत्र नियंत्रक का कार्यालय, भा.वि.प्रा., औरंगाबाद, दूरभाष : (0240) 2477802,
O/O The Airport Director, AAI, Aurangabad. Phone No: (0240)2477802,

30.07.25
sm(g-e)
वरि. प्रबंधक (अभि-विद्युत)
भाविप्रा औरंगाबाद हवाईअड्डा

3. आपके निविदा के साथ प्राप्त बयाना राशि **3,66,268.00** रुपए को प्रतिभूति जमा के हिस्से के रूप में परिवर्तित किया जाएगा। कृपया इस पत्र के जारी होने की तिथि से 15 दिनों के भीतर प्रतिभूति जमा राशि **6,26,927.00** रुपये ठेके के दस्तावेज के अनुसार जमा कर दें, अन्यथा निविदा में पृष्ठ जी सी सी 16 पर दी गई धारा 1(A) के अनुसार कटौती की जाएगी।

The earnest money amount of **Rs.3,66,268.00** received along with your tender will be treated and converted as part of Security Deposit. Please deposit **Rs. 6,26,927.00** towards security deposit within 15 days from the date of issue of this letter, failing which the same will be deducted as per condition of clause 1(A) at GCC Page 16 of the Contract Document.

4. आपसे निवेदन है कि आप केन्द्रीय और राज्य सरकारों के 1970 अधिनियम अनुबन्ध श्रम नियम तथा 1971 के केन्द्रीय नियम (नियमन तथा उन्मूलन) एवं केन्द्र तथा राज्य सरकारों के न्यूनतम वेतन अधिनियमों और नियमों के प्रवधानों के अनुपालन करें।

You are requested to comply with the provisions of contract labour (Regulation and abolition) Act of 1970 and contract labour (Regulation and abolition) Central rules 1971 and minimum wages Act & rules thereof Central and State Governments.

5. आपको निर्देश दिया जाता है कि आप तुरंत प्रबंधक (अभियांत्रिकी -विद्युत), से मिलें वह आपको साईट सौंपने कि व्यवस्था करेंगे।

You are also directed to contact **Manager (Engg-Elect.)**, AAI, Aurangabad Airport immediately who will arrange to hand over the site to you.

6. कृपया नोट करें कि कार्य करने का समय **04 (चार) माह** रहेगा, जोकी कार्य आदेश जारी होने के दसवें दिन से माना जायेगा।

Please note that the time allowed for carrying out the work shall be **04 (Four) Months** and same shall be reckoned from the 10th day of the date of placing of work order.

7. यदि अंग्रेजी और हिंदी पाठ में कोई अंतर पाया जाता है तो अंग्रेजी विवरण सही माना जाएगा।

If there is any discrepancy between English and Hindi then meaning derived in English will be given precedence.

8. ई निविदा प्रक्रिया के दौरान उठाए गए सभी शुद्धी पत्र, प्रश्न, स्पष्टीकरण इत्यादि और उपर उल्लिखित पत्रों सहित उत्तरों के जवाब भी करारनामे के हिस्से होंगे।

All corrigendum, queries, clarifications etc., raised during e-tendering process and replies there of including the letters referred above shall also form part of the agreement.

9. इस ठेके के संबंध में आगे को कोई भी पत्राचार वरि. प्रबंधक (अभि.- विद्युत), भाविप्रा. औरंगाबाद हवाईअड्डा, औरंगाबाद - 431007 के पते पर किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Sr. Manager (Engg-Elect), AAI, Aurangabad Airport, Aurangabad - 431007.


10. कृपया इस पत्र को स्वीकार करे और हस्ताक्षर करने के बाद इसके साथ संलग्न पत्र की डुप्लिकेट प्रति स्वीकृति के प्रतीक के रूप में अधोहस्ताक्षरी को वापिस करें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

संलग्न : मात्रा की अनुसूची

Encl : Schedule of Quantity (SOQ)

भवदीय/ Yours faithfully,


30.07.25

वरि. प्रबंधक [अभि - विद्युत]
Sr. Manager (E-E)
भाविप्रा, औरंगाबाद हवाईअड्डा, औरंगाबाद
AAI, Aurangabad Airport, Aurangabad

वरि. प्रबंधक (अभि-विद्युत)
भाविप्रा औरंगाबाद हवाईअड्डा

Validate

Print

Help


Item Rate BoQ

Tender Inviting Authority: Senior Manager (Engg.-Electrical), Airports Authority of India, Aurangabad Airport, Aurangabad- 431007.


Name of Work: Provision of Runway Turn Pad Lights and other associated work at Aurangabad Airport.

Contract No: 2025_AAI_233481 _1

Name of the Bidder/ Bidding Firm / Company :	Rewinder Techno Electricals					
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Supply of FAA certified Inset Type Uni Directional Green Turning Pad Light meeting ICAO requirements LED lamp of series circuit 6.6 amps current with 8" dia shallow base and matching body of the fitting, inner body and outer cover made of die cast aluminium complete with pre-focused reflector LED lamps with connected heat resistant accessories, prism assembly, optical assembly, "O" ring seal, pressure relief test plug, lense(s), two-pole secondary plug, hardware and all standard accessories and ready for site installation as required and as per the enclosed particular specifications and suitable for operation control and monitoring on existing ALCMS (Airfield Lighting Control and Monitoring System).	100.00	Each	40000.00	4000000.00	INR Forty Lakh Only



 30.07.25
 SM(E-E)
 वरि.प्रबंधक (अभि-विद्युत)
 भाविमा औरंगाबाद हवाईअड्डा

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
2	Installation, testing and commissioning of following sizes inset fitting with core cutting, aligning and setting including providing sealing material of reputed make and installation of isolating transformer, crimping/jointing of plug receptable and connection of secondary leads along with other accessories required for commissioning including supply of all materials like receptables/connectors (5 kV grade dry plug type) etc as required, excluding the fixture, secondary lead and isolating transformer etc. (a). Fitting size upto 8 inch	86.00	Each	2000.00	172000.00	INR One Lakh Seventy Two Thousand Only
3	Supply of 5000V, 50 Hz Series Isolating Transformers encapsulated in black cross linked polychloroprene compound like TPE /TPR / TPV with primary and secondary connections suitable for suitable for Item no: 1. The transformer shall be water tight and shall be designed for direct burial in the earth or installation in a base confirming to specifications as required and compatible to use on ALCMS as per Technical Specifications.	86.00	Each	4000.00	344000.00	INR Three Lakh Forty Four Thousand Only



 30.07.25
 SM(E-E)

वरि. प्रबंधक (अभि-विद्युत)
 भाविप्रा औरंगाबाद हवाईअड्डा


SI. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
4	SITC of 4KW Indoor Type Air Cooled Constant Current Regulator (CCR) of Micro Processor Controlled, Thyristor Type suitable for operation on single phase 230V PE $\pm$ 10%, 50 Hz input AC supply with 5 steps variation of current output (2.8, 3.4, 4.0, 5.2 and 6.6 Amp) and able to communicate with PC or PLC controlled system with digital output ammeter (0-10 Amps), over current, over voltage, open circuit and earth fault protection and earth leakage meter, two stage earth leakage detector, positive back indication Equipments, hours run counter, LCD display complete as required for the following rating and confirm to specifications enclosed and suitable for operation on the existing Airfield Lighting Control and Monitoring System (ALCMS) with communication, local and remote control and monitoring even and data recording and history keeping etc complete as required.	3.00	Each	200000.00	600000.00	INR Six Lakh Only
5	Supply of 2C x 6 sqmm Airfield Lighting (AFL) 5 KV grade, Single Core, Copper Conductor, XLPE insulated, and with inner and outer semiconductor, Polyethylene (PE) outer sheathed, Unarmoured Underground Cable for airfield lighting Primary Circuit, confirming to specification as specified in technical specification of the following sizes as required.	4400.00	Meter	400.00	1760000.00	INR Seventeen Lakh Sixty Thousand Only
6	Supply of 6 sq.mm 5 KV grade Single Core unarmoured Primary Circuit Cable with Stranded Annealed Plain Copper Conductor, XLPE insulated and Polyethylene (PE) sheathed, Cable for airfield lighting conforming to IS 1554 (part-2/ IS 7098(part -2) and as per technical specification etc. as required.	1420.00	Meter	160.00	227200.00	INR Two Lakh Twenty Seven Thousand Two Hundred Only


 30.07.2023
 त्रि. प्रबन्धक (अ. विद्युत)
 भाविप्रा औरंगाबाद हवाई अड्डा

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
7	Supply of 2C x 4 sq.mm., 1.1 KV Grade Flexible Copper Conductor, EPR insulated & CPE (Chlorinated Polyethylen, cross - linked, heavy duty) outer sheath (Black colour) Secondary cable for Airport lighting circuits conforming as specified in particular specification of following sizes as required.	1900.00	Meter	245.00	465500.00	INR Four Lakh Sixty Five Thousand Five Hundred Only
8	Supply of 1C x 4 sq.mm., 1.1 KV Grade Flexible Copper Conductor, EPR insulated & CPE (Chlorinated Polyethylen, cross - linked, heavy duty) outer sheath (Black colour) Secondary cable for Airport lighting circuits conforming as specified in particular specification of following sizes as required.	1900.00	Meter	75.00	142500.00	INR One Lakh Forty Two Thousand Five Hundred Only
9	Supply and fixing of Secondary connector kit (male and female) suitable for connection 2X 4 sq. mm multi stranded annealed conductor, CPE sheathed unshielded secondary airfield lighting cables (600 V grade) as per specification etc. as required.	86.00	Each	700.00	60200.00	INR Sixty Thousand Two Hundred Only


 20.07.25
 Sm (E-E)
 वरि.प्रबंधक (अभि-विद्युत)
 भाखिमा औरंगाबाद हवाईअड्डा


Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
10	Supply of Cast iron Isolating Transformer housing box, water tight round type, metal container of outside dia 330 mm, height 450 mm made of 10 mm thick cast iron moulding all round, except the top surface, which is 15 mm thick cast iron moulding suitable to receive a light fitting base plate/cover plate on the top and underground housing associated with transformer power cable and having three/two/one nos holes as per site requirement on the periphery centre, 75 mm above bottom surface suitable to receive 63 mm HDPE pipes as required . The box should have two SS earth bolts of M10 x 40 mm tapped inside near the hole (4" away from the hole centre) and having a drain hole at the bottom suitably tapped to receive 15 mm dia, 'B' class GI pipe and having clear opening of 220 mm at the top surface and 6 Nos. M10 tapped hole having centre to center distance of 260 mm alongwith bolts as required as per the drawings. The CI top cover of 310 mm dia 15 mm thick with suitable rubber gasket and 6 Nos. M10 tapped hole and bolts as required.	86.00	Each	5500.00	473000.00	INR Four Lakh Seventy Three Thousand Only


30.07.25


SM (E-E)

वरि.प्रबंधक (अभि-विद्युत)
भाविमा औरंगाबाद हवाईअड्डा


Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
11	Installation of CI housing box of size 330 mm dia and 450 mm deep i/c cutting/excavation of surface/earth, providing one no, 250 mm long 15 mm dia 'B' class GI pipe in the bottom surface for drainage of water etc., cutting & threading of pipe, i/c leveling of housing box with suitable instrument etc, painting of box with one coat of primer and two coats of black enamel paint and installation of housing box in soil providing base cement concrete of 1:3:6 of size 630 x 630 x 100 mm thick, and PCC of 1:2:4 all around the housing box of width not less than 150 mm and pedestal of 0.30 mtr. and 0.10 mtr. thick all around the box making suitable slop to level of runway all around the housing box, painting, lettering, numbring etc i/c disposal of excavated earth, debris/malba and making good the same as original complete as required.	86.00	Each	750.00	64500.00	INR Sixty Four Thousand Five Hundred Only
12	Supply and laying of follwing size double wall corrugated high density polyethylene (DWC HDPE pipe) pipe confirming to IS:14930 (part-2) with latest amendment, complete with accessories like couplers, bends, tee etc. in the soil for GLF work upto 750 mm deep, back filling & making good the same as per site requirement. (a) OD 63 mm/ ID 50 mm	4000.00	Meter	200.00	800000.00	INR Eight Lakh Only
13	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 5 KV grade of 2C X 6 Sqmm size in the existing RCC/ HUME/ METAL/HDPE pipe as required.	4000.00	Meter	5.00	20000.00	INR Twenty Thousand Only


 20.07.24
 वरि. प्रबंधक (अभि-विद्युत)
 भाविप्रा औरंगाबाद हवाई मैड्डा

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
14	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 5 KV grade of 1C X 6 Sqmm size in the existing RCC/ HUME/ METAL/HDPE pipe as required.	1290.00	Meter	5.00	6450.00	INR Six Thousand Four Hundred & Fifty Only
15	Cutting of cable groove with kerf cutting machine for laying following number of 2 x 4 Sq.mm secondary leads and 1 X 4 Sq.mm earthing cable meant for inset type runway fitting on the concrete/ bituminous runway surface including kerfing, chiseling, cleaning and filling the groove with sealant compound after putting sealant primer after laying secondary lead including jute covering for protection or it should be covered with cold bitumin as per the direction of EIC etc. as required. (cost should be including laying of cable and all requirements) a) 01 Run of Cable (meter) will be considered as laying of 2 x 4 Sq.mm and 1 x 4 Sq.mm cable.	1720.00	Meter	150.00	258000.00	INR Two Lakh Fifty Eight Thousand Only
16	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc.with charcoal/ coke and salt as required.	16.00	Each	4000.00	64000.00	INR Sixty Four Thousand Only
17	Providing and laying earth connection from earth electrode with 6 SWG dia G.I. Wire in 15 mm dia G.I. pipe from earth electrode including connection with G.I. thimble excavation and re-filling as required.	520.00	Meter	150.00	78000.00	INR Seventy Eight Thousand Only


 30.07.25
 त्रि. प्रबंधक (आ. वि. वि. वि.)
 भाविमा औरंगाबाद हाईवे अड्डा


Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
18	Excavation of the cable trenches in hard rock not exceeding 1.5 meters in width and lift up to 1.5 meters , including getting out the excavated soil and disposal of excavated soil as directed with in a lead of 50 meters.	21	Cum	100.00	2100.00	INR Two Thousand One Hundred Only
19	Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zoneIII) : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design : Inside size 120x90 cm and 90 cm deep including C.I. cover with frame (heavy duty) 560 mm internal diameter, total weight of cover and frame to be not less than 208 kg (weight of cover 108 kg and weight of frame 100 kg). With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	7.00	EA	5000.00	35000.00	INR Thirty Five Thousand Only
20	Supply and Laying of 63 mm dia HDPE pipe with HDD trenchless method direct in ground (upto 07 meter below ground level) in all type of soil, coupling of pipe etc complete as per requirement in all aspect.	150.00	Meter	450.00	67500.00	INR Sixty Seven Thousand Five Hundred Only


 30.07.25
 वरि.प्रबंधक (अभि-विद्युत)
 भाकिरा औरंगाबाद हवाईअड्डा

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Rs. P (Excluding GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
21	Supply of elevated, low intensity LED type, omni directional, blue lens with minimum average intensity of 2cd, taxiway/apron edge light fittings complete with LED lamp, holder, lens clamping mechanism, encapsulated driver unit, suitable heat sink, breakable coupling, central column assembly, 2 pin secondary lead, rubber gasket, base plates with minimum 6 nos M10 stainless steel bolts with threading, spring washer and other accessories etc. as required.	60.00	Each	3000.00	180000.00	INR One Lakh Eighty Thousand Only
22	Supply of isolating transformer of 5 KV grade suitable to operate LED light of low intensity light fitting encapsulated in polyester resin finally moulded in neopren rubber with primary and secondary connection as required. 15W, 6.6/6.6 A	40.00	Each	2800.00	112000.00	INR One Lakh Twelve Thousand Only
Total in Figures					9931950.00	INR Ninety Nine Lakh Thirty One Thousand Nine Hundred & Fifty Only
Quoted Rate in Words		INR Ninety Nine Lakh Thirty One Thousand Nine Hundred & Fifty Only				

Signature Not Verified

Digitally signed by SATEESH KUMAR KANAUJIYA
Date: 2025.10.08 18:36:45 IST
Location: eProcurement System for Central PSUs



21/10/25
30.07.25
SM(E-E)

वरि.प्रबंधक (अभि-विद्युत)
भाविप्रा औरंगाबाद हवाईअड्डा