



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA



ISO 9001:2015 Certified

AAI/ TUT/NTB/ COVERED PARKING/ 25-26 / 028

Date: 17.07.2025

To,

M/s. Yasees Associates.

No. 98, Punnakkad House,
Chungam, Kondotty,
Malappuram, Kerala, 673638

Name of work: "Provision of Covered Parking using Tensile Fabric for new ATC cum Technical Block, and other ancillary works in the New ATC cum Technical Block and New Fire Station at Tuticorin Airport."

Ref: (i) Your E-Tender (Financial Bid) opened through CPP Portal on 02.07.2025

(ii) Tender ID: 2025_AAI_238177_1

Dear Sir(s),

1. Your E-Tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rate quoted by you totaling to **Rs.1,81,81,997.00/-** (Rupees One Crore Eighty-One Lakhs Eighty-One Thousand Nine Hundred and Ninety-Seven only) exclusive of GST which is **17.35% below** the estimated cost put to tender of Rs. 2,20,00,000/- (Rupees Two Crores Twenty Lakhs only).
2. **Senior Manager (Engg-Civil), AAI, Tuticorin Airport, Tuticorin** shall be the Engineer-in-charge of the work. You are requested to attend the office of Senior Manager (Engg-Civil), AAI, Tuticorin Airport, within 15 days from the stipulated date of start of work to sign and complete the contract agreement. The Contract Agreement shall be executed on a non-judicial stamp paper of value Rs.100 /- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.
3. The Earnest Money Amount of **Rs.6,60,000 /- (Rupees Six Lakhs Sixty Thousand only)** received online through CPP Portal along with your tender will be refunded to your source of account. Please deposit **Rs.18,18,200 /- (Rupees Eighteen Lakhs Eighteen Thousand Two Hundred only)** towards security deposit within 10 days from issue of this letter, failing which the same will be deducted from each running bill as per Clause No-1A, of Page No. 36 GCC of contract document.
4. You are hereby requested to get yourself registered with provident fund organization, Employees state insurance organization & obtain the necessary PF, ESI & GST code numbers from these departments. Copy of the documents should be submitted to this office. Further, you are also requested to deposit the requisite PF, ESI and GST amounts and submit copy of periodical returns to AAI.

1

[Signature]
17/07/2025
SM (E-C)



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA


JAS-ANZ



ISO 9001:2015 Certified

5. You are requested to comply with the provision of Contract Labour (Regulation and abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971, Child Labour (Prohibition & Regulation Act 1986, Construction Workers (Regulation of Employment and Conditions of Service Act 1996, Building and other construction workers Welfare Cess Act 1996 and rules thereof Central and State Governments.
6. You are also directed to contact Senior Manager (Engg-Civil), AAI, Tuticorin Airport immediately, who will arrange to hand over the site to you.
7. Please note that the time allowed for carrying out the work is **06 (Six) Months** & shall be reckoned from **10 days** of issue of this letter.
8. All taxes as applicable will be deducted from your bill.
9. Any further correspondence in connection with the contract should normally be addressed to the Senior Manager (Engg-Civil), AAI, Tuticorin Airport, Tuticorin.
10. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Yours Sincerely,


(SARIKA K.P.)

Senior Manager (Engg -Civil)
AAI, Tuticorin Airport
For and on behalf of Chairman,
Airports Authority of India.

Encl : Schedule-"A" (14 Pages)



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA



ISO 9001:2015 Certified

Schedule-"A"

"Provision of Covered Parking using Tensile Fabric for new ATC cum Technical Block, and other ancillary works in the New ATC cum Technical Block and New Fire Station at Tuticorin Airport."

SL. NO	Item Description	Quantity	Unit	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	20.00	cum	166.59	3331.80
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed. All kinds of soil	1800.00	cum	100.00	180000.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	10.00	cum	6200.00	62000.00
4	Centering and shuttering including strutting, propping etc. and removal of form for : For Foundation, Footings, Bases for Column	180.00	Sqm	250.98	45176.40
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more.	1000.00	kg	95.00	95000.00

[Signature]



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA



ISO 9001:2015 Certified

6	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works upto plinth level a) Concrete of M25 grade with minimum cement content of 330 kg /cum	10.00	cum	8500.00	85000.00
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :Cement mortar 1:6 (1 cement : 6 coarse sand)	70.00	Cum	7800.00	546000.00
8	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement: 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc, complete at all levels. Granite stone slab of colour black, Cherry/Ruby red. area of slab over 0.50 sqm.	20.00	Sqm	3400.00	68000.00



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA



ISO 9001:2015 Certified

9	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge. Granite work	30.00	metre	327.01	9810.30
10	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete. 300 X 16mm	10.00	Each	194.08	1940.80
11	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 300 X 10mm	10.00	Each	83.26	832.60
12	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :125 mm For Doors	20.00	Each	42.40	848.00
13	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. Single rubber stopper	10.00	Each	25.34	253.40
14	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. a) Hot finished welded type tubes	20000.00	Kg	110.00	2200000.00
15	Providing and fixing mild steel round holding down bolts with nuts and washer plates complete.	660.00	kg	90.00	59400.00
16	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	6000.00	Kg	110.00	660000.00

[Signature]
SMT




भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA



ISO 9001:2015 Certified

17	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel	12700.00	kg	110.00	1397000.00
18	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm	300.00	Sqm	1100.00	330000.00
19	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 600x600 mm	210.00	Sqm	1100.00	231000.00


SHAKIL



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA



ISO 9001:2015 Certified

20	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with :12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- Part I	300.00	Sqm	950.00	285000.00
21	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	40.00	Sqm	225.00	9000.00

[Signature]
GM (F)



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA



ISO 9001:2015 Certified

22	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	100.00	Sqm	110.00	11000.00
23	Inner plastering : 12 mm cement plaster of mix 1:6 (1 cement: 6 fine sand)	500.00	Sqm	225.00	112500.00
24	15 mm cement plaster on rough side of single or half brick wall of mix: : 1:6 (1 cement: 6 fine sand)	240.00	Sqm	225.00	54000.00
25	Finishing with Deluxe Multi surface paint system for interiors using Primer as per manufacturers specifications :Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm	450.00	Sqm	110.00	49500.00
26	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm)	300.00	sqm	120.00	36000.00
27	Making the opening in brick masonry including dismantling in floor or walls by cutting masonry and making good the damages to walls, flooring and jambs complete, to match existing surface i/c disposal of mulba/ rubbish to the nearest municipal dumping ground, all complete as per direction of Engineer-in-Charge. For door/ window/ clerestory window	10.00	Sqm	1000.00	10000.00
28	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge.	10.00	Sqm	56.35	563.50
29	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	10.00	cum	1500.00	15000.00
30	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity , dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the subgrade and disposal of surplus earth with lead upto 50 metres.	1500.00	Sqm	140.00	210000.00



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA



ISO 9001:2015 Certified

31	Extra for compaction of earth work in embankment under optimum moisture conditions to give at least 95% of the maximum dry density (proctor density).	1500.00	Sqm	15.00	22500.00
32	Providing and laying design mix cement concrete of M-30 grade, in roads/ taxi tracks/ runways, using cement content as per design mix, using coarse sand and graded stone aggregate of 40 mm nominal size in appropriate proportions as per approved & specified design criteria, providing dowel bars with sleeve/ tie bars wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/ camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction/ expansion, construction & longitudinal joints (10 mm wide x 50 mm deep) by groove cutting machine, providing and filling joints with approved joint filler and sealants, complete all as per direction of Engineer-in-charge (Item of joint fillers, sealants, dowel bars with sleeve/ tie bars to be paid separately). Note:- Cement content considered in M-30 is @ 340 kg/cum. Excess/ less cement used as per design mix is payable/ recoverable separately. Cement concrete manufactured in automatic batching plant (RMC plant) i/c transportation to site in transit mixer	270.00	Cum	9500.00	2565000.00
33	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-II (size range 53 mm to 0.075 mm) having CBR Value-25	295.00	Cum	1950.00	575250.00

[Handwritten signature]
6/11/17



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA



ISO 9001:2015 Certified

34	Providing and laying dry lean cement concrete with coarse and fine aggregate conforming to IS:383, the size of coarse aggregate not exceeding 26.5 mm, aggregate cement ratio not exceed 15:1, aggregate gradation after blending to be as per specification, cement content not to be less than 150 kg/cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 MPa at 7 days, mixed in a batching plant as per mix design, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonne vibratory roller, finishing and curing etc complete as per specification and direction of the Engineer-in-Charge.	110.00	Cum	3800.00	418000.00
35	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge)	30.00	Cum	10000.00	300000.00
36	Providing and laying factory made chamfered edge Cement Concrete paver blocks In foot path, park & lawns driveway or light & traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of course sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, all complete as per manufacturer's specifications & direction of Engineerin-Charge. 60mm thick cement concrete paver block of M-35 grade with approved colour, design & pattern.	610.00	Sqm	1000.00	610000.00



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

JAS-ANZ



ISO 9001:2015 Certified

37	Providing and laying factory made chamfered edge Cement Concrete paver blocks In foot path, park & lawns driveway or light & traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of coarse sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, all complete as per manufacturer's specifications & direction of Engineerin-Charge. 80 mm thick C.C. paver block of M-35 grade with approved colour design and pattern.	150.00	Sqm	1000.00	150000.00
38	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a single 15 mm C.P. brass pillar tap	3.00	Nos	1558.45	4675.35
39	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 : 15mm nominal bore	3.00	Nos	354.76	1064.28
40	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 15mm nominal dia pipes	10.00	meters	348.46	3484.60



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA



ISO 9001:2015 Certified

41	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 20 mm nominal dia pipes	50.00	meters	376.32	18816.00
42	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron)	3000.00	kg	385.00	1155000.00
43	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/ sqm)	40.00	Sqm	1200.00	48000.00

[Signature]
SM/KS



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA



ISO 9001:2015 Certified

44	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron)	600.00	Kg	425.00	255000.00
45	Filling the gap in between aluminium frame & adjacent RCC/ Brick/ Stone work by providing weather silicon sealant over backer rod or mortar or white cement or any such material of approved quality as per the direction of Engineer-in-charge complete. Upto 5mm depth and 5 mm width	50.00	metre	85.00	4250.00
46	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer-in-charge. Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side	24.00	Sqm	850.00	20400.00

[Signature]
SMK-1



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA



ISO 9001:2015 Certified

47	Providing and fixing double glazed hermetically sealed glazing in aluminium windows, ventilators and partition etc. with 6 mm thick clear float glass both side, having 12 mm air gap, including providing EPDM gasket, perforated aluminium spacers, desiccants, sealant (Both primary and secondary sealant) etc. as per specifications, drawings and direction of Engineer-in-charge complete.	200.00	Sqm	3750.00	750000.00
48	Disposal of moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved municipal dumping ground for lead upto 10 km for all lifts, complete as per directions of Engineer-in-charge.	540.00	cum	350.00	189000.00
49	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials up to a lead of 1000 metres, stacking serviceable and unserviceable materials separately	10.00	cum	1500.00	15000.00
50	Supplying and fixing in position Zebra / Sheer dimout/Translucent Silvanus Blinds of VISTA/Marvel make, complete for required width and height as per the direction and satisfaction of Engineer-in-charge. Roller Zebra blind	220.00	Sqm	120.00	26400.00
51	Construction of Subgrade embankment with Moorum brought out from approved quarry out side the airport premises. The complete operation will include spreading the Moorum with dozer, dressing, levelling, providing camber, grading with motor grader and consolidating with vibratory roller 8-10 tonne capacity including making good the undulation etc. as per technical specifications and drawings complete and directions of Engineer-in-Charge. (Cost includes all leads ,taxes, royalty and operations)	1070.00	Cum	1350.00	1444500.00



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA



ISO 9001:2015 Certified

52	Tensile Membrane Fabric: Providing, fabricating, assembling and erection of Special Architectural Tensile Membrane Fabric structure in desired profile as per drawing, with Mehler Technologies Valmex Type-III Mehatop N or Serge Ferrari TX30 Type-III fabrics or equivalent having weight of 1050 g/sqm, minimum tensile strength of 6000/5500 N/50 mm (warp/weft direction) and tear strength of 900/800 N (warp/weft direction) with flame retardancy EN 13501-1:BS2D0. Weldable PVDF lacquer on both sides. Color of the fabric should be white, Conditional Warranty of 20 years on the fabric, over steel frames with all fittings and fixtures such as Galvanized MS Membrane/ End Plate, Shackles, Rigging Screws, Turnbuckles, swedge, fork, keder rods & galvanized MS strands/ cables with stainless steel end terminals complete as per Drawing/ Detail & as per technical specifications and as per the instructions of Engineer-in-charge. (Rate includes cost of fabric, shop drawings, forming, cutting, fabrication, hot weld stitch of fabric, Transport to the site, assembling and installation with GI cables, hardware, Aluminium flat, EPDM gasket and required accessories wherever required complete including lifts up to all heights, tools and plants, and necessary scaffolding etc. required for all operations in all respect as per direction of Engineer-In-Charge). Supporting structural steel frame and RCC foundation shall be paid separately. (Note: Actual Plan area of canopy shall only be measured for payment.)	940.00	Sqm	2600.00	2444000.00
----	--	--------	-----	---------	------------



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

JAS-ANZ



ISO 9001:2015 Certified

53	Providing & fixing at all heights, levels and locations colour finish Aluminium alloy roofing sheets of alloy IS designation 31500, temper Hx8 conforming to IS 737 and dimensions as per IS code 2676 with characteristics of good formability and corrosion resistance. The profile sheets shall be fixed to truss members in slope or required pitch or curvature with Hex cap headed self drilling/tapping Stainless steel screws M6, 50 mm long with 3 mm EPDM seal washer etc. all inclusive of labour, scaffolding, T&P and sundries etc. complete as per directions of the Engineer-In-Charge. (Cost of truss/frame work shall be paid separately).0.56 mm, Aluminium Colour coated troughed profile with center to center pitch of 200 mm, depth of 32 mm, overall profile width1092 mm, cover width 1000mm.	380.00	Sqm	725.00	275500.00
54	Providing and fixing of Pre-coated colour or mill finish Aluminium Roofing Accessories in 0.71 mm thickness ,Alloy 31500 (IS designation) [Aluminium Alloy (AA) 3004 (ISO designation)] For color, coating shall be 5-7 microns epoxy primer on both sides of the sheet and polyester top coat 15-18 microns, using self drilling/tapping SS screws of size 6 x 50mm with 3mm thick Precoated/mill finish aluminium Ridges plain (500- 600mm)	40.00	metre	850.00	34000.00
55	Providing and fixing of Pre-coated colour or mill finish Aluminium Roofing Accessories in 0.71 mm thickness ,Alloy 31500 (IS designation) [Aluminium Alloy (AA) 3004 (ISO designation)] For color, coating shall be 5-7 microns epoxy primer on both sides of the sheet and polyester top coat 15-18 microns, using self drilling/tapping SS screws of size 6 x 50mm with 3mm thick Precoated/mill finish aluminium Gutter (600 mm over all girth)	70.00	metre	1200.00	84000.00

Total = 18181997.00
(Excl.GST)

(SARIKA K.P)

Senior Manager (Engg -Civil)
AAI, Tuticorin Airport
For and on behalf of Chairman,
Airports Authority of India.