



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

एएआई-(सी)एजीएम/(सी)इंजीनियरिंग/II/आर एंड एम-2025/52-डब्ल्यू/विशेष मरम्मत-6/2023 दि:15.09.2025
AAI/ENGG(C)/AGM(C)-II/R&M-Spl. Repairs/ W-52/2025-26 Date:15.09.2025

//BY SPEED POST //

सेवामें / To

सुमन फैब्रिकेटर्स अंड कंटाक्टर्स / Suman Fabricators and Contractors,
डी/D-228, जी.आई.डी.सी इंडस्ट्रियल एस्टेट / GIDC Industrial Estate,
जुआरी नगर, (पी. ओ) / Zuari Nagar, (PO),
संकोल / Sancoale,
गोवा / Goa:403726.

Name of Work: कोयंबटूर अंतर्राष्ट्रीय हवाई अड्डे के प्रशासनिक ब्लॉक, पावर हाउस, एसी प्लांट, इंजीनियरिंग कार्यालयों और शहर की ओर स्थित अन्य भवनों की विशेष मरम्मत / Special Repairs to Admin Block, Power House, AC Plant, Engg Offices and other Buildings in City Side at Coimbatore International Airport.

Reference: उपरोक्त कार्य हेतु आपकी निविदा दिनांक 06.08.2025 को खुली /Your Tender for the above work opened on Dated 06.08.2025. संदर्भ: निविदा आईडी- 2025_एएआई_238225_1)/ (Tender ID No: 2025_AAI_238225_1).

महोदय / Dear Sir,

- उपर्युक्त कार्य के लिए आपकी ई-निविदा, आपके द्वारा उद्धृत मद दरों पर भारतीय विमानपत्तन प्राधिकरण के अध्यक्ष की ओर से स्वीकार की जाती है और उद्धृत दरों पर 4.5% की समग्र छूट के साथ कुल 32,65,842.00/- रुपये (बत्तीस लाख पैसठ हजार आठ सौ बयालीस मात्र) प्लस 18% की दर से लागू जीएसटी है, जो कि निविदा में रखी गई अनुमानित लागत 31.25 लाख रुपये (जीएसटी को छोड़कर) से 4.49% अधिक है।/ Your E-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you and negotiated over all discount of 4.5% on the quoted rates totaling to Rs. 32,65,842.00/- (Thirty-Two Lakhs Sixty-Five Thousand Eight Hundred and Forty-Two Only) plus applicable GST @ 18%, which is 4.49% above the estimated cost put to tender of Rs. 31.25 Lakhs (Excl, GST).

कोयंबटूर अन्तरराष्ट्रीय हवाई अड्डा / Coimbatore International Airport, कोयंबटूर / Coimbatore - 641014

Phone : 0422 - 2571941, 2571956, 2573603, 2573602, 2573561, Fax : 0422 - 2592884 / 2573223

Email: apdcoimbatore@aai.aero



Recycled & Crafted by
AAI Paper Recycling Unit
ISO 14001 : 2004 CERTIFIED UNIT

RE THINK → REDUCE → RE USE → RE CYCLE

15/9/25
Asst. General Manager (Engg. Civil)
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
कोयंबटूर अन्तरराष्ट्रीय हवाई अड्डा / Coimbatore Intl. Airport
कोयंबटूर / Coimbatore - 641 014



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

2. भा.वि.प्रा, कोयंबतूर अंतरराष्ट्रीय हवाई अड्डा के सहायक महाप्रबंधक (इंजि-वि), कार्य के प्रभारी इंजिनियर होंगे। आपसे अनुरोध है कि ठेका करार पर हस्ताक्षर करने और उसे पूरा करने के लिए कार्य शुरू होने की निर्धारित तिथि से 15 दिनों के भीतर सहायक महाप्रबंधक (इंजीनियरिंग-सिविल)-II, भा.वि.प्रा, कोयंबतूर अंतरराष्ट्रीय हवाई अड्डा, कोयंबतूर के कार्यालय में उपस्थित हों। ठेका करार 100/- रुपये (केवल एक सौ रुपये) मूल्य के गैर-न्यायिक स्टाम्प पेपर पर निष्पादित किया जाएगा और स्टाम्प पेपर की लागत आपके द्वारा वहन की जाएगी। / Asst. General Manager (Engg-Civil)-II, AAI, Coimbatore International Airport, shall be the Engineer-In-Charge of the work. You are requested to attend the office of the **Asst. General Manager (Engg-Civil)-II, AAI, Coimbatore International Airport, Coimbatore** within 15 days from the stipulated date of start of work to sign and complete the Contract Agreement. The Contract Agreement shall be executed on a non-judicial stamp paper of value of **Rs.100/-** (Rupees One Hundred only) and the cost of stamp paper shall be borne by you.
3. आपको इस पत्र के जारी होने की तारीख से 10 दिनों के भीतर सुरक्षा जमा के रूप में रु. **326584** (तीन लाख छब्बीस हजार पांच सौ चौरासी रुपये मात्र) जमा करने का निर्देश दिया जाता है, अन्यथा, निविदा दस्तावेज के पृष्ठ संख्या 40 पर खण्ड संख्या 1(ए) की जीसीसी के अनुसार किए गए कार्य के मूल्य का 10% सुरक्षा जमा के रूप में चालू खाता बिलों से काट लिया जाएगा। सीपीपी पोर्टल के माध्यम से आपके टेंडर के साथ ऑनलाइन भुगतान प्राप्त की गई बयाना मासिक राशि रु. **93762/-** (केवल तिरानबे हजार सात सौ बासठ रुपये) सुरक्षा जमा के जमा होने के बाद या चालू बिलों से सुरक्षा जमा के रूप में ईएमडी राशि की कटौती के बाद वापस कर दी जाएगी। / You are directed to deposit **Rs. 326584 /-** (Rupees Three Lakhs Twenty-Six Thousand Five Hundred and Eighty-Four Only) towards security deposit within 10 days from the date of issue of this letter, failing which, 10% of value of work done will be deducted from the running account bills as security deposit as per GCC of Clause No. 1(A) on page No. 40 of the Tender Document. The Earnest Money Amount of **Rs. 93762 /-** (Rupees Ninety-Three Thousand Seven Hundred and Sixty-Two only) received online payment through CPP portal along with your tender will be refunded after depositing of security deposit or after deduction of the EMD amount as Security deposit from the running bills.

[Handwritten signature]
15/11/24
Amu-2

कोयंबतूर अंतरराष्ट्रीय हवाई अड्डा / Coimbatore International Airport, कोयंबतूर / Coimbatore - 641014

Phone : 0422 - 2571941, 2571956, 2573603, 2573602, 2573561, Fax : 0422 - 2592384 / 2573223

Email: apdcoimbatore@aai.aero



Recycled & Crafted by
AAI Paper Recycling Unit
ISO 14001 : 2004 CERTIFIED UNIT

RE THINK → REDUCE → RE USE → RE CYCLE

भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
कोयंबतूर अंतरराष्ट्रीय हवाई अड्डा / Coimbatore Intl. Airport
कोयंबतूर / Coimbatore - 641 014



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

4. आपसे अनुरोध है कि आप ठेका श्रम (विनियमन एवं उन्मूलन) अधिनियम 1970 तथा ठेका श्रम (विनियमन एवं उन्मूलन) केन्द्रीय नियम 1971, बाल श्रम (प्रतिषेध एवं विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार विनियमन एवं सेवा शर्त) अधिनियम 1996, भवन एवं अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996, जैसा कि निविदा की जीसीसी के पृष्ठ 74 पर खण्ड 19 में निर्दिष्ट है, न्यूनतम मजदूरी अधिनियम तथा केन्द्रीय एवं राज्य सरकारों के नियमों के प्रावधानों का अनुपालन करें। / You are requested to comply with the provisions of Contract Labour (Regulation and Abolition) Act of 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction workers (Regulation of Employment and Condition of Service) Act 1996, Building and other Construction workers welfare Cess Act 1996 as specified in Clause 19 on page 74 of GCC of tender, Minimum Wages Act and rules of Central and State Governments.
5. आपको यह निर्देश दिया जाता है कि आप तत्काल नीचे हस्ताक्षरकर्ता से संपर्क करें, जो की आपको साइट सौंपने की व्यवस्था करेंगे। / You are also directed to contact the undersigned immediately who will arrange to hand over the site to you.
6. कृपया ध्यान दें कि कार्य करने के लिए स्वीकृत समय 06 (छह) महीने होगा, जिसमें बारिश के लिए 02 महीने शामिल होंगे तथा इसकी गणना इस पत्र के जारी होने की तारीख से 10 वें दिन से की जाएगी। / Please note that the time allowed for carrying out the work shall be **06 (Six) Months including 02 Months considered for rain** and same shall be reckoned from the 10th day from the date of issue of this letter.

[Handwritten signature]
15/9/25
Asst. Genl. Mgr.

कोयम्बतूर अन्तरराष्ट्रीय हवाई अड्डा / Coimbatore International Airport, कोयम्बतूर / Coimbatore - 641014

Phone : 0422 - 2571941, 2571956, 2573603, 2573602, 2573561, Fax : 0422 - 2592384 / 2573223

Email: apdcoimbatore@aai.aero

कोयम्बतूर अन्तरराष्ट्रीय हवाई अड्डा / Coimbatore Intl. Airport

कोयम्बतूर / Coimbatore - 641 014



Recycled & Crafted by
AAI Paper Recycling Unit
ISO 14001 : 2004 CERTIFIED UNIT

RE THINK → REDUCE → RE USE → RE CYCLE




भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

7. ठेका से संबंधित कोई भी आगे के पत्राचार को सामान्यतः प्रभारी इंजीनियर को संबोधित किया जाना चाहिए।
/ Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-Charge.
8. कृपया पावती भेजें और यहां संलग्न पत्र को हस्ताक्षर के बाद उसके प्रतिलिपि को अधोहस्ताक्षरी को प्राप्ती के तौर पर भेजें। / Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned, as a token of acceptance.

वदीय / Yours faithfully,

Encl: 1. Schedule of Quantities.
2. Form -III


मुरली कृष्ण टी / Murali Krishna T
सहा महाप्रबंधक (इंजी-सि) भ विल / AGM (Engg-Civil)-II
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
कोयंबतूर अंतर्राष्ट्रीय हवाई अड्डा / Coimbatore International Airport
कोयंबतूर / Coimbatore- 641 014

कोयंबतूर अंतर्राष्ट्रीय हवाई अड्डा / Coimbatore International Airport, कोयंबतूर सहायक महाप्रबंधक (इंजी-सि) / Coimbatore Asst. General Manager (Engg-Civil)
Phone : 0422 - 2571941, 2571956, 2573603, 2573602, 2573561, Fax : 0422 - 2592384 / 2573223
Email: apdcoimbatore@aai.aero भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
कोयंबतूर अंतर्राष्ट्रीय हवाई अड्डा / Coimbatore Intl. Airport
कोयंबतूर / Coimbatore - 641 014



Recycled & Crafted by
AAI Paper Recycling Unit
ISO 14001 : 2004 CERTIFIED UNIT

RE THINK → REDUCE → RE USE → RE CYCLE



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

एएआई/इंजीनियरिंग)सी/(एजीएम)सी-(II)/आर एंड एम-विशेष मरम्मत/डब्ल्यू2-2025/52-6
AAI/ENGG(C)/AGM(C)-II/R&M-Spl. Repairs/ W-52/2025-26

दि: 15.09.2025

Date: 15.09.2025

FORM – III

[Under rule 21(2) Of the Contract Labour (Regulation and Abolition) Central Rules, 1971; and rule 7(3) of the Inter-State Migrant Workmen (Regulation of Employment and Conditions of Service) Central Rules, 1980]

Form of Certificate by Principal Employer

Certified that:

1. I have engaged the applicant M/s. Suman Fabricators and Contractors, GIDC Industrial Estate, Zuari Nagar, (PO), Sancoale, Goa:403726 as a contractor in my establishment for the work of Special Repairs to Admin Block, Power House, AC Plant, Engg Offices and other Buildings in City Side at Coimbatore International Airport.
2. to be carried out from 29.09.2025 to 28.03.2026.
3. I undertake to be bound by all the provisions of the Contract Labour (Regulation and Abolition) Act, 1970 (37 of 1970) and the Contract Labour (Regulation and Abolition) Central Rules, 1971 / the Inter-State Migrant Workmen (Regulation of Employment and Conditions of Service) Act, 1979 (30 of 1979) and the Inter-State Migrant Workmen (Regulation of Employment and Conditions of Service) Central Rules, 1980 in so far as the provisions are applicable to me in respect of the employment of contract labour/inter-state migrant workmen by the applicant in my establishment.
4. The engagement of contract labour in the said work is not prohibited under sub section (1) of section 10 of the Contract Labour (Regulation and Abolition) Act, 1970 (37 of 1970) or an award or a settlement.

सहा महाप्रबंधक (सिविल)/ AGM (Civil) - १५

भारतीय विमानपत्तन प्राधिकरण / Airport Authority of India
कोयंबतूर अंतर्राष्ट्रीय हवाई अड्डा / Coimbatore International Airport

कोयंबतूर / Coimbatore- 641014
Asst. General Manager (Engg. Civil)

Place : Coimbatore

Date : 12.09.2025

Registration Number of the Principal Employer's establishment: R.02/2013-A/M

Name of the work: Special Repairs to Admin Block, Power House, AC Plant, Engg Offices and other Buildings in City Side at Coimbatore International Airport

LIN: 1-3429-7087-8

कोयंबतूर अंतर्राष्ट्रीय हवाई अड्डा / Coimbatore International Airport, कोयंबतूर / Coimbatore - 641014

Phone : 0422 - 2571941, 2571956, 2573603, 2573602, 2573561, Fax : 0422 - 2592384 / 2573223

Email: apdcoimbatore@aaiaero



Recycled & Crafted by
AAI Paper Recycling Unit
ISO 14001 : 2004 CERTIFIED UNIT

RE-THINK → REDUCE → RE-USE → RE-CYCLE

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Asst. Gen. Manager (Engg-civil) - II, AAI, Coimbatore International Airport

Name of Work: Special Repairs to Admin Block, Power House, AC Plant Engg Offices and other Buildings in City Side at Coimbatore International Airport

Contract No: AAI/ENGG(C)/AGM(C)-II/R&M-Spl.Repairs/W-52/2025-26

Tender ID No. 2025_AAI_238225_1

Name of the Bidder/
Bidding
SUMAN FABRICATORS AND CONTRACTORS**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excl. GST) in Figures Rs. P	TOTAL AMOUNT (Excl. GST) In Words
1	2	4	5	13	53	55
1	Providing and fixing up to floor five level precast cement concrete solid block including hoisting and setting in position with cement mortar 1:3 (1 cement : 3 coarse sand), cost of required centering, shuttering complete : 1:1½:3 (1 Cement : 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	3.50	Cum	11500.00	40250.00	INR Forty Thousand Two Hundred & Fifty Only
2	Centering and shuttering including strutting, propping etc. and removal of form for : Suspended floors, roofs, landings, balconies and access platform with water proof ply 12 mm thick	40.00	Sqm	800.00	32000.00	INR Thirty Two Thousand Only
3	Centering and shuttering including strutting, propping etc. and removal of form for : Lintels, beams, plinth beams, girders, columns, bressumers and cantilevers with water proof ply 12 mm thick	137.60	Sqm	800.00	110080.00	INR One Lakh Ten Thousand & Eighty Only
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.: Thermo-Mechanically Treated bars of grade Fe-500 D or more.	4600.00	Kg	90.00	414000.00	INR Four Lakh Fourteen Thousand Only
5	15 mm cement plaster on rough side of single or half brick wall of mix : 1:4 (1 cement: 4 coarse sand)	40.00	Sqm	400.00	16000.00	INR Sixteen Thousand Only
6	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-charge. : With cement mortar 1:4 (1cement: 4 coarse sand).	290.00	Sqm	500.00	145000.00	INR One Lakh Forty Five Thousand Only


सहायक अभियंता (सिविल)
Asst. General Manager (Engg. Civil)

भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
कोयंबटूर अन्तरराष्ट्रीय हवाई अड्डा / Coimbatore Intl. Airport

Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excl. GST) in Figures Rs. P	TOTAL AMOUNT (Excl. GST) In Words
7	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube chollies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after .The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer in-charge .The elevation area of the scaffolding shall be measured for payment purpose .The payment will be made once irrespective of duration of scaffolding.	570.00	Sqm	300.00	171000.00	INR One Lakh Seventy One Thousand Only
8	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thick water proofing membrane, black finished reinforced with glass fibre matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/sqm by the same membrane manufactured of density at 25°C, 0.87 - 0.89 kg/litre and viscosity 70 - 160 cps. Over the primer coat the layer of membrane shall be laid using butane torch and sealing all joints etc., and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 350/300 N/5 cm. Tear strength in longitudinal and transverse direction as 60/80N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D - 5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane : 3 mm thick	880.00	Sqm	590.00	519200.00	INR Five Lakh Nineteen Thousand Two Hundred Only
9	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. : In cement mortar	1.40	Cum	2500.00	3500.00	INR Three Thousand Five Hundred Only
10	Chipping of unsound/weak concrete material from slabs, beams, columns etc. with manual Chisel and/ or by standard power driven percussion type or of approved make including tapering of all edges, making square shoulders of cavities including cleaning the exposed concrete surface and reinforcement with wire brushes etc. and disposal of debris for all lead and lifts all complete as per direction of Engineer-In-Charge : 50 mm average thickness	210.00	Sqm	150.00	31500.00	INR Thirty One Thousand Five Hundred Only
11	Cleaning of reinforcement from rust from the reinforcing bars to give it a total rust free steel surface by using alkaline chemical rust remover of approved make with paint brush and removing loose particles after 24 hours of its application with wire brush and thoroughly washing with water and allowing it to dry, all complete as per direction of Engineer-In-Charge. : Bars above 12 mm diameter	2250.00	Metre	10.00	22500.00	INR Twenty Two Thousand Five Hundred Only
12	Drilling suitable holes in reinforced or plain cement concrete with power driven drill machine to a minimum depth of 100mm upto 200mm in RCC beams, lintels, columns and slabs to introduce steel bars for sunshades/balconies including fixing the steel bars in position using epoxy resin anchor grout of approved make but excluding the cost of reinforcement, all complete as per direction of Engineer-In-Charge.	2040.00	Each	250.00	510000.00	INR Five Lakh Ten Thousand Only


 Asst. General Manager (Engineering Cell)
 भारतीय विमानपत्तन निधिकरण / Airports Authority of India
 कोयंबटूर अन्तरराष्ट्रीय हवाईअड्डा / Coimbatore Intl. Airport
 कोयंबटूर / Coimbatore - 431 011


Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excl. GST) in Figures Rs. P	TOTAL AMOUNT (Excl. GST) In Words
13	Providing, mixing and applying bonding coat of approved adhesive on chipped portion of RCC as per specifications and direction of Engineer-In-charge complete in all respect. : SBR Polymer (@10% of cement weight) modified cementitious bond coat @ 2.2 kg cement per sqm of surface area mixed with specified proportion of approved polymer	240.00	Sqm	200.00	48000.00	INR Forty Eight Thousand Only
14	Providing, mixing and applying bonding coat of approved adhesive on chipped portion of RCC as per specifications and direction of Engineer-In-charge complete in all respect. Epoxy bonding adhesive having coverage 2.20 sqm/kg of approved make	200.00	Sqm	305.00	61000.00	INR Sixty One Thousand Only
15	Providing and injecting approved grout in proportion recommended by the manufacturer into cracks/honey-comb area of concrete/ masonry by suitable gun/pump at required pressure including cutting of nipples after curing etc. complete as per directions of Engineer-in- Charge. (The payment shall be made on the basis of actual weight of approved grout injected.) : Stirrer mixed SBR Polymer (of approved make) modified Cement slurry made with Shrinkage Compensating Cement in concrete/RCC work.	730.00	Kg	150.00	109500.00	INR One Lakh Nine Thousand Five Hundred Only
16	Supply and stacking including loading, unloading and secure stacking at site ready to use micro concrete Renderoc RG of FOSROC or equivalent self levelling flow grade micro concrete composed of good quality special cement, graded aggregates & additives/ chemicals to produce a free flowing non shrink repair material used & designed for repairing of damaged reinforced concrete elements like columns, beams & structure where the areas are restricted or not easily accessible for proper placement of concrete using vibrator .Bags with valid shelf life only shall be permitted and shall be consumed within the period of shelf life nothing extra shall be paid on expiry of shelf life.	23100.00	Kg	22.00	508200.00	INR Five Lakh Eight Thousand Two Hundred Only
17	Cutting, demolishing of old RCC Over Head Water Tank lying inside shaft of departure terminal building by engaging approved demolishing agency having previous experience in similar nature of works. RCC slab / RCC wall / RCC column members shall be cut into pieces of required size 0.30x0.30, 0.30x0.60 and 0.60x0.91 OR approved size by using wall saw cutter (Diamond wire saw rope) machine of approved make including safely lowering the cut pieces / blocks to ground level using chain pully / suitable similar arrangement including necessary anchoring/staging. Demolished / cut RCC blocks shall be taken outside from shaft / terminal building & stacking at designated place (minimum 100M far from terminal building) and safely transport from airport premises to approved local dump yards including necessary arrangement of loading & transportation charges etc complete as per the directions of EIC. All the debris generated (at inside shaft & outside stacking area) during demolishing & stacking shall cleared by agency on own expenses. Cost of work shall include all charges for deploying necessary machinery, skilled man power (including necessary insurance & safety measures), shifting of material & transport to dump yard & including cost adjustment for reinforcement bars generated from demolished concrete member (Approximate 2.5 to 3 Mt of reinforcement may be present in RCC structure). Work shall be carried inside terminal building during night 11 PM upto 6 AM without causing hindrance to passenger movement & operations.	1.00	Job	535000.00	535000.00	INR Five Lakh Thirty Five Thousand Only


 सहायक महाप्रबंधक (सिविल)
 Asst. General Manager (Civil)
 भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
 कोयंबटूर अंतरराष्ट्रीय हवाई अड्डा / Coimbatore Intl. Airport
 कोयंबटूर

Sl. No.	Item Description	Quantity	Units	BASIC RATE (Excl. GST) in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT (Excl. GST) in Figures Rs. P	TOTAL AMOUNT (Excl. GST) In Words
18	Shotcreting R.C.C. columns, beams and slabs etc. using in layers with approved grade and mix of micro concrete having the specified minimum characteristic compressive strength [with Renderoc RG or equivalent self levelling micro concrete, cement and silt free graded stone aggregate of 10 mm maximum size in proportion as per design criteria] as directed by Engineer-in-Charge Note: Rates shall include the providing necessary ground wires etc. The levelling gauges, if used, shall be paid for separately. Rates shall not include Rendroc RG or Equivalent Micro Concrete, cement, centering and shuttering. Payment under this item shall be made only after proper wet curing has been done and surface has been satisfactorily evaluated by sounding/ tapping with a blunt metal instrument.	220.00	Sqm	650.00	143000.00	INR One Lakh Forty Three Thousand Only
Total in Figures					3419730.00	INR Thirty Four Lakh Nineteen Thousand Seven Hundred & Thirty Only
Quoted Rate in Words		INR Thirty Four Lakh Nineteen Thousand Seven Hundred & Thirty Only				

Less Rebate offered by Agency during
negotiation @ 4.5% on quoted (-) 1,53,887.85/-
Amount of Rs 34,19,730/-

Net Amount: Rs 32,65,842.15/-
By Rs 32,65,842/-

 15/9/24

सहायक महाप्रबन्धक (इंजी. सि.)
Asst. General Manager (Engg. Civil)

भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
कोयंबटूर अंतरराष्ट्रीय हवाई अड्डा / Coimbatore Intl. Airport
कोयंबटूर / Coimbatore - 441 014