



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

सं.स. : भाविप्रा / वारा / अभि. / डीवीओआर / डब्लू-116 / 1539-52/5860-75
Ref No.: AAI/VNS/ENGG/DVOR /W-116/
सेवा में,

दिनांक: 05.08.2025
Date: 05.08.2025
06

मेसर्स एस.के. कन्स्ट्रक्शन
ग्राम-बरेमा, पोस्ट-रामेश्वर
वाराणसी-221405

M/s SK Construction,
Vill-Barema, Post-Rameshwar,
Varanasi-221405

विषय : एलबीएसआई हवाई अड्डा, वाराणसी में नए डीवीओआर भवन का निर्माण।

Construction of new DVOR building at LBSI Airport, Varanasi (Tender ID : 2025_AAI_239535_1)

संदर्भ : ई-निविदा खुलने की तिथि : 31.07.2025

प्रिय महोदय/Dear Sir,

- 1) उपरोक्त कार्य की, कुल निविदा रकम रुपये 1,19,63,493.45 (रुपया एक करोड़ उन्नीस लाख तीरसठ हजार चार सौ तीरान्बे एवं पैतिलिस पैसे मात्र) (जी.एस.टी. रहित) की मद दर निविदा, जो कि कार्य की अनुमानित लागत रुपये 174.25 लाख (जी.एस.टी. रहित) से 31.34% (इक्तीस दशमलव तीन चार प्रतिशत) कम है, आपके द्वारा निविदा प्रपत्र की अनुसूची 'अ' में दर्शायी गयी मद दरों पर भरी गई है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the net tender amount Rs. 1,19,63,493.45 (Rupees One Crore Nineteen Lakhs Sixty Three Thousand Four Hundred Ninety Three and Forty Five Paise only) (excluding GST) which is 31.34% (Thirty One Point Three Four percent) below to the estimated cost put to tender of Rs. 174.25 lakhs (excluding GST).

- 2) वरि० प्रबन्धक (अभि०-सिविल), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी इस कार्य के कार्य प्रभारी अभियन्ता होंगे तथा प्रबन्धक (अभि०-सि०), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी उनके प्राधिकृत प्रतिनिधि होंगे। आपसे अनुरोध है कि दिनांक 30.08.2025 तक वरि० प्रबन्धक (अभि०-सिविल) के कार्यालय में उपस्थित होकर संविदा अनुबन्ध को हस्ताक्षरित कर पूर्ण करें। अनुबन्ध 100/- रुपये के गैर न्यायिक स्टाम्प पेपर पर सम्पादित किया जाएगा, स्टाम्प पेपर की कीमत आपके द्वारा वहन की जाएगी।

The Sr. Manager (Engg-Civil), AAI, Lal Bahadur Shastri International Airport, Varanasi shall be the Engineer-in-charge of the work and Manager (E-C), AAI, Lal Bahadur Shastri International Airport, Varanasi shall be our authorised representative. You are requested to attend the office of the Sr. Manager (Engg-Civil) by 30.08.2025 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- and the cost of stamp paper shall be borne by you.

- 3) धरोहर राशि रुपये 5,22,750.00 (रुपया पाँच लाख बाइस हजार सात सौ पचास मात्र) संविदा प्रपत्र के अनुच्छेद 1ए पेज 16 के अनुसार प्रतिभूति निक्षेप राशि का हिस्सा मानकर उसमें बदल दिया जाएगा। कृपया शेष प्रतिभूति निक्षेप राशि रुपये 6,73,600.00 (रुपया छः लाख तीहत्तर हजार छः सौ मात्र) इस पत्र के निर्गत दिनांक से दस दिनों के भीतर जमा करें अन्यथा उक्त धनराशि की कटौती संविदा प्रपत्र की उक्त संदर्भित शर्त के अनुसार चालू लेखा बिलों से की जाएगी।

The earnest money amount of Rs. 5,22,750.00 (Rupees Five Lakhs Twenty Two Thousand Seven Hundred Fifty only) received along with your tender will be treated and converted as a part of security deposit. Please deposit Rs.6,73,600.00 (Rupees Six Lakhs Seventy Three Thousand Six Hundred only), towards balance security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from the Running Account Bills as per condition GCC 1A on page 16 of the contract document.

शेष पृष्ठ 2 पर....

कार्यालय: निदेशक विमानपत्तन, लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी-221006 टेलीफोन: 2622155, फैक्स नं० 0542-2622320
O/o Airport Director, Lal Bahadur Shastri Airport, Varanasi-221006 Phone: 2622155, Fax: 0542-2622320

वरि० प्रबन्धक (अभि. सिविल)
भा.वि.प्रा. (अभि. सिविल)
आर. प्र. विमानपत्तन प्राधिकरण
Airports Authority
लाल बहादुर शास्त्री अंतर्राष्ट्रीय
हवाई अड्डा, वाराणसी
Lal Bahadur Shastri International
Airport, Varanasi

- 4) आपसे अनुरोध है कि संविदा श्रमिक प्रावधान (विनिमय एवं उन्मूलन) एक्ट 1970, श्रमिक प्रावधान (विनिमय एवं उन्मूलन)-केन्द्रीय नियम 1971, न्यूनतम मजदूरी अधिनियम एवं इस सम्बन्ध में केन्द्र/राज्य सरकार के नियमों का पालन करना सुनिश्चित करें।
You are requested to comply with the provisions of Contract Labour (Regulation & Abolition) Act of 1970 and Contract Labour (Regulation & Abolition) Central rules 1971 and Minimum Wages Act & Rules thereof Central and State Governments with upto date amendments.
- 5) आपको निर्देशित किया जाता है कि आप तुरन्त प्रभाव से प्रबन्धक (अभि०-सि०), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी से सम्पर्क करें जो आपको कार्यस्थल सौपने की व्यवस्था करेंगे।
You are also directed to contact the Manager (E-C), AAI, Lal Bahadur Shastri International Airport, Varanasi, immediately who will arrange to hand over the site to you.
- 6) कृपया ध्यान दें कि कार्य पूर्ण करने की अवधि 06 महीने (एक महीना वर्षा काल सहित) हैं, जो कि इस पत्र के जारी होने के 10वें दिन से प्रभावी मानी जाएगी।
Please note that time allowed for carrying out the work shall be 06 months (i/c one month rainy season) and the same shall be reckoned from the 10th day after issue of this letter.
- 7) संविदा के सन्दर्भ में किसी भी प्रकार का पत्राचार सामान्यतः वरि० प्रबन्धक (अभि-सिविल), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी-221006, को सम्बोधित करें।
Any further correspondence in connection with the contract should normally be addressed to the Sr. Manager (Engg-Civil), AAI, Lal Bahadur Shastri International Airport, Varanasi-221006
- 8) कृपया इस पत्र की पावती भेजें एवं पत्र कि अनुलिपि जो कि संलग्न है को हस्ताक्षरित कर अधोहस्ताक्षरी को स्वीकृत चिन्ह के रूप में वापस करें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
- 9) विषयक कार्य से संबंधित अनुसूची-अ, (कुल प्रष्ठ 13 (सिविल कार्य रु. 1,19,63,493.45) संलग्न है।
Schedule 'A' (total page 13) (Civil works Rs. 1,19,63,493.45) of the work is enclosed.

उपरोक्त के हिन्दी पाठ में कोई अन्तर या द्विधार्थकता होने की स्थिति में अंग्रेजी पाठ मान्य होगा।

In case of difference or ambiguity in Hindi and English version, the English version will prevail.

धन्यवाद।

भवदीय

संलग्नक- यथोपरि

Encl:- As above

व०प्र.(अभि.-सिविल),
SM (Engg-Civil)

अध्यक्ष, भा०वि०प्रा० के लिए व उनकी तरफ से
For and on behalf of the Chairman, AAI

वरि० प्रबन्धक (अभि. सिविल)
Sr. Manager (Engg. Civil)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
लाल बहादुर शास्त्री अन्तर्राष्ट्रीय



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

प्रतिलिपि:

मूल प्रति पर नहीं (NOO)

अ. बाहरी-

1. कार्यपालक निदेशक (MIS & STD), भाविप्रा, सी.एच.क्यू., नई दिल्ली: सूचनार्थ
2. क्षेत्रीय कार्यपालक निदेशक (उ0क्षे0), भाविप्रा, आर.एच.क्यू., नई दिल्ली I: सूचनार्थ
3. महाप्रबन्धक (अभि)-(MIS & STD), भाविप्रा, सी.एच.क्यू., नई दिल्ली: सूचनार्थ
4. सहायक श्रम आयुक्त (सी), 189-ए/4ए, अलोपी बाग, पोस्ट-दारागंज, प्रयागराज : सूचनार्थ
5. श्रम प्रवर्तन अधिकारी (सी), 189-ए/4ए, अलोपी बाग, पोस्ट-दारागंज, प्रयागराज : सूचनार्थ

ब. आंतरिक-

- | | | |
|-------------------------------------|---|------------------------|
| 1. निदेशक विमानपत्तन | : | सूचनार्थ |
| 2. महाप्रबन्धक(अभि)-परियोजना | : | -तदैव- |
| 3. सं.म.प्र. (अभि-विद्युत)-परियोजना | : | -तदैव- |
| 4. उ.म.प्र. (अभि-सिविल)-परियोजना | : | -तदैव- |
| 5. उ.म.प्र. (अभि-सिविल)-अनुरक्षण | : | -तदैव- |
| 6. सं.म.प्र. (अभि-विद्युत)-अनुरक्षण | : | -तदैव- |
| 7. प्रभारी (वित्त) | : | -तदैव- |
| 8. प्रबन्धक (अभि-सिविल) | : | आवश्यक कार्यवाही हेतु। |
| 9. कार्यादेश फाईल | : | |
| 10. अनुबन्ध | : | |

Handwritten signature

व०प्र.(अभि.-सिविल),
भा.वि.प्रा, लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन,
वाराणसी

हरीश प्रबन्धक (अभि-सिविल)
Sr. Manager (Admin. Civil)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
लाल बहादुर शास्त्री अन्तर्राष्ट्रीय
हवाई अड्डा, वाराणसी
Lal Bahadur Shastri International
Airport, Varanasi

Tender Inviting Authority: Airports Authority of India

Name of Work: Construction of new DVOR building at LBSI Airport, Varanasi.

Contract No: 2025_AAI_239535_1

Name of the Bidder/ Bidding Firm / Company : SK CONSTRUCTION PROP SURENDRA KUMAR YADAV R/O BAREMA POST RAMESHWAR VARANASI

PRICE SCHEDULE

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
1	2	3	4	5	7	8	10
0.1	Civil Works						
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. a) All kinds of soil.	Item1	1118.00	Cum	65.00	72670.00	INR Seventy Two Thousand Six Hundred & Seventy Only
2	Extra for every additional lift of 1.5 m or part thereof in excavation / banking excavated or stacked materials. All kinds of soil	Item2	111.00	cum	20.00	2220.00	INR Two Thousand Two Hundred & Twenty Only
3	Excavating trenches by mechanical / manual means of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, for all depth, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m : All kinds of soil a) Pipes, cables etc. exceeding 80 mm dia. but not exceeding 300 mm dia	Item3	498.00	Mtr	36.00	17928.00	INR Seventeen Thousand Nine Hundred & Twenty Eight Only
4	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 and for all lift.	Item4	1118.00	Cum	60.00	67080.00	INR Sixty Seven Thousand & Eighty Only
5	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	Item5	140.00	Cum	925.00	129500.00	INR One Lakh Twenty Nine Thousand Five Hundred Only
6	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m.	Item6	1391.00	Sqm	10.00	13910.00	INR Thirteen Thousand Nine Hundred & Ten Only
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	Item7	197.00	Cum	4180.00	823460.00	INR Eight Lakh Twenty Three Thousand Four Hundred & Sixty Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand (zone-II) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	Item8	439.00	Cum	5180.00	2274020.00	INR Twenty Two Lakh Seventy Four Thousand & Twenty Only
9	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	Item9	11.00	Cum	5060.00	55660.00	INR Fifty Five Thousand Six Hundred & Sixty Only
10	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works upto plinth level (a). Concrete of M25 grade with minimum cement content of 330 kg /cum	Item10	218.00	Cum	6480.00	1412640.00	INR Fourteen Lakh Twelve Thousand Six Hundred & Forty Only
11	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works above plinth level upto floor V level (a). Concrete of M25 grade with minimum cement content of 330 kg /cum	Item11	45.00	Cum	6560.00	295200.00	INR Two Lakh Ninety Five Thousand Two Hundred Only
12	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. (Thermo-Mechanically Treated bars of grade Fe-500D or more.)	Item12	26160.00	Kg	62.00	1621920.00	INR Sixteen Lakh Twenty One Thousand Nine Hundred & Twenty Only
13	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. (Thermo-Mechanically Treated bars of grade Fe-500D or more.)	Item13	5400.00	Kg	65.00	351000.00	INR Three Lakh Fifty One Thousand Only
14	Providing and fixing mild steel round holding down bolts with nuts, washer & plates complete.	Item14	750.00	Kg	102.00	76500.00	INR Seventy Six Thousand Five Hundred Only

SM (E-C)

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
15	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete	Item15	1372.00	Kg	91.00	124852.00	INR One Lakh Twenty Four Thousand Eight Hundred & Fifty Two Only
16	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	Item16	477.00	Kg	95.00	45315.00	INR Forty Five Thousand Three Hundred & Fifteen Only
17	Centering and shuttering including strutting, propping etc. and removal of form for : (a) Foundations, footings, bases for columns etc. for mass concrete.	Item17	676.00	Sqm	115.00	77740.00	INR Seventy Seven Thousand Seven Hundred & Forty Only
18	Centering and shuttering including strutting, propping etc. and removal of form work for : (a) Columns, piers, abutments, pillars, posts and struts	Item18	452.00	Sqm	225.00	101700.00	INR One Lakh One Thousand Seven Hundred Only
19	Centering and shuttering including strutting, propping etc. and removal of form work for : (Lintels, beams, plinth beams, girders, bressumers and Cantilevers.)	Item19	492.00	Sqm	125.00	61500.00	INR Sixty One Thousand Five Hundred Only
20	Centering and shuttering including strutting, propping etc. and removal of form work for : (Suspended floors, roofs, landings, balconies and access platform)	Item20	72.00	Sqm	365.00	26280.00	INR Twenty Six Thousand Two Hundred & Eighty Only
21	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in : a) cement mortar 1:4 (1 cement : 4 coarse sand)	Item21	54.77	Sqm	680.00	37243.60	INR Thirty Seven Thousand Two Hundred & Forty Three and Paise Sixty Only
22	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. : a) cement mortar 1:4 (1 cement : 4 coarse sand)	Item22	2.25	Sqm	710.00	1597.50	INR One Thousand Five Hundred & Ninety Seven and Paise Fifty Only
23	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in : a) Cement mortar 1:6 (1 cement : 6 coarse sand)	Item23	129.50	Cum	5160.00	668220.00	INR Six Lakh Sixty Eight Thousand Two Hundred & Twenty Only
24	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : a) Cement mortar 1:6 (1 cement : 6 coarse sand)	Item24	108.61	Cum	5280.00	573460.80	INR Five Lakh Seventy Three Thousand Four Hundred & Sixty and Paise Eighty Only
25	12 mm cement plaster of mix : 1:4 (1 cement: 4 coarse sand)	Item25	1012.28	Sqm	195.00	197394.60	INR One Lakh Ninety Seven Thousand Three Hundred & Ninety Four and Paise Sixty Only
26	12 mm cement plaster finished with a floating coat of neat cement :	Item26	34.79	Sqm	265.00	9219.35	INR Nine Thousand Two Hundred & Nineteen and Paise Thirty Five Only
27	15 mm cement plaster on rough side of single or half brick wall of mix: 1:4 (1 cement: 4 coarse sand)	Item27	954.08	Sqm	225.00	214668.00	INR Two Lakh Fourteen Thousand Six Hundred & Sixty Eight Only
28	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	Item28	399.00	Sqm	165.00	65835.00	INR Sixty Five Thousand Eight Hundred & Thirty Five Only

SM (E-C)

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
29	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Item29	402.00	Sqm	75.00	30150.00	INR Thirty Thousand One Hundred & Fifty Only
30	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	Item30	300.00	Sqm	95.00	28500.00	INR Twenty Eight Thousand Five Hundred Only
31	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm)	Item31	1870.96	Sqm	85.00	159031.60	INR One Lakh Fifty Nine Thousand & Thirty One and Paise Sixty Only
32	Distemping with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gram/litre, of approved manufacturer and of required shade and colour all complete to achieve even shade and colour : New work (two or more coats) over and including water thinnable priming coat with cement primer having VOC content less than 50 gram/litre	Item32	285.00	Sqm	65.00	18525.00	INR Eighteen Thousand Five Hundred & Twenty Five Only
33	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete at all levels. Granite stone slab colour black, Cherry/Ruby red or approved by EIC. a) Area of slab over 0.50 sqm	Item33	2.00	Sqm	3260.00	6520.00	INR Six Thousand Five Hundred & Twenty Only
34	Extra for providing opening of required size & shape for wash basin/ kitchen sink in kitchen platform, vanity counter and similar location in marble/ Granite/ stone work, including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete.	Item34	1.00	Each	1200.00	1200.00	INR One Thousand Two Hundred Only
35	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. a) 60mm thick cement concrete paver block of M-35 grade with approved colour, design & pattern.	Item35	90.00	Sqm	860.00	77400.00	INR Seventy Seven Thousand Four Hundred Only

 SM (E-C)

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
36	Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only. Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily. a) Glazed Vitrified tiles Matt/Antiskid finish of size i) Size of Tile 600 x 600 mm	Item36	65.00	Sqm	1040.00	67600.00	INR Sixty Seven Thousand Six Hundred Only
37	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 600x600 mm	Item37	20.00	Sqm	1120.00	22400.00	INR Twenty Two Thousand Four Hundred Only
38	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) a) For fixed portion 1) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	Item38	140.00	Kg	415.00	58100.00	INR Fifty Eight Thousand One Hundred Only
39	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) a) For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) i) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	Item39	250.00	Kg	440.00	110000.00	INR One Lakh Ten Thousand Only

SM (E-C)

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
40	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer-in-charge. a) Prelaminated particle board with decorative lamination on one side and balancing lamination on other side.	Item40	16.00	Sqm	680.00	10880.00	INR Ten Thousand Eight Hundred & Eighty Only
41	Providing and fixing false ceiling at all heights with integral densified calcium silicate reinforced with fibre and natural filler false ceiling tiles of Size 595x595 mm of approved texture, design and patterns having NRC (Noise Reduction coefficient) of 0.50 (minimum) as per IS 8225:1987, Light reflectance of 85% (minimum). Non combustible as per BS:476 (part-4), fire performance as per BS:476 (part 6 & 7), humidity resistance of 100%, thermal conductivity < 0.043 W/m K as per ASTM 518:1991, in true horizontal level suspended on inter-locking metal powder coated T-Grid of hot dipped galvanised iron section of 0.40 mm thick on Silhouette profile, rotary stitched double webbed white with 6 mm reveal profile (white/black), comprising of main-T runners of size 15x42 mm of length 3000 mm, cross - T of size 15x42 mm of length 1200 mm and secondary intermediate cross-T of size 15x42 mm of length 600 mm to form grid module of size 600 x 600 mm, suspended from ceiling using galvanised mild steel items (galvanizing @ 80 grams per sqm) i.e. 50 mm long, 8 mm outer diameter M-6 dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape level adjuster of size 85x25x2 mm. Galvanised iron perimeter wall angle of size 22x19x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450 mm center to center and 40 mm long dry wall S.S screws. The work shall be carried out as per specifications, drawing and as per directions of the Engineer-in-Charge. a) With 15 mm thick integral densified micro edge lightweight calcium silicate false ceiling tiles	Item41	48.00	Sqm	1650.00	79200.00	INR Seventy Nine Thousand Two Hundred Only

SM (E-C)

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
42	Providing and fixing in position wall panelling at all heights with integral densified calcium silicate panels/tiles of size 595 x 595 mm, having NRC (Noise Reduction coefficient) of 0.50 (minimum) as per IS 8225:1987, Light reflectance of 85% (minimum). Non combustible as per BS:476 (part-4), fire performance as per BS:476 (part 6 & 7), humidity resistance of 100%, thermal conductivity <0.043 W/m K as per ASTM 518:1991, comprising of a frame made from especially fabricated galvanised mild steel sheet 0.50 mm thick pressed section (galvanizing @120 grams per sqm including both sides) i.e. vertical studs of size 48 x 34 x 36 mm are placed at 600 mm centre to centre in a floor and ceiling channel section of size 50 x 32 mm fixed to the floor and soffit at 600 mm centre using 12 mm dia, 50 mm long wedge type expanded zinc alloy dash fastener with 10 mm bolt. This same channel is then to be fixed in horizontal direction at 600 mm centre to centre so as to form a grid of 600 mm x 600 mm. Glasswool of 50 mm thickness is then to be inserted in the slots and finally calcium silicate non combustible panels/tiles are to be screw fixed with self tapping pan head nickel coated mild steel screws of size 13 x 3.2 mm on to this grid leaving an even groove of 1 mm between the panels. The joints between the panels are to be duly jointed and finished using recommended jointing calcium silicate based compound and fiber joint tape roll 50 mm wide (90 metre)roll and two coats of primer suitable for panelling as per manufacturer's specification as per direction of Engineerin- Charge all complete. a) With 15 mm thick fully perforated square/butt edge light weight calcium silicate panels/ tiles	Item42	38.00	Sqm.	1260.00	47880.00	INR Forty Seven Thousand Eight Hundred & Eighty Only
43	Providing and fixing aluminium window stay hook with necessary screws etc. complete as per direction of Engineering In-charge.	Item43	6.00	Each	125.00	750.00	INR Seven Hundred & Fifty Only
44	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): a) With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)	Item44	18.00	Sqm	780.00	14040.00	INR Fourteen Thousand & Forty Only
45	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply and all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. a) Internal work-Exposed on wall -25 mm nominal dia Pipes	Item45	20.00	Mtr.	315.00	6300.00	INR Six Thousand Three Hundred Only
46	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply and all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. a) Internal work-Exposed on wall - 50 mm nominal dia Pipes	Item46	75.00	Mtr.	460.00	34500.00	INR Thirty Four Thousand Five Hundred Only

SM (E-C)

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
47	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings and fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. a) 20 mm nominal dia Pipes	Item47	25.00	Mtr.	365.00	9125.00	INR Nine Thousand One Hundred & Twenty Five Only
48	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.a) External work - 25 mm nominal dia Pipes	Item48	256.00	Mtr.	380.00	97280.00	INR Ninety Seven Thousand Two Hundred & Eighty Only
49	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	Item49	1000.00	Ltr.	14.00	14000.00	INR Fourteen Thousand Only
50	Making soak pit 2.5 m diameter 3.0 metre deep with 45 x 45 cm dry brick honey comb shaft with bricks and S.W. drain pipe 100 mm diameter, 1.8 m long complete as per standard design. With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	Item50	1.00	Each	16800.00	16800.00	INR Sixteen Thousand Eight Hundred Only
51	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x 300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design: 100x100 mm size P type With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	Item51	2.00	Each	1280.00	2560.00	INR Two Thousand Five Hundred & Sixty Only
52	Providing & Fixing of CP brass towel rail complete with brackets fixed to wooden cleats & screws with concealed fitting arrangement of approved quality as per direction and satisfaction of Engineer-in-charge. 600mm x 20mm size.	Item52	1.00	Each	380.00	380.00	INR Three Hundred & Eighty Only
53	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete	Item53	1.00	Each	1100.00	1100.00	INR One Thousand One Hundred Only
54	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: a) White Vitreous China Flat back wash basin size 550x 400 mm with single 15 mm C.P. brass pillar tap	Item54	1.00	Each	1650.00	1650.00	INR One Thousand Six Hundred & Fifty Only
55	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 25 mm nominal bore	Item55	2.00	Each	850.00	1700.00	INR One Thousand Seven Hundred Only
56	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete : a) 25 mm nominal bore	Item56	2.00	Each	1160.00	2320.00	INR Two Thousand Three Hundred & Twenty Only
57	Providing and fixing uplasticsed PVC connection pipe with brass unions : a) 45 cm length - 15 mm nominal bore	Item57	3.00	Each	25.00	75.00	INR Seventy Five Only

SM(E-C)

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
58	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : a) W.C. pan with ISI marked white solid plastic seat and lid	Item58	1.00	Each	6500.00	6500.00	INR Six Thousand Five Hundred Only
59	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 : a) 15 mm nominal bore	Item59	3.00	Each	650.00	1950.00	INR One Thousand Nine Hundred & Fifty Only
60	Providing and fixing toilet paper holder : C.P. brass	Item60	1.00	Each	125.00	125.00	INR One Hundred & Twenty Five Only
61	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms.	Item61	1.00	Each	600.00	600.00	INR Six Hundred Only
62	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 a) 15mm nominal bore	Item62	5.00	Each	555.00	2775.00	INR Two Thousand Seven Hundred & Seventy Five Only
63	P/F Stainless Steel anti cockroach floor Jali of approved make of 100 mm dia fixing over water outlet complete as per direction and satisfaction of Engineer-in-charge	Item63	3.00	Each	350.00	1050.00	INR One Thousand & Fifty Only
64	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge.	Item64	1.00	Each	960.00	960.00	INR Nine Hundred & Sixty Only
65	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required : Kitchen sink without drain board 610x510 mm bowl depth 200 mm	Item65	1.00	Each	5650.00	5650.00	INR Five Thousand Six Hundred & Fifty Only


SM (E-C)

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Rs. P	TOTAL AMOUNT in Words
66	Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc consisting of following operations: (a) Applying a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge over the RCC slab including adjoining walls upto 300 mm height including cleaning the surface before treatment. (b) Laying brick bats with mortar using broken bricks/brick bats 25 mm to 115 mm size with 50% of cement mortar 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge over 20 mm thick layer of cement mortar of mix 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge to required slope and treating similarly the adjoining walls upto 300 mm height including rounding of junctions of walls and slabs. (c) After two days of proper curing applying a second coat of cement slurry using 2.75 kg/ sqm of cement admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge. (d) Finishing the surface with 20 mm thick jointless cement mortar of mix 1:4 (1 cement : 4 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge including laying glass fibre cloth of approved quality in top layer of plaster and finally finishing the surface with trowel with neat cement slurry and making pattern of 300x300 mm square 3 mm deep. (e) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test. "All above operations to be done in order and as directed and specified by the Engineer-in-Charge". 1) With average thickness of 120 mm and minimum thickness at khurra as 65 mm.	Item66	88.00	Sqm.	1600.00	140800.00	INR One Lakh Forty Thousand Eight Hundred Only
67	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete.	Item67	10.00	Each	860.00	8600.00	INR Eight Thousand Six Hundred Only
68	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : a) 250x16 mm	Item68	12.00	Each	180.00	2160.00	INR Two Thousand One Hundred & Sixty Only
69	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : a) 150x10 mm	Item69	6.00	Each	150.00	900.00	INR Nine Hundred Only
70	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : a) 125 mm	Item70	20.00	Each	110.00	2200.00	INR Two Thousand Two Hundred Only
71	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. a) Single rubber stopper	Item71	10.00	Each	80.00	800.00	INR Eight Hundred Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
72	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : a) 100 mm dia. R.C.C. Pipe	Item72	274.00	Mtr.	365.00	100010.00	INR One Lakh & Ten Only
73	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : a) 150 mm dia. R.C.C. Pipe	Item73	225.00	Mtr.	425.00	95625.00	INR Ninety Five Thousand Six Hundred & Twenty Five Only
74	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : a) 250 mm dia. R.C.C. Pipe	Item74	50.00	Mtr.	540.00	27000.00	INR Twenty Seven Thousand Only
75	Providing and fixing in position pre-cast R.C.C. manhole cover and frame of required shape and approved quality 1) M D - 10	Item75	2.00	each	4450.00	8900.00	INR Eight Thousand Nine Hundred Only
76	a) Circular shape 500 mm internal diameter Providing & fixing roller blinds of Mac, blackout or equivalent of required size (as per site) all complete as per direction of Engineer-in-charge.	Item76	6.25	sqm	3120.00	19500.00	INR Nineteen Thousand Five Hundred Only
77	Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with floating coat of neat cement complete as per standard design : a) Inside size 90x80 cm and 45 cm deep including C.I. cover with frame (light duty) 455x610 mm internal dimensions, total weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) - With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	Item77	2.00	Each	6500.00	13000.00	INR Thirteen Thousand Only
78	Providing and fixing bright finished brass 100 mm mortice latch and lock with 6 levers and a pair of lever handles of approved quality with necessary screws etc. complete.	Item78	6.00	Each	1410.00	8460.00	INR Eight Thousand Four Hundred & Sixty Only
79	Providing and filling in position, blown bitumen (VG-10) in joints including cutting the joints in concrete surface with joint cutting machine, cleaning the joints, applying masking tape along the edge of joint to prevent accidental spillage of bitumen on top surface and to give neat finish to the bitumen and removing the masking tape after application of sealant etc. complete as per direction of Engineer in-Charge. a) Construction joint of size 10 mm wide and 50 mm depth.	Item79	2.50	cum	120410.00	301025.00	INR Three Lakh One Thousand & Twenty Five Only
80	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. A) 110 mm diameter	Item80	14.00	Mtr.	460.00	6440.00	INR Six Thousand Four Hundred & Forty Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
81	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. a) 110 mm bend	Item81	4.00	Each	80.00	320.00	INR Three Hundred & Twenty Only
82	Providing and fixing to the inlet mouth of rain water pipe cast iron grating 15 cm diameter and weighing not less than 440 grams.	Item82	4.00	Each	350.00	1400.00	INR One Thousand Four Hundred Only
83	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. a) Shoe (Plain) i) 110 mm Shoe	Item83	4.00	Each	85.00	340.00	INR Three Hundred & Forty Only
84	Providing and laying uPVC pipes for drainage (soil, waste and vent), including jointing, leaving 10 mm gap for thermal expansion, (i) Single socketed 110 mm dia pipes all includes as per direction and satisfaction of Engineer In Charge.	Item84	55.00	Mtr.	465.00	25575.00	INR Twenty Five Thousand Five Hundred & Seventy Five Only
85	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-II (size range 53 mm to 0.075 mm) having CBR Value-25	Item85	47.70	cum	1680.00	80136.00	INR Eighty Thousand One Hundred & Thirty Six Only
86	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	Item86	47.70	cum	1810.00	86337.00	INR Eighty Six Thousand Three Hundred & Thirty Six and Paise One Hundred Only
87	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. Note-Compaction shall be done with needle vibrator and screed vibrator. The panel shall be made with C-Channel of the full height of concrete to be laid and floater will be applied there upon and proper texture will be made with booming. Initially Mechanically cutting of dummy joints 3mm wide x 1/3rd thickness shall have to cut. Subsequently groove cutting as per dummy/construction/expansion joints will be done 10mm width x 50mm deep as per satisfaction of Engineer-in-Charge and Noting extra shall be paid for performing these activity.	Item87	60.00	cum	5680.00	340800.00	INR Three Lakh Forty Thousand Eight Hundred Only
88	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 metres.	Item88	72.00	sqm	65.00	4680.00	INR Four Thousand Six Hundred & Eighty Only

SM (E-C)

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
89	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	Item89	325.00	metre	305.00	99125.00	INR Ninety Nine Thousand One Hundred & Twenty Five Only
90	Add for using extra cement in the items of design mix over and above the specified cement content therein	Item90	66.00	Qtl	625.00	41250.00	INR Forty One Thousand Two Hundred & Fifty Only
91	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :	Item91	20.00	Mtr.	3240.00	64800.00	INR Sixty Four Thousand Eight Hundred Only
92	Preparation and submission of detailed structural design and drawings of DVOR building etc. complete as per scope of work including vetting through IIT/NIT/govt. institute as per direction of Engineer-In-Charge	Item92	1.00	JOB	125000.00	125000.00	INR One Lakh Twenty Five Thousand Only
Total in Figures						11963493.45	INR One Crore Nineteen Lakh Sixty Three Thousand Four Hundred & Ninety Lakh Sixty Three
Quoted Rate in Words							INR One Crore Nineteen Lakh Sixty Three Thousand Four Hundred & Ninety Three and Paise Forty Five Only

Signature

For Manager (Engg. Civil)
 Sr. Manager
 Ministry of Road Transport and Highways
 National Highway Authority of India
 Airport, Varanasi

Signature Not Verified

Digitally signed by VINOD KUMAR PANDEY
 Date: ... : IST
 Location: eProcurement System for Central PSUs