



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

VIJAYAWADA AIRPORT, VIJAYAWADA-521102

26/10/2025
25/04/2026

Ref no. AAI/VIJ/ENGG(C)/MISC-04/25-26/113

Dt. 15-10-2025

To,

M/s K Constructions,
Ground Floor, Plot no.213 & 214, C Block,
Vagdevi Nilayam, Gachibowli, Miyapur Road,
Kondapur, Hyderabad, Rangareddy,
Telangana-500 084.

Name of work: Construction of New Integrated Terminal building and associated works at
Vijayawada Airport.

Sub Head: Miscellaneous Civil works of New Integrated Terminal building.

- Ref:** 1. Tender ID: 2025_AAI_240106_1
2. Financial bid opened on 10.09.2025
3. This office vide e-mail dated 07-10-2025
4. Your letter vide no. NIL dt.07-10-2025

Dear Sir(s),

1. Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs. 4,30,47,286/- (Rupees Four Crores Thirty Lakhs Fourty Seven Thousand Two Hundred and Eighty-Six only)**, which is 25.31% below the estimated cost put to tender of Rs. 5,76,37,200/- (excluding GST).
2. Dy. General Manager (Engg-C), AAI, Vijayawada Airport, Vijayawada shall be the Engineer-In-Charge of the work. You are requested to attend the office of Dy. General Manager (Engg - C), AAI, Vijayawada Airport, by 30/10/2025 to sign and complete the contract agreement. The contract agreement shall be executed on non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred Only) and the cost of the stamp paper shall be borne by you.
3. Please deposit Rs. 21,52,365/- (Rupees Twenty-One Lakhs Fifty-Two Thousand Three Hundred and Sixty-Five only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause no.1(A) at page GCC-16 of the contract document.

[Signature]
15/10/2025



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

VIJAYAWADA AIRPORT, VIJAYAWADA-521102

4. Within 30 days of issue of acceptance letter, you shall submit to AAI, a Performance guarantee as per condition of Clause 1 on page GCC-15 for an amount of Rs. 21,52,365/- (Rupees Twenty-One Lakhs Fifty-Two Thousand Three Hundred and Sixty-Five only) in the form of Insurance Surety Bonds, Account Payee Demand Draft, or Bank Guarantee (including e-bank guarantee) on the proforma appended at Appendix XI on page no. GCC-112 of contract document.
5. You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause No. 19 on page no. GCC-48 of GCC of tender and minimum wages Act 1948 and Employees Provident Fund and Misc. Provision Act 1952 and ESI Act 1948 as specified in Clause No. 20 on Page No. GCC-55 of GCC of tender and rules there of Central and State Government.
6. You are also directed to contact Sr. Manager (Engg-C), AAI, Vijayawada Airport immediately, who will arrange to hand over the site to you.
7. Please note that the time allowed for carrying out the work shall be six (06) months and same shall be reckoned from the 10th day after issue of this letter.
8. Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-Charge, AAI, Vijayawada Airport.
9. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Yours faithfully,

[Handwritten signature]
15/10/2025

DGM (Engg-Civil)

For and on behalf of the Chairman,
Airports Authority of India,
Vijayawada Airport

Encl: Item Rate BOQ



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

VIJAYAWADA AIRPORT, VIJAYAWADA-521102

Copy to: For kind information (By e-mail):

- (1) ED (Engg.), AAI, Vijayawada.
- (2) JGM (Engg-Elect)I & II, AAI, Vijayawada.
- (3) DGM (Engg-Civil)-II, AAI, Vijayawada.
- (4) SM (Finance), AAI, Vijayawada
- (5) SM (Engg-Civil), AAI, Vijayawada

Paul
15/10/2025
DGM (E-C)

Sl. No.	Item Description	Item Code / Make	Quantity	Unit	TEXT #	NUMBER #	TEXT #	BASIC RATE in Figure including all taxes but excluding GST to be entered by the Bidder	TOTAL AMOUNT including all taxes but excluding GST	TEXT #
1	2	3	4	5	6	7	8	9	10	11
1	Fixing double scaffolding system (cup lock type) supplied by AAVDOR agency on the exterior/interior side, up to seven story height made with 40 mm dia. M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube chaises, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracing, runners, connection with the building etc. wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge. The elevational area of the scaffolding shall be measured for payment purpose.	Item 8	1000.00	Sqm	INR		117.00	117000.00	INR One Lakh Seventeen Thousand & Paise Zero Only	
2	Providing and fixing double scaffolding system (cup lock type) on the exterior/interior side, up to seven story height made with 40 mm dia. M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube chaises, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracing, runners, connection with the building etc. wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge. The elevational area of the scaffolding shall be measured for payment purpose.	Item 9	1000.00	Sqm	INR		200.00	200000.00	INR Two Lakh Sixty Thousand & Paise Zero Only	
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 5.0 in foundation and plinth in:	Item 10	20.00	Cum	INR		5600.00	112000.00	INR One Lakh Twelve Thousand & Paise Zero Only	
4	(a) Cement mortar 1:6 (1 cement : 6 coarse sand)	Item 11	55.00	Cum	INR		5900.00	319000.00	INR Three Lakh Nineteen Thousand & Paise Zero Only	
5	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 5.0 in superstructure above plinth level up to floor V level in all shapes and sizes in:	Item 12	100.00	Sqm	INR		800.00	80000.00	INR Eighty Thousand & Paise Zero Only	
6	(a) Cement mortar 1:6 (1 cement : 6 coarse sand)	Item 13	147.00	cum	INR		6000.00	999600.00	INR Nine Lakh Ninety Nine Thousand Six Hundred & Paise Zero Only	
7	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 5.0 in superstructure above plinth level up to floor V level.	Item 14	560.00	Sqm	INR		261.00	146160.00	INR One Lakh Forty Six Thousand One Hundred Sixty & Paise Zero Only	
8	(a) Cement mortar 1:4 (1 cement : 4 coarse sand)	Item 15	275.00	Sqm	INR		297.00	81675.00	INR Eighty One Thousand Six Hundred Seventy Five & Paise Zero Only	
9	Providing and laying Autoclaved Aerated concrete (AAC) blocks masonry with 100mm/150mm/200mm/230/300 mm thick with Grade-I AAC blocks of density 551 to 650 kg/cum conforming to IS: 2185 (Part 3) in super structure above plinth level up to floor V level with RCC band at self level and lined level with approved block laying polymer modified adhesive mortar all complete as per direction of Engineer-in-Charge. (The payment of RCC band and reinforcement shall be made for separately)	Item 16	825.00	Sqm	INR		108.00	89100.00	INR Eighty Nine Thousand One Hundred & Paise Zero Only	
10	12mm Cement Plaster of mix : 1:4 (1Cement : 4 fine sand)	Item 17	1470.00	Sqm	INR		144.00	211680.00	INR Two Lakh Eleven Thousand Six Hundred Eighty & Paise Zero Only	
11	15mm Cement Plaster on the rough side of single or half brick wall of mix: 1:4 (1Cement : 4 fine sand)	Item 18	1465.00	Sqm	INR		390.00	571350.00	INR Five Lakh Seventy One Thousand Three Hundred Fifty & Paise Zero Only	
12	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Item 19	1500.00	Sqm	INR		45.00	67500.00	INR Sixty Seven Thousand Five Hundred & Paise Zero Only	
13	(a) Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489-2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Dupot Treated) with silicon additives.	Item 20	1500.00	Sqm	INR		90.00	135000.00	INR One Lakh Thirty Five Thousand & Paise Zero Only	
14	(a) New work (Two or more coats applied @ 143 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm.	Item 21	600.00	Kg	INR		450.00	270000.00	INR Two Lakh Seventy Thousand & Paise Zero Only	
15	Providing and applying 12 mm thick (average) premixed formulated one coat gypsum lightweight plaster having additives and light weight aggregates as vermiculite perlite respectively conforming to IS: 2547 (Part - 1 & II) 1976, applied on hatched / uneven background such as bare brick/ block/ RCC work on walls & ceiling at all floors and locations, finished in smooth line and level etc. complete.									
16	Applying priming coats with primer of approved brand and manufacturer, having low VOC (Volatile Organic Compound) content.									
17	(a) With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre									
18	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacturer, including applying additional coats wherever required to achieve even shade and colour.									
19	(a) Two Coats									
20	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber neoprene gasket etc.									
21	Aluminium sections shall be smooth, rust free, straight, milled and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately).									
	(a) For fixed portion - Powder coated aluminium (minimum thickness of powder coating 50 micron)									

By General Manager (Engg-2) 1002/2023
 Date 15/08/2023
 For General Manager (Engg-2) 1002/2023

Item Rate BoQ

Tender Inviting Authority: Sr. Manager (Engg-Civil), Airports Authority of India, Vijayawada Airport, Vijayawada - 521102, Phone No. Telephone-91 773952481

Name of Work: Construction of New Integrated Terminal Building and Associated works including Maintenance, Operational and A/C/MC at Vijayawada Airport SRI Miscellaneous civil works of NITB (New Integrated Terminal Building)

Tender id : 2025_AAI_240104_1

K CONSTRUCTIONS

K CONSTRUCTIONS									
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)									
Sl. No.	Item Description	Item Code / Make	Quantity	Units	TEXT #	Quoted Currency in INR / Other Currency	BASIC RATE in Figures including all taxes but excluding GST To be entered by the Bidder	TOTAL AMOUNT including all taxes but excluding GST in Rs. p	TEXT #
1	Supplying & fixing Aluminium Composite Panel (ACP) of FR A2 grade in cladding/ceiling/built nose, in approved shape made out of ACP (Aluminium Composite Panel) sheet material comprising of aluminium skin of 0.5mm with KYNAR 500 based PVDF by double coat double bake method as per AAMA 2605 standards / FEVE based fluorocarbon paint finish on top + 3mm core comprising around 90% non-combustible mineral and balance virgin polymer + 0.5mm aluminium skin with mill finish/service coat at bottom. (Overall weight of ACP shall be 8.1 Kg/Sqm (+/-5%)). Mild Steel hot dipped galvanized C channels of minimum size 75mm x 50 mm x 6 mm with slot of 8mm x 15mm are fixed to the existing RCC columns / walls / structural steel members or any other backing surface. Aluminium hollow section (22 - 25 micron anodic coating) tube of size 36mm x 50mm x 2mm thick in grid of maximum 1200mm x 1200mm shall be fixed to these brackets both vertically and horizontally by using M6 x 75mm stainless steel bolts and nuts. Panel fixing shall be by cutting the composite panels to size, routed, corners notched and bent as per the dimensions specified. After the panels are bent aluminium cleats of size 16mm x 16mm by 25mm length are fixed to the edge of the panels by using aluminium pop rivets. The panels are fixed to the framework by using stainless steel screws. The gap of 12mm or 16mm between the panels (both vertical and horizontal) are filled with closed cell polyethylene light weight backer rod of size 12mm x 20mm or 16mm x 20mm, weather proof silicon sealant shall be used to fill the grooves, Non-Staining Weather sealant should have minimum bearing strength 4.0N/mm, shore A hardness 24 (ISO 988), joint movement capability +30% (As per ASTM C-920), one part natural cure, sealant shall be DOW CORNING (DC-785) or equivalent etc., including erection of necessary scaffolding and dismantling of the same etc., as per the direction of Engineer in Charge.	Item 1	3580.00	Sqm	INR		5031.00	16010880.00	INR One Crore Eighty Lakh Ten Thousand Nine Hundred Eighty & Paise Zero Only
2	Supply and installation of plain 300C (Edenor) false ceiling system of approved colour at all heights consisting of panel 300mm wide 30mm deep x 600mm thick with bevelled edge, panel length up to 6 metres. Coil coated on a continuous paint line, double baked and roll formed from enamelled corrosion resistance aluminium alloy AA3005 (Al.Mg) for higher strength and good roof forming characteristics. The panel shall be about each other with a narrow V groove. Panel shall be clipped to a beaded enamelled aluminium panel carrier of 41.5 mm wide x 62mm deep x 0.95 mm thick in standard length of 6 meter made double baked black enamelled aluminium alloy AA 5050 (Al. Mg) with cut outs to hold the panels in a module of 300mm closed at a distance 2.4mtr. Panel carrier shall be suspended as per the manufacturers drawing etc., complete as per the direction of Engineer in Charge.	Item 2	730.00	Sqm	INR		4000.00	2920000.00	INR Twenty Nine Lakh Twenty Thousand & Paise Zero Only
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed member, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Item 3	2770.00	Kg	INR		117.00	325025.00	INR Three Lakh Twenty Five Thousand Twenty Six & Paise Zero Only
4	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolting with special shaped washers etc. complete.	Item 4	45570.00	Kg	INR		117.00	5331690.00	INR Fifty Three Lakh Thirty One Thousand Six Hundred Ninety & Paise Zero Only
5	Providing & applying painting system to structural steel works consisting of the following coats : (a) Intermediate Coat : A two component Epoxy Micaaceous Iron Oxide Intermediate with minimum volume solids of 90% having VOC less than 250gms/ltr of approved make of total minimum dry film thickness (DFT) 75 microns. (b) Finish Coat : To be applied in two coats: Two component High Gloss Acrylic Polyurethane Finish Paint with approximate Volume solids of 70-77%, having VOC < 250 gnltr, with gloss retention of minimum 80% after 2000 hours exposure to UV A Fluorescent lamp as per ASTM D523 of approved make of total minimum dry film thickness (DFT) 100 microns (Total DFT of two coats). Note : The entire paint system shall be of same manufacturer.	Item 5	2250.00	Sqm	INR		225.00	506250.00	INR Five Lakh Six Thousand Two Hundred Fifty & Paise Zero Only
6	Providing & fixing decorative high pressure laminated sheet of plain / wood grain in glass / matt suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS: 2046 Type S, including coat of adhesive of approved quality.	Item 6	245.00	Sqm	INR		1200.00	294000.00	INR Two Lakh Ninety Four Thousand & Paise Zero Only
7	Providing and fixing BWP plywood plain lining on existing block wall/RCC wall/ wooden frame/steel frame work with necessary screws suitable for the type of wall as per the directions of Engineer-in-charge. (a) 12mm thick Marine Plywood	Item 7	245.00	Sqm	INR		1125.00	275625.00	INR Two Lakh Seventy Five Thousand Six Hundred Twenty Five & Paise Zero Only

C-NIL : NIL, O-NIL

Handwritten signature and stamp:
 15/07/25
 S. Prasad
 (Sri. Prasad)
 (Sri. Prasad)

NUMBER #	TEXT #	TEXT #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Ground Currency in INR / Other Currency	GAAR RATE in Rupees including all taxes but excluding GST To be entered by the bidder	TOTAL AMOUNT including all taxes but excluding GST in Rupees	TOTAL AMOUNT Excluding GST in Words
1	For shutters of doors, windows & ventilators including providing and fixing hinges/pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (fittings shall be paid for separately).	Item 22	250.00	Kg	INR	480.00	120000.00	INR One Lakh Twenty Thousand & Paise Zero Only
22	(a) Powder coated aluminum (minimum thickness of powder coating 50 micron)	Item 23	100.00	Sqm	INR	900.00	90000.00	INR Ninety Thousand & Paise Zero Only
23	Providing and fixing 12 mm thick perforated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in parrelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge	Item 24	100.00	Sqm	INR	800.00	80000.00	INR Eighty Thousand & Paise Zero Only
24	Providing and fixing glazing in aluminum door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminum snap bearing shall be paid in basic item)	Item 25	25.00	Each	INR	180.00	4500.00	INR Four Thousand Five Hundred & Paise Zero Only
25	(a) With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)	Item 26	25.00	Each	INR	150.00	3750.00	INR Three Thousand Seven Hundred Fifty & Paise Zero Only
26	Providing and fixing aluminum tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS: 1808) transparent or dyed to required colour or shade, with necessary screws etc. complete	Item 27	16.00	Each	INR	150.00	2400.00	INR Two Thousand Four Hundred & Paise Zero Only
27	(a) 200x10 mm	Item 28	36.00	Each	INR	180.00	6480.00	INR Six Thousand Four Hundred Eighty & Paise Zero Only
28	Providing and fixing chromium plated brass handles with necessary screws etc. complete	Item 29	15.00	Each	INR	900.00	13500.00	INR Thirteen Thousand Five Hundred & Paise Zero Only
29	(a) 125 mm	Item 30	10.00	Each	INR	500.00	5000.00	INR Five Thousand & Paise Zero Only
30	Providing and fixing Brass 100mm mortice latch and lock with 8 levers without pair of handles (best make of approved quality) for aluminum door including necessary cutting and making good etc. complete.	Item 31	350.00	Kg	INR	540.00	192150.00	INR One Lakh Ninety Two Thousand One Hundred Fifty & Paise Zero Only
31	Providing and fixing anodised aluminum grill (anodised transparent or dyed to required shade according to IS: 1866 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P. brass/stainless steel screws @ 200 mm center to center, including cutting the grill to proper opening size for fitting and operation of handles and fixing approved anodised aluminum standard section around the opening, all complete as per requirement and direction of Engineer-in-charge. (Only weight of grill to be measured for payment)	Item 32	500.00	metre	INR	90.00	45000.00	INR Forty Five Thousand & Paise Zero Only
32	Filling the gap in between aluminum frame & adjacent RCC/Brick Stone work by providing weather silicon sealant over blacker rod of approved quality as per architectural drawings and direction of Engineer-in-charge complete.	Item 33	53.00	metre	INR	750.00	39750.00	INR Thirty Nine Thousand Seven Hundred Fifty & Paise Zero Only
33	(a) Upto 5mm depth and 5 mm width	Item 34	20.00	Sqm	INR	2200.00	44000.00	INR Forty Four Thousand & Paise Zero Only
34	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid plain flush door shutter of required size comprising of virgin polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/rice husk/wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) having minimum density of 650 kg/cum and screw withdrawal strength of 1800 N (Face) & 900 N (Edge), minimum compressive strength 50 N/mm2, modulus of elasticity 850 N/mm2 and resistance to spread of flame of Class A category with property of being termite/boiler proof, water/moisture proof and fire retardant and fixed in position with MS hold fastings/SS dash fasteners of required dia and length complete as per direction of Engineer-in-charge. (MS hold fastings or SS dash fasteners shall be paid for separately)							
	Note: For WPC solid door/window frames, minus 5mm tolerance in dimensions i.e depth and width of profile shall be acceptable. Variation in profile dimensions on plus side shall be acceptable but no extra payment on this account shall be made.							
	(a) Frame size 45 x 70 mm							
	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid plain flush door shutter of required size comprising of virgin polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/rice husk/wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) having minimum density of 650 kg/cum and screw withdrawal strength of 1800 N (Face) & 900 N (Edge), minimum compressive strength 50 N/mm2, modulus of elasticity 850 N/mm2 and resistance to spread of flame of Class A category with property of being termite/boiler proof, water/moisture proof and fire retardant and fixed in position with MS hold fastings/SS dash fasteners of required dia and length complete as per direction of Engineer-in-charge. (MS hold fastings or SS dash fasteners shall be paid for separately)							
	(a) 30 mm thick							

CONFIDENTIAL

General Manager (Engg. Control)

2015-12-10

NUMBER #	TEXT #	Item Description	Item Code / Make	NUMBER #	Units	TEXT #	Quoted Currency in INR / Other Currency	NUMBER #	BASIC RATE in Figures including all taxes but Excluding GST To be entered by the Bidder	NUMBER #	TOTAL AMOUNT including all taxes but Excluding GST in Rupee	TEXT #	TOTAL AMOUNT Excluding GST in Words
1	2		3	4	5	6	7	8	9	10	11	12	13
86		Deployment of Backhoe loader / JCB (1 cum bucket capacity / 30 cum/hr) on hire for the works wherever required etc., unsuitable to measurement, along with operator, fuel, etc., complete as per direction of Engineer-in-charge.	11cm 86	480.00	Hour	INR		1950.00		504000.00	INR Five Lakh Four Thousand & Paise Zero Only		
87		Supply of machineries on hire for works wherever required etc. unsuitable to measurement along with operator, fuel, etc. complete as directed by the Engineer-in-charge. a) Hydra Crane of 12MT capacity	11cm 87	240.00	Hour	INR		1200.00		288000.00	INR Two Lakh Eighty Eight Thousand & Paise Zero Only		
88		Supply of machineries on hire for works wherever required etc. unsuitable to measurement along with operator, fuel, etc. complete as directed by the Engineer-in-charge. a) Tipper (10 Tonne)	11cm 88	75.00	Day	INR		7200.00		540000.00	INR Five Lakh Forty Thousand & Paise Zero Only		
89		Supply of machineries on hire for works wherever required etc. unsuitable to measurement along with operator, fuel, etc. complete as directed by the Engineer-in-charge. a) Tractor with tractor unit, 3 cum capacity	11cm 89	75.00	Day	INR		3400.00		255000.00	INR Two Lakh Fifty Five Thousand & Paise Zero Only		
90		Supply of machineries on hire for works wherever required etc., unsuitable to measurement along with operator, fuel, etc. complete as directed by the Engineer-in-charge. a) Welding Machine of required Capacity along with welding rods, oxygen cylinders and other required materials for welding.	11cm 90	20.00	Day	INR		2500.00		50000.00	INR Fifty Thousand & Paise Zero Only		
91		Supply of machineries on hire for works wherever required etc., unsuitable to measurement along with operator, fuel, etc. complete as directed by the Engineer-in-charge. a) Tractor Dozer	11cm 91	45.00	Day	INR		7600.00		337500.00	INR Three Lakh Thirty Seven Thousand Five Hundred & Paise Zero Only		
92		Supply of machineries on hire for works wherever required etc., unsuitable to measurement along with operator, fuel, etc. complete as directed by the Engineer-in-charge. a) Hand Held grass Cutting machine of petrol driven	11cm 92	15.00	Day	INR		2000.00		30000.00	INR Thirty Thousand & Paise Zero Only		
93		Supply of machineries on hire for works wherever required etc., unsuitable to measurement along with operator, fuel, etc. complete as directed by the Engineer-in-charge. a) Air Compressor of 250cfm (Diesel)	11cm 93	10.00	Day	INR		6080.00		60800.00	INR Sixty Thousand & Paise Zero Only		
94		Supply of machineries on hire for works wherever required etc., unsuitable to measurement along with operator, fuel, etc. complete as directed by the Engineer-in-charge. a) Supply of Skilled labourers i.e., Masons (1st Class), Plumbers, Fitter (1st Class), fabricators (steel/aluminium etc.) for works, unsuitable to measurement as and when required including necessary tools.	11cm 94	300.00	Day	INR		1000.00		300000.00	INR Three Lakh & Paise Zero Only		
95		Supply of Semi-Skilled labourers i.e., Painters, Masons (2nd Class), Carpenters (2nd Class), Fitter (2nd Class) for works, unsuitable to measurement as and when required including necessary tools. Note: "Day" implies engaging one labour for 8 hours shift.	11cm 95	270.00	Day	INR		900.00		243000.00	INR Two Lakh Forty Three Thousand & Paise Zero Only		
96		Supply of unskilled labourers for works, unsuitable to measurement as and when required including necessary tools. Note: "Day" implies engaging one labour for 8 hours shift.	11cm 96	1200.00	Day	INR		798.00		958600.00	INR Nine Lakh Fifty Eight Thousand Eight Hundred & Paise Zero Only		
										43047285.00	INR Four Crore Thirty Lakh Forty Seven Thousand Two Hundred Eighty Six & Paise Zero Only		
													INR Four Crore Thirty Lakh Forty Seven Thousand Two Hundred Eighty Six & Paise Zero Only

M. V. Vijayawada Airport-521102
 Sr. Asst. Manager (Engineering)
 Sr. Asst. Manager (Engineering)
 Sr. Asst. Manager (Engineering)

Signature Not Verified

Digitally signed by RANJITH B
 Date: 2025.11.27 16:32:59 IST
 Location: eProcurement System for Central PSUs